User Manual

for Leapfrog Works Version 4.0

© 2020 Seequent Limited ("**Seequent**"). All rights reserved. Unauthorised use, reproduction, or disclosure is prohibited. Seequent assumes no responsibility for errors or omissions in this document. LEAPFROG, SEEQUENT and 24 are trade marks owned by Seequent. All other product and company names are trade marks or registered trade marks of their respective holders. Use of these trade marks in this document does not imply any ownership of these trade marks or any affiliation or endorsement by the holders of these trade marks.

Contents

Getting Started	1
Signing In to Leapfrog Works With Seequent ID	1
Graphics and Drivers	2
Running the Graphics Test	2
The Leapfrog Works Projects Tab	4
Recording Reference Codes	5
Managing Leapfrog Works Projects	5
Saving Projects	6
Saving Zipped Copies of Projects	6
Saving Backup Copies of Projects	6
Compacting Projects	6
Upgrading Projects	6
Converting Leapfrog Geo and Leapfrog Geothermal Projects	7
An Overview of Leapfrog Works	8
Keyboard Shortcuts in the Main Window	9
The Project Tree	10
Importing Data	10
Data Object Options	11
Organising Objects in the Project Tree	14
Subfolders	15
Copying Objects	16
Renaming Objects	16
Finding Objects	17
Deleting Objects	17
Sharing Objects	18
Object Properties	18
Comments	19
Object Processing	20
Controlling Processing	21
Prioritising Objects	22
Freezing Objects	25
Correcting Errors	27
Project Tree Keyboard Shortcuts	27
The 3D Scene	28
Locating an Object from the Scene	31

Clicking in the Scene	32
Clicking in the Shape List	
Slicing Through the Data	
Slicer Properties	
Object Slice Mode	
Slicer Shortcuts	
Measuring in the Scene	
Determining a Location	
The Moving Plane	41
The Ruler	42
Working With Split Views	
Visualising Data	
Colour Options	
Single Colour Display	
Category Colourmaps	51
Numeric Colourmaps	
Continuous Colourmaps	
Discrete Colourmaps	
Importing Colour Gradients	
Importing and Exporting Colourmaps	62
Opacity	
Property Buttons	63
Legends	63
Slice Mode	64
Filtering Data Using Queries	64
Filtering Data Using Values and Categories	65
Working With Data Tables	65
Importing Data Tables and Mapping Data Columns	65
Data Tables in the Project Tree	70
Viewing Table Data	71
Adding and Updating Data for Existing Tables	72
Importing Additional Columns to a Data Table	72
Adding New Rows to Existing Data Tables	73
Reloading Data Tables	73
Correcting Data Errors in Leapfrog Works	74
Identifying Errors in Data Tables	74
Exporting Data Errors	

Viewing and Correcting Errors in Leapfrog Works	
Replacing Values in a Column	
Common Errors and How to Fix Them	
Duplicate Points Error (Points Tables)	
Duplicate Hole ID Error	
Hole ID Not in Collar Table Error	
Collar Max Depth Error	
Invalid Max Depth Error	
From Depth Exceeds To Depth Error	
Overlapping Segments Error	
No Samples for Collars Warning	
No Surveys for Collar Warning	
Wedges Found Warning	
Handling Special Values	
Evaluations	
Query Filters	91
Using a Query Filter in Displaying Data	
Using a Query Filter in a Model	92
The Standard Query Builder	94
Leapfrog Works Query Syntax	
The Build Query Window	96
The Advanced Query Builder	
The Points Query Builder	
Insert Query Elements Using Ready Reference	
Write a Query in Query Editor	
Write a Query Using the Query Builder	101
Drawing in the Scene	
The Drawing Toolbar	104
Drawing Hotkeys	
Drawing 3D Lines	
Drawing 2D Lines	
Polyline Properties	
Tangents and Ribbons	
Drawing Points	
Organising Your Workspace	
Detaching Tabs	
Detaching and Minimising the Project Tree	

Organising the Scene View Tab	
Concepts	
What is Implicit Modelling?	
What are the Advantages of Implicit Modelling?	
Implicit Modelling Makes Assumptions Explicit	
Best Practices	119
Interpolant Functions	
The Spheroidal Interpolant Function	
Total Sill	
Nugget	
Nugget to Total Sill Ratio	
Base Range	
Alpha	
Drift	
Accuracy	
The Linear Interpolant Function	
Total Sill and Base Range	
Nugget	
Drift	
Accuracy	
Surface Resolution in Leapfrog Works	
Modifying Surfaces	
Adding Data to Surfaces	
Honouring Surface Contacts	
Editing Surfaces With Polylines	
Editing Surfaces With Structural Data	
Modifying Surfaces With Anisotropic Trends	140
Applying a Structural Trend	141
Trends and Anisotropy	144
Global Trends	144
Anisotropic or Ellipsoidal Distance	145
Structural Trends	146
Creating a Structural Trend	148
Compatibility	
Variable Orientation	
Variography	152
Polarity in Leapfrog Works	

Polarity and Polylines	154
Invert Polyline Polarity	
Adjust Polyline Polarity Using Tangents	
Polarity and Surfaces	
Polarity and Structural Data	
Boundaries in Leapfrog Works Projects	
The Clipping Boundary	159
Object Extents	
Extending a Surface	
Central Integration	
Enabling Central Connectivity	
Switching to Using Seequent ID	
Connecting to Central	
Troubleshooting Connectivity Issues	
Central Projects	
Viewing a Project's History	
Locking Branches	
Project Included	
Project Stages	
Comments and Attachments	171
Sharing Projects	
Downloading a Local Copy of a Project	
New Central Projects	
Creating a New Central Project	
Adding a Project to Central	
Publishing to Central	
Unfinished Publish Events	
Selecting Objects	
Setting the Project Workflow Stage	
Including the Project	
Adding Revision Information and Branching	
Preparing the Package	
Uploading the Package	
Importing Data From Central	
Object Availability	
Importing Central Data Objects	
Updating Out-of-Date Objects	

Appending Rows and Adding Columns to Data Tables	
Settings	
Display and Navigation Settings	
3D Acceleration Mode	
Font Size	
Z Axis Scale	
Rotation Settings	
Camera Settings	
Overlay Settings	
Screen Grid Settings	
Axis Lines Settings	
Other Overlay Settings	
Colour Scheme	
Lighting Settings	
Processing Settings	
User Interface Settings	
Show Tree Lines	
Show Save Scene Button	
Upload to View	
Tab Position	
Central Settings	
Usage Policy Settings	
Network Settings	
Help Settings	
Reporting a Problem	
Getting Support	
Checking Connectivity With Seequent Start	
Supplying Your Licence Details	
Data Types	
GIS Data, Maps and Images	
Displaying GIS Data	
Custom Topography Views	
Importing Vector Data	
Importing a MapInfo Batch File	
Importing Data from an ESRI Geodatabase	
Reloading GIS Data	
Reloading Points, Lines and Polygons	

Reloading an ESRI Database	
Importing a Map or Image	
Importing a Single Image	
Importing Multiple Images	
Cropping Images	
Manually Georeferencing Images	
Overriding Georeference Data	
Exporting a Georeferenced Image	
Setting Elevation for GIS Objects and Images	
Creating a New GIS Line	210
Drawing a New GIS Line	
Creating a New GIS Line from Intersecting Meshes	
Exporting GIS Data	212
Borehole Data	
Displaying Boreholes	214
Displaying Boreholes as Lines or Cylinders	215
Hiding Lithologies	218
Displaying a Legend	
Changing Colourmaps	
Viewing Multiple Interval Tables	
Selecting from Multiple Columns	
Displaying Interval Data in the Scene	221
Displaying Borehole Traces	
Displaying Borehole Graphs	
Viewing Borehole Data Table Statistics	
Importing Borehole Data	
Expected Borehole Data Tables and Columns	
The Collar Table	
The Survey Table	
The Screens Table	
Interval Tables	
Points Tables	
AGS Format Borehole Data	
The Collar Table	
The Survey Table	
Interval Tables	
Depth Points Tables	

Importing Drilling Data From the Central Data Room	
Selecting the ODBC Data Source	230
Selecting Tables	
Connecting to an OpenGround Cloud Database	
Importing Interval Tables	233
Importing Point Values Down Boreholes	234
Importing LAS Points Down Boreholes	
LAS File Mapping	235
LAS File Inconsistencies	
Importing Downhole Structural Data	235
Borehole Desurveying Options	
The Spherical Arc Approximation Algorithm	
The Balanced Tangent Algorithm	238
The Raw Tangent Algorithm	
Processing Borehole Data	
Category Composites	
Converting Ignored Segments	
Filtering Short Segments	243
Viewing Category Composite Statistics	244
Majority Composites	
Viewing Majority Composite Statistics	
Numeric Composites	
Creating a Numeric Composite	
Compositing in the Entire Borehole	
Compositing Length	
Minimum Coverage	
Residual End Length Handling	
Additional Weighting Column	
Compositing in a Subset of Codes	
Using Intervals From Another Table	
Viewing Numeric Composite Statistics	251
Compositing Comparison	
Compositing Interval Lengths	254
Grouping Lithologies	254
Automatic Lithology Groups	257
Splitting Lithologies	
Interval Selection	

Overlaid Lithology Column	
Category Column from Numeric Data	
Back-Flagging Borehole Data	
Comparing Modelled Values to Drilling Lithologies	
Comparing Drilling Lithologies to Modelled Values	
Refining the Geological Model to Improve Correlation Statistics	
Merged Borehole Data Tables	
Core Photo Links	
The ALS CoreViewer Interface	
Setting Up the ALS CoreViewer Interface	
Using the ALS Interface	
Removing the ALS Link	
The Coreshed Core Photo Interface	
Setting Up the Coreshed Interface	
Using the Coreshed Interface	
Removing the Coreshed Link	
The Imago Core Photo Interface	
Setting Up the Imago Interface	
Using the Imago Interface	
Removing the Imago Link	
Exporting Borehole Data	
Exporting All Borehole Data	
Exporting Borehole Data in IFC Format	
Exporting a Single Borehole Data Table	
Design Models	
Designs	
Reloading Designs	
Displaying Designs	
Moving Designs	
Working With Design Meshes	
Editing Design Lines	
Exporting Designs	
Alignments	
Reloading Alignments	
Displaying Alignments	
Using Alignments in the Project	
Points Data	

Importing Points Data	292
Selecting the ODBC Data Source	
Reloading Points Data	
Appending Points Data	
Importing a Column	
Setting Elevation for Points	
Evaluating Points Data	
Displaying Points	
Viewing Points Table Statistics	
Exporting Points Data	
Exporting Intrusion Values	
Exporting Interval Midpoints	
Extracting Points from Borehole Data	
Extracting Contact Points from Borehole Data	
Extracting Intrusion Values from Borehole Data	
Intrusion Point Generation Parameters	
Extracting Interval Midpoints from Borehole Data	
Creating Guide Points	
Categorising Points	
Geophysical Data	
2D Grids	
UBC Grids	
Importing a UBC Grid	
Evaluating UBC Grids	
Mapping Category Evaluations	
Exporting a UBC Grid	
GOCAD Models	
Structural Data	
Creating New Planar Structural Data Tables	
Importing Planar Structural Data	
Selecting the ODBC Data Source	
Importing Lineations	
Displaying Structural Data	
Viewing Statistics on Structural Data	
Bingham Analysis	
Fisher Statistics	
Assigning Structural Data to Categories	

Editing the Orientation of Planar Structural Data	
Declustering Planar Structural Data	
Setting Elevation for Structural Data	
Estimating Planar Structural Data	
Meshes	
Cleaning Up a Mesh	
Importing a Mesh	
Meshes With Textures	
Reloading a Mesh	
Displaying Surfaces	
Draping an Image on a Mesh	
Exporting Meshes	
Exporting a Single Mesh	
Exporting Multiple Meshes from the Meshes Folder	
Exporting Multiple Meshes from Models	
Visualising Issues With Imported Meshes	
Examining Mesh Properties	
Visualising Self Intersections	
Visualising Borders	
Visualising Non-Manifold Edges	
Options for Handling Mesh Issues	
Non-Editable Meshes	
Mesh from the Moving Plane	
Combining Meshes	
Clipping a Volume	
Clipping a Mesh	
Merging 2D Meshes	
Extracting Mesh Parts	
Interpolated Meshes	
Creating an Interpolated Mesh	
Refining an Interpolated Mesh	
Surface Resolution Settings	
Snap Settings	
Other Options	
2D Interpolant Meshes	
Offset Meshes	
Triangulated Meshes	

Elevation Grids	
Importing an Elevation Grid	
Exporting an Elevation Grid	
Thickness Grids	
Polylines	
Creating Polylines	
Displaying Polylines	
Sharing and Unsharing Polylines	
Importing Polylines	
Reloading Polylines	
Exporting Polylines	
Open Mining Format (OMF) Export and Import	
OMF Export	
OMF Import	
Importing OMF Files From the Central Data Room	
Analysing Data	
Statistics	
Table of Statistics	
Scatter Plots	
Q-Q Plots	
Box Plots	
Univariate Graphs	
Borehole Correlation Tool	
Selecting Collars	
The Correlation Set Window	
Navigating in the Correlation Set Window	
Correlation Column Layouts	
Managing Styles	
Interpretation Tables	
Assigning Lithologies	
Modifying the Interpretation Table	
Stereonets	
Creating a Stereonet	
Displaying the Stereonet in the 3D Scene	
Plot Options	
Data Display Options	
Viewing Stereonet Statistics	

Selecting Data in the Stereonet	
Using the Scene Window With the Stereonet	
Exporting a Stereonet	
Form Interpolants	404
Creating a Form Interpolant	
Setting a Trend	
Adding Isosurfaces	
The Form Interpolant in the Project Tree	405
Form Interpolant Statistics	
Planning Boreholes	
Adding Planned Boreholes	
Planning Options	
Drilling Prognoses	411
Exporting Planned Boreholes	411
Export Parameters	411
Export as Interval Table	411
Importing Planned Boreholes	
Calculations and Filters	
Defining Calculations and Filters	
The Calculations Window	414
Creating a New Calculation or Filter	416
Variables	
Numeric Calculations	417
Category Calculations	
Filters	418
Understanding Errors Reported in the Errors Pane	
Building Calculations and Filters	420
Examples of Variables	
Example of a Numeric Calculation	422
Example of a Filter	
Example of a Category Calculation	
Null Values	
Catalogue of Metadata, Syntax and Functions	
Existing Items	
Metadata	429
Evaluations	
Variables, Calculations and Filters	

Syntax and Functions	433
Statements	
Basic Operators	
Complex Comparisons	439
Invalid Values	
Mathematics	442
Limits and Rounding	444
Text	
Date/Time	
Unit Conversion	452
Modelling	456
Assigning Attributes to Volumes	456
Defining a Topography	
Topography From Elevation Grid	458
Topography From Surfaces, Points or GIS Vector Data	459
Fixed Elevation Topography	
Adding Height Data to the Topography	
Changing Topography Settings	
Changing the Size of the Topography	
Topography Resolution	462
Applying a Trend to the Topography	
Topography Display Options	463
Setting Elevation for Collar Points	
Geological Models	
Creating a New Geological Model	
The Base Lithology	
Surface Resolution	
Model Extents	
The Geological Model in the Project Tree	
Geological Model Display	
Copying a Geological Model	469
Creating a Static Copy of a Geological Model	
Geological Model Volumes and Surfaces Export Options	
Extracting Model Volumes	
Editing a Geological Model	471
Changing the Query Filter	
Surface Generation Options	

Volume Generation Options	
Surface Resolution for a Geological Model	
Modifying a Geological Model's Boundary	
Creating Extents for a Geological Model	
Extent From a Polyline	
Extent From GIS Vector Data	
Extent From Points	
Extent From Structural Data	
Extent From a Surface	
Extent From Distance to Points	
Extent From a Distance Function	
Base From Lithology Contacts	
Changing an Extent's Settings	
Surface Resolution	
Contact Honouring	
Applying a Trend	
Adding Data to an Extent	
Editing an Extent With a Polyline	
Editing an Extent With Structural Data	
Removing an Extent From a Geological Model	
Model Lithologies	
Faulted Models	
The Fault System	
Fault Interactions	
Activating the Fault System	
Copying the Surface Chronology to an Empty Fault Block	
Faulted Model Display Options	
Editing Faults	492
Surfacing Options for Faults	
Boundary Filtering	
Snapping to Data	493
Changing Fault Inputs	
Replacing Fault Inputs With a Single Mesh	
Adding Data to the Fault	
Snap Settings for Individual Inputs	
Boundary Filtering Settings for Individual Inputs	
Applying a Trend to a Fault	

Contact Surfaces	496
Contact Surfaces in the Surface Chronology	
Contact Surfaces Types	
Deposit and Erosion Contact Surfaces	
Intrusion Contact Surfaces	
Vein Contact Surfaces	
Younging Direction	
Deposits and Erosions	
Creating Deposits and Erosions	
Deposits and Erosions From the Base Lithology	
Deposits and Erosions From Other Lithology Contacts	
Deposits and Erosions From Other Data	
Deposits/Erosions in the Project Tree	
Refining Deposits and Erosions	
Surfacing Options for Deposits and Erosions	
Boundary Filtering	
Snapping to Data	
Setting the Surface Resolution	
Applying a Trend to a Deposit/Erosion	
Intrusions	
Creating Intrusions	511
Intrusions from Lithology Contacts	
Intrusions from Other Data	
Intrusions in the Project Tree	
Displaying Intrusion Points	
Refining Intrusions	515
Surfacing Options for Intrusions	515
Boundary Filtering	
Snapping to Data	
Surface Resolution	516
Applying a Trend to an Intrusion	517
Clipping Values for Intrusions	
Interpolation Settings	
Veins	
Creating Veins	
Veins From Lithology Contacts	
Veins From Other Data	

Veins in the Project Tree	521
Displaying Veins	522
Refining Veins	
Surfacing Options for Veins	
Boundary Filtering	
Snapping to Data	
Surface Resolution	524
Vein Thickness	524
Vein Pinch Out	524
The Vein Reference Surface	525
Curved Reference Surface	526
Planar Reference Surface	
Custom Reference Surface	528
The Vein Boundary	
Editing Vein Segments	530
Vein Systems	531
Creating a Vein System	
Adding Veins to the Vein System	534
Editing the Veins	534
Changing Vein System Lithology Settings	534
Setting Vein Interactions	535
Stratigraphic Sequences	
Creating a Stratigraphic Sequence	540
Boundary Filtering	
Snapping to Data	
Surface Stiffness	543
Editing the Stratigraphic Sequence	543
Correcting Pinch-Out Errors	
Surfacing Options	544
Applying a Trend	544
Editing Individual Surfaces	544
Contact Honouring and Boundary Filtering for Individual Surfaces	544
Adding Data to Individual Surfaces	
Editing Surface Contacts	
Offset Surfaces	
Creating an Offset Surface	
The Offset Surface in the Project Tree	

Refining an Offset Surface	548
Changing Surfacing Options for an Offset Surface	
Boundary Filtering	
Snapping to Data	
Surface Resolution	
Smoothing	
Changing Offset Limits	
Changing to a Constant Offset	
Changing to an Offset to Points	
Changing the Reference Mesh	
Editing the Reference Mesh	
Structural Surfaces	
Creating a Structural Surface	
The Structural Surface in the Project Tree	
Refining a Structural Surface	
Surfacing Options for a Structural Surface	
Setting the Surface Resolution	554
Boundary Filtering	
Snapping to Input Data	
Non-Contact Structural Inputs Settings	555
Applying a Trend to a Structural Surface	555
Value Clipping	
The Surface Chronology	555
Refined Models	
Editing the Sub-Model	
Numeric Models	
Importing a Variogram Model	
Copying a Numeric Model	
Creating a Static Copy of a Numeric Model	
Exporting Numeric Model Volumes and Surfaces	
Exporting Numeric Model Midpoints	
RBF Interpolants	
Creating an RBF Interpolant	
Values Used	
Applying a Query Filter	
Applying a Surface Filter	
The Interpolant Boundary	

Compositing Options	FCF
Compositing Options	
The RBF Interpolant in the Project Tree	
Interpolant Display	
RBF Interpolant Statistics	
Modifying an RBF Interpolant's Boundary With Lateral Extents	
Creating Lateral Extents	
Extent From a Polyline	
Extent From GIS Vector Data	
Extent From Points	
Extent From Structural Data	
Extent From a Surface	
Extent From Distance to Points	
Extent From a Distance Function	
Changing a Lateral Extent's Settings	
Surface Resolution	
Contact Honouring	
Applying a Trend	
Adding Data to an Extent	
Editing an Extent With a Polyline	
Editing an Extent With Structural Data	
Removing an Extent from an Interpolant	
Changing the Settings for an RBF Interpolant	
Adjusting the Values Used	
Adding a Contour Polyline	
Adding Points	
Compositing Parameters for an RBF Interpolant	
Adjusting the Interpolant Boundary	
Clipping and Transforming Values for an RBF Interpolant	
Changing the Trend for an RBF Interpolant	
Using a Global Trend	
Using a Structural Trend	
Adjusting Interpolation Parameters	
Output Settings for an RBF Interpolant	
Multi-Domained RBF Interpolants	
Creating a Multi-Domained RBF Interpolant	
Compositing and Filtering the Values Used	

Selecting Domains	
Clipping and Transforming Values	
Setting the Trend	
Interpolation Parameters	
Output Options	
The Multi-Domained RBF Interpolant in the Project Tree	
Interpolant and Sub-Interpolant Display	
Sub-Interpolant Statistics	
Distance Functions	594
Creating a Distance Function	
Setting the Boundary	597
Setting a Trend	
Adding Buffers	
The New Distance Function in the Project Tree	
Combined Models	
Creating a Combined Model	600
The Combined Model in the Project Tree	601
Editing a Combined Model	
Creating a Static Copy of a Combined Model	
Combined Model Export	603
Contaminant Models	604
Contaminant Estimations	604
Creating a Contaminant Estimation	605
Defining the Domain	606
Selecting Values	607
Setting Compositing Options	608
Boundary Validation	609
The Contaminant Estimation in the Project Tree	611
Viewing Statistics	
Copying a Contaminant Estimation	613
The Ellipsoid Widget	613
Display and Editing Modes	613
Changing Movement Handles	614
Changing Look Direction	617
Changing Controls in Edit Mode	617
Experimental Variography and Variogram Models	618
The Variogram Model Window	

Variogram Model Controls	
Linear, Spherical and Spheroidal Model Options	623
Type = Linear	624
Type = Spherical	625
Type = Cubic	625
Type = Exponential	626
Type = Gaussian	626
Type = Generalised Cauchy	627
Type = Spheroidal	
Normalised Y Axis	630
Direction	
Experimental Controls	631
Experimental Variogram Parameters	634
Capping	
Defining the Search Space	
Radial Plot Parameters	
Changing Axis Limits	638
Changing Variogram Display	638
Axis Aligned Variograms	
Standard Estimators	641
Inverse Distance Estimators	641
Nearest Neighbour Estimators	643
Kriging Estimators	644
Kriging Attributes	
RBF Estimators	648
Variable Orientations	650
Visualisation Options for Variable Orientations	
Creating Variable Orientations	653
Selecting the Inputs	653
Setting the Global Plunge	656
Setting Visualisation Options	658
The Variable Orientation in the Project Tree	659
Applying a Variable Orientation	660
Exporting Rotations	
Block Models	
Importing a Block Model	
Creating a Block Model	664

Displaying a Block Model	
Viewing Block Model Statistics	
Table of Statistics	
Exporting Block Models	
Selecting From Evaluated Items	
Setting Row Filtering Options	
Setting Numeric Precision	
Setting Status Code Text Sequences	
Selecting the Character Set	
Visualising Estimators	670
Validation and Reporting	
Block Estimate Interrogation	672
Swath Plots	675
Reports	
Flow Models	685
MODFLOW Models	
Creating a MODFLOW Model	686
Horizontal Grid Spacing	
Vertical Grid Layering	
Editing a MODFLOW Model	
Importing a MODFLOW Model	
MODFLOW Evaluations	693
Assigning an Evaluation for Export	693
Combined Evaluations	
MODFLOW Hydrological Properties	
Setting Hydrological Properties	695
Zone Numbers	696
MODFLOW Model Display	697
Grid Display Options	697
Viewing Block Information	
Head Values and MT3D Concentrations	698
Generating a Head Value Mesh	
MODFLOW Model Export	
As a MODFLOW File	
For Groundwater Vistas	700
As a Groundwater Vistas Update	
FEFLOW Models	700

FEFLOW Model Display	
Displaying a 3D Model	
Displaying a 2D Model	
Viewing Block Information	
Importing a FEFLOW Grid	
Creating a 2D FEFLOW Model	
Boundary Options	
Element Size	
Adding Features to the Grid	
Creating a 3D FEFLOW Model	
FEFLOW Evaluations	
Assigning an Evaluation for Export	
Combined Evaluations	
FEFLOW Material Types	
FEFLOW Model Export	
Presentation	
Uploading to View	
Signing in to View	
Uploading to View	
Uploading the 3D View	
Uploading Saved Scenes	
Troubleshooting Connectivity Issues	
Sections	
Evaluating on Sections	
Exporting Sections	
Exporting Section Layouts	
Creating Cross Sections	
Importing Cross Sections	
Fence Sections	
Serial Sections	
Setting the Base Section	
Setting the Offset Sections	
The Serial Section in the Project Tree	
Displaying a Serial Section	
Exporting a Serial Section	
Alignment Serial Sections	
Creating an Alignment Serial Section	

Using an Existing Line	
Using a New Polyline	
The Alignment Serial Section in the Project Tree	731
Displaying an Alignment Serial Section	731
Exporting an Alignment Serial Section	731
Section Layouts	
Setting Up the Section	733
Creating New Section Layouts	
Copying Section Layouts	734
Creating Master Section Layouts	735
Working With the Section Layout Editor	736
Changing Page Properties	737
Changing the Basic Section Properties	738
Organising Objects on the Section	741
Adding and Styling Models	742
Adding Styling Boreholes and Planned Boreholes	749
Adding and Styling Surfaces	753
Adding and Styling Lines	754
Setting Up the Legend	755
Adding and Organising Annotations	759
Displaying a Title	
Displaying a Title Block	760
Displaying a Scale Bar and Location Information	
Text Boxes	
Images	
Rendered Images	764
Background Rendering	
Saved Scenes	765
Saving Scenes	
Exporting Scenes	
Linking to Scene Files	767
Movies	
Contour Lines	
Creating Contour Lines	
Exporting GIS Contours	

Getting Started

Once Leapfrog Works is installed, there are some first steps to carry out before you begin working with projects. This topic describes those first steps and then provides an overview of Leapfrog Works project files. This topic is divided into:

- Signing In to Leapfrog Works With Seequent ID
- Graphics and Drivers
- The Leapfrog Works Projects Tab
- Recording Reference Codes
- Managing Leapfrog Works Projects

Once you have carried out these first steps, see <u>An Overview of Leapfrog Works</u> for a description of the different parts of the Leapfrog Works main window and <u>Concepts</u> for information that is important to helping you get the most out of Leapfrog Works.

Signing In to Leapfrog Works With Seequent ID

To use Leapfrog Works, you need a Seequent ID and the correct permissions.

If you do not have a Seequent ID, you can sign up for one by launching Leapfrog Works and clicking the **Register** button.

To find out more about different permissions, visit the <u>Flexible Leapfrog Software Subscription</u> <u>Options</u> page.

Once you have a Seequent ID and the correct permissions, launch Leapfrog Works, enter your details and click the button to sign in.


In the next window, you can:

- Select your group, if your organisation has a number of different groups.
- Select what extensions you wish to use. Some Leapfrog Works features are only available with an extension.
- Select how long you wish to check out a seat, if your organisation is set up to check out seats on a day-by-day basis.

Select your options, then click the **Get Started** button.

Signing in to Leapfrog Works also signs you in to View, so you can upload scenes to View.

The **Seequent ID** menu in the upper right-hand corner of the main window is used to manage your MySeequent identity.



If your organisation shares Leapfrog seats between users, signing out when you are finished working with Leapfrog Works releases your seat for other Leapfrog users in your organisation.

The menu is displayed in grey rather than green when you are working offline. You will not be able to sign out of MySeequent when you are offline.

Graphics and Drivers

Many laptop computers come with two graphics options: low-powered graphics integrated into the CPU and a high-performance dedicated graphics option (a GPU). To save power, often the laptop's default setting is to run programs using the slower integrated graphics option. However, selecting high-performance graphics options is very important to Leapfrog's performance. If you have a dedicated graphics option, you should be using it. It's also important to have the most up-to-date drivers to make the most of your computer's capabilities.

To determine what graphics capabilities your computer has:

- 1. From the Leapfrog Works menu, select About.
- 2. Click on the System Info tab.

Under the **Summary**, you will see the following details:

- **Graphics in use by** shows the graphics option being used. Note that Leapfrog Works uses only the option indicated; if there are two options available, Leapfrog Works does not use both simultaneously.
- All available graphics hardware lists the options available. If there are two options listed, you will want Leapfrog Works to use the dedicated graphics option rather than the slower integrated graphics.
- Driver date shows the date at which the driver was last updated for each graphics option.

If your graphics drivers are out of date, it is recommended that they be updated prior to switching the graphics in use by Leapfrog Works. You can find detailed information on setting up your graphics correctly for Leapfrog Works on <u>MySeequent</u>.

You may need to know your installation path. The default installation path for Leapfrog Works version 4.0 is: C:\Program Files\Seequent\Leapfrog Works4.0\bin\Works.exe.

Running the Graphics Test

Leapfrog Works can run in one of three acceleration modes. These modes are selected by clicking on the button at the bottom of the main window:

🔗 <no code=""></no>	Full Acceleration	Z-Scale 1.0 19 hours to go


See <u>3D Acceleration Mode</u> in <u>Settings</u> for more information on these settings.

A newer computer will run in **Full Acceleration** mode without issues. However, if you are running Leapfrog Works on a computer that is more than five years old, it is a good idea to run the graphics test to test your computer's graphics capabilities.

To start the test, open Leapfrog Works and select **Test Graphics** from the **Leapfrog Works > Diagnostics** menu:



The graphics test displays a series of image pairs that test your computer's capabilities for the currently selected acceleration mode. For each pair, compare the images:



Even if the differences are slight, click the **Images Differ** button. If the images match, click the **Images Match** button. The next test will be displayed.

At the conclusion of the test, the result is displayed. If one or more tests have failed, information about solving problems will be displayed.

If you click on **Save Report**, you will be prompted to save the file on your computer.

If the test has failed, try switching to a different acceleration mode and running the test again. If possible, avoid using **Software Rendering** as it can be very slow.

If you cannot resolve the problem, save a copy of the graphics test report and contact technical support as described in <u>Getting Support</u>. Be sure to include information about your system copied from the **About > System Info** tab.

The Leapfrog Works Projects Tab

After you have signed in to My Leapfrog, the Leapfrog Works main window will appear with the **Projects** tab displayed:

🗳 Leapfrog Works				– 🗆 🗙
Leapfrog Works	Projects	Central Projects (Offline)	• A 2	Alex Rock
Project Iree 0 1 0 0	<u>N</u> ew Project <u>O</u> pen Project			
	RECENT PROJECTS			
	Clear Recent Projects	Joint Base Cape Cod		
	View projects in: C:\Users\Geologist\Leapfrog Project	ts Joint Base Cape Cod	Lake Aura Demo	
C Logged Out √	Ŀ,	🖉 <no code<="" th=""><th>> Full Acceleration 100+ FPS</th><th>Z-Scale 1.0</th></no>	> Full Acceleration 100+ FPS	Z-Scale 1.0

Thumbnails for the most recent projects are displayed in the **Recent projects** list. The second set of thumbnails is for projects contained in the **Search** folder:

- Click on the folder button () or press the F5 key to change the **Search** folder. The **Search** folder is useful if you have one folder in which you keep most of your Leapfrog Works projects.
- Click on the **Refresh** button (⁽⁾) or press the F4 key to update the list of projects in the **Search** folder.

Projects from other Leapfrog modelling products are indicated in the **Projects** tab. Leapfrog Geo and Leapfrog Geothermal projects can be converted to Leapfrog Works projects. See <u>Converting Leapfrog</u> <u>Geo and Leapfrog Geothermal Projects</u> for more information. Leapfrog Hydro projects can be opened without converting them, and you will still be able to open them in Leapfrog Hydro.

Click on a thumbnail to open a project. You can also navigate directly to the required project file by clicking on **Open Project File**.


Once a project file has been opened, Leapfrog Works switches to displaying the Scene View tab.

See <u>Managing Leapfrog Works Projects</u> below for more information on saving, compacting and upgrading projects.

Recording Reference Codes

You can enter a reference code to track work on specific projects. The time associated with each reference code is included in your monthly usage report.

To enter a code, click the button in the status bar on the bottom edge of the Leapfrog Works main window:



Select from the codes defined and click **OK**. The code entered will be displayed in the status bar:



To define new reference codes or delete old ones, click on the **Manage Codes** button. See <u>Usage</u> Policy Settings.

To work without a code, click on the button, select <No Code>, then click **OK**. Note that whether it's possible to use Leapfrog Works without first entering a reference code depends on a setting in the **Settings > Usage Policy** window.

Managing Leapfrog Works Projects

To create a new project, click **New Project** at the top of the **Projects** tab. The new project will be saved in the **Search** folder.

Leapfrog Works project files use the extension **.aproj**. A folder is also created that contains information used by the project.

Do not change the name of your project folder or alter its contents. Doing so could render your project file unusable.

A **.lock** file is created when a project is opened. The **.lock** file protects the project from being moved while the project is open and from being opened by another instance of Leapfrog Works, which can happen when projects are saved on shared network drives.

Leapfrog is optimised for working off your local hard drive, and you will experience increased processing times and object load times if you access your project from a different storage system. It is strongly recommended that you do not work from network drives, synced drives (e.g. OneDrive, DropBox) or USB drives as working in this way can result in corrupted projects.

Saving Projects

Leapfrog Works automatically saves an open project each time a processing task has been completed or settings have changed. Projects are also saved when they are closed so that scene settings can be restored when the project is next opened.

Saving Zipped Copies of Projects

You can save a zipped copy of a project by selecting **Save A Zipped Copy** from the **Leapfrog Works** menu. You will be prompted to choose a name and location for the zipped project. Click **Save** to create the zip file.

Saving Backup Copies of Projects

You can save a backup copy of a project by selecting **Save A Copy** from the **Leapfrog Works** menu. You will be prompted to choose a new name and location for the saved project. Click **OK** to create the new project file. Leapfrog Works will save a copy of the project in the location selected.

Once the backup copy is saved, you can open and use it from the **Projects** tab. Otherwise, you can keep working in the original copy of the project.

Compacting Projects

When you delete objects from a project file, Leapfrog Works retains those objects but notes that they are no longer used. Over time, the project file will grow in size and data stored in the database may become fragmented.

Compacting a project removes these unused objects and any unused space from the database. When you compact a project, Leapfrog Works will close the project and back it up before compacting it. Depending on the size of the project, compacting it may take several minutes. Leapfrog Works will then reopen the project.

To compact a project, select **Compact This Project** from the **Leapfrog Works** menu. You will be asked to confirm your choice.

Upgrading Projects

When you open a project that was last saved in an earlier version of Leapfrog Works, you may be prompted to upgrade the project. A list of affected objects will be displayed. For large projects with many objects that need to be reprocessed, the upgrade process may take some time. However, it is a

good idea to back up projects before opening them in a new version of Leapfrog Works and backing up the project is strongly recommended.

Tick the **Back up the project before upgrading** button, then click **Upgrade and Open**. Navigate to the folder in which to save the backup and click **Save**.

For large projects with many objects, upgrading without backing up the project is not recommended.

Converting Leapfrog Geo and Leapfrog Geothermal Projects

Leapfrog Geo and Leapfrog Geothermal projects can be converted to Leapfrog Works projects. However, the process is one-way, and projects opened in Leapfrog Works can no longer be opened in Leapfrog Geo/Leapfrog Geothermal.

When you open a Leapfrog Geo/Leapfrog Geothermal project, you will be prompted to save a backup before converting the project.

It is strongly recommended that you back up the project before converting it.


An Overview of Leapfrog Works

This topic provides an overview of the different parts of the Leapfrog Works main window. For more detailed information on using the controls in the different parts of the main window, see the following topics, which describe different aspects of using Leapfrog Works:

- The Project Tree
- The 3D Scene
- Visualising Data
- Working With Data Tables
- Correcting Data Errors in Leapfrog Works
- Evaluations
- Query Filters
- Drawing in the Scene
- Organising Your Workspace

For more information on basic concepts that are important to getting the most out of Leapfrog Works, see the <u>Concepts</u> section.

The Leapfrog Works main window is divided into three main parts:



The **Project Tree 1** contains all the data in the project and tools for working with that data. When you want to change how this data is used in the project, work with the objects in the project tree. See <u>The</u> <u>Project Tree</u>. The **Scene View** tab **2** displays a 3D representation of selected objects from the project

tree. Changing how you view objects in the scene window does not change those objects in the project tree. See <u>The 3D Scene</u>. Tools for changing the appearance of data in the scene window are available in the shape list and the shape properties panel 3. Changing the appearance of these objects does not change those objects in the project tree.

You can add objects to the scene window by dragging them from the project tree. You can temporarily hide them in the scene or remove them altogether using the controls in the shape list.

Leapfrog Works is unit-less and adopts the units used in the data you import. For example, if your imported data is in metres, the units displayed will be metres, and figures such as resolution, measured distances and slicer thickness will be in metres. It is important, therefore, to be consistent in the units used in the data you import. If you are importing data that uses different coordinate systems, you will need to pre-process the data so that it is using the same coordinate system.

When you open a Leapfrog Works project, the project is displayed in the state it was in when it was closed.

Keyboard Shortcuts in the Main Window

Use the Tab and Shift+Tab keys to move between the different parts of the main window in the following order:

- Project tree
- Scene toolbar
- Scene window
- Shape list
- Shape properties panel

Key(s)	Action
F8	Maximise scene, minimise project tree and shape list. Press F8 again to restore.
Ctrl+1	Activate the Select tool (\Im)
Ctrl+2	Activate the Draw slicer line tool (Z)
Ctrl+3	Activate the Draw plane line tool ($ otin D$)
Ctrl+4	Activate the Ruler tool (🖉)
Ctrl+\	Split the scene view
F10 or Alt L	Open the Leapfrog Works menu
F11	Open the Seequent ID menu
F1	Open Leapfrog Works help
Ctrl+Q	Quit Leapfrog Works

The Project Tree


The series of folders in the project tree are used to organise objects such as datasets, maps and images into categories. These folders also provide tools that let you import information into the project and generate models. Right-click on each folder to view the actions you can perform using that folder.

This topic provides an introduction to working with the project tree. It is divided into:

- Importing Data
- Data Object Options
- Organising Objects in the Project Tree
- Object Properties
- Comments
- Object Processing
- Project Tree Keyboard Shortcuts

Importing Data


Leapfrog Works has tools for importing, creating and working with many different types of data, and these tools are available by right-clicking on the different folders in the project tree. For example, right-clicking on the **GIS Data, Maps and Photos** folder gives you options for importing vector data and maps, along with options for batch importing GIS data:



Leapfrog Works is unit-less and adopts the units used in the data you import. For example, if your imported data is in metres, the units displayed will be metres, and figures such as resolution, measured distances and slicer thickness will be in metres. It is important, therefore, to be consistent in the units used in the data you import. If you are importing data that uses different coordinate systems, you will need to pre-process the data so that it is using the same coordinate system.

Data Object Options


You can right-click on data objects within the top-level folders to view more information on that object or carry out actions specific to that object. For example, right-clicking on a table of imported borehole data reveals a menu showing possible actions:



When a bold option appears in the right-click menu, as **Open** does in the menu above, that option can also be selected by double-clicking on the object.

You can select more than one object in the project tree by holding down the Shift key or the Ctrl key while clicking. This is useful for viewing or deleting multiple objects at once.


The way folders and objects are organised in the project tree lets you reveal or hide information about an object to focus on objects you are currently working with. This is also useful when you are exploring a project and want to determine how something was put together. The arrows next to objects in the project tree let you reveal or hide an object's details to focus on objects you are currently working with. Here, the **Topographies** folder is expanded to show a **Topography** object that is made up of a mesh:



Also note that:


- The mesh itself is stored in the **Meshes** folder, but is hyperlinked to from wherever it is used in the project.
- The **Borehole Data** folder and the **Boreholes** object have been expanded to show the borehole data tables.
- Folders that have no arrow have no detail stored.

Expanding a data table (IIIII) shows the columns in that table contains, including category data columns (IIIII), numeric data columns (IIIII) and query filters (IIII):



Some tables are marked as having errors (IIII), which are discussed in Identifying Errors in Data Tables.

Expanding a geological model reveals information about how it was built. Here, a geological model has been expanded to show the basic objects that make up a model:




The five objects underneath the geological model "GM" represent the five basic parts of a geological model:

- The **Boundary** object defines the outer limits of the geological model.
- The Fault System object defines faults and their interactions in the geological model.
- The Lithologies object defines the lithologies in the model.
- The **Surface Chronology** object defines the structure of the model's contact surfaces.

• The **Output Volumes** folder contains the generated units (outputs) that make up the geological model.


Here, boundary objects for a geological model have been expanded to show how they were created:



The **Topography** object is included as the model's upper boundary. The "East_boundary" object was created using a polyline from the **Polylines** folder and the "North_boundary" object was created using a GIS data object in the **GIS Data, Maps and Photos** folder. Clicking on the hyperlinks will locate the object from which the extent was created.

Organising Objects in the Project Tree

Leapfrog Works has a number of tools to help you organise the large numbers of objects in a project. One of these tools is the use of display lines in the project tree to better show relationships:



If you wish to display line in the project tree, open the **Settings** window from the **Leapfrog Works** menu. Click on **User Interface** and enable **Show Tree Lines**.

When you have a large number of folders open in the project tree, you can close all folders by rightclicking on the top of the project tree and selecting **Collapse All**:

Project <u>T</u> ree	⊢e Hide project tree	Look y B
 Topographies A Topography 	Detach project tree	
Tekapo DTM		Ctrl+Shift+Left
> 📋 Draped GIS Object	s	


Hotkeys for opening and closing folders include:

- Ctrl + shift + left arrow collapses all folders.
- Right arrow expands a collapsed folder or object but keeps child objects collapsed.
- Shift + right arrow expands a collapsed folder or object and child objects.
- Left arrow collapses an expanded folder or object but keeps child objects expanded.
- Shift + left arrow collapses an expanded folder or object and child objects.

Hotkeys work with more than one object selected.

Subfolders


In many project tree folders, you can create subfolders that help in organising large numbers of data objects. For example, here colour gradients have been organised into subfolders:



To add a subfolder, right-click on a folder in the project tree and select **New Subfolder**. Add objects to subfolders by dragging and dropping them. You can also use **Cut** (Ctrl-X) and **Paste** (Ctrl-V) shortcuts to move objects and subfolders.

Subfolders can be renamed, moved and deleted, but cannot be moved to other top-level folders.

Subfolders have the same right-click commands as their parent folder, which means you can import or create new data objects inside the subfolder rather than in the parent folder. You can also add comments to folders to aid in keeping data organised:



You can view all objects in the subfolder by dragging the folder into the scene or by right-clicking on the subfolder and selecting **View All**.

When lists of objects are displayed, the subfolder organisation will be reflected in the list. For example, when creating an interpolant, the list of data objects that can be interpolated is displayed organised by subfolder:

Wew RBF Interpolant					×
Values To Interpolate		Interpol	lant Boundary		
Numeric values:	👭 RQD	K Cust			
Query Filter	V DBoreho	le Data	M	inimum	Maximum
	V Bor	eholes	st): 115	8938.1 🗘	1165562.1 🗘
Surface Filter	\sim	Lake_Aura_RQD	rth): 488	6405.9 0	4895573.9 🗘
Interpolant <u>B</u> oundary		RQD			1466.0
O <u>t</u> her	V Points	929	-160	5.0 👙	1466.0 🗘
Compositing		acted points		Enc	lose Object 🛛 🗸
Composite in:			m del bou	ndary or volu	ume
Compositing length:		Granodiorite			elect Surface
If residual end length less	than: 0.00	General			
then dis	card	Surfa	ce resolution:	300.0	0 Adaptive
Minimum coverage:	50%	⊖ ⊻olun	nes enclose:	Intervals	~
Additional weighting colun	nn: < <u>None></u>				
Name: RQD 2					
0			Cancel		ок
\bigcirc			Gancel		<u>o</u> k

Subfolders cannot be created in the **Borehole Data** folder, although they can be created in the **Composites** and **Planned Boreholes** folders.

Copying Objects

Many objects in the project tree can be copied. Right-click on an object and select **Copy**. You will be prompted to enter a name for the object's copy.

The copied object is not linked to the original object. However, if the original object is linked to other objects in the project, the copy will also be linked to those objects.

Renaming Objects

When an object is created in Leapfrog Works, it is given a default name. It is a good idea to give objects in Leapfrog Works names that will help you distinguish them from other objects, as large projects with complicated models will contain many objects.

To rename an object in the project tree, right-click on the object and select **Rename**. The **Rename Object** window will be displayed:

🐕 Rename Object		
Danama Ouhfaldar		
Rename Subfolder		
to: Imported points		
<u>C</u> ancel	<u>R</u> ename	

Enter a new name for the object. Click **Rename** to change the object's name.

Finding Objects

To find objects in the project tree, click the search button at the top of the project tree:

Project <u>T</u> ree 0	Q	🔚 Look - 🧞 Ø 🦨 🔲 - 🕞 Ø 🖉 Ø	
✓ ☐ Topographies			
> 🌛 Topography	- 11		
> Draped GIS Objects	- 11	Find	×
V 🗋 GIS Data, Maps and Photos	- 11	in the second se	
🛃 fault	- 11	Find what:	- I
🥰 🗭 GIS line	- 11	Match whole labels only Match case	-
🗸 🐩 ersgrid	- 11		
Au_ppm	- 11	Close Select All Backwards Forwards	
Cu_ppm	- 11		

You can also click anywhere in the project tree and type "Ctrl-F".

In the **Find** window, enter the information you are searching for, then click **Backwards** or **Forwards** to locate the object in the project tree.

Deleting Objects

When you delete an object from the project tree, a window will be displayed listing all other objects in the project that will also be deleted and those that will be reprocessed. Some objects will be put into an error state; you will need to correct those errors before the affected object can be used elsewhere in the project.

Consider carefully the effects on other objects in the project, as once an object is deleted, it cannot be recovered.


Deleting data from the project may cause other objects to be reprocessed, which can take some time.

To delete more than one object from the tree, hold down the Shift key or the Ctrl key while selecting objects.

Sharing Objects

Some objects are created as part of working with other objects and are not available elsewhere in the project. An example of this is a polyline drawn as part of creating a model boundary. To share such objects within the project, right-click on the object in the project tree and click **Share**. The shared object will be copied to the relevant location in the project tree and a hyperlink added to the object it was shared from.

For example, here a polyline created as part of a lateral extent is shared:



The polyline is saved to the **Polylines** folder and a hyperlink to it appears as part of the model's boundary. Whenever the polyline is updated, changes will be made wherever it is shared in the project.

Polylines that have been shared can be unshared. See <u>Sharing and Unsharing Polylines</u> for more information.

Object Properties

You can view the properties of most objects imported into or created in Leapfrog Works. To do this, right-click on the object in the project tree and select **Properties**.

The information available in the **Properties** window depends on the type of object. Tabs may include:

• A **Processing** tab that shows the current status of the processing (queued to process, processing, finished).


- An **Errors** tab that displays errors that have occurred while processing the object. See <u>Object</u> <u>Processing</u>.
- A **General** tab that summarises information about the object. The amount of information in the **General** tab will vary according to the type of object. For example, for table objects, the **General** tab shows the table's data structure.
- A **Statistics** tab that shows statistics for some types of interpolants.
 - For RBF interpolants, see <u>RBF Interpolant Statistics</u>.
 - For multi-domained RBF interpolants, see <u>Sub-Interpolant Statistics</u>.
- A History tab that records information about who created and modified an object and when.

The **History** tab was introduced in Leapfrog Works 2.1. For objects created in earlier versions of Leapfrog Works, the **History** tab will display changes made to the object in version 2.1 and later.

Comments

Another aid to documenting work in a project is comments.

You can record comments on many objects in the project tree, including subfolders. This can be helpful when the project contains many objects and when several different people are working on a model. Objects that have comments are indicated in the project tree by a comment balloon (\bigtriangledown). The comment will be displayed when you right-click on the object:




Tab or click to add a new comment or edit an existing one. You can also add standard information to a comment, such as date and time. If you add a URL to a comment, it will be converted to a clickable link.

You can add information about the project as a whole using the **Notes** object (a), which is the last object in the project tree. Double-click on the **Notes** object to open it and add information. When viewing projects in the **Projects** tab, information in a project's **Notes** will be displayed when you hold the mouse cursor over the project's thumbnail:

${\sim}$ Leapfrog Works		Projects
<u>N</u> ew Project		
Open Project		
RECENT PROJECTS		
Clear Recent Projects		
	015	
Contraction of the second seco	C:\Users\Geologist\Leapfrog Projects\LakeAuraDemo\Lak Demo aproj	ke Aura
Lake Aura Demo	GM with several alignment s sections (Alt+1)	serial Project

Object Processing

Objects that are up-to-date are displayed in the project tree using black text. When an object is being processed, its processing state is indicated in the project tree in either green or grey text. For example, here the Maia Geological Model is being updated:



The four surfaces displayed in green are currently being processed, and the objects displayed in grey are awaiting processing. The **Surface Chronology** and the geological model itself are displayed in grey because one or more of their child objects are being processed or are awaiting processing.

The processing queue shows how many tasks are currently being processed:

🔏 Lake Aura Demo - Leapfrog W	orks		
$\frac{1}{-\sqrt{2}}$ Leapfrog Works		665 🕨	D DD HINKOW
Project <u>T</u> ree		0 (II) Q	🔚 Look - 🧳 🖉 🗗 🔲
> 🗋 Topographies			
> 📄 GIS Data, Maps and Pho	tos		

The button will turn grey when all processing is complete.

Click the button or press Alt + P to view the processing queue:

637 💽 🔽 🏯 Projects	Scene Vie	
Processing	371 of 1008	
0:01:07 371 of 1008 tasks complete	37%	
Run All Priority Or	nly P <u>a</u> use	
n Surface Chronology	Merging volumes	
🌰 Casing	Complete	
ntere Chronology	Building 6 out of 9 volumes	
<i>[</i> 0.75	Seeding[2]: done	
췕 Dike	Waiting	
🍘 GnD	Waiting	
🌰 D1	Waiting	
🌰 D2	Waiting	
🌰 D3	Waiting	
🌰 D4	Waiting	
🌰 D5	Waiting	
🃦 Maia Geological Model	Waiting	
🤗 Boundary	Waiting	
<u>/</u> 1.0	Waiting	
<u>/</u> 1.25	Waiting	
<u>/</u> 1.5	Waiting	
holeid	Waiting	

Objects will be added to the processing queue when you make changes to them via the project tree.

- To pause processing, press Ctrl + P.
- To resume processing, press Ctrl + P again.

You can close a project while it is still running tasks. When you next open the project, the remainder of the tasks in the processing queue will be processed.

Controlling Processing

When a project contains only a small amount of data, all changes can be processed when they are made without interrupting your work. As a project grows larger and more complex, you may wish to use the different processing controls to determine when changes you make to objects are processed. There are two ways to control when objects are processed:

- Prioritising Objects
- Freezing Objects

These tools are described below. Experiment with both of them separately to get an idea of how they work; this will help in determining the approach that best suits your projects as you add more data and models to them.

The project tree may also contain restricted objects:




Restricted objects were created using features only available in extensions. You can display restricted objects in the scene and change how they are displayed, but you cannot make changes to the objects themselves or export them. When changes are made to objects that are inputs to restricted objects, the restricted objects will not be processed. Instead, they will remain in the processing queue marked as "frozen".

Contact Customer Support as described in <u>Getting Support</u> for more information about extensions.

Prioritising Objects


Objects can be prioritised so that they and their inputs are processed before other objects. To prioritise an object, right-click on it the project tree and click the **Prioritise** button (\uparrow). Prioritised objects are marked in the project tree with an arrow:



Prioritising an object is useful when you are editing it and wish to view the effect of changes without reprocessing all objects in the project. For example, you may be modifying a surface that is used for a

model boundary. You can prioritise the surface, then run it each time you make changes; the surface and objects it is dependent on will be processed before any other objects are processed.


To limit processing of other objects further, you can set the processing queue so that only prioritised objects are processed. If your project has a lot of objects that are dependent on the object you are working on, this is useful for limiting the amount of time Leapfrog Works dedicates to processing. To restrict processing in this way, click the processing queue button, then click **Priority Only**:



The processing queue button will change to show that only priority tasks will be run:

	Projects		Scene Vie	w
Processing Provity		15	8 of 158	13 I
0:00:10 158 of 158 tarks complete			100%	
Run All	Priority Only	Pause		

When changes are made to the prioritised object, the only objects processed will be those needed to make the prioritised object valid. For example, here the Intermineral diorite surface has been prioritised. The geological model itself, its surface chronology and its output volumes will not be updated when the prioritised surface is updated:



Objects not needed to validate the prioritised object will remain in the processing queue in **Waiting** and **Queued** states:

¹⁶² 10 &	Projects	Scene View
Processing Priority		12 of 174
0:00:05 12 of 174 tasks comp	olete	7%
<u>R</u> un All	Priority <u>O</u> nly	Pause
Muse Chronology	Waiting	0%
Geological model: Dacite	Queued	0%
🎓 Dacite	Queued	0%
🏹 Surface Chronology	Queued	0%
😝 Boundary	Queued	0%
0.26	Queued	0%
0.52	Queued	0%
1.01	Queued	0%
a 0.52 – 1.01	Queued	0%
a 0.26 – 0.52	Queued	0%
a < 0.26	Queued	0%
a > 1.01	Queued	0%
AU_gpt within dykes	Queued	0%
AU_gpt within dykes	Queued	0%
🇁 Dacite	Queued	0%

The number of objects that have been prioritised is indicated by the button at the top of the project tree (\uparrow):



To view prioritised objects, click the button. All prioritised objects will be selected and displayed in the project tree.

To reset a priority object, right-click on it and click the **Clear Priority** button (**b**).

Click the processing queue button, then click **Run All** to resume normal processing.


Freezing Objects

Objects can also be frozen so that they will not be processed, which is a useful way of working on one object without having all linked objects reprocess upon each change. For example, you may wish to modify a surface in a geological model, in which case you can freeze all objects other than the surface.


You can display frozen objects in the scene, change how they are displayed and export them, but you cannot make changes to the objects themselves.

Some objects become frozen because they are restricted objects created using features only available in extensions. Frozen restricted objects can only be unfrozen if you switch to using the relevant extension.

To freeze an object, right-click on it the project tree and click the **Freeze** button (^(III)). You can also quickly freeze multiple objects by selecting them and then right-clicking on the selection:



Frozen objects are marked in the project tree with a pause button (^(III)). Here, some of the contact surfaces and all of the output volumes have been frozen so that work can be done on the Intermineral diorite surface without processing all other changes to the model:



When a frozen object has unprocessed changes, it will be displayed in the project tree greyed out, which is the case here for the model's output volumes:



The frozen contact surfaces are still displayed in black because changing the Intermineral diorite surface does not change those other surfaces. However, all of the output volumes are displayed using blue text because they have unprocessed changes as a result of the changes made to the Intermineral diorite surface.

The number of objects in a project that have been frozen is indicated by the button at the top of the project tree. To quickly select all frozen objects, click the button. All frozen objects will be selected in the project tree.



To view frozen objects, click the button. All frozen objects will be selected and displayed in the project tree.

Correcting Errors

If processing of an object fails, all other objects dependent on that object will also fail. Open the processing queue to view the errors. To inspect the source of error, right-click on the object in the queue and select **Show Error**:

207 🕨 😪	Projects	Scene View	
Processing		256 of 286	ź
0:03:42 256 of 286 tasks co	omplete	90%	
<u>R</u> un All	Priority Only	Pause	
Treams vertical wall	A Go to Project Tree	e 0%	1
NP WP	Retry Failed Task		
]‡ 100000004	() Show Error	6%	1
]‡ 100000002		52%	
🚫 Face dip	Complete	100%	

The object's **Properties** window will be opened with the **Errors** tab displayed. The information in this tab may be helpful in fixing the error.

Project Tree Keyboard Shortcuts

Keyboard shortcuts for navigating in the project tree are as follows:

Key(s)	Action	
Up and down arrows	Navigate up and down the tree	
Right arrow	Expand folder/object or go down one level	
Left arrow	Close folder/object or go up one level	
Ctrl+shift+left arrow	Close all folders/objects	
Shift+right arrow	Expand the selected folder/object and any objects in it	
Shift+left arrow	Close the selected folder/object and any objects in it	
Ctrl+A and Ctrl+/	Selects all folders and objects	
Ctrl+F	Search for objects	
Enter	The equivalent of double-clicking on an object	
Ctrl-X	Cut an object or subfolder. Use with Ctrl-V to move objects and subfolders.	
Ctrl-V	Paste an object or subfolder	

Some actions are not available until data has been imported into the project.

The 3D Scene


This topic describes how to interact with the 3D scene. It is divided into:

- Locating an Object from the Scene
- Slicing Through the Data
- Measuring in the Scene
- Working With Split Views

How to change the way objects are displayed in the scene is described in a separate topic, <u>Visualising</u> <u>Data</u>.

The best way to navigate the 3D scene in Leapfrog Works is using the mouse. If you are running Leapfrog Works on a laptop, it is recommended that you plug in a mouse rather than using the laptop's touchpad for navigation. However, you can also navigate in the scene using the keyboard.

Action	Mouse	Keyboard
Changing the viewing angle	Click and drag to rotate the scene	Press the arrow keys to rotate the scene For smaller steps, hold down the Shift key while pressing the arrow keys
Zooming in and out of the scene	Use the scroll wheel Hold the right mouse button while moving the mouse	Press the Page Up or Page Down keys For smaller steps, hold down the Shift key while pressing the Page Up or Page Down keys
Panning the scene	Click and hold both mouse buttons, then drag Hold the scroll wheel and drag	Hold down the Alt key while pressing the arrow keys
Centre an object in the scene	Click the scroll wheel Click both mouse buttons together	




Use the **Look** menu above the scene window to switch to different viewing angles:

If you prefer to navigate using the keyboard, use the following keyboard shortcuts:

Key(s)	Action
Arrow keys	Rotate the scene in 10 degree steps
Shift+Arrow keys	Rotate the scene in 2 degree steps
Home	Reset the view, showing all visible objects in scene
U, D, E, W, N, S	Look Up, Down, East, West, North and South
L	Look at the slicing plane
Shift+L	Look at the back of the slicing plane
М	Look at the moving plane
Shift+M	Look at the back of the moving plane
Ctrl+M	Look down the moving plane pitch
Shift+Ctrl+M	Look up the moving plane pitch
Р	Select Perspective view
0	Select Orthographic view
Ctrl+Delete	Clear the scene
Ctrl+B	Bookmark the viewing angle and zoom
В	Display the bookmarked viewing angle and zoom

Key(s)	Action
Ctrl+'	Save the scene
Ctrl+C	Copies the scene to the clipboard. The image can then be pasted into another application, such as an image editor.
Ctrl+/	Add the slicer to the scene. Press Ctrl+/ to remove the slicer from the scene.
Ctrl+;	Add the moving plane to the scene. Press Ctrl+; to remove the moving plane from the scene.

The current viewing angle and scale are displayed in the lower right-hand corner of the scene window:



You can change how the viewing angle and scale are displayed in the **Overlays** tab of the **Settings** window.


You can save the current viewing angle as a bookmark by selecting **Bookmark Viewing Angle** from the **Look** menu or by pressing Ctrl+B. Restore the bookmark by selecting **Look > Restore Bookmark** or by pressing B.

Only one viewing angle bookmark can be saved. The bookmark is not saved when Leapfrog Works is shut down.

The scene window displays a 3D representation of selected data from the project tree. You can add objects from the project tree to the scene in two ways:

- Click on the object and drag it into the scene. Hold down the Shift key or the Ctrl key while clicking to select multiple items, then add them to the scene.
- Right-click on the object and tick the **View Object** box.

Dragging objects into the scene window may be blocked by other applications on your computer. For example, if you are sharing a screen using Skype, you will not be able to drag objects into the scene.



Once you have added objects to the scene window, you can change the appearance of those objects using the controls in the shape list and the shape properties panel.

This is described further in <u>Visualising Data</u>.

Changing how you view objects in the scene window does not change those objects in the project tree.


All objects in the shape list have a button (\times) that will remove the object from the scene. Most objects also have a visibility button (@) that can temporarily hide that object in the scene. It is often easier to make an object temporarily invisible than to remove it from the list. Some objects have an edit button (?) that you can click to begin editing the object.

Locating an Object from the Scene

When you have a number of objects displayed in the scene, it may not be readily apparent where you can find more information about those objects. Leapfrog Works helps you find the object in the project tree and the shape list in two ways, by <u>Clicking in the Scene</u> and by <u>Clicking in the Shape List</u>.

Clicking in the Scene


Clicking on an object in the scene displays a window that contains a summary of the data and, for many objects, a link to the corresponding data in the project tree. For example, here borehole data is displayed in the scene and clicking on a segment displays the corresponding data:



Note that clicking on an object in the scene also selects it in the shape list.

Clicking in the Shape List

When you have objects displayed in the shape list and want to locate them in the project tree, simply right-click on the object in the shape list and select **Go to Project Tree**:




The object's location in the project tree will be expanded and the object will be selected.

Slicing Through the Data

The slicer is a powerful tool for revealing data that is concealed behind other objects and for emphasising data. Slicing can be considered a form of dynamic sectioning.

Two buttons in the toolbar can be used to add the slicer to the scene:



You can add the slicer to the scene by clicking the **Show slicer** button (\mathscr{P}). The slicer will appear in the scene and you can adjust its position using the controls in the shape list:

You can also click the **Draw slicer line** button (\mathbb{Z}), then click and drag in the scene to cut a slice through the scene.


The scene may appear empty because the slicer has removed all visible data. Reposition the slicer or turn it off.

Slicer Properties

You can change the way the slice appears in the scene using the controls in the shape list, and finer controls are available in the shape properties panel:

	₿ Slicer	\times) 🜒 🌒	، کا	ê 🖗			-	Slicer		
0	M_Geology	×	A V	Edit Colours	-		••• A		Slice width:	50.00	Û T
0	┢ RockType: D1	×	è		-	▶ []•	\triangleright		Step size:	20.00	¢ -
0	┢ RockType: D2	\times	è v			▶ []	\triangleright		Dip:	90.0	<u></u>
0	┢ RockType: D3	×	è v		-	▶ []	\triangleright		Dip az.:	270.0	^
0	┢ RockType: D4	\times	è ~			▶ []	\triangleright				~
0	┢ RockType: D5	×	è v			▶ []	\triangleright				
0	┢ RockType: I1	\times	è ~			▶ []•	\triangleright			Set location to	~
0	┢ RockType: I2	×	\			▶ []•	\triangleright		X : 7551.64	17839749125	
									Y: 4463.63	36032993403	0
										1011 100076	· ·
									Z: 453.594	14211499276	

Right-click on the slicer in the shape list to view more information about each option:



The **Lock to Camera** (a) option locks the slice to the current view so that moving the scene changes the direction of the slice.

These options can also be controlled from the **Look** menu:



The **Set location to** list in the shape properties panel contains standard views, together with any sections displayed in the scene:

Ø Slicer			
Slice width:	50.00		ر م
Step size:	20.00		÷ Č
Dip:	90.0		<u></u>
Dip az.:	270.0		0
	Set lo	cation to	N Y
🂓 East ()	() Axis		- KS
North			
	(Y) Axis		
	(Y) Axis	3	0
	(Y) Axis on (Z) Axis	3	ÿ
		3	

To move the slicing plane in a direction orthogonal to the slicing plane, hold down the Ctrl key and the right mouse button while dragging the mouse.


To change the thickness of a thick slice, hold down the Ctrl key and the middle mouse button while dragging the mouse. If you have a two-button mouse, hold both buttons.

Object Slice Mode

When you draw a slice in the scene, how objects in the scene are displayed in relation to the slicer is controlled in the properties panel for that object. For example, here the M_Geology table is selected in order to change how the boreholes are displayed in relation to the slicer:

M_Geology	
Slice mode:	Unsliced
Query filter:	From Scene
Filter trace	Unsliced
	Thick Slice
Line radius:	Remove Front
	Remove Back

The From Scene setting is the default; the object is sliced according to the properties set for the slicer.



By changing the **Slice mode** for objects in the scene, you can illustrate how a model has been constructed:

Slicer Shortcuts

Use the following keyboard shortcuts to control the slicer:

Key(s)	Action
Ctrl+/	Add the slicer to the scene. Press Ctrl+/ to remove the slicer from the scene.
L	Look at the slicing plane
Shift+L	Look at the back of the slicing plane
Т	Thick slice (🔎)
F	Remove front ()
К	Remove back (簲)
Ctrl+V	Orient the slicer to the current view
Ctrl+E	Slice the east (X) axis (🔊)
Ctrl+N	Slice the north (Y) axis ()
Ctrl+D	Slice the elevation (Z) axis (♥)

Key(s)	Action
Ctrl+L	Lock the slicer to the camera (🖻)
С	Centre the slicer in the scene (1967)
Ctrl+right mouse button	Move the slicer forward and backward in the scene
Ctrl+middle (or left+right) mouse button	Change the slice width
, (comma)	Step the slicer forward
. (full stop)	Step the slicer backward


Measuring in the Scene

Leapfrog Works has a number of tools for making quantitative measurements in the scene. These include:

- Clicking on an object in the scene. This will open a window containing more information about the object.
- Viewing an object's properties to determine its size. Right-click on the object in the project tree and select **Properties**. Information on the size of the object will be displayed in the **General** tab.
- Using the cursor to determine an approximate location in the scene. See <u>Determining a Location</u>.
- Using the moving plane to measure trends. See <u>The Moving Plane</u>.
- Using the ruler to measure in the scene. See <u>The Ruler</u>.


Determining a Location

The simplest way of measuring an approximate location in the scene is to first display an object in the scene window, then position the cursor over the location. The position of the cursor is displayed at the bottom of the Leapfrog Works window:




The position of the cursor in the scene is calculated using the depth buffer on the graphics card and so is not an exact method of measuring in the scene.

If you require an exact position, click on the object. Leapfrog Works will compute the exact position of the point highlighted in the scene and display it in a pop-up window:



The Moving Plane

In Leapfrog Works, the moving plane is used for measuring planar structures and defining coordinate system orientations. There are two tools in the toolbar that relate to the moving plane:



To use the moving plane, click the **Show plane** button (\mathcal{P}) and position the plane in the scene. The main axis of the moving plane is defined by the green line. The second axis is defined to be in the plane at right angles (orthogonal) to the main axis. Third axis is perpendicular to the plane.

There are three ways to position the plane. You can:

- Use the handles in the scene window to move the plane. If you cannot see the handles, click on the moving plane.
- Use the **Plane** controls in the shape properties panel to change the **Dip**, **Dip Azimuth**, **Pitch** and **Centre Point**.
- Orient the scene to look parallel to the required plane position, then click on the Draw plane line button (2). Draw the required line in the scene.

Plane movement can be aligned to the Axes or to the Camera:

- With the Axes option, the handles move in cartesian coordinates. .
- With the **Camera** option, the handles move relative to the camera angle.

Drawing the plane line is usually the most convenient method of defining a planar structure.

To remove the moving plane from the scene:

- Click the **Show plane** button (\mathcal{Q}) .
- In the shape list, click the delete button (\times) for the moving plane.


Use the following keyboard shortcuts to control the moving plane:

Key(s)	Action
Ctrl+;	Add the moving plane to the scene. Press Ctrl+; to remove the moving plane from the scene.
М	Look at the moving plane
Shift+M	Look at the back of the moving plane
Ctrl+M	Look down the moving plane pitch
Shift+Ctrl+M	Look up the moving plane pitch

The Ruler

You can use the ruler to measure distances in three dimensional space and between boreholes and planned boreholes.

The easiest way to use the ruler is to click on the **Ruler** button (\checkmark) and click and drag between points in the scene to start making measurements. A ruler line will appear in the scene to indicate the measurement. Information about the distance measured will appear in the scene and in the shape properties panel:



The ruler tool stays active in the scene so you can make as many measurements as required.

You can also measure the distance between boreholes or between boreholes and a point. To do this, click on the **Calculate Distance** button in the shape properties panel. The **Distance Calculator** window will appear:

						MRV121	MRV122	■MRV123		MRV12
					7	233.73 642.67 77.90 03.10°/179.22°				
				MRV112	MAR	MRV113 009	MRV114	MRV115	MRV116	MRV1:
Distance Calculator	-	-	-	-	×	MRV102	■MRV103	■MRV104	MRV105	MRV1
Show shortest distance between	- and an									
⊖ this <u>o</u> bject:	collar									
this <u>h</u> ole:	MRV114						EMDV/25	EMDV04	= MI	
⊖ this point:	0	, 0	, 0		5		4235.05(+1.3 7545.91(-96.7 472.66 (-5.24	2) ^{- MRV94} 75)	Looking down	
and						0	= 96.90 50		100	150
○ this object:	M_Assays					= M005	50		100	150
this hole:	MRV25					🖉 Ruler				
this point Distance: 96.90	0	, 0	0		\square	Distance:	96.90	Start:	7	233.73 642.67 477.90
						Plunge:	3.10	End:	7	235.05 545.91 472.66
						Plunge-Az:	179.22	Differen	ce:	1.32
						Calculate D	Distance			-96.75 -5.24
?			<u>Z</u> oom	<u>C</u> alcula	ate					

You can select both boreholes and planned boreholes. Click **Calculate** to calculate the distance and update the ruler in the scene. The distance value will appear in the **Distance Calculator** window.

You can also select a point in the scene by clicking the **Select** button (\mathbb{D}) in the **Distance Calculator** window, then clicking in the scene. The location of the point in the scene will appear in the **Distance Calculator** window.

After measuring a distance, it is a good idea to change the viewing angle to confirm that the measurement has been made between the correct points in three dimensions.

There are two ways to remove the ruler from the scene:


- Click the **Select** button (\mathbb{D}).
- Click the delete button ($^{\times}$) for the ruler object in the shape list.

Working With Split Views

The **Split View** button (**I**) in the toolbar allows you to view up to two alternative views of the objects displayed in the scene:

Projects	Scene View
	Split Into <u>T</u> wo Vertically
	Split Into Three Vertically
	Split Into Two Horizontally
	Split Into Three Horizontally
	New Split View Tab

The alternative views available are a **Plan View** or a **Zoomed Out** view:




You can also open an alternative view in a new tab by choosing the **New Split View Tab** option:

\searrow	8 Projects	Scene View	C Central Projects
	Look 🗸 🧳	8 5 💽 🗟 2 8 1	
		Split Into Two Vertically	
		Split Into Two Horizontally	
		Split Into Three Horizontally	Alter Alter
	1 m	New Split View Tab	

You can resize the scene and the alternative views and Leapfrog Works will remember the position of each view when you switch to that split view again.


To return to displaying only the scene view, click the **Split View** button (\square) .

Each alternative view has a toolbar that gives you different options for displaying the view. Use the **Enclose Object** list to zoom into or out of the alternative view:




The list displayed includes all objects available in the project, plus the clipping boundary and the current scene view.

Click the **Visibility** button to change what objects from the scene view are visible in the alternative view:




An object must be visible in the scene view's shape list for its visibility to be controllable from the alternative view's **Edit Visibility** list. What this means is that objects hidden in the scene view cannot be made visible in an alternative view.


When the slicer is in the main scene view, you can display the contents of the alternative view sliced or unsliced. Click the **View Unsliced** button (\times). The slicer, shown in blue in this image, remains displayed in the alternative views, but the view's contents are displayed unsliced:



In alternative views, you can display a view window that shows what part of the alternative view is displayed in the scene view. Click the **Enable View Window** button ((E)):



Each alternative view has a **Settings** button (\gtrsim) that lets you change what overlays are displayed for that view. The alternative view can use the scene view settings, or you can customise the display of the screen grid, axis lines and scale bar:



Visualising Data

Visualising data is an important part of interpreting and refining data and making modelling decisions. This topic describes the tools available for changing how data objects are displayed in the scene. It is divided into:

- <u>Colour Options</u>
- Opacity
- Property Buttons
- Legends
- Slice Mode
- Filtering Data Using Queries
- Filtering Data Using Values and Categories

Tools for visualising data are accessed via the shape list and the shape properties panel:



The tools available depend on the type of object being displayed.

Changing how you view objects in the scene window does not change those objects in the project tree.

The view list is available for objects that can be displayed in different ways. For example, a lithology data table may contain several columns and the column displayed can be selected from the view list:

	Slicer		\times	۱ کې کې کې کې	۵ 🛞 🕲	÷₿€			WP_lith	
0	WP_lith	Ø	×	🐘 Spli 📐 Edi	Colours			HI A	Slice mode:	Unsliced ~
0	췕 Wolf PasBasement		×	کر Flat colour			▶ []	\triangleright	Query filter:	No Filter 🗸
0	췕 Wolf Pass GM: Dacite		×	🎎 grouped_lith			▶ []	\triangleright	Filter trace	lines
0	췕 Wolf Passly Diorite		×	NOCK			▶ []	\triangleright	Line radius:	10.00 🗘
0	췕 Wolf Passal Diorite		×	🦺 Split_Dykes			▶ []	\triangleright		
Ø	췕 Wolf Pass GM: Recent		×	X 100				\triangleright		Format Display Text

Geological and numeric model evaluations are also selected from the view list. See Evaluations.

The shape properties panel adjacent to the shape list provides more detailed control of the appearance of the selected object:

	Slicer		\times	🔎 🜒 🗑 😂 🌒 🛞 😸 😭) <i>→5</i> €		WP_lith
0	WP_lith	O	\times	A Spli V Edit Colours	•	10 HI A 🗄	Slice mode: Unsliced ~
0	I Wolf PasBasement		\times	췆 Lith 🗸 📕	•	▶ △• ▷ 🗄	Query filter: No Filter ~
0	┢ Wolf Pass GM: Dacite		\times	À Lith 🗸 📕	-•	▶ []• ▷ 🗄	Filter trace lines
0	IVOIF Pass Iy Diorite		\times	À Lith 🗸 📕	-•	► [I• ▷ 🗄	Line radius: 10.00
0	衡 Wolf Passal Diorite		\times	🖕 Lith 🗸 📕	-•	► [I• ▷ 🗄	
Ø	🌰 Wolf Pass GM: Recent		×	À Lith 🗸 🔳		► [I• ▷ 🗄	Format Display Text


You can select multiple objects in the shape list and change their display properties using the shape properties panel. To do this, hold down the Shift or Ctrl key while clicking each object you wish to change:

	Slicer		\times	، چ پ پ چ 📦 🌒	i 🕅		📄 3 shapes
0	WP_lith	Ø	×	🗛 Spli 🗸 Edit Colours	-•	🔟 👫 🗄	Slice mode: From Scene ~
\odot	I Wolf PasBasement		\times	🖕 Lith 🗸 📃		► []• ▷ 📰	L
0	b Wolf Pass GM: Dacite		\times	À Lith 🗸 📕	-•	I I	
0	IVOIF Pass Iy Diorite		\times	À Lith 🗸 📕		► []• ▷ 🗄	1
0	b Wolf Passal Diorite		\times	🖕 Lith 🗸 📕	•	► [I• ▷ 📰	
Ø	b Wolf Pass GM: Recent		\times	À Lith 🗸 🔳		► [I• ▷ 📰	

Only controls common to the selected objects are available.

Colour Options

The colour options for an object are changed in the shape list, and the options available depend on the type of object. Three different colour display options are shown below:




- The collar table is displayed using a single colour. Click the colour chip to change the colour. See <u>Single Colour Display</u>.
- The Geology table is displayed according to a colourmap of the categories in the table. These colours can be changed by clicking on the **Edit Colours** button, then clicking on each colour chip in the **Legend** window. See <u>Category Colourmaps</u>.
- The Contaminant table uses a colourmap to display the numeric data. Numeric data coloumaps are automatically generated based on the data, and manually changing a colourmap can often help in understanding the data. See <u>Numeric Colourmaps</u>.

If your organisation uses standard colour coding for category and numeric data, you can import colourmaps for these data types. See <u>Importing and Exporting Colourmaps</u>.

Single Colour Display

Many objects viewed in the scene are displayed using a single colour. To change the colour, add the object to the scene window, then click on the colour chip in the shape list. A window will appear in which you can change the colour:








You can:

- Click and drag the crosshair to pick a colour, then select the darkness or lightness of the colour from the triangle (2 and 3).
- Click on the **Pick Colour** button, then click on something elsewhere on the screen to select the colour of that part of the screen.
- Select a colour chip from the palette.
- Click on the **Random** button to set a random colour.
- Enter specific values for the colour to use.

Changes made are automatically applied to the scene. The **Revert** button changes back to the colour assigned when the window was first opened.

Category Colourmaps

Category data colourmaps can be edited by adding the data column to the scene, then clicking on the **Edit Colours** button in the shape list:



To change the colour used for a category, click on its colour chip in the **Legend** window.


Category colourmaps can also be imported and exported, as described in <u>Importing and Exporting</u> <u>Colourmaps</u> above.

Numeric Colourmaps

There are two types of colourmap used for displaying numeric data:

- Continuous Colourmaps
- Discrete Colourmaps

To edit the colourmap for an object, add the object to the scene. Click on the colourmap in the shape list and click the pencil (\mathcal{O}).



An **Edit Colourmap** window will display the colourmap that is currently being used to display the data; this window will be different for continuous and discrete colourmaps. Any changes you make in the **Edit Colourmap** window will be reflected in the scene. To save the currently displayed colourmap, click **Close**.

To create a new colourmap, click on a colourmap in the shape list and select **New Colourmap**. In the window that appears, select whether you wish to create a continuous colourmap or a discrete colourmap:

						🖉 New Colourmap 🛛 🗙 🗙
0	Contaminant	×	Contami 🗸	Contaminant 🗸 💶	🔟 🎋 🗰 A 🗄	
Ø	Geology	×	🙀 Lithology 🗸 🗸	Contaminant 🔗 💶		What type of colourmap do you want to create?
0	collar	×	À Flat colour 🗸	New Colourmap	A	Continuous Create a new colourmap using a gradient whose colours are stretched across a range of values.
						Discrete Create a new colourmap with discrete intervals. Specify the number of intervals to use to colour your data, define the boundaries of those intervals and select the colours to use.


Leapfrog Works contains a number of preset colour gradients that are used in displaying both continuous and discrete numeric colourmaps. These are:

- **Rainbow (bgyr)**. This is a perceptually uniform rainbow.
- **Rainbow (bgyrm)**. This is similar to Rainbow (bgyr), but follows red with magenta, which is common in geophysics software and RQD (geotech).
- Viridis. This is a good linear gradient.
- Plasma. This is the default colourmap for face dip.
- Linear (gow). This gradient is useful for elevation data.
- **Diverging (bwr)**. This colourmap can be used when you are interested in data at either end of the spectrum.
- **Spectral**. With this colourmap, the middle is not white, and white is reserved for bins that have no data.
- **Cyclic (mygbm)**. This is a good colourmap for azimuth data. Northern directions are displayed in blue and southern in yellow.
- Grey (10-95). This grey colourmap works well on white and black backgrounds as it doesn't start or end in white or black.


Additional colour gradients can be imported into a project. See Importing Colour Gradients.

Continuous Colourmaps

A continuous colourmap uses a gradient whose colours are stretched across a range of values. In the **Edit Colourmap** window, the **Gradient** list includes all inbuilt gradients and any that have been imported into the **Colour Gradients** folder.



Click the **Generate Curve** button to change the **Curve mode** used and the **Number of lines** on the histogram:



You can limit the range of values used back in the **Edit Colourmap** window by disabling **Dynamic** and then setting the minimum and maximum values.


The curve modes all stretch the colourmap so that each line groups the histogram bars by colour. The available curve modes are:

- **Quantile**. The sum of the histogram bars between each pair of lines is equal.
- **Progressive**. The sum of the histogram bars between each pair of lines is progressively smaller, covering a smaller percentage of values towards the end of the curve.
- **Progressive Double**. This is similar to **Progressive**, but the effect is emphasised by increasing the percentage difference between lines.
- **Logarithmic Intervals**. This stretches the colours using a logarithmic transform, which may be preferred for data with a wide range of values.


Experiment with the different settings and click **Apply** to see the effects of changes. To edit the curve points on the histogram, close the **Generate Curve** window:

🔏 Edit Colo	urmap				×
<u>G</u> radient		v (bgyr)	~	Options ~ Histogram	
	ert grad		<u> </u>		
Limits	ertyrau	lient		- 20	
<mark>. ⊡</mark> yr	namic			T.	
Minim		0.02		- 15	
M <u>a</u> xin	num:	2.0		- 15 (%) 10 10 10 Lie 10 L	
		Set limits from data		- 10 be	
	G <u>e</u>	enerate Curve		-5	
Name				025 0.5 0.75 1 1.25 1.5 1.75 2	
	ontinuo	us		025 0.5 0.75 1 1.25 1.5 1.75 2 M_Assays: Au	
?				Revert <u>C</u> lose	

Note that if you use more than 10 lines in generating the curve, you will not be able to edit the curve points on the histogram:



You can change the **Bin Width** in the **Options** menu:



Enable **Histogram of the Log** to see the value distribution with a log scale X-axis. You can also view a **Cumulative** distribution function for the values, with or without a log scale X-axis.

If the numeric data column for which the colourmap is defined has been produced from other data sources in the project, you will be able to select whether to display the **Local Values** or the values from the **Parent Data**. For example, for a numeric data column that is part of a merged table, you can display the values from only the merged table or from the parent table:

Gradient Rainbow (Invert gradie Limits		Options					
✓ Dynamic							
Minimum: Maximum: Curve Points Lower: Upper:	0.02 () 2.0 () Set limits from data	Change plotted values M_Assays: Au Local Values Merged_Table_1: Au - 5					
Gene Name	erate Curve	0.25 0.5 0.75 1 1.25 1.5 1.75 2 M_Assays: Au					

If the **Dynamic** option is enabled, the gradient will be updated when the data is updated, such as when borehole data is appended. If the option is disabled, the values manually set for the **Minimum** and **Maximum** limits will control the lower and upper bounds of the colourmap. Reducing the range of the upper and lower bounds is useful if the bulk of the data points have values in a range much smaller than the overall range of the data. This is common in skewed data.

The **Set limits from data** button automatically adjusts the **Minimum** and **Maximum Limit** values so that the colourmap would follow the actual data distribution of the input data. The values that lie outside the **Limits** are coloured with the last colour at the relevant end of the colourmap.


Both continuous and discrete colourmaps can be used to display date information. If a date is displayed using a continuous colourmap, the curve points represent the start and end dates:




When you click **Revert**, all changes you have made in the window are discarded.

Discrete Colourmaps

With a discrete colourmap, you can define intervals and select which colours are used to display each interval:





Click the Generate Intervals button to generate intervals based on various statistical methods:

Select an Interval Mode. The options are:

- **Quantile**. This attempts to create the specified number of intervals so that each interval contains the same number of values.
- **Progressive**. This attempts to create intervals that enclose progressively smaller percentages of values. For example, 1000 unique values organised into 5 intervals would have the following percentiles: ~33%, ~27%, ~20%, ~13%, ~6%.
- **Progressive Double**. This is similar to **Progressive**, but is "steeper". For example, 1000 values organised into 5 intervals would have the following percentiles: ~50%, ~25%, ~12.5%, ~6.25%, ~3%.
- Equal Intervals. This creates intervals at equal spacing across the range of the values.
- Logarithmic Intervals. This creates intervals at equal spacing, in log-space, across the range of values.
- **K Means Clustering**. This is an iterative algorithm that sorts values into clusters in which each value belongs to the cluster with the nearest mean. This option can take some time, especially with large datasets and a large number of intervals.

Set the **Number of Intervals** and the **Colour Gradient** to be used as the basis for the interval colourings. The first interval is assigned the first colour of the selected **Colour Gradient** and the last interval is assigned the gradient's last colour; selecting **Invert Gradient** swaps this around.

how	Min		Colour		Max	Data	Options
~	inf	<		≤	0.17	17.24%	Histogram of the Log
~	0.17	<		≤	0.34	17.08%	Cumulative - 70
~	0.34	<		≤	0.51	16.12%	Bin Width 1.0 - 60
~	0.51	<		≤	0.78	16.62%	- 50
~	0.78	<		≤	1.31	16.29%	- 30 - 40 - 30
~	1.31	<		≤	inf	16.66%	
	.imits					Generate Intervals	- 20 - 10
2.5	Ŷ	× 10)-3 - 4	3.6	Ŷ	Set limits from data	0
me AU_q	pt discre	te					10 20 30 40 WP_assay: AU_gpt

You can change the **Bin Width** in the **Options** menu:

Enable **Histogram of the Log** to see the value distribution with a log scale X-axis. You can also view a **Cumulative** distribution function for the values, with or without a log scale X-axis.


If the numeric data column for which the colourmap is defined has been produced from other data sources in the project, you will be able to select whether to display the **Local Values** or the values from the **Parent Data**. For example, for a numeric data column that is part of a merged table, you can display the values from only the merged table or from the parent table:

Show	Min		Colour		Max	Data	Options 🗸
V	inf	<		≤	0.17	17.24%	Histogram of the Log
\checkmark	0.17	<		≤	0.34	17.08%	Cumulative
\checkmark	0.34	<		≤	0.51	16.12%	Bin Width 1.0
~	0.51	<		≤	0.78	16.62%	Change plotted values
~	0.78	<		≤	1.31	16.29%	WP_assay: AU_gpt
~	1.31	<		<	inf	16.66%	LOCAL VALUES
+) -Axis I	 Limits					Generate Intervals	- 20
2.5	0	× 1	0-3 - 4	3.6	0	Set limits from data	
ame							10 20 30 40
	pt discre	te					WP_assay: AU_gpt

The **Set limits from data** button automatically adjusts the **X-Axis Limits** so that the colourmap would follow the actual data distribution of the input data.

Experiment with the different settings and click **Apply** to see the effects of changes.

You can also add intervals manually by clicking the **Add** button. For example, if you create a discrete colourmap to show the different stages of a drilling campaign, the initial colourmap contains only two intervals:



Click the **Add** button to add new intervals and use the **Min** and **Max** entries in the table to set the start and end points of each interval:



When you click **Revert**, all changes you have made in the window are discarded.

Importing Colour Gradients

Additional colour gradients can be imported into a project in the following formats:

- Geosoft Colour Files (*.tbl)
- ERMapper Lookup Tables (*.lut)
- MapInfo Colour Files (*.clr)
- Leapfrog Colour Files (*.lfc)

Perceptually uniform colourmaps are available at http://peterkovesi.com/projects/colourmaps/, where they can be downloaded in ERMapper (*.lut), Geosoft (*.tbl) and Golden Software Surfer (*.clr) format.


Colourmaps used in earlier versions of Leapfrog Works can be downloaded from http://downloads.leapfrog3d.com/Colourmaps/older_leapfrog_gradients.zip.

Matplotlib colour gradients can be downloaded from

http://downloads.leapfrog3d.com/Colourmaps/matplotlib_colour_gradients.zip.

Imported colour gradients are stored in the project tree in the **Colour Gradients** folder. To import a colour gradient right-click on the **Colour Gradients** folder and select **Import Gradient**. In the window

that appears, navigate to the folder containing the gradient file and click **Open**. The gradient will be added to the **Colour Gradients** folder and you can then select it from the **Gradients** list when editing a colourmap:




If you delete a colour gradient from the **Colour Gradients** folder and it is in use in the project, you will need to select a replacement gradient for all colourmaps that use that gradient. Select the replacement colour gradient from those available in the project:

🖉 Confirm Delete		×
Confirm Delete Delete the following objects? Objects to delete		
Colour Gradients	Objects to reprocess	
Replace in-use colour gradients with:	Rainbow (bgyr)	∨ Delete

Importing and Exporting Colourmaps

Colourmaps can easily be shared between projects on a column-by-column basis, which is useful if your organisation uses standard colourmaps. To import or export a colourmap, expand the data object in the project tree and right-click on a column. The **Import** and **Export** options are available from the **Colours** menu:



To export a colourmap, right-click on the data object and select **Colours > Export**. If more than one colourmap is associated with the selected object, you will be prompted to choose from those available. Click **Export**.

In the window that appears, navigate to the folder where you wish to save the colourmap. Enter a filename and click **Save**. The colourmap will be saved in *. If c format.

When you import a colourmap:

- For category colourmaps, the existing colourmap will be overwritten.
- For numeric colourmaps, the imported colourmap will be added to those already defined.

To import a colourmap, right-click on the data object and select **Colours > Import**. Navigate to the folder containing the colourmap file and click **Open**.

If the object has more than one colourmap associated with it, you will be prompted to choose which one to overwrite.


If the column you expected is not listed, check to see if you have selected the correct file. The columns displayed are those that correspond to the type of data in the selected file (category or numeric).

Click Import.

Leapfrog Works will map the information in the file to the information in the selected data column.

Opacity

The opacity slider in the shape list controls the transparency of objects in the scene:



Property Buttons

The property buttons available in the shape list vary according to the type of object selected. For example, property buttons can show or hide the triangles on a mesh, render points as spheres or display a surface clipped to a model boundary. You can always find out what a button does by holding the cursor over the button:

Ø	M_Assays		\times	Au	\sim	Au continuous 🗸	•	🔟 🔆 🙌 🗛 📰 📗 🛞 D2 - D1 contacts
0	M_Geology	Ø	\times	K GroupedR	\sim	Edit Colours	•	🔟 🗰 👗 Slice mode: From Scene 🗸
0	collar		\times	Completed	\sim	Date Comple 🗸	•	I 🔆 🔺 📃
0	RockType: D2 - D1 contacts		\times	🛶 Lithology	\sim		•	
0	RockType: D3 - D2 contacts		×	À Lithology	\sim		•	Show clipped surface
0	RockType: D4 - D3 contacts		\times	À Lithology	\sim		•	
٢	RockType: D5 - D4 contacts		×	À Lithology	\sim		•	

Legends


You can display a legend for many objects, including lithologies. To do this, click the legend button in the shape list:

												-
Ø	M_Assays		\times	Au	\sim	Au continuous 🗸	•	🔟 🎋 배 🗛		M Geology		
0	M_Geology	Ø	×	K GroupedR	\sim	Edit Colours	•			Slice mode:	Unsliced ~	·
0	Collar		×	Completed	\sim	Date Comple 🗸	•	🔟 🎋 🛛 🗛	Show	legend in scene	No Filter 🗸	7
0	RockType: D2 - D1 contacts		\times	췆 Lithology	\sim		•	▶ []• ▷ 🤘		Filter trace	lines	
0	RockType: D3 - D2 contacts		×	췆 Lithology	\sim		•	▶ []• ▷ 💞		Line radius:	8.00	
0	RockType: D4 - D3 contacts		×	Lithology	\sim		•	▶ 🕩 ⊳ 🖑			Format Director Taut	
0	RockType: D5 - D4 contacts		×	🛶 Lithology	\sim		•	► []• ► 🖋			Format Display Text	

To remove the legend from the scene, either click the legend button again or click the red X in the scene window:



To reorder the legend, click the **Edit Colours** button in the shape list to open the **Legend** window. Click on an item in the list, then use the arrows to move it up or down. The legend shown in the scene will be updated when you close the **Legend** window.



Slice Mode

When an object is selected in the shape list, a **Slice mode** property is available in the properties panel. See <u>Object Slice Mode</u> for more information.

Filtering Data Using Queries

When a data table is selected in the shape list, you can use the controls in the shape properties panel to apply filters to the data in the scene. If query filters are available for the selected object, they will be listed in the **Query filter** list:

M_Geology	
Slice mode:	From Scene V
Query filter:	No Filter
Filter trace	No Filter
Line radius:	🖓 collar: Campaign 1
	🖓 collar: Campaign 2
	🖓 collar: Campaign 3
	🖓 collar: Campaigns 1 and 2

Filtering Data Using Values and Categories

In the shape properties panel, you can also filter the range of values displayed. Tick the **Value filter** box, then set the upper and lower limits of the range of data displayed:

°•́← 🕴	I A	M_Assays		
ψ.	I A	Slice mode:	From Scene	\sim
° ←	Α	Query filter:	No Filter	\sim
		 Filter trace 	lines	
-		Value filter:	0.02	$\hat{\mathbf{v}}$
		Line radius:	10.00	$\hat{}$
		Radius values:	Fixed Radius	Δ
			Format Display Text	

If the data includes date information, you can use the **Value filter** option to restrict the display to a range of dates.

Working With Data Tables

This topic describes how to work with data tables in Leapfrog Works. It is divided into:

- Importing Data Tables and Mapping Data Columns
- Data Tables in the Project Tree
- Viewing Table Data
- Adding and Updating Data for Existing Tables

Importing Data Tables and Mapping Data Columns

Importing data tables into Leapfrog Works involves selecting the files to import and then mapping the data columns in the files to the format Leapfrog Works expects. The data columns Leapfrog Works expects differs for different data types, and you can find more information about the expected format in the help for each data type. See:

- Importing Borehole Data
- Importing Points Data
- Geophysical Data
- Importing Planar Structural Data
- Importing Lineations

Once you have selected the file or files to be imported, Leapfrog Works prompts you to map the columns in the file to the expected format. For example, here we are importing a set of points. **File Data** shows a snapshot of the data in the file. The **Column Summary** shows what columns are in the file and how Leapfrog Works will map these columns, unless you make changes in this window.

e Dat					-	Column Summary			
	East (X) 🛛 🗸	North (Y) 🗸 🗸	Elev (Z) 🛛 🗸	Not Imported $$	Not Imported V	Column	Column type	Import Name	
	х	Y	Z	AG_gpt	CU_pct	Х	East (X)	✓ East (X)	
2	444245.368	492164.187	2596.092915	0.0016645	0.00061655	Υ	North (Y)	✓ North (Y)	
3	444245.368	492364.187	2496.23881289	0.0021691	0.00071943	Z	Elev (Z)	✓ Elev (Z)	
ŧ.	444245.368	492564.187	2607.67565575	0.0028482	0.00094787	AG_gpt	Not Imported	~	
5	444245.368	492764.187	2703.15698387	0.003755	0.0012668	CU_pct	Not Imported	~	
ò	444245.368	492964.187	2760.98140938	0.0049519	0.0016963				
7	444245.368	493164.187	2808.66389914	0.0065045	0.0023143				
3	444245.368	493364.187	2860.99008804	0.0084448	0.0032584				
•	444245.368	493564.187	2901.99451172	0.010613	0.0046964				
0	444245.368	493764.187	2898.58065869	0.012359	0.0067481	Nama	a a il a rid		
1	444245.368	493964.187	2946.49095108	0.012721	0.01038	Na <u>m</u> e:	soil_grid		
2	444245.368	494164.187	3006.50120165	0.011534	0.01535	Character encoding:	Auto (Windows-1	252)	
3	444245.368	494364.187	3090.26949836	0.009425	0.018279		hlana		
4	444245.368	494564.187	3148.3967538	0.0071158	0.018184	Unique row ID:	None		
5	444245.368	494764.187	3202.70217585	0.0051351	0.01685	Select header row:	1		
6	44445.368	492164.187	2540.9603122	0.002015	0.00080477		Impo	ort All Columns	
7	44445.368	492364.187	2527.35414194	0.0027251	0.0010039				
8	44445.368	492564.187	2603.70182796	0.0037383	0.0013453	> Date and time for	mats		
9	444445.368	492764.187	2653.20530777	0.0051865	0.0018221	> CSV characters			

The fields below the **Column Summary** allow you to change settings such as the character encoding and date and time formats.

The dark header row shows how each column will be mapped in Leapfrog Works and the row labelled one is the first row in the file.

Impor	t Points - soil_gr	id									
File Dat	а										Column Summary
	East (X)	~	North (Y)	~	Elev (Z)		Not Imported	Not Imported	-		Column
1	Х		Y		Z		AG_gpt	CU_pct		Ľ	X
2	444245.368		492164.187		2596.09291	5	0.0016645	0.00061655			Y
3	444245.368		492364.187		2496.23881	289	0.0021691	0.00071943			Z
4	444245.368		492564.187		2607.67565	575	0.0028482	0.00094787			AG_gpt

For this file, columns X, Y and Z in the file have been mapped in Leapfrog Works to columns **East (X)**, **North (Y)** and **Elev (Z)**. These are shown in green.

The AG_gpt and Cu_pct columns are currently marked as **Not Imported**.

Each type of table being imported will have different column assignments available, but all table types will display:

- The categories columns can be assigned to (top of the list)
- The option to not import the column
- The required columns, which in this example are East (X), North (Y) and Elev (Z)
- Any optional columns, which in this example is the Hole ID column
- The option to select a custom name

You can see the options available for importing columns by clicking on the column header. Here the AG_ gpt column will be set to be a numeric data column:

	East (X) 🗸 🗸	North (Y)	~	Elev (Z) V	Not Imported V	Not Ir	nported	~ I	Column	Column type	Import Name	
	X	Y		Z.			it	11	X	East (X)	 East (X) 	
	444245.368	492164.187		2596.092915	"AG_gpt" Lithol		61655		Y	North (Y)	 North (Y) 	
	444245.368	492364.187		2496.23881289	"AG_gpt" <u>C</u> ateg	lory	71943		Z	Elev (Z)	 Elev (Z) 	
	444245.368	492564.187		2607.67565575	"AG_gpt" <u>T</u> ext		94787					
	444245.368	492764.187		2703.15698387	"AG_gpt" <u>N</u> ume	eric 📐	2668		AG_gpt	Not Imported		
	444245.368	492964.187		2760.98140938	"AG_gpt" Time	Stamp	6963		CU_pct	Not Imported	~	
	444245.368	493164.187		2808.66389914	"AG_gpt" Date		3143					
	444245.368	493364.187		2860.99008804	"AG_gpt" URL		2584					
	444245.368	493564.187		2901.99451172	Net Imported		6964					
0	444245.368	493764.187		2898.58065869	Not Imported		7481					
1	444245.368	493964.187		2946.49095108	East (X)		38		Na <u>m</u> e:	soil_grid		
2	444245.368	494164.187		3006.50120165	North (Y)		35				0.50)	
3	444245.368	494364.187		3090.26949836	Elev (Z)		279		Character encoding:	Auto (Windows-1	252)	
4	444245.368	494564.187		3148.3967538			184		Unique row ID:	None		
5	444245.368	494764.187		3202.70217585	Hole ID		85		Select header row:	1		
6	44445.368	492164.187		2540.9603122	C <u>u</u> stom Name		80477					
7	44445.368	492364.187		2527.35414194	0.0027251	0.001	10039			Įmpo	rt All Columns	
8	44445.368	492564.187		2603.70182796	0.0037383		13453		> Date and time for	mats		
9	44445.368	492764.187		2653.20530777	0.0051865	0.001	18221		> CSV characters			

Note that both the **File Data** table and the **Column Summary** have been updated, with the new column assignment indicated in yellow:

e Dat	а					Column Summary		
	East (X) 🗸 🗸	North (Y) 🛛 🗸	Elev (Z) 🛛 🗸	AG_gpt ~	Not Imported 🛛 🗸 🗸	Column	Column type	Import Name
1	х	Y	Z	AG_gpt	CU_pct	Х	East (X) 🗸 🗸	· East (X)
2	444245.368	492164.187	2596.092915	0.0016645	0.00061655	Y	North (Y) V	North (Y)
3	444245.368	492364.187	2496.23881289	0.0021691	0.00071943	Z	Elev (Z)	
4	444245.368	492564.187	2607.67565575	0.0028482	0.00094787	AG_gpt	Numeric ~	AG_gpt
5	444245.368	492764.187	2703.15698387	0.003755	0.0012668	CU_pct	Not Imported	
6	444245.368	492964.187	2760.98140938	0.0049519	0.0016950			
7	444245.368	493164.187	2808.66389914	0.0065045	J.J023143			
8	444245.368	493364.187	2860.99008804	0.0084448	0.0032584			
9	444245.368	493564.187	2901.99451172	0.010613	0.0046964			
10	444245.368	493764.187	2898.58065869	0.012359	0.0067481	" Name:	soil_grid	
11	444245.368	493964.187	2946.49095108	0.012721	0.01038	Na <u>m</u> e.	son_griu	
12	444245.368	494164.187	3006.50120165	0.011534	0.01535	Character encoding:	Auto (Windows-12	52)
13	444245.368	494364.187	3090.26949836	0.009425	0.018279	Unique seus ID:	None	
14	444245.368	494564.187	3148.3967538	0.0071158	0.018184	Unique row ID:	None	
15	444245.368	494764.187	3202.70217585	0.0051351	0.01685	Select header row:	1	
16	44445.368	492164.187	2540.9603122	0.002015	0.00080477		Import	All Columns
17	444445.368	492364.187	2527.35414194	0.0027251	0.0010039	> Date and time for	moto	
18	44445.368	492564.187	2603.70182796	0.0037383	0.0013453	> Date and time for	lidts	
19	44445.368	492764.187	2653.20530777	0.0051865	0.0018221	> CSV characters		

If you choose not to import a column, you can do so later using the **Import Column** option, which is described in Importing Additional Columns to a Data Table below.

When setting import options for a column you can also work with the **Column Summary**. Here the Cu_ pct column will be set to be a numeric data column:

Dat	а					Column Summary		
	East (X) 🗸 🗸	North (Y) 🗸 🗸	Elev (Z) V	AG_gpt ~	Not Imported V	Column	Column type	Import Name
	х	Y	Z	AG_gpt	CU_pct	х	East (X) 🛛 🗸	East (X)
	444245.368	492164.187	2596.092915	0.0016645	0.00061655	Υ	North (Y) V	North (Y)
	444245.368	492364.187	2496.23881289	0.0021691	0.00071943	Z	Elev (Z) 🗸 🗸	
	444245.368	492564.187	2607.67565575	0.0028482	0.00094787	AG_gpt	Numeric 🗸	AG_gpt
	444245.368	492764.187	2703.15698387	0.003755	0.0012668	CU_pct	Not Imported 🗸	
	444245.368	492964.187	2760.98140938	0.0049519	0.0016963		Lithology	
	444245.368	493164.187	2808.66389914	0.0065045	0.0023143		Category	
	444245.368	493364.187	2860.99008804	0.0084448	0.0032584		Text	
	444245.368	493564.187	2901.99451172	0.010613	0.0046964		Numeric	
0	444245.368	493764.187	2898.58065869	0.012359	0.0067481		Time Stamp	
1	444245.368	493964.187	2946.49095108	0.012721	0.01038		Date	
2	444245.368	494164.187	3006.50120165	0.011534	0.01535	Na <u>m</u> e:	URL	
3	444245.368	494364.187	3090.26949836	0.009425	0.018279		ONL	
4	444245.368	494564.187	3148.3967538	0.0071158	0.018184	Character encoding:	Not loss and a	2)
5	444245.368	494764.187	3202.70217585	0.0051351	0.01685	Unique row ID:	Not Imported	
6	44445.368	492164.187	2540.9603122	0.002015	0.00080477	Select header row:	5-100	
7	44445.368	492364.187	2527.35414194	0.0027251	0.0010039	Solder nedder jew.	East (X)	
8	44445.368	492564.187	2603.70182796	0.0037383	0.0013453		North (Y)	ul Columns
9	44445.368	492764.187	2653.20530777	0.0051865	0.0018221	> Date and time form	Elev (Z)	
0	44445.368	492964.187	2678.61592289	0.0072574	0.0025006	> CSV characters		
1	444445 368	493164 187	2729 41961754	0 010249	0 0036247	/ USV characters	Hole ID	

If you wish to import all columns, click on the **Import All Columns** button, then check that all columns have been correctly mapped.

You can select a column for import, then use it as a **Unique Row ID**. This can specify the column being used in other data systems to uniquely identify rows in a table. The column must not contain duplicate values. If a **Unique Row ID** is specified, Leapfrog Works will use this column to match rows when appending columns or reloading tables.

If the data contains date and time information and the date and time format is not detected, click on **Date and Time Formats** to reveal more information:

e Dat	a					_			Column Summary		
	East (X) 🗸 🗸	North (Y)	~	Elev (Z) 🗸 🗸	AG_gpt		CU_pct	~	Column	Column type	Import Name
1	Х	Y		Z	AG_gpt		CU_pct	Ť	X	East (X) 🗸	 East (X)
2	444245.368	492164.187		2596.092915	0.0016645		0.00061655		Υ	North (Y)	North (Y)
3	444245.368	492364.187		2496.23881289	0.0021691		0.00071943		Z	Elev (Z)	
4	444245.368	492564.187		2607.67565575	0.0028482		0.00094787		AG_gpt	Numeric ~	AG_gpt
5	444245.368	492764.187		2703.15698387	0.003755		0.0012668		CU_pct	Numeric v	CU_pct
6	444245.368	492964.187		2760.98140938	0.0049519		0.0016963				
7	444245.368	493164.187		2808.66389914	0.0065045		0.0023143		Name:	soil_grid	
8	444245.368	493364.187		2860.99008804	0.0084448		0.0032584				
9	444245.368	493564.187		2901.99451172	0.010613		0.0046964		Character encoding:	Auto (Windows-12	52)
10	444245.368	493764.187		2898.58065869	0.012359		0.0067481		Unique row ID:	None	, ,
11	444245.368	493964.187		2946.49095108	0.012721		0.01038		Select header row:	1	
12	444245.368	494164.187		3006.50120165	0.011534		0.01535		Select fielder tow.	-	`
13	444245.368	494364.187		3090.26949836	0.009425		0.018279			<u>I</u> mport	t All Columns
14	444245.368	494564.187		3148.3967538	0.0071158		0.018184		✓ Date and time for	mats	
15	444245.368	494764.187		3202.70217585	0.0051351		0.01685				
16	44445.368	492164.187		2540.9603122	0.002015		0.00080477		Date format:	DD/MM/YYY	Y ~
17	44445.368	492364.187		2527.35414194	0.0027251		0.0010039		Time stamp form	nat: DD/MM/YYY	Y hh:mm:ss V
18	44445.368	492564.187		2603.70182796	0.0037383		0.0013453				
19	444445.368	492764.187		2653.20530777	0.0051865		0.0018221		> CSV characters		


If the date and time format you wish to use is not among the options, you can create a custom format.

For *.csv files that use characters other than the comma as the separator, you can specify the delimiter, comment leader, quote and decimal characters in the **Import** window. Click on **CSV characters** to enter the characters used in the data files:

e Dat	а					Column Summary		
	East (X) 🗸 🗸	North (Y) 🗸 🗸	Elev (Z) 🗸 🗸 🗸	AG_gpt ~	CU_pct ~	Column	Column type	Import Name
1	Х	Y	Z	AG_gpt	CU_pct	X	East (X) 🛛 🗸	East (X)
2	444245.368	492164.187	2596.092915	0.0016645	0.00061655	Υ	North (Y) 🗸 🗸	North (Y)
3	444245.368	492364.187	2496.23881289	0.0021691	0.00071943	Z	Elev (Z) V	
1	444245.368	492564.187	2607.67565575	0.0028482	0.00094787	Manage	and and	
5	444245.368	492764.187	2703.15698387	0.003755	0.0012668	Na <u>m</u> e:	soil_grid	
5	444245.368	492964.187	2760.98140938	0.0049519	0.0016963	Character encoding:	Auto (Windows-125	(2)
7	444245.368	493164.187	2808.66389914	0.0065045	0.0023143			
3	444245.368	493364.187	2860.99008804	0.0084448	0.0032584	Unique row ID:	None	
•	444245.368	493564.187	2901.99451172	0.010613	0.0046964	Select header row:	1	
10	444245.368	493764.187	2898.58065869	0.012359	0.0067481	1	Import	All Columns
11	444245.368	493964.187	2946.49095108	0.012721	0.01038			
12	444245.368	494164.187	3006.50120165	0.011534	0.01535	> Date and time for	mats	
13	444245.368	494364.187	3090.26949836	0.009425	0.018279	✓ CS <u>V</u> characters		
14	444245.368	494564.187	3148.3967538	0.0071158	0.018184			
15	444245.368	494764.187	3202.70217585	0.0051351	0.01685	Delimiter charac	ter: ,	
16	44445.368	492164.187	2540.9603122	0.002015	0.00080477	Co <u>m</u> ment leader	character: #	
17	44445.368	492364.187	2527.35414194	0.0027251	0.0010039	Quote character:		
18	44445.368	492564.187	2603.70182796	0.0037383	0.0013453			
19	444445.368	492764.187	2653.20530777	0.0051865	0.0018221	Decimal charact	er: .	

Data Tables in the Project Tree

Expand a data table in the project to see the columns in the table. Here the WP_points table contains three numeric data columns (!!) and two category data columns (!!):




To delete a column, right-click on it and select **Delete**. You will be asked to confirm your choice, as any objects in that project that have been created from that data column will also be deleted.

To rename a column, right-click on it and select **Rename**. If you later export the table and wish to use your new column name in the exported table, make sure you untick the **Use original column names** option:

💋 Export Points	×
Export WP_points Export Options	
All rows in table	Use original column names
Changed rows only	Add changed <u>f</u> lags
Valid rows only	Add evaluations
	Export raw columns
? <u>C</u> ance	ei <u>E</u> xport

You can evaluate models onto data tables, as described in $\underline{Evaluations}$. Evaluated models will appear under the table as a separate set of objects:



Viewing Table Data

To view the contents of a data table, double-click on it in the project tree. The **Table** window will appear:

	collar		×					
Fix Erro	ors 🛛 🗂	?						
> Query	All 171 rows							
Ignored	trench	id ^	holeid	x	у	z	maxdepth	Completed
		1	M001	3999.231	7499.063	727.169	250.0	1996-03-05
		2	M002	4050.382	7500.755	726.926	250.0	1996-03-09
		3	M003	4098.904	7500.572	727.68	250.0	1996-03-14
		4	M004	4149.058	7501.102	728.876	275.0	1996-03-20
		5	M005	4199.59	7499.877	729.739	300.0	1996-03-27
		6	M006	4250.21	7099.258	707.249	480.0	1996-04-09
		7	M007	4249.95	7149.795	703.073	425.0	1996-04-23
		8	M008	4250.86	7200.874	706.324	409.0	1996-04-30
		9	M009	4250.021	7250.971	710.789	410.0	1996-05-10
		10	M010	4500.726	7099.169	693.874	500.0	1996-05-18
		11	M011	4500.938	7149.709	696.017	500.0	1996-05-27

To view the contents of the attribute table for a GIS object, right-click on the object and select **Attribute Table**.

If the **Ignored** column is ticked, then Leapfrog Works completely ignores that row, as though it has been deleted. This is useful for suppressing erroneous data from being processed.

If a row in a collar table is ignored, then all other data associated with that hole (e.g. surveys and interval measurements in other tables) are also ignored.

Collar tables have a **trench** column that indicates whether or not the borehole is from a trench. When the **trench** column is ticked for a borehole, the trench will be desurveyed in a different manner from other boreholes. See The Raw Tangent Algorithm for more information.

Cells in a table are editable, apart from the **id** column, which Leapfrog Works uses as unique identifier. Double-click in a cell to edit it. If the cell you wish to edit is already selected, press the space bar to start editing.

When you edit a cell, the change will be indicated in bold text:

Image: A start of the start	*collar			×					
Fix Err	ors 👸	?							
> Query	All 171 rows	6							
Ignored	trench	id	^	holeid	x	у	z	maxdepth	Completed
		1		M001	3999.231	7499.063	727.169	250.0	1996-03-05
		2		M002	4050.39	7500.755	726.926	250.0	1996-03-09
		3		M003	4098.904	7500.572	727.68	250.0	1996-03-14
		4		M004	4149.058	7501.102	728.876	275.0	1996-03-20

When you save the table, the edited text will no longer be displayed in bold.

The controls in the table toolbar provide quick access to table operations:

.

	collar			×	
Fix Erro	ors	?			
> Query	All 171 rows		1		
Ignored	trench	id	^	holeid	x
		1		M001	3999.231

Click on **Fix Errors** to begin correcting errors in the table. See <u>Correcting Data Errors in Leapfrog</u> <u>Works</u> and <u>Handling Special Values</u> for more information.

Click on **Query** to open up the query editor:

\checkmark	collar			×						
	Fix Errors	6 ?)						😵 Build Query	×
∨ <u>Q</u> ı	uery All 17	1 rows								
	Apply Exis	ting		Query					Select from collar	
	Apply Exis	sung 🗸 📋		Query					Match: • All of the following Any of the following	
									Column Test Value Bui	ld
									~ ~	
Ignor	red tren	ch id	~	holeid	x	v	z	maxdepth		
ignor		1		M001	3999.231	7499.063	727,169	250.0	•	
					4050.382					
				M003	4098.904					_
		4		M004	4149.058	7501.102	728.876	275.0	Advanced Apply	
				M005	4199.59	7499.877	729.739	300.0		
		6		M006	4250.21	7099.258	707.249	480.0	<u>Cancel</u> <u>OK</u>	
				M007	4249.95	7149.795		425.0		-
		8		800M	4250.86	7200.874	706.324	409.0	1996-04-30	

See the Query Filters topic for more information on how to build and use queries.

Adding and Updating Data for Existing Tables

If you wish to add or update data for an existing data table, you have several options. Which you choose depends on what new data is available:

- If new columns of data are available or if when you imported a table, you did not import all the columns, use the **Import Column** option. See Importing Additional Columns to a Data Table below.
- If new rows of data are available, use the **Append Data** option. See <u>Adding New Rows to Existing</u> <u>Data Tables</u> below.
- When the data in the table has been updated outside of Leapfrog Works and you wish to refresh the data, use the **Reload** option. Note that the **Reload** option overwrites existing data. See <u>Reloading</u> <u>Data Tables</u> below.

Importing Additional Columns to a Data Table

If new columns of data are available or if when you imported a table into Leapfrog Works you did not import all the available columns, you can add more columns by right-clicking on the existing table and selecting **Import Column**. You can choose the file to use as part of this process, so the new columns can be in the original file or in separate files.

Importing a column is similar to importing tables themselves. Leapfrog Works will display the data in the file in the **Add Table Column** window and you can select how you wish to import any additional columns. Here, we will import the AG_gpt column as numeric data:

	a								n i	olumn Su					
	East (X) 🗸 🗸	North (Y)	~	Elev (Z) V	Not Imported 🗸	Not In	nported	~		Column	Column type	•	Import Name	Action	ľ
1	Х	Y		Z	"AG_gpt" Litholo	gy	t			Х	East (X)	\sim		Match	
2	444245.368	492164.187		2596.092915	"AG_gpt" Catego	ory	61655			Υ	North (Y)	\sim	North (Y)	Match	
3	444245.368	492364.187		2496.23881289	"AG_gpt" Text		71943			Z	Elev (Z)	\sim		Match	
4	444245.368	492564.187		2607.67565575	"AG_gpt" <u>N</u> umer	ic 、	94787			AG_gpt	Not Importe	ed 🗸			
5	444245.368	492764.187		2703.15698387	"AG_gpt" Time S	tamp	-			CU_pct	Not Importe	ed 🗸			
5	444245.368	492964.187		2760.98140938	"AG_gpt" Date	Carrip	6963								
7	444245.368	493164.187		2808.66389914			3143								
3	444245.368	493364.187		2860.99008804	"AG_gpt" <u>U</u> RL		2584								
•	444245.368	493564.187		2901.99451172	Not Imported		6964								
10	444245.368	493764.187		2898.58065869	Hole ID		7481								
11	444245.368	493964.187		2946.49095108	Hole ID		38								
12	444245.368	494164.187		3006.50120165	Custom Name		35			Na <u>m</u> e:		soil_g	grid		
13	444245.368	494364.187		3090.26949836	East (X)		279			0		Mind	ows-1252		
14	444245.368	494564.187		3148.3967538			184			Characte	r encoding:	wind	0WS-1232		
15	444245.368	494764.187		3202.70217585	North (Y)		85			Select he	ader <u>r</u> ow:	1			
16	44445.368	492164.187		2540.9603122	Elev (Z)		80477						Import All	Columns	
17	44445.368	492364.187		2527.35414194	0.0027251	0.001	0039								
18	44445.368	492564.187		2603.70182796	0.0037383	0.001	3453			> Date	and time forr	nats			
19	444445.368	492764.187		2653.20530777	0.0051865	0.001	8221			> cs <u>v</u>	characters				

It is not necessary to re-import any columns that are already part of the project.

Click **Finish** to import the new column.

Adding New Rows to Existing Data Tables

If new data rows are available for a table you have already imported into Leapfrog Works, you can add the new data by appending it to the existing table.

Append data when you wish to add extra data to existing columns.

- If you wish to add new data columns to the table, use the **Import Column** option, which is described in Importing Additional Columns to a Data Table above.
- If you wish to refresh the entire table, overwriting all existing data, use the **Reload Data** option, which is described in Reloading Data Tables below.

To append new data rows to an existing table, right-click on the table in the project tree and select **Append Data**. The **Import Data For Appending** window will be displayed. Check that the columns that will be appended have been correctly mapped, then click **Finish**.

Reloading Data Tables

When data in a table has been updated outside of Leapfrog Works and you wish to refresh the data, use the **Reload Data** option.

Reloading a data table overwrites all existing data. If you have data you wish to add to the project without overwriting existing data, use the **Append Data** or **Import Column** options.

To reload a data table, right-click on it in the project tree and select **Reload Data**. The **Reload Table** window will be displayed. Check that the data has been correctly mapped, then click **Finish**.

Correcting Data Errors in Leapfrog Works

This topic describes how to correct errors in data tables in Leapfrog Works. It is divided into:

- Identifying Errors in Data Tables
- Exporting Data Errors
- Viewing and Correcting Errors in Leapfrog Works
- Common Errors and How to Fix Them
- Handling Special Values

Identifying Errors in Data Tables

Leapfrog Works automatically identifies and flags common data errors when data tables are imported. In the project tree, there are three ways Leapfrog Works marks tables that contain conflicts or errors:

- Tables marked with a red exclamation mark (III) contain errors that mean data cannot be used for processing. These errors can be corrected by opening the **Errors** window, which is described in <u>Viewing and Correcting Errors in Leapfrog Works</u> below.
- Numeric data columns marked with a red exclamation mark (b) contain non-numeric values, which means that the rules that are used to handle non-numeric and negative values need to be reviewed. If a table has data that contain non-numeric and negative values, the affected rows cannot be used for further processing until the rules are verified, which is described in <u>Handling Special Values</u> below.
- Tables marked with a yellow exclamation mark (IIII) contain warnings. Affected rows can be used for further processing, but the information in the warning can indicate that the data requires further attention. For example, if a warning indicates there is data missing for a borehole defined in the collar table, it may be that a borehole has been duplicated or that not all required data files have been loaded. Warnings are listed along with table errors in the **Errors** window.

Until errors are corrected, the rows that contain those errors are excluded for all processing that uses the table, including viewing in the scene. For example, if the ID for a collar position contains an invalid coordinate, that collar will not be displayed in the scene as its location is not known. Likewise, any processing will ignore data associated with this borehole.

It is worth correcting errors as soon as possible, as correcting them later can result in significant recomputation time.

When a table contains errors and warnings, only the errors will be apparent in the project tree view. However, all errors and warnings relevant to a particular table will be displayed in the **Database Errors** window. There are two approaches to correcting errors in data:

- Correct the data in the primary source. Export the errors as described in <u>Exporting Data Errors</u> below. Then, when the errors have been corrected, reload the borehole data as described in <u>Reloading Data Tables</u>.
- Correct the data in Leapfrog Works. If you need a record of corrected errors, first export the errors as described in <u>Exporting Data Errors</u> below. Then correct errors as described in <u>Viewing and</u> Correcting Errors in Leapfrog Works below.

Exporting Data Errors

If you need a record of corrected errors, first export the errors. This must be done first, as once errors have been corrected in Leapfrog Works, they cannot be exported, as they no longer exist.

For individual borehole tables, points tables and structural data tables, export the errors by right-clicking on the table and selecting **Export Errors**. Choose a location where the file will be saved and click **Save**.

To export all errors in the borehole data set, right-click on the **Boreholes** object and select **Export > Export Errors**. The **Export Borehole Errors** window will appear:

📽 Export Boreho	le Errors	×
Eolder:	C:\Users\Geologist\Leapfrog Projects	
Base file name:	Indirana_Drilling_Errors	
Name	File Name	
collar	C:\Users\Geologist\Leapfrog Projects\Indirana_Drilling_Errors_collar.csv	
survey	C:\Users\Geologist\Leapfrog Projects\Indirana_Drilling_Errors_survey.csv	
M_Assays	$\label{eq:c:Users} C: Users \ C: \ Users \$	
M_Geology	$\label{eq:c:Users} C: \label{eq:constraint} C: \label{eq:constraint} C: \label{eq:constraint} Users \label{eq:constraint} C: \label{eq:constraint} C: \label{eq:constraint} Users \label{eq:constraint} C: \label{eq:constraint} Users \label{eq:constraint} C: \label{eq:constraint} Users \label{eq:constraint} C: \label{eq:constraint} Users \label{eq:constraint} Users \label{eq:constraint} C: \label{eq:constraint} Users \label{eq:constraint} C: \label{eq:constraint} Users \labe$	
?	<u>Cancel</u> Export	

The list shows the files that will be created, one for each table that contains errors. Choose a folder where the files will be saved, then enter a **Base file name**, which will be added to the front of each file name.

Click **Export** to export the error files.

Viewing and Correcting Errors in Leapfrog Works

If you require a record of the errors in data, export the errors as described in <u>Exporting Data Errors</u> above before starting to correct the errors in Leapfrog Works.


To correct errors in a data table, right-click on the table and select **Fix Errors**. The **Errors** window will appear. For drilling data, you can display collated errors for the data set as a whole or on a table-by-table basis. To display collated errors for the whole data set, right-click on the **Borehole Data** object in the project tree and select **Fix Errors**.

Leapfrog Works identifies a range of common errors, and all errors identified are grouped by type. Click on an error type to expand it and see more information. Here the errors are shown for a survey table. The **Hole ID not in collar table** error has been expanded and the error in row 9 is displayed, showing the value that is causing the error:

🖂 🐣 Projects	Scene View		C Cen	tral Projects		Errors: survey ×	\bigtriangleup	Q Alex Rock
Group errors by: Type 🗸 🔨	Edit 🗸	0	860	2				
V Errors (6)	Current Error (in table survey) Showing holeid 'M005'					only		
\checkmark Hole ID not in collar table (4)	Ignored	id ^	holeid	depth	dip	azimuth		
V survey (4)		9	M005	0.0	90.0	0.0		
row 9		10	M005	300.0	73.0	300.0		
row 10								
row 17								
row 18								
> Collar max-depth exceeded (2)								
✓ Warnings (2)								
> No surveys for collar (1)								
> Wedges found (possible duplicate								
No numeric columns								

You can change the size of the **Errors** window and the columns in the table to view more information easily. When you have finished fixing errors, click the **Save** button (🖹). Leapfrog Works will then update the database.

Errors are automatically grouped by **Type**, but if there are many errors, you may find it useful to view them grouped by **Table** or by the **Hole**:



When a row that contains an error is selected, a red box indicates the source of the error. When two rows of data conflict, both rows will be displayed, which may be useful in determining how to fix the error:

Group errors by: Type Edit Edit Edit Current Error (in table survey) Showing holeid 'M014' only Invalid Quest For Collar (1) Wedges found (possible duplicate Survey (1) Tow 27, conflicts row 30, No numeric columns Current Conflict (in table survey) Showing holeid 'M015' only Current Conflict (in table survey) Showing holeid 'M015' only	Projects	Scene View	Cent	tral Projects		Errors: survey ×
 Hole ID not in collar table (4) Collar max-depth exceeded (2) Warnings (2) No surveys for collar (1) Wedges found (possible duplicate survey (1) row 27, conflicts row 30 Invalid Values Handling (0) No numeric columns 	Group errors by: Type V	/ Edit 🗸 🔍 📕		\mathbf{D}		
> Collar max-depth exceeded (2) > Warnings (2) > No surveys for collar (1) > Wedges found (possible duplicate > survey (1) row 27, conflicts row 30 > Invalid Values Handling (0) No numeric columns	✓ Errors (6)	Current Error (in tab	le survey)	Showing ho	leid 'M014' o	only
Warnings (2) 28 M014 500.0 68.0 310.0 No surveys for collar (1) 29 M014 425.0 68.0 310.0 Wedges found (possible duplicate 29 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 M014 425.0 68.0 310.0 wedges found (possible duplicate 9 9 M014 425.0 68.0 310.0 Monumeric columns 9 9 9 9 9 9 9 Monumeric columns 9 9 9 9 9 9 9 <th>> Hole ID not in collar table (4)</th> <th>Ignored id ^</th> <th>holeid</th> <th>depth</th> <th>dip</th> <th>azimuth</th>	> Hole ID not in collar table (4)	Ignored id ^	holeid	depth	dip	azimuth
No surveys for collar (1) Wedges found (possible duplicate survey (1) row 27, conflicts row 30 Invalid Values Handling (0) No numeric columns	> Collar max-depth exceeded (2)	27	M014	0.0	90.0	0.0
 Wedges found (possible duplicate survey (1) row 27, conflicts row 30. Invalid Values Handling (0) No numeric columns 	∨ Warnings (2)	28	M014	500.0	68.0	310.0
<pre>v survey (1) row 27, conflicts row 30 V Invalid Values Handling (0) No numeric columns </pre>	> No surveys for collar (1)	29	M014	425.0	68.0	310.0
Curren Conflict (in table survey) Showing holeid 'M015' only	 survey (1) row 27, conflicts row 30. Invalid Values Handling (0) 					2002002
		[©] Currel, Conflict (in	table surve	y) Showing	holeid 'M01	15' only
Ignored id A holeid depth dip azimuth		Ignored id ^	holeid	depth	dip	azimuth
30 M015 0.0 90.0 0.0		30	M015	0.0	90.0	0.0
31 M015 550.0 80.0 300.0		31	M015	550.0	80.0	300.0

The **Edit** button gives you a number of options for correcting data errors:

Group errors by: Type \checkmark	~	Edit 🔨 🔍 👫 🏳 🤅)	
✓ Errors (18)	С	Edit Error Coll	Ctrl+E	004
> Invalid Max Depth (1)	lg	Write to Selected Rows	Ctrl+L	
✓ Duplicate Hole ID (1)	-3	Ignore Error Row	Ctrl+I	1.1
✓ collar (1)		Ignore Conflict Row	Ctrl+Shift+I	9.8
row 4, conflicts row 5				-

- Use Edit Error Cell to edit the incorrect value.
- The Write to Selected Rows option opens the Replace All option, which is described below, in Replacing Values in a Column.
- Use **Ignore Error Row** to mark selected rows to be ignored.
- When two rows of data conflict, use **Ignore Conflict Row** to mark the conflicting row as ignored.

Replacing Values in a Column

The **Replace All** button () in the toolbar may be useful in correcting any errors without closing the **Errors** window. With the **Replace All** button, you can replace an incorrect value that occurs multiple times in a column. To do this, click the **Replace All** button. Select the **Column** to search and enter the new value:

Group errors by: Type 🗸 🔨	Edit 🗸	0		\mathbf{D}							
V Errors (1)	Current Er	ror (i. tabl	e Mar_Ass	ays) Shov	ving holeid 'N	/IAR061' only					
\checkmark Hole ID not in collar table (1)	Ignored	id 📐	holeid	from	to	Au					
V Mar_Assays (1)		535	MAR061	22.5	25.0	0.43197349					
row 535		536	MAR061	25.0	27.5	0.685565833					
✓ Warnings		550	JAR061	60.0	62.5	0.207557161					
No warnings		562	I AR061	90.0	92.5	0.296579409					
Invalid Values Handling (1) Mar_Assays (1)											
Group errors by: Type V Edit V Edit Q III AR016 Replace All Occurrences X											
$ \lor $ Errors (1)	Current Er	ror (in tabl	e Mar_Ass	ays) Shov	ving holeid 'N	/IAR061' only					
\checkmark Hole ID not in collar table (1)	Ignored	id ^	holeid	from	to	Au					
V Mar_Assays (1)		535	MAR061	22.5	25.0	0.43197349					
row 535		536	MAR061	25.0	27.5	0.685565833					
\vee Warnings		550	MAR061	60.0	62.5	0.207557161					
No warnings		562	MAR061	90.0	92.5	0.296579409					
Invalid Values Handling (1) Mar_Assays (1)											

Click **Replace All Occurrences** to make the changes.

You can also select a number of rows and replace values in a selected column with a single value. To do this, use the Shift and Ctrl keys to select the rows you wish to edit, then click the **Edit** button and select **Write to Selected Rows**:

Group errors by: Type \checkmark	Edit)		
Column: 🚺 holeid 🗸 Find: M	IARI E	dit Error Cell		Ct	rl+E	Replace All Occurrences X
		/rite to Selecte	ed Rows	C	trl+L	
Errors (1)		nore Error Ro		C	trl+l	MAR061' only
\checkmark Hole ID not in collar table (1)	lg _{lg}	nore Conflict	Row	Ctrl+Sh	ift+I	Au
✓ Mar_Assays (1)		333	MARUUT	22.J	23.0	0.43197349
row 535		536	MAR061	25.0	27.5	0.685565833
✓ Warnings		550	MAR061	60.0	62.5	0.207557161
No warnings		562	MAR061	90.0	92.5	0.296579409
Invalid Values Handling (1) Mar_Assays (1)						

The **Replace All Occurrences** button will change to a **Write to Selected Rows** button. In the fields that appear, enter the **New value**, then click the **Write to Selected Rows** button:

Group errors by: Type -	🖌 Edit 🗸	0	6	\mathcal{D}						
Column: holeid \sim New value	e: MAR016	MAR016 Write to Selected Rows								
✓ Errors (1)	Current Error (in table Mar_Assays) Showing holeid 'MAR061' only									
\checkmark Hole ID not in collar table (1)	Ignored	id ^	holeid	from	to	Au				
Mar_Assays (1)		535	MAR061	22.5	25.0	0.43197349				
row 535		536	MAR061	25.0	27.5	0.685565833				
\vee Warnings		550	MAR061	60.0	62.5	0.207557161				
No warnings		562	MAR061	90.0	92.5	0.296579409				
Invalid Values Handling (1) Mar_Assays (1)										

Common Errors and How to Fix Them

There are many possible sources of error in the data itself and you may be able to correct the errors directly in the **Errors** window. With borehole data, however, the message given in the **Errors** may actually point to an error elsewhere in the dataset, in which case you will need to open the other table from the project tree and edit it directly.

The errors and warnings described are:

- Duplicate Points Error (Points Tables)
- Duplicate Hole ID Error
- Hole ID Not in Collar Table Error
- Collar Max Depth Error

- Invalid Max Depth Error
- From Depth Exceeds To Depth Error
- Overlapping Segments Error
- No Samples for Collars Warning
- No Surveys for Collar Warning
- Wedges Found Warning

Duplicate Points Error (Points Tables)

Points tables will have **Duplicate Points** errors when rows have identical x, y and z values:

Group errors by: Type	Edit v	0 🚆							
 Errors (14) 	Current E	ror (in tabl	e midpoint	is)					
✓ Duplicate Points (14)	Ignored	id ^	x	у	z	Au			
v midpoints (14)		1	3999.2	7499.0	725.919	M001	0.0584457		
row 2, conflicts row 1		2	3999.2	7499.0	725.919	M001	0.0584457		
row 5, conflicts row 4		3	3999.2	7499.0	723.41	M001	0.709237		
row 18, conflicts row 6		4	3999.2	7499.0	720.91	M001	0.955436		
row 19, conflicts row 7		5	3999.2	7499.0	720.91	M001	0.955436		
row 20, conflicts row 8		6	3999.1	7499.0	718.41	M001	0.483431		
		7	3999.1	7499.0	715.91	M001	1.42281		
row 21, conflicts row 9		8	3999.1	7499.1	713.41	M001	2.15717		
row 22, conflicts row 10		9	3999.1	7499.1	710.91	M001	1.34305		
row 23, conflicts row 11		10	3999.0	7499.1	708.42	M001	0.393816		
row 24, conflicts row 12		11	2000 0	7/00 1	705.02	M001	0.425043		
row 25, conflicts row 13	Current C	onflict (in t	able midpo	pints)					
row 26, conflicts row 14	Ignored	id ^	x	у	z	holeid	Au		
row 27, conflicts row 15		1	3999.2	7499.0	725.919	M001	0.0584457		
row 28, conflicts row 16		2	3999.2	7499.0	725.919	M001	0.0584457		
17		3	3999.2	7499.0	723.41	M001	0.709237		

Tick **Ignored** for the rows you wish to ignore. If there are many duplicate points in the table, click the **Ignore Duplicates** button (...). When you save the table, all duplicate rows will be marked as **Ignored**.

Duplicate Hole ID Error

Collar tables will have **Duplicate Hole ID** errors when collars have been assigned the same ID. Here, rows 4 and 5 have the same ID but are clearly different holes:

Group errors by: Type V Edit V Q 👫 Time ?												
✓ Errors (18) Current Error (in table collar) Showing holeid 'M004' only												
Invalid Max Depth (1) Ignored id ^ holeid x y z maxdep trench Completed												
\checkmark Duplicate Hole ID (1)		4	M004	4149.05	7501.10	728.876	275.0	0	1996-03-20			
✓ collar (1)		5	M004	4199.59	7499.87	729.739	300.0	0	1996-03-27			
row 4, conflicts row 5												
> Hole ID not in collar table (10)												
> From depth >= to depth (1)												
> Collar max-depth exceeded (4)												
> Overlapping Segments (1)												
$\sim~$ Warnings (4)												
> No samples for collar (2)												
> No surveys for collar (1)												
> Wedges found (possible duplicate	> Wedges found (possible duplicate Current Conflict (in table collar) Showing holeid 'M004' only											
Invalid Values Handling (1)	Ignored	id ^	holeid	x	У	z	maxdep	trench	Completed			
> III M_Assays (1)		4	M004	4149.05	7501.10	728.876	275.0	0	1996-03-20			
		5	M004	4199.59	7499.87	729.739	300.0	0	1996-03-27			

Changing the hole ID for one of the boreholes will correct the error. If the collar has been recorded twice by accident, tick the **Ignored** box for the duplicate collar.

Hole ID Not in Collar Table Error

Interval tables will have **Hole ID not in collar table** errors when the hole ID specified in the interval table is not found in the collar table.

Group errors by: Type V Edit V Q 👫											
Errors (18)	Current Error (in table M_Assays) Showing holeid 'M005' only										
> Invalid Max Depth (1)	Ignored	id ^	holeid	from	to	Au					
> Duplicate Hole ID (1)		415	M005	0.0	2.5	0.02					
\checkmark Hole ID not in collar table (10)		416	M005	2.5	5.0	0.02					
✓ M_Assays (4)		417	M005	5.0	7.5	0.02					
row 415		418	M005	7.5	10.0	0.02					
row 1068		419	M005	10.0	12.5	0.132019027					
row 2210		420	M005	12.5	15.0	0.130456449					
		421	M005	15.0	17.5	0.714647081					
row 2376		422	M005	17.5	20.0	0.734139351					
> M_Geology (2)		423	M005	20.0	22.5	0.48973995					
> survey (4)		424	M005	22.5	25.0	0.922992852					
> From depth >= to depth (1)		425	M005	25.0	27.5	1.570789879					
> Collar max-depth exceeded (4)		426	M005	27.5	30.0	0.481513287					
> Overlapping Segments (1)		427	M005	30.0	32.5	0.229774069					
✓ Warnings (4)		428	M005	32.5	35.0	0.413308159					
		429	M005	35.0	37.5	0.035621953					
> No samples for collar (2)		430	M005	37.5	40.0	0.02					
> No surveys for collar (1)		431	M005	40.0	42.5	0.02					
> Wedges found (possible duplicate		432	M005	42.5	43.4375	0.374198316					

Affected intervals cannot be displayed. There are two possibilities for fixing this error:

- The collar table uses the wrong hole ID. Edit the collar table to correct the hole ID.
- The interval table uses the wrong hole ID. Use the **Replace All** tool to the incorrect values with the correct one. See <u>Replacing Values in a Column</u> above.

Collar Max Depth Error

Interval tables will have **Collar max-depth exceeded** errors when the **depth** values in the interval table exceeds the **maxdepth** value defined in the collar table. The **maxdepth** defined in the collar table is often a theoretical value established before drilling. If the **depth** value flagged as an error is not unrealistic, click on the **Fix Max Depths** button (**!!**):

✓ Errors (18)	Current Er	ror (in tabl	e survey)	Showing ho)leid 'M015' (only
> Invalid Max Depth (1)	Ignored	id ^	holeid	depth	dip	azimuth
> Duplicate Hole ID (1)		30	M015	0.0	90.0	0.0
> Hole ID not in collar table (10)		31	M015	550.0	80.0	300.0
> From depth >= to depth (1)						
✓ Collar max-depth exceeded (4)						
> M_Assays (1)						
> M_Geology (1)						
✓ survey (2)						
row 4, column depth, conflicts collar row 2						
row 31, column depth, conflicts collar row 15						
> Overlapping Segments (1)						

This results in the collar table being updated with a maximum depth value that reflects the data in the interval tables.

Invalid Max Depth Error

Collar tables will have **Invalid Max Depth** errors when the **maxdepth** value is negative or non-numeric:

Group errors by: Type \checkmark	Edit 🗸	Q	1 6	\mathbf{D}					
✓ Errors (18)	Current Er	ror (in t	Fix maximu	m depths in o	collar table	ly			
✓ Invalid Max Depth (1)	Ignored	id	^ holeid	x	у	z	maxdep	trench	Completed
✓ collar (1)		2	M002	4050.381	7500.75	726.926	-250.0	0	1996-03-09
row 2									
> Duplicate Hole ID (1)									
> Hole ID not in collar table (10)									

These errors are often the result of data entry mistakes and can be corrected by editing the table in the **Errors** window.

From Depth Exceeds To Depth Error

Interval tables will have **From depth > = to depth** errors when the **from** and **to** values in a row do not make sense:

Group errors by: Type V Kelit V	0							
Errors (18) Current Error (in table M_Geology) Showing holeid 'm001' only								
> Invalid Max Depth (1)	Ignored	id ^	holeid	from	to	RockTy	Simple	Weathering_Zone
> Duplicate Hole ID (1)		1	m001	0.0	2.5	D2	andésite	OX
> Hole ID not in collar table (10)		2	m001	2.5	5.0	D2	andésite	OX
✓ From depth >= to depth (1)		3	m001	5.0	7.5	D2	andésite	OX
✓ M_Geology (1)		4	m001	7.5	10.0	D2	andésite	OX
row 7		5	m001	10.0	12.5	D2	andésite	OX
> Collar max-depth exceeded (4)		6	m001	12.5	15.0	D2	andésite	OX
> Overlapping Segments (1)		7	m001	17.5	15.0	D2	andésite	OX
		8	m001	17.5	20.0	D2	andésite	OX
Warnings (4)		9	m001	20.0	22.5	D2	andésite	OX
> No samples for collar (2)		10	m001	22.5	25.0	D2	andésite	OX
> No surveys for collar (1)		11	m001	25.0	27.5	D2	andésite	OX
> Wedges found (possible duplicate hole) (1)		12	m001	27.5	31.0	D2	andésite	OX
\sim Invalid Values Handling (1)		13	m001	30.0	32.5	D2	andésite	OX
> III M_Assays (1)		14	m001	32.5	35.0	D2	andésite	OX
		15	m001	35.0	37.5	D2	andésite	OX

These errors are often the result of data entry mistakes and can be corrected by editing the table in the **Errors** window.

Until the error is corrected, the affected interval cannot be displayed, although all non-conflicting intervals will still be displayed for that borehole.

Overlapping Segments Error

Interval tables will have **Overlapping Segments** errors when intervals are in the same place for the same hole or when two holes are in the same place. Here, row 12 overlaps row 13 and the error can be corrected in the **Errors** window by entering the correct **to** value for row 12:

Group errors by: Type - Edit -	0	1 ?						
V Errors (18)	Current E	rror (in tabl	e M_Geolo	ogy) Show	ing holeid 'N	1001' only		
> Invalid Max Depth (1)	Ignored	id ^	holeid	from	to	RockTy	Simple	Weathering_Zone
> Duplicate Hole ID (1)		8	m001	17.5	20.0	D2	andésite	OX
> Hole ID not in collar table (10)		9	m001	20.0	22.5	D2	andésite	OX
> From depth >= to depth (1)		10	m001	22.5	25.0	D2	andésite	OX
> Collar max-depth exceeded (4)		11	m001	25.0	27.5	D2	andésite	OX
		12	m001	27.5	31.0	D2	andésite	OX
		13	m001	30.0	32.5	D2	andésite	OX
V M_Geology (1)		14	m001	32.5	35.0	D2	andésite	OX
row 13, conflicts row 12		15	m001	35.0	37.5	D2	andésite	OX
 Warnings (4) 		16	m001	37.5	40.0	D2	andésite	OX
> No samples for collar (2)		17	m001	40.0	42.5	D2	andésite	MX
> No surveys for collar (1)		18	m001	42.5	45.0	D2	andésite	MX
> Wedges found (possible duplicate hole) (1)	[©] Current C	onflict (in t	able M_Ge	eology) Si	howing holei	d 'm001' only	1	
\vee Invalid Values Handling (1)	Ignored	id ^	holeid	from	to	RockTy	Simple	Weathering_Zone
> III M_Assays (1)		7	m001	17.5	15.0	D2	andésite	OX
		8	m001	17.5	20.0	D2	andésite	OX
		9	m001	20.0	22.5	D2	andésite	OX
		10	m001	22.5	25.0	D2	andésite	OX
		11	m001	25.0	27.5	D2	andésite	OX
		12	m001	27.5	31.0	D2	andésite	OX
		13	m001	30.0	32.5	D2	andésite	OX
		14	m001	32.5	35.0	D2	andésite	OX

If an interval has been defined twice, click **Ignored** for one of the rows. Until the error is corrected, the affected intervals cannot be displayed, although all non-conflicting intervals will still be displayed for that borehole.

No Samples for Collars Warning

Interval tables will have **No values for Hole ID** warnings when there are no values in the interval table that correspond to a collar defined in the collar table. In this example, a hole called M090 has been defined in the collar table, but there is no data for it in the M_Assays table.

Group errors by: Type \checkmark \checkmark Edit \checkmark	Q 📲 🛅 ?
V Errors (18)	Current Error (in table M_Assays) Showing holeid 'M090' only
> Invalid Max Depth (1)	Ignored id ^ holeid from to Au
> Duplicate Hole ID (1)	
> Hole ID not in collar table (10)	
> From depth >= to depth (1)	
> Collar max-depth exceeded (4)	
> Overlapping Segments (1)	
✓ Warnings (4)	
\checkmark No samples for collar (2)	
V M_Assays (1)	
No values for Hole ID M090, collar row 9	
> M_Geology (1)	
> No surveys for collar (1)	
> Wedges found (possible duplicate hole) (1)	
imes Invalid Values Handling (1)	
> III M_Assays (1)	

There are three possibilities:

- There are no values in this interval table for that collar. There is no need to do anything to remedy the warning as it will not affect further processing of the data.
- The collar table uses the wrong hole ID. This may be the case if there is also a **Hole ID not in collar table** warning listed. Edit the collar table to correct the hole ID.
- There are values for that collar in the interval table but they use the wrong collar ID. Again, there may also be a **Hole ID not in collar table** warning listed. Edit the interval table and correct the hole ID for the affected intervals.

No Surveys for Collar Warning

This survey table error is similar to <u>No Samples for Collars Warning</u> above: there are no values in the survey table that correspond to a collar defined in the collar table. Check that the collar table and the survey table are using the right hole ID. You will need to edit the survey table or collar table directly before this warning can be cleared.

Wedges Found Warning

Wedges found warnings occur in the collar table or in the survey table when boreholes appear to be duplicates because they are very close together in space.


Group errors by: Type \checkmark K Edit \checkmark	0 📲	$\square ?$)			
V Errors (18)	Current Er	ror (in tabl	e survey)	Showing ho	leid 'M014' o	only
> Invalid Max Depth (1)	Ignored	id ^	holeid	depth	dip	azimuth
> Duplicate Hole ID (1)		27	M014	0.0	90.0	0.0
> Hole ID not in collar table (10)		28	M014	500.0	68.0	310.0
> From depth >= to depth (1)		29	M014	425.0	68.0	310.0
> Collar max-depth exceeded (4)						
> Overlapping Segments (1)						
V Warnings (4)						
> No samples for collar (2)						
> No surveys for collar (1)						
✓ Wedges found (possible duplicate hol (1)						
√ survey (1)						
row 27, conflicts row 30	Current Co	onflict (in ta	able surve	y) Showing	holeid 'M01	5' only
✓ Invalid Values Handling (1)	Ignored	id ^	holeid	depth	dip	azimuth
> III M_Assays (1)		30	M015	0.0	90.0	0.0
		31	M015	550.0	80.0	300.0

Leapfrog Works flags boreholes that are less than 1° apart as possible duplicates; if you have two boreholes that are that close together, you may need to adjust the collar location of one of the boreholes to clear the warning. You can do this by editing the collar table.

Handling Special Values

Assay data often contains special values to represent different situations, such as grade values that are below a detection limit, cores that have been lost or segments that were not sampled. In addition, it is not uncommon for a borehole to contain some intervals that have no values.

When borehole data tables and points data are imported, Leapfrog Works will mark columns containing non-numeric special values and missing intervals so that you can review these missing and non-numeric values and determine how Leapfrog Works will handle them. For example, here numeric data columns that contain errors are marked with a red X:



To review these errors, double-click on the column. The **Errors** window will appear with the error displayed for the selected column:

Errors: Contaminant ×						
Group errors by: Type 🗸 🔨	🖊 Edit 🗸 🔍 📗		\mathbf{O}			
∨ Errors	<u>These rules hav</u>	e been reviewed				
No errors	Missing values:				1 value	occurring 5 times
Warnings (1) No samples for collar (1)	Value	Occurrences	Action		Replace	e With
 Invalid Values Handling (2) 	Missing interval	5	Omit	\sim		
Contaminant	Non-numeric value	es:			0 values	s occurring 0 times
🏥 Mean				Add	Rule	
	Value	Occurrences	Action	Repla	ce With	Remove
	Default Action	0	Omit \sim			

Leapfrog Works will automatically set missing and non-numeric intervals to be omitted from further processing. Negative values are automatically set to **keep**. To change the **Action**, select another action from the list:

- Select **replace** to enter a numeric value to be used for further processing.
- Select keep to use a negative value in further processing.

For non-numeric and negative values, all values are initially treated as a single rule. However, if values have different meanings, you can define specific rules to determine how each value is handled. To do this, click on the **Add Rule** button. The window that appears will show the values present in the data. To define a new rule for a specific value:

- Select that value in the list.
- Tick the box for The value I want is not in the list.

- Enter the Value.
- Click OK.


In the **Invalid Value Handling** window, the value will be listed separately and you can choose the **Action** to apply.

Once you have reviewed the rules that will be applied to the column, tick the **These rules have been reviewed** box and click **OK**. The rules will be applied and used in further processing.

When you open a data table, the original values will be displayed. In all further processing of that data, the assigned special values will be used.

Evaluations

In Leapfrog Works, models can be evaluated onto other objects in the project. To do this, right-click on an object and select **Evaluations**:




See <u>Back-Flagging Borehole Data</u> for information on evaluating boreholes on geological models.

See <u>Evaluating on Sections</u> for information on evaluating surfaces on cross sections and fence sections.

See <u>Evaluating Points Data</u> for information on evaluating surfaces on points.

A window will appear listing all objects in the project that can be used for an evaluation. Once you have selected one or more objects, click **OK**.

The evaluations will be added to the object in the project tree:



When you display objects in the scene, you can select the evaluations from the view list:

0	s CS	\times	SL.	•
			A Flat colour	
			👔 Oliver Geological Model	
			👔 Weathering Model - oxide contacts	
			nu in QzP	
			n Vein Au in Vein	
			📐 CS Layout	
				,

Query Filters

Query filters can be used to select or view a subset of rows in a table. A query filter can be created for any type of table in a Leapfrog Works project, including borehole data, GIS data, points data and structural data.


Two different query builders are used in Leapfrog Works, the standard query builder that is used for most data tables and the points query builder that is used for imported points data tables.

The rest of this topic describes how to build and use query filters in Leapfrog Works. It is divided into:

- Using a Query Filter in Displaying Data
- Using a Query Filter in a Model
- The Standard Query Builder
- The Points Query Builder

Using a Query Filter in Displaying Data

To apply a query filter to the scene, select the object in the shape list, then select the filter from the **Guery filter** list in the shape properties panel:



For a borehole data table, this displays only the data selected by the filter. The trace lines remain displayed in the scene. To filter out the trace lines so they are not displayed in the scene, tick the **Filter trace lines** box:

HI A 🗉	M_Geology Slice mode:	Unsliced	~
	Query filter: Filter trac Line radius:	© collar: Campaig ce lines 8.00 Format Display Text	gn 1 ~ ≎
ull Acceleration	100+ FPS	Z-Scale 1.0	4 hours to go

Using a Query Filter in a Model

When creating or editing a model, you can use a query filter to filter the data used. For example, here you can use one of the query filters defined for the borehole data to create a new geological model from the borehole data for a specific drilling campaign:

😹 New Geolog	jical Model	×
General		
Base <u>l</u> itholo	ogy column:	NockType 🗸 🗸
<u>F</u> ilter data:		<none> ~</none>
Surface <u>r</u> es	olution:	<none></none>
Model Extents		🖓 Campaign 1
	Minimu	🖓 Campaign 2
<u>X</u> (East):	2516.84114	🖓 Campaign 3 😽
Y (North):	6037.61993	🖓 Campaigns 1 and 2
<u>Z</u> (Elev):	-6232.0	€ 1832.0 €
		Enclose Object 🗸 🗸
<u>N</u> ame: Geo	logical Model	
?	<u>C</u> ancel	<u>о</u> к

Here a structural data table is used to create a form interpolant. The query filters on the structural data table can be used to filter the data used in the interpolant:

💋 New Form Interpolant		×
Inputs Boundary	Trend Outputs	
Structural Data	Query Filter Use Polarity Boundary Filter	
	No filter selected all_structural_data: Basement all_structural_data: Cover	
Name: Form Interpolant		
	<u>C</u> ancel <u>O</u> K	

It is also possible to change the filter used for a model after the model has been created. In a geological model, for example, you cannot change the data column used for the model, but you can edit the model and apply a new query filter to the data:

🖉 Geological Mod	lel - GM				×
General B	oundary	Fault System	Lithologies	Chronology	
Base Litholog Base litholog		Geology - Strat			
<u>F</u> ilter data:		<none></none>		\sim	
Surface Gene Surface res Snap to da Maximum ☑ Exact cl Volume Gene	solution: ta: snap <u>d</u> istanc ipping	🗧 🖓 Cam	paign 1 paign 2 paign 3 paigns 1 and 2		
Merge ou	tput volume:	s: Fast		~	
?		<u>C</u> ancel		<u>о</u> к	

The Standard Query Builder

The standard query builder is used for creating queries for all data tables in Leapfrog Works except for imported points data tables. For information on building queries for points data tables, see <u>The Points</u> <u>Query Builder</u> below.

		🗱 Advanced Query - collar	×
		Criteria to <u>M</u> atch	Data
		V AND	Table Columns
	🛱 Build Query X		V 🌃 collar
			id (Integer)
😝 New Query Filter 🛛 🗙	Select from collar Match: All of the following Any of the following		holeid (Category)
Select rows from collar	Column Test Value Build		x (Numeric)
Build Query			y (Numeric)
			z (Numeric)
			Select
			Symbols
Name: Query filter		\oplus \square \land \lor $<$ $>$	AND BETWEEN LIKE
			OR IN IS NULL
Cancel OK	Advanced Apply	Query	NOT REGEXP NOT NULL
			- + < ≥ < + -
	? Cancel OK		× / %
		Check Apply	Date List Value
		?	<u>C</u> ancel <u>O</u> K

There are three windows that make up the standard query builder:

In the first window, the **New Guery Filter** window, you can type in a query using the query syntax described in <u>Leapfrog Works Query Syntax</u>. Press Ctrl-Enter for a new line in longer queries.

The second window, the **Build Query** window helps you build some common queries by selecting from the data columns in the table and defining different tests. Open the **Build Query** window by clicking the ... button in the **New Query Filter** window. See <u>The Build Query Window</u> for more information on building queries in this way.

The third window, the **Advanced Guery** window, shows all the data columns and possible operations. See <u>The Advanced Query Builder</u> for more information.

To create a query filter for a data table, right-click on the table in the project tree and select **New Query Filter**. The **New Query Filter** window will appear and you can choose which way you prefer to build your query. Assign the filter a name and click **OK** to save it. It will appear in the project tree under the table to which it applies:



Query filters defined for collar tables are available to all other borehole data tables.

Leapfrog Works Query Syntax

The Leapfrog Works query syntax is based on the WHERE clause of the Structured Query Language (SQL) with some restrictions:

- Unary operators are not allowed
- SQL functions cannot be used
- The SELECT statement should not be used (as in 'holeid in (SELECT holeid FROM ...)')
- Following statements are also prohibited: CASE, WHEN or MATCH

There is also one main SQL extension:

• IN and NOT IN will accept a partition group for the value list. E.g. 'zone IN layers.weathered' where "layers" is a partition of the "zone" column that has a group called 'weathered'.

These are some examples of valid Leapfrog Works query statements:

- holeid in ('m-001', 'm-002')
- holeid not in ('m-001', 'm-002')
- holeid not like 'MAR%'

To enter a query that contains an apostrophe, enter two apostrophes. Adding the second apostrophe lets the query builder treat this as a mid-phrase apostrophe instead of an end-of-phrase marker, and results in a valid query.

The **Query** box allows the following shortcut queries:

- Typing a single word will match all hole-ids starting with that string. For example, typing "MAR" is a shortcut for "holeid like 'MAR%'"
- Typing a comma-separated list of words will match all hole-ids that exactly match the given words. For example typing "M001, M002" is a shortcut for "holeid in ('M001', 'M002')".

The Build Query Window

Many common queries can be built using the **Build Query** window:

🖉 Build Query			×
Select from Contaminant Match:	◯ A <u>n</u> y o	f the follow	wing
Column	Test	Value	Build
Contaminant.Contaminant	<pre>> <</pre>	2.0	
×	 		
\oplus \blacksquare	Ad <u>v</u> ance	ed	<u>A</u> pply
? <u>Cancel</u>		<u>о</u> к	

This window aims to be easy to use rather than comprehensive in its support for the full Leapfrog Works query syntax.

To add a criteria, click **Column** to view a list of columns available in the table. Select a **Test** and enter a **Value**. What can be entered for the **Value** depends on the type of column and test selected.

Quotes are not required around text values entered in the value column as they are in SQL. Leapfrog Works will add quotes and brackets to the value "MX, PM" to make a valid SQL list of strings "('MX', 'PM')" when the query is saved.

Click on the **Apply** button to apply to query to the context in which the dialog was opened.

Use the **Delete** button to delete the criteria in the selected row and the **Add** button to add a blank row.

The Advanced Query Builder

The **Advanced Query** window provides a powerful and flexible query building using the Leapfrog Works query language.

💋 Advanced Query - Contaminant			×
Criteria to <u>M</u> atch	Data		
V AND	🗸 🗁 Table Colum	ns	
Contaminant > 2.0	🗸 🔢 Contami	nant	
	id (Intege	r)	
	holeid (Ca	ategory)	
	from (Nu	meric)	
	to (Nume	eric)	
	Contamir	nant (Numeric)	
	Mean (Nu	umeric)	
	🗸 🏢 collar		
	id (Intege	r)	
	holeid (C	ategory)	
			Select
	Symbols		
	AND	BETWEEN	LIKE
\oplus \square \land \checkmark $<$ $>$	OR	IN	IS NULL
Query	NOT	REGEXP	NOT NULL
Contaminant > 2.0			
	= ≠ <	≤ _>	2 + -
	× / %		
Chec <u>k</u> Apply	Date	List	Value
(?)		<u>C</u> ancel	<u>о</u> к
0			

Enter the query in the **Criteria to Match** area on the left. The query is displayed as a tree structure with AND and OR terms as the branch nodes and conditions as the leaves. Use the **Delete** button to delete a row from the query and the **Add** button to add a blank row. The **Check** button can be used at any time to check if the current query statement is valid. Below the buttons is a box showing the raw SQL form of the query.

Except for the arrow buttons, the buttons down the middle of the dialog are used for entering values into the query. The arrow buttons are used for moving the currently selected criteria to a different position in the query. The **Date**, **List** and **Value** buttons will open a builder dialog for the column selected in the current row. If there is no column found or the column is of the wrong type, an error message is displayed.

The tree on the right contains all the columns available to the query. Double-click on a column name to insert it into the query.

The Points Query Builder

Imported points data tables use a different query builder from that used for other data tables.

To create a query filter for a points data table, right-click on the table in the project tree and select **New Query Filter**.

💋 New Query Filter	×
Select rows from Selected_Earthquakes Build Query Insert Insert If (=+) If (=+) If (=+)	
[
Name: filter	
? <u>C</u> ancel <u>Q</u> K	

You can define filters by three methods:

- Construct the query using the **Insert** options to add columns, operators and other elements
- Write the query using query syntax directly in the query editor
- Use the query builder

Insert Query Elements Using Ready Reference

Click the **Insert** button to expand the window to see an adjacent ready reference. This provides quick access to all the numeric columns, metadata variables, operators and functions that can be used in constructing a query.

Build Query	nsert 🗸 ii(🕂 i		Apply			
	Click on either	list below to in	sert that item			
	Existing items:			Synt	ax and functi	ons:
	METADATA			\sim	Statements	
	id	Row ID	1 to 1.867e+05		()	Brackets
	×		6.794e+05 to 2.385e+06		if(::)	If block
	у		4.177e+06 to 6.484e+06	\sim	Basic Opera	tors
lame: filter	z	Location Z	-7.5e+05 to 0		+	Add
	IMPORTED		0.01000 1. (1.1.)		-	Subtract
?	mag_sc		0.01029 to 61.16 0.1014 to 7.82		*	Multiply
-	time	Ide	1 to 1.926e+05		/	Divide
	CALCULATIO	ONS	1101.9206403		%	Modulo
Me - C (the phase				^	Power
ົ 🧕	FILTERS				and	Logical and
(🖓 contem	porary			or	Logical or
· · · · · · · · · · · · · · · · · · ·	🖓 historic				not	Logical not
©_ (=	Equal
👡 🍳					! =	Not equal
20					<	Less than
Denne					<=	Less or equal
YOUR TO BE					>	Greater than
de soo					>=	Greater or equal
0.037					Complex Co	

The **Insert** list will assist you in constructing a valid query in the same syntax as used for Calculations and Filters. For full details on each of the **Existing items** and **Syntax and Functions**, see <u>Catalogue of</u> Metadata, Syntax and Functions.

Select an item from the **Insert** list and the item will be added to the query at the cursor location.

Select rows from Select	ted_Earthquakes				×		
Build Query Ir	nsert v ii(🕂 ii)	• > 0	Apply				
	Click on either lis						
[magnitude]	Existing items:			Synt	ax and functi	ons:	
	METADATA			✓ Statements			
	id	Row ID	1 to 1.867e+05		()	Brackets	
	x x	Location X	6.794e+05 to 2.385e+06		if(::)	lf block	
() Error: Express	y y	Location Y	4.177e+06 to 6.484e+06	\sim	Basic Opera	tors	
<u>N</u> ame: filter	z	Location Z	-7.5e+05 to 0		+	Add	
	IMPORTED				-	Subtract	
?	mag_scal		0.01029 to 61.16		*	Multiply	
C	magnitude	e 🖓	0.1014 to 7.82		/	Divide	
	CALCULATION	10	1 to 1.926e+05		*	Modulo	
See	the phase	15			~	Power	
o o	FILTERS				and	Logical and	
- Č		rary			or	Logical or	
O					not	Logical not	
© ∑7	0				=	Equal	
🔍 🏹					!=	Not equal	
					:=	Less than	
65-50CC					<=	Less or equal	
AT CAR					>	Greater than	
A CAR					>=	Greater or equal	
				\sim	Complex Co		
					Lower	< n < upper	
					Lower	<= n < upper	

While the query is being built, it is normal to see errors appear under the partly-constructed query. This is because the query is incomplete. Once you have completed building your query, if you still see an error message, the description of the error can help you identify what you need to change in the query to make it valid.

The **if(::)** *if block* option is special in that it allows for multiple rows of conditions to be defined. Once added, putting the cursor inside the if block will result in the **Add Row** button ([®]) becoming available. If condition rows have been added, the **Delete Row** button ([®]) will be available whenever the cursor is inside a condition row.

🗱 New Query Filter	×
Select rows from Selected_Earthquakes Build Query Insert # # Build Query Insert	
$if \begin{pmatrix} [time] < 100000 \rightarrow [magnitude] > 7 \\ [time] < 150000 \rightarrow [magnitude] > 6 \\ otherwise & [magnitude] > 5 \end{pmatrix}$	
Name: filter	
? <u>C</u> ancel <u>O</u> K	

The **Undo** and **Redo** buttons make it easy to revert a change you made to a query, or repeat a change you have just reverted.

Assign the filter a name and click **OK** to save the filter and close the query filter window. It will appear in the project tree under the table to which it applies. **Apply** will change the filter in use so the effect may be seen in the scene without closing the query filter window.

Write a Query in Query Editor

It is not necessary to use the **Insert** list to add elements to the query under construction. Once you become familiar with the query syntax you may find it quicker to simply type the query directly into the query editor window.

📽 New Query Filter		×
Select rows from S	elected_Earthquakes	
Build Query	Insert > # 🗄 # 🛱 🏈 🔗 Apply	
[magnitude]	> 6	
Name: filter		
<u>in</u> ame. Inter		
?	<u>C</u> ancel <u>O</u> K	
~	<u>C</u> ancel <u>O</u> K	

For full details on the syntax for this query filter editor, please see <u>Catalogue of Metadata, Syntax and</u> <u>Functions</u>.

Write a Query Using the Query Builder

Many common queries can be built using the **Build Guery** window:

Build Query			×					
Select from Selected_Earthquakes Match: \bigcirc All of the following $$ Any of the following								
Column	Test	Value	Build					
mag_scaled \vee	> \	25						
magnitude $\!$	> \							
~	\sim							
①			<u>A</u> pply					
?	<u>C</u> ance	el	<u>0</u> K					

This window aims to be easy to use rather than comprehensive in its support for the full Leapfrog Works query syntax.

To add a criteria, click **Column** to view a list of columns available in the table. Select a **Test** and enter a **Value**. What can be entered for the **Value** depends on the type of column and test selected.

Click on the **Apply** button to apply to query to the context in which the dialog was opened.

Use the **Delete** button to delete the criteria in the selected row and the **Add** button to add a blank row.

Drawing in the Scene

In Leapfrog Works, you can draw polylines to define many surfaces, including lateral extents and contact surfaces. You can also use polylines to make adjustments to surfaces and create new GIS lines.

This topic describes drawing polylines in Leapfrog Works. It is divided into:


- The Drawing Toolbar
- Drawing Hotkeys
- Drawing 3D Lines
- Drawing 2D Lines
- Polyline Properties
- Tangents and Ribbons
- Drawing Points

For information on importing and exporting polylines, see <u>Polylines</u>.


When drawing in Leapfrog Works, you can draw on surfaces or on the slicer.

- If you are drawing on surfaces (D), the line will be in 3D.
- If you are drawing on the slicer (), the line will be in 2D and locked to the plane it was drawn in. It can be converted to a 3D line.


When you start drawing a polyline, drawing tools are added to the scene window. If you are drawing a GIS line or if the slicer was already in the scene, the drawing mode will be set to be on the slicer. Toggle between the two options using the toolbar buttons:



When drawing and otherwise working with the polyline, tooltips are displayed in the scene that show what actions are currently possible:



For example, if the drawing mode is set to on slicer (\circledast), you will be warned if the slicer is not in the scene:



You can disable these tooltips once you are more familiar with how the polyline tool works. Open the **Settings** window by clicking on the **Leapfrog Works** menu and selecting **Settings**. Click on **Overlays** and disable the **Polyline help text** option:



The Drawing Toolbar

The **Draw lines** (\checkmark) and **Draw points** (\ddagger) tools are used to create new lines and points. The tools in the second row are for controlling whether the polyline is drawn (on the slicer (\circledast) or on surfaces (\circledast)). The **Select** list lets you select different parts of the polyline.

The other tools are for working with selected parts of the polyline:

- Making line segments straight (→) or curved ()
- Adding nodes (5) to lines

- Adding tangents to lines or reorienting selected tangents (5)
- Flipping selected tangents and disks (12)
- Add disks to points (🔊)
- Converting a 2D polyline to 3D (💷)
- Setting the slicer to a 2D polyline (\checkmark)
- Simplifying the line by reducing the number of nodes (§C)

There are also buttons for undoing (>) and redoing actions (<), as well as saving the polyline (\square) or deleting selected parts of it (\square).

Drawing Hotkeys


Use the following keyboard shortcuts while drawing:

Key(s)	Action
Ctrl+5	Draw lines (🏈)
Ctrl+6	Draw points/disks (🤣)
Ctrl+S	Save (🛅)
Ctrl+W	Close editor (×)
Ctrl+Z	Undo (🦻)
Ctrl+Y	Redo(<♥)
Delete	Delete the selected segment, node, tangent or disk (🗐)
X	Draw/move on slicer (🖗)
Shift+X	Draw/move on objects (🐡)
Q	Make segments curved (^)
Shift+Q	Make segments straight (***)
Shift-A	Add node (🗔)
A	Add/reorient tangent (5)
V	Flip tangent/disks (12)
Shift+D	Add/remove disk (🛸)
Shift+E	Make selected line 3D (4)
Shift+W	Set slicer to selected 2D line (🕼)
Shift+S	Simplify the line by reducing the number of nodes (\ref{G})
Ctrl+A	Select all

Key(s)	Action
Shift+Ctrl+Alt+L	Select all lines
Shift+Ctrl+Alt+T	Select all tangents
Shift+Ctrl+Alt+P	Select all points without disks
Shift+Ctrl+Alt+D	Select all points with disks

Drawing 3D Lines


Polylines are made up of nodes, which are added where you click in the scene using the **Draw lines** (vol. This is a 3D polyline, which is indicated in the scene by the dashed line:




Click to select a node and drag to move it in the scene parallel to the screen. If you hold down the Ctrl key while moving the node, it will snap onto surfaces in the scene.

When borehole segments are in the scene, the polyline tool will snap to the end of nearby intervals.

When you click to add a node, dragging the mouse before releasing the button lets you control the curvature:




When you start drawing a polyline, a tangent is automatically added to the first node. This is oriented in the direction of the camera, and you will need to rotate the scene to see that it is a cone.



You can hide the tangent cones in the scene, if it makes drawing difficult. To do this, click on the polyline in the shape list and disable the **Show tangent cones** option:



There are also bezier control points on curved segments. These are used to control the curvature of the segment, and you can click on a control point and drag it to change the curve of the segment:



If you can't see the bezier control points, click on the polyline in the shape list and enable the **Show bezier control points** option:


٢	a map_fig2_topo		×		•		C 3D polyline		
٢	C 3D polyline [Editing]	2	×		•	H =	Slice mode:	From Scene	\sim
							Line width:	3 () pb	xels
							Node size:	10 0 pi	xels
							Ribbon width:	20 🗘 🖉 pb	xels
							Point size:	8 🗘 💟 🖬 pb	xels
							🕨 🗹 Show tange	nt cones	
						-	Show bezie	r control points	

When you have finished drawing, right-click to end the polyline. Switch to the **Select** tool ($\[Be]$) to make changes to the polyline.


- Click on a node to move it.
- Click on a segment away from a node and drag it to change its curvature.
- Click on one or more segments, then make them straight (---) or curved (---).
- Select a point on the polyline, then click (5) to add a node.
- Select a point on the polyline. The point selected is indicated in the scene by a red cone. You can then click (to add a tangent oriented in the direction of the camera.
- Select a tangent and click (to change the orientation of the segment to that of the camera.
- Select a tangent and click (M) to flip it.

Begin drawing again by selecting the **Draw lines** button (\checkmark). To continue from an existing node at the start or end of a polyline, click on the node.

Use as many nodes as necessary to draw the polyline. You can later reduce the number of nodes using the **Simplify polyline** tool (§C). Each time this tool is used, Leapfrog Works attempts to halve the number of nodes on the select segments:




Although you can make the line curved while adding nodes, an easy way to draw a curved polyline is to simply click to add a series of points. Set the curvature of the whole line by selecting all segments and then clicking the **Make selected segments curved** button (^):



You can then make any adjustments to the curves required by dragging the segments or using the bezier control points.

Drawing 2D Lines

Working with a 2D polyline is similar to working with a 3D polyline, except that drawing is restricted to the 2D plane set by the slicer. A 2D polyline is indicated in the scene by an unbroken line:



Polyline Properties

In the shape list, you can control the colour of the positive (red) and negative (blue) surfaces of the line and of the line itself (green):

٢	🔜 map_fig2_topo		×	_					C 3D polyline	•			
۲	C 3D polyline [Editing]	a	×			•	ME		Slice mode:	From Scene			~
							_		Line width:	3		0	pixels
									Node size:	10		0	pixels
								1	Ribbon width:	20		V (pixels
									Point size:	8		Z.	pixels
									Show tangent cones				
									Show bezie	r control points			

For contact surfaces, the colour of the positive and negative sides of a ribbon will be determined by the lithologies or categories assigned to either side of the surface.

With the controls in the properties panel, you can change the size of different parts of the polyline to make working with the polyline easier.

٢	amap_fig2_topo	×		3D polyline
۲	C 3D polyline [Editing]	∠a ×	E E • H =	Slice mode: From Scene ~
				Line width: 3 🗘 pixels
				Node size: 10 🗘 pixels
				Ribbon width: 20 🗘 💟 pixels
				Point size: 8 🗘 💟 pixels
				Show tangent cones
				Show bezier control points


For **Ribbon width** and **Point size**, the setting is, by default, in pixels, but both can be displayed in realworld size, which may make editing the polyline easier in some circumstances.

You can also choose whether or not to show tangent cones and bezier control points.

Tangents and Ribbons

The **Surface ribbon** (M) and **Normal ribbon** (M) help you to determine the orientation of the polyline in the scene. The surface ribbon reflects the orientation of the polyline and the normal ribbon is perpendicular to the surface ribbon.

For example, click on the **Surface ribbon** button (▶●) to determine which side of the polyline is positive (red) and which side is negative (blue):



If you are having trouble seeing the ribbons, you can change their size using the **Ribbon width** control in the properties panel.


When you first draw a polyline, it has only one tangent, located at the first node and oriented in the direction of the camera. You can add more nodes by clicking at a point along the polyline and then clicking the **Tangent** button (). A tangent is added to the polyline, which is updated to reflect the new information. The tangent's orientation is taken from the camera angle. To reorient a tangent, click on it in the scene, change the camera angle to reflect the orientation you wish to set, then click the **Tangent** button ().

You can also flip selected tangents by clicking on the **Flip tangents and disks** button (M).

You can add as many tangents as required, although it is best to keep them to a minimum.


Drawing Points

Polylines can also include points, which are drawn using the **Draw points** tool (*b*). Clicking adds a point, and clicking and dragging adds a point with a normal:




Normals are shown in the scene as disks intersecting the points.

The scene below shows one point with a normal and one without:




To move a point without a normal, switch to the **Select** tool ($\[b]$). Click on the point and drag it. To add a normal to the point, click on it in the scene and click the **Add disk** button ($\[b]$).

To edit the orientation of a point with a normal, click on it in the scene. There are two rotation modes. In the first, the handles adjust the dip and azimuth of the disk:




Click on the disk to change the rotation mode.

In the second rotation mode, dragging the disk rotates it in the plane indicated by the handles:



Change the angle of the plane by moving the mouse cursor over the disk.

You can also change the orientation of a disk by drawing over it. To do this, make sure the **Draw points** tool (¹/₂) is selected. Hold the cursor over the point you want to edit. The cursor will turn green to indicate that you can adjust the disk's angle:



Drag to adjust the angle and release the mouse button when finished:

You can also flip selected disks by clicking on the Flip tangents and disks button (M).

Organising Your Workspace

You can split the Leapfrog Works main window into separate parts to make better use of your screen space. In addition, some Leapfrog Works windows open in separate tabs that can be used either docked or detached. This topic describes how to change the main window to make the best use of your screen space. It is divided into:

- Detaching Tabs
- Detaching and Minimising the Project Tree
- Organising the Scene View Tab


Detaching Tabs

To detach a tab, either:

- Click on it and drag it away from the main window.
- Right-click on it and select Move to New Window.

You can then move and resize the detached tab.


To dock a detached tab, click on it and drag it to where you want to dock it:



When the move handle (Φ) appears, release the mouse and the tab will dock.

Tabs can be docked to the main window or to other tabs. Drag tabs to reorder them.

You can view a list of all open tabs by clicking the **List open tabs** button, which is the down arrow to the right of the processing queue button:



When you close a project, the position of open tabs will be saved and restored when the project is next opened.

For Leapfrog Works windows that open in separate tabs, the position in which tabs open is determined by the **New tab position** setting in the **Settings** window:


- Open all tabs in the main window.
- Open all tabs in separate windows.
- Tabs can open where the last tab was moved to. This setting can be used for creating a window in which all tables and dockable windows open, with the scene window, project tree and shape list in another window.

To change this setting, click on the **Leapfrog Works** menu, select **Settings** and then click on the **User Interface** tab.

Detaching and Minimising the Project Tree

The project tree can also be detached from the main window. To do this, either:

• Right-click at the top of the project tree and select **Detach**:



• Click on the List open tabs button and select Detach project tree:

\searrow	🛞 Projects 👘 Se	сеп
용 <u>P</u>	rojects	
େ ପ୍	entral Projects	Ł
💼 <u>S</u>	cene View	
	estore All Windows	
X 🖸	lose All Tabs Below Ctrl+Shift+F4	
Ŀ. н	ide project tree	
D	etach project tree 💦	

To reattach the project tree, click the X to close the tab. It will reappear docked to the main window. You can also click on the **List open tabs** button and select **Attach project tree**.

You can also hide the project tree. To do this, right-click on it and choose **Hide project tree** or press the F8 key. Restore the project tree by:

- Clicking on the List open tabs button and selecting Show project tree.
- Pressing the F8 key once again.

Organising the Scene View Tab

The **Scene View** tab is made up of the scene window, the shape list and the shape properties panel. The shape list and shape properties panel can be displayed on the right-hand side of the scene rather than below the scene. To do this, right-click in the shape list and select **Move List to Right**:



You can also detach the shape list and display it as a tab, which can then be detached from the main window. To do this, right-click in the shape list and select **Put List in Separate Tab**:



You can then detach the tab from the main window:

Projects	Scene View	Shape List	× 🧟 Central Projects
		•	

To dock the shape list to the **Scene View** tab, right-click in the **Shape List** tab and choose where you wish to dock the list:



Concepts

This section of the help describes important concepts you can refer to as you start working with Leapfrog Works. You don't need a complete understanding of these topics in order to start working with Leapfrog Works, but you can come back to these topics as you start working with different features. The topics in this section complement the topics in An Overview of Leapfrog Works.

What is Implicit Modelling?

Implicit modelling is a game-changing innovation in geological modelling.

Traditionally, geological models are produced using a manual drawing process. Sections are defined, and lithologies, faults and veins are drawn on the sections. Lines are then drawn to connect surfaces across multiple sections. Modelling geology in this manner is time-consuming and inflexible as it is difficult to update the model when more data becomes available. Early assumptions that later are proved incorrect could shape a model in a way that is never corrected because of the effort involved in starting over. Instead of using their knowledge to reveal important information about the study site, geologists spend significant proportions of their time engaged in mechanical drawing.

Implicit modelling, on the other hand, allows geologists to spend more time thinking about the geology. Implicit modelling eliminates the laborious legwork by using mathematical tools to derive the model from the data. A mathematical construct is built that can be used to visualise different aspects of the data in 3D. Leapfrog Works uses FastRBF[™], a mathematical algorithm developed from radial basis functions. FastRBF uses the data and parameters supplied by the geologist to derive any one of a number of variables to be modelled. Discrete variables such as lithologies can be used to construct surfaces, as well as continuous variables such as ore grades.

Instead of presenting a model constructed from rigid geometric constructs, the visualisations echo the natural forms found in reality.

What are the Advantages of Implicit Modelling?

Implicit models are easy to keep up-to-date with the latest data. New borehole data can quickly be integrated, instead of taking weeks or longer manually modifying the model.

Implicit modelling allows several alternative hypothetical models to be produced from the data, quickly and easily. New data that affects the model, even in very significant or fundamental ways, can be assimilated and integrated with little effort. Models can be built rapidly, which means that a range of geological interpretations can be continually tested.

Because less effort is involved in creating a model, more time is available to spend on understanding the geology and studying more complex details such as faulting, stratigraphic sequences, trends and veins. The model can be developed to reflect reality to a greater degree of precision than was previously possible.

Geological risk is reduced when modelling is done implicitly. With traditional modelling, the effort involved means that the first model developed may be held to as the ground truth, despite mounting evidence that may discredit it. Instead, implicit modelling supports an approach that follows the proven scientific method, developing hypothetical models, experimenting to find new data to corroborate or discredit models and, ultimately, allowing the best model to be revealed. A geologist can experiment with alternative parameters at the limits of what is geologically reasonable to determine if there is any significant variation in the resulting models, which can then bracket the model with conceptual error bars. Geostatistical analysis can be conducted to identify what models are the most valid.

It is easy to change your mind when modelling implicitly. Perhaps models have been produced demonstrating isometric shells enclosing specific grades of ore. Commodity price changes then make it desirable to recreate the model using alternative ore grade values. If the model had been produced manually, doing so would not be practical. But with implicit modelling, the ease of generating a new model with new interpolation parameters means this valuable business information can be readily produced.

New questions can be answered more easily. A model tends to answer one question or class of questions well, and new questions require new models. If a model takes months to produce, those new questions may remain forever unanswered. If it can be produced with only days or hours worth of effort, valuable insights can be gained that could provide critical business value.

Implicit Modelling Makes Assumptions Explicit

Often, there is insufficient information in the data alone. For instance, borehole data may well need to be supplemented with known details about the geology. When a geologist is constructing a model using traditional techniques, they use their knowledge of the geology to make decisions about the model as it is constructed. This is something the geologist will do automatically, which irretrievably conflates measured data with hypothesised data, hiding away subjective assumptions that have influenced the development of the model.

Implicit modelling, however, keeps the measured data separate from interpretations. The geologist can use polylines and structural disks to interpret the data without equating them to measured data. Implicit modelling makes assumptions explicit; there is a clear separation between hard data and user-introduced interpretations.

Implicit modelling and the presentation of a selection of models communicating different aspects of the geology provide new tools a geologist can use to communicate with professionals in other parts of the business.

On a purely business level, specialist staff can be putting their skills to use in productive, valuable geological modelling, rather than drawing lines on sections ad infinitum.

Implicit models are more repeatable and, therefore, more auditable, because they are derived from actual data and explicitly communicated geological interpretations, with selected parametric variables as inputs and processed using a mathematical algorithm.

The only thing implied in implicit modelling is the unknown value between two known values. Everything else is explicit. For this reason, it is best to refer to traditional modelling techniques as 'traditional modelling' rather than 'explicit modelling', assuming that it should be labelled with a name that is the inverse of 'implicit modelling'. Implicit modelling is much more explicit than traditional modelling.

Best Practices


- Analyse data. Analyse your data using borehole interpretation and data visualisation tools. Use 3D visualisation to look for errors in the data set.
- Stay focussed. Produce a model that answers a specific question or addresses a specific problem. Don't unnecessarily model all the data available just because it is there. When a new question is asked, produce a model that answers that question using the necessary data.
- Experiment and explore. Produce variations of the same model, or even models, using quite different fundamental assumptions. Plan boreholes that will help reveal what model fits best and then discard models that are inconsistent with new data.
- Understand risk. Model using a range of input parameters and assumptions to understand the level of geologic risk.
- Share. Discuss and explore alternatives.
- Adapt. Previously, the effort of production and review of traditional models meant that there is reluctance to rebuild a model when new data becomes available soon after model completion. However, with implicit modelling, you should integrate new data and refine the model as soon as the

new data is available. The revised model could indicate that planned activities should be redirected as expensive resources would be wasted persisting with the original plan, for little return.

• Evaluate and review. Don't assume that because it's easy to generate a model that you have quickly produced the right model. Understanding the geology is vital for validating the model and producing something that is geologically reasonable.

Interpolant Functions

Leapfrog Works's powerful 3D interpolation engine can interpolate any numeric data (e.g. ore grade or piezometric head measurements) to describe how a real, numerical quantity varies in three dimensional space. Interpolation produces an estimate or "interpolated value" of a quantity that is not known at a point of interest but is known at other points.



The simplest way to estimate values is to take the average of known values. Using this method, estimated values are the same everywhere, regardless of the distance from known data. However, this is not ideal as it is reasonable to assume that an estimated value will be more heavily influenced by nearby known values than by those that are further away. The estimates for unknown points when varying the distance from known point values is controlled by the interpolant function. Any interpolation function and the various parameters that can be set for each will produce a model that fits all the known values, but they will produce different estimates for the unknown points. It is important to select interpolation function functions and parameters that make geologic sense. It may be necessary to identify a location that models predict differently, and plan boreholes to identify the best fit option.

Leapfrog Works uses two main interpolant functions:


- The Spheroidal Interpolant Function
- The Linear Interpolant Function

The Spheroidal Interpolant Function

In common cases, including when modelling most metallic ores, there is a finite range beyond which the influence of the data should fall to zero. The spheriodal interpolant function can be used when modelling in these cases.

The spheroidal interpolant function closely resembles a spherical variogram, which has a fixed range beyond which the value is the constant sill. Similarly, the spheroidal interpolant function flattens out when the distance from X is greater than a defined distance, the range. At the range, the function value is 96% of the sill with no nugget, and beyond the range the function asymptotically approaches the sill. The chart below labels the y-axis interpolant. A high value on this axis represents a greater uncertainty relating to the known value, given its distance from X. Another way to think of this is that higher values on this axis represent a decreasing weight given to the known value.

Known values within the range are weighted proportionally to the distance from X. Known values further from X than the range will all be given approximately the same weight, and have about the same influence on the unknown value. Here, points A and B are near X and so have the greatest influence on the estimated value of point X. Points C and D, however, are outside the range, which puts them on the flat part of the spheroidal interpolant curve; they have roughly the same influence on the value of X, and both have significantly less influence than A or B:



The parameters used to define a spheroidal interpolant are <u>Total Sill</u>, <u>Nugget</u>, <u>Nugget to Total Sill Ratio</u>, <u>Base Range</u>, <u>Alpha</u>, <u>Drift</u> and <u>Accuracy</u>.

To edit the parameters for an interpolant, double-click on the interpolant in the project tree and click on the **Interpolant** tab. The graph on the tab shows how the interpolant function values vary with distance and is updated as you change interpolant parameters:

Edit RBF Interpo	lant							
Values Co	mpositing	Boundary	Value T	ransform	Trend	Interpolant	Outputs	
Variance:	16.2							
In <u>t</u> erpolant:	Spheroidal		\sim	Alp <u>h</u> a:	9		Ş	
Total <u>S</u> ill:	10.0		Ŷ	N <u>ugg</u> et:	1.00		0	
Base <u>R</u> ange:	4.00		¢	Max = 4; In	t = 4; Min =	= 4		
<u>D</u> rift:	Constant		~	Accuracy:	0.0400		Û	
.5	1.0 - 7.5 - 1.0 - 0 0	1		listance	4	15		
<u>N</u> ame: Spheroid	dal R4							
?					<u>C</u> ance		<u>о</u> к	

The yellow line indicates the **Base Range**. For this interpolant, the value of the interpolant is offset by the value of **Nugget**.

Total Sill


The **Total Sill** defines the upper limit of the spheroidal interpolant function, where there ceases to be any correlation between values. A spherical variogram reaches the sill at the range and stays there for increasing distances beyond the range. A spheroidal interpolant approaches the sill near the range, and approaches it asymptotically for increasing distances beyond the range. The distinction is insignificant.

Nugget

The **Nugget** represents a local anomaly in sampled values, one that is substantially different from what would be predicted at that point, based on the surrounding data. Increasing the value of **Nugget** effectively places more emphasis on the average values of surrounding samples and less on the actual data point, and can be used to reduce noise caused by inaccurately measured samples.

Nugget to Total Sill Ratio


It is the **Nugget** to **Total Sill** ratio that determines the shape of the interpolant function. Multiplying both these parameters by the same constant will result in an identical interpolant. Here, the interpolant on the left has a nugget of 3 and a sill of 25; the one on the right has a nugget of 6 and a sill of 50. Note that because the nugget and sill have been increased by the same factor, the function has the same shape.



Base Range


The **Base Range** is the distance at which the interpolant value is 96% of the **Total Sill**, with no **Nugget**. The **Base Range** should be set to a distance that is not significantly less or greater than the distance between boreholes, so it can reach between them. As a rule of thumb, it may be set to approximately twice the average distance between boreholes.

Here the effect of different range settings on the value of X is demonstrated using our trivial example of four boreholes:











Range = 8








When the range is set to 1, it is too small to describe any real effect between boreholes. When the range is set to 30, distant boreholes have more influence, increasing the spatial continuity. Also illustrated is the range set to approximately the average distance between boreholes (range = 4) and the range set to about twice the average distance between boreholes (range = 8). Of these, the range set to 8 might be the best choice.


Alpha

The **Alpha** constant determines how steeply the interpolant rises toward the **Total Sill**. A low **Alpha** value will produce an interpolant function that rises more steeply than a high **Alpha** value. A high **Alpha** value gives points at intermediate distances more weighting, compared to lower **Alpha** values. This figure charts an interpolant function for each alpha setting, using a nugget of 8, sill of 28, and range of 5000. A spherical variogram function is included for comparative purposes. The inset provides a detailed view near the intersection of the sill and range.




An alpha of 9 provides the curve that is closest in shape to a spherical variogram. In ideal situations, it would probably be the first choice; however, high alpha values require more computation and processing time, as more complex approximation calculations are required. A smaller value for alpha will result in shorter times to evaluate the interpolant.

The following demonstrates the difference between alpha = 3 and alpha = 9:



Alpha = 3

Alpha = 9




There is a measurable difference between the estimates at the point being examined, but for many purposes, using a lower alpha will result in satisfactory estimates and reduced processing time.

Drift

The **Drift** is a model of the value distribution away from data. It determines the behaviour a long way from sampled data.


- Constant: The interpolant goes to the approximated declustered mean of the data.
- Linear: The interpolant behaves linearly away from data, which may result in negative values.
- None: The interpolant pulls down to zero away from data.

Here, the three **Drift** options for the interpolant are shown evaluated on grids:






Drift = Linear



Drift = None



In this example, the boundary is larger than the extent of the data to illustrate the effect of different **Drift** settings.

Away from the data, the value of the interpolant when **Drift** is **Constant** and **Linear** is not reasonable in this case, given the distance from the data. The low value when **Drift** is **None** is more realistic, given the distance from the data.

If when using the spheroidal interpolant you get a grade shell that fills the model extents, it is likely that the mean value of the data is higher than the threshold chosen for the grade shell in question. If this occurs, try setting the **Drift** to **None**.

Accuracy


Leapfrog Works estimates the **Accuracy** from the data values by taking a fraction of the smallest difference between measured data values. Although there is the temptation to set the **Accuracy** as low as possible, there is little point to specifying an **Accuracy** significantly smaller than the errors in the measured data. For example, if values are specified to two decimal places, setting the **Accuracy** to 0.001 is more than adequate. Smaller values will cause the interpolation to run more slowly and will degrade the interpolation result. For example, when recording to two decimals, the range 0.035 to 0.044 will be recorded as 0.04. There is little point in setting the accuracy to plus or minus 0.00001 when intrinsically values are only accurate to plus or minus 0.005.

The Linear Interpolant Function


Generally, estimates produced using the linear interpolant will strongly reflect values at nearby points and the linear interpolant is a useful general-purpose interpolant for sparsely and/or irregularly sampled data. It works well for lithology data, but is not appropriate for values with a distinct finite range of influence.

The linear interpolant function is multi-scale, and, therefore, is a good general purpose model. It works well for lithology data, which often has localised pockets of high-resolution data. It can be used to quickly visualise data trends and whether or not compositing or transforming values will be required. It is not appropriate for values with a distinct finite range of influence as it aggressively extrapolates out from the data. Most ore grade data is not well interpolated using a linear interpolant function.

The linear interpolant function simply assumes that known values closer to the point you wish to estimate have a proportionally greater influence than points that are further away:



In the above diagram, points A and B will have the most effect on point X as they are closer to X than points C and D. Using the linear interpolant function in Leapfrog Works gives a value of 7.85, which is between the nearby high grade values of A (10) and B (7). Because of their distance from X, the low grade values at C and D have a much weaker effect on the estimate of point X, and they have not dragged the estimate for X lower.



The parameters used to define a linear interpolant are <u>Total Sill and Base Range</u>, <u>Nugget</u>, <u>Drift</u> and <u>Accuracy</u>.

To edit the parameters for an interpolant, double-click on the interpolant in the project tree and click on the **Interpolant** tab. The graph on the tab shows how the interpolant function values vary with distance and is updated as you change interpolant parameters:

🎸 Edit RBF Interpolant	× Edit RBF Interpolant ×
Values Compositing Boundary Value Transform Trend Interpolant Outputs	Values Compositing Boundary Value Transform Trend Interpolant Outputs
Variance: 2.75 Interpolant: Linear Total Sill: 2.0 C) Nugget: 0.05 C) Base Range: 2000.0 C) Max = 2000; Int = 2000; Min = 2000 C) Drift: Constant Accuracy: 0.002 ^^ 0 0 0 Max = 2000; Int = 2000; Min = 2000 C) 0 0 0 Accuracy: 0.002 ^^ 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0<	Variance: 2.75 Interpolant: Linear Total Şili: 2.0 Base Bange: 2000.0 Qinft: Constant Accuracy: 0.002 Image: Constant Accuracy: Image: Constant Image: Constant Image: C
(?) <u>Cancel</u> <u>QK</u>	(?) <u>Cancel</u> OK

The yellow line indicates the **Base Range**. For this interpolant, the value of the interpolant is offset by the value of **Nugget**.

Total Sill and Base Range

A linear interpolant has no sill or range in the traditional sense. Instead, the **Total Sill** and **Base Range** set the slope of the interpolant. The **Base Range** is the distance at which the interpolant value is the **Total Sill**. The two parameters sill and range are used instead of a single gradient parameter to permit switching between linear and spheroidal interpolant functions without also manipulating these settings.

Nugget


The **Nugget** represents a local anomaly in values, one that is substantially different from what would be predicted at that point based on the surrounding data. Increasing the value of **Nugget** effectively places more emphasis on the average values of surrounding samples and less on the actual data point, and can be used to reduce noise caused by inaccurately measured samples.

Drift

The **Drift** is a model of the value distribution away from data. It determines the behaviour a long way from sampled data.


- **Constant**: The interpolant goes to the approximated declustered mean of the data.
- Linear: The interpolant behaves linearly away from data, which may result in negative values.

Here, the two **Drift** options for the interpolant are shown evaluated on grids:



Drift = Constant





In this example, the boundary is larger than the extent of the data to illustrate the effect of different **Drift** settings.

Accuracy

Leapfrog Works estimates the **Accuracy** from the data values by taking a fraction of the smallest difference between measured data values. Although there is the temptation to set the **Accuracy** as low as possible, there is little point to specifying an **Accuracy** significantly smaller than the errors in the measured data. For example, if values are specified to two decimal places, setting the **Accuracy** to 0.001 is more than adequate. Smaller values will cause the interpolation to run more slowly and will degrade the interpolation result. For example, when recording to two decimals, the range 0.035 to 0.044 will be recorded as 0.04. There is little point in asking Leapfrog Works to match a value to plus or minus 0.00001 when intrinsically that value is only accurate to plus or minus 0.005.


Surface Resolution in Leapfrog Works

In Leapfrog Works, meshes are used to represent surfaces in the form of vertices and triangles that define the 3D shape of the surface. The resolution of a surface is controlled by the size of the triangles used to create a surface. A lower surface resolution value means smaller triangles and, therefore, a finer resolution. A higher surface resolution value will take less time to process but the surface may not show the level of detail required.


When a surface is imported, Leapfrog Works automatically sets a surface resolution based on the information in the file. It is not possible to change the resolution of surfaces imported into Leapfrog Works. The exception is elevation grids (see Importing an Elevation Grid).

When surfaces are created, Leapfrog Works sets a default resolution based on the data available. You can set a lower value, but calculations will take longer. In addition, the resolution for many surfaces can be adaptive; that is, areas closer to data will have a finer resolution than areas further away from data.


To see the effect of different resolution settings, consider a simple geological model of three rock types. Here, the surface resolution is set to 50 and the adaptive isosurfacer is disabled:



Here, the resolution has been reduced, which results in smaller triangles:



For both resolution settings above, the triangles are the same size everywhere in each surface, even where real data is available. Once the adaptive isosurfacer has been enabled, the triangles closer to the boreholes are smaller than those further away:



Areas of the surface that have large triangles indicate that there is less data in those areas to guide the interpolation of the surface.

In Leapfrog Works, the resolution for different types of surfaces can be controlled as follows:

- For geological models, a resolution can be set for the model as a whole, but individual surfaces can have different settings. See <u>Surface Resolution for a Geological Model</u>.
- For interpolants, the resolution of the output isosurfaces is controlled by a single setting that can be overridden for individual surfaces. See <u>Output Settings for an RBF Interpolant</u>.
- The resolution can be changed for editable interpolated meshes (🎯) and can be adaptive. See Interpolated Meshes.
- When the topography has been defined using multiple data sources, the resolution can be set and the adaptive option is available. See <u>Changing Topography Settings</u>.

Modifying Surfaces


This topic describes aspects of modifying surfaces in Leapfrog Works. It is divided into:

- Adding Data to Surfaces
- Honouring Surface Contacts
- Editing Surfaces With Polylines
- Editing Surfaces With Structural Data
- Modifying Surfaces With Anisotropic Trends
- Applying a Structural Trend

Trends can also be applied to reshape surfaces. For more information on the concept of trends, see <u>Trends and Anisotropy</u>.

Adding Data to Surfaces

Many surfaces can be refined by adding points, structural data, GIS data and polylines. If a surface can be modified in this way, an **Add** menu will appear for the object when you right-click on it in the project tree. For example, the **Add** menu for this contact surface shows the data types that can be used to refine the surface:



Select the type of data you wish to use to modify the surface. Leapfrog Works will display all the suitable objects in the project. Select the required object and click **OK**. A hyperlink to the added data will appear under the surface in the project tree. The added data can be removed from the surface by expanding the surface in the project tree, then right-clicking on the hyperlinked data object and selecting **Remove**.


Honouring Surface Contacts

In Leapfrog Works, surfaces can be created from borehole data, points data, structural data, GIS data and polylines. When surfaces are created from several different objects, it may be desirable to snap the surface to some data objects but not to others.

There are several options for snapping surfaces to data:


- Off. The surface does not snap to the data used to create it.
- All data. The surface snaps to data within the Maximum snap distance, which includes borehole data and any data added to the surface.
- **Drilling only**. The surface snaps to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surface. For example, the surface will honour points data derived from borehole data, but not points data imported into the **Points** folder.
- Custom. The surface snaps to selected data objects within the Maximum snap distance.

Snapping forces surfaces to honour the specified contacts, moving triangles on the surface so that the surface precisely intersects the contact. For example, snapping is disabled for the surface on the left, but enabled for the surface on the right. The points used to generate the surface are shown in red, and the triangles are displayed so you can see how snapping to data affects the surface:



When snapping is enabled, the **Maximum snap distance** is used to determine what data should affect the surface. The **Maximum snap distance** is, by default, set to half of the **Surface resolution** setting, but you can adjust that up or down, if required.

In this image, three surfaces are shown, along with the points used to generate the surface (red). The grey surface is the surface that results when snapping is **Off**. For the yellow surface, snapping to the points is enabled and the **Maximum snap distance** has been set to a high value, resulting in the yellow surface snapping to the distant point indicated by the arrow. Snapping to points is also enabled for the blue surface, but the **Maximum snap distance** has been set to a lower value, so that the surface snaps to some close points, but does not snap to the distant point.



While the most suitable snapping option is always project- and purpose-specific, if you have sufficient drilling data, snapping to **Drilling only** is recommended. This option gives the highest priority to the input data itself while still allowing the surface to be influenced by manual interpretations. Contrary to the **All data** snapping option, the **Drilling only** option also reduces the potential for complications resulting from contradictory data (e.g. the drilling data indicates a surface contact is in one place, but a polyline indicates it's somewhere else).

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data.

For example, here the **Snap to data** has been set to **Drilling only** for a mesh created from multiple data objects:

B	Edit Mesh	- Mesh from mult	iple data t	/pes			×
l	General	Boundary	Trend	Value Transform	Interpolant		_
	<u>S</u> nap to	resolution: 50 data: Drilling o m snap distance Input GIS line 102 contacts D2 contacts	nly tacts	<u>A</u> daptive		25.00	
		C contacts					
	<u>N</u> ame:	Mesh from mult	iple data t	/pes			
(?			Cano	cel	<u>0</u> K	

Note that the only objects **Snap** is enabled for are the contacts derived from borehole data.

Here, **Snap to data** has been set to **Custom**, which makes it possible to enable **Snap** for only the selected data objects:

ø	Edit Mesh	- Mesh from mu	ltiple data i	types		×
	General	Boundary	Trend	Value Transform	Interpolant	
	Surface	resolution: 50		Adaptive		
	Snap to	data: Custom				~
	Maximu	m snap <u>d</u> istance		•		25.00
	Snap	Input				
		🚝 GIS line				
	V	🎎 D2 - D1 co	ntacts			
		D2 contac	ts			
		points				
		🦿 contacts				
	-					
	Name:	Mesh from mu	Itiple data t	types		
	_					
(?)			<u>C</u> a	ncel	<u>о</u> к

In Leapfrog Works, the snap settings for different types of surfaces can be controlled as follows:

- For geological models, **Snap to data** can be set for the model as a whole, but individual surfaces can have different settings. For more information, see:
 - Editing a Geological Model
 - Surfacing Options for Deposits and Erosions
 - Surfacing Options for Intrusions
 - Surfacing Options for Veins
 - Surfacing Options for Faults
 - Changing Fault Inputs
- For editable interpolated meshes and offset meshes (a), **Snap to data** can be set by doubleclicking on the mesh and changing the settings in the **General** tab. See <u>Refining an Interpolated</u> <u>Mesh</u> and <u>Offset Meshes</u> for more information.

Editing Surfaces With Polylines


In Leapfrog Works, many surfaces can be edited using polylines, including contact surfaces, geological model extents and editable meshes.

To edit a surface with a polyline, it is a good idea to first add the object you wish to edit to the scene and draw a slice across the scene where you plan to edit the surface. Next, right-click on the surface in the project tree and select **Edit > With Polyline**.


The drawing toolbar will appear for the type of polyline selected and a new polyline will be added to the scene. Draw the polyline and adjust it as described in <u>Drawing in the Scene</u>, then click the **Save** button () to view the effect of the polyline on the surface. To remove the polyline from the surface, expand the surface in the project tree. Right-click on the polyline object and select **Remove**.

In cases where you have existing polyline edits (control points), you can import them and add them to the surface. To do this, import the polylines to the **Polylines** folder, then add them to the surface by right-clicking on the surface and selecting **Add > Polyline**.


How a polyline can be used to edit a surface can be illustrated by the following surface, where a small volume is disconnected from the main surface:




First, a slice is drawn through the surface where it will be edited:



Next, a polyline is created, using two lines to represent contacts that link up the surfaces:



When the polyline edits are saved, the surface is updated to reflect the edits:



It is best to keep polyline edits to a minimum, as small edits can have significant effects on the shapes of surfaces.

If editing a surface with a polyline results in a distorted surface, use the surface and normal ribbons to check the orientation of the polyline and its segments. See <u>Tangents and Ribbons</u> for more information.

When you save the polyline, the object will be updated to reflect the additional points. The polyline will be added to the project tree as part of the object that was edited. You can edit the polyline by doubleclicking on it or by right-clicking and selecting **Edit Polyline**.

Editing Surfaces With Structural Data

In Leapfrog Works, many surfaces can be edited using planar structural data points drawn in the scene. Surfaces that can be edited in this way include contact surfaces, model extents and interpolated editable meshes. There are two ways to do this:

- If you have a structural data table created in or imported into Leapfrog Works that you want to use to adjust the surface, right-click on the surface in the project tree and select Add > Structural Data. You will be prompted to select from the structural data tables available in the project.
- If you want to create structural data points to use to adjust the surface, right-click on the surface in the project tree and select **Edit > With Structural Data**.

To edit a surface with structural data using the second option, it is a good idea to first add the object you wish to edit to the scene. Next, right-click on the surface in the project tree and select the **Edit > With Structural Data** option.

The structural data toolbar will appear and a new structural data object will be added to the scene. Draw the structural data points and adjust them as described in <u>Creating New Planar Structural Data Tables</u>,


then click the **Save** button (a) to view the effect on the surface. Structural data tables created in this way cannot be used by other objects in the project until the table has been shared. To do this, right-click on the table in the project tree and select **Share**. The structural data table will be saved to the **Structural Modelling** folder.

To remove the structural data from the surface, expand the surface in the project tree. Right-click on the structural data object and select **Remove**.


Modifying Surfaces With Anisotropic Trends


More detailed information on <u>Global Trends</u> can be found in the <u>Trends and Anisotropy</u> topic.

How the moving plane can be used to adjust a surface in this manner is illustrated by the following intrusive contact surface:



The intrusion surface has two bodies that are not connected, and we can apply a trend to connect the two parts. Here, the intrusion surface has been hidden in the scene and the scene rotated to line up the QzP segments. A plane line can then be drawn through the QzP segments:





Using the plane settings to adjust the surface results in the two parts of the intrusion joining up:

Applying a Structural Trend

More detailed information on <u>Structural Trends</u> can be found in the <u>Trends and Anisotropy</u> topic.

To apply a structural trend to an interpolated editable mesh or an interpolant, double-click on the object in the project tree and click on the **Trend** tab:


Edit QzP							
Lithologies	Sur	facing	Inputs	Trend	Value 0	lipping	Interpolant
🔿 Global Tr <u>e</u> n	d						
		Dip		Dip Azim	uth	Pitch	
Directions:		34.33		, 132.09		, 179.07	
		Maximun	n	Intermed		Minimur	m
Ellipsoid Ra	atios:	3		, 3		, 1	
Vie	w Pla	ne	Set	From Plane	e	<u>S</u> et t	to
Structural T	rend						
_{structura}	al tren	d					\sim
Outside value:	-1						0
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
Outsi <u>d</u> e value:	-1						
	-1						

To apply a structural trend to an intrusion contact surface, enable **Show additional surfacing options** in the **Surfacing** tab, then click on the **Trend** tab:


🔏 Edit QzP		×
Lithologies	Surfacing Inputs Trend	
Boundary filter:	Custom	~
Snap to data:	Inherit from GM (Off)	~
Maximum snap	distance: 1	2.50
✓ Inherit resolut	tion from GM	
Surface resol	Iution: 25.00 🗘 🗌 Adaptive	
Additional op	tions	
Name: QzP		
?	<u>C</u> ancel <u>Q</u> K	

Click on **Structural Trend**, then select the required trend from the list. Click **OK** to apply the trend to the surface.

When a structural trend is applied, surfaces may appear distorted further away from the data:



If this is the case, experiment with the **Outside value** setting. The **Outside value** is the long-range mean value of the data. Setting a value of -1 for intrusions (where the positive values are on the inside) and +1 for other surfaces will result in a smoother surface in most cases. For example, here, the **Outside value** has been set to -1 for this intrusion, resulting in a much smoother surface:



Trends and Anisotropy

A point source of light radiates in all directions equally, and the intensity of that radiated light decreases at a rate equal to the inverse of the square of the distance from the source. This radiation is isotropic, and in many fields isotropic behaviour can be assumed when making measurements. Geologists are well aware that, in their field, this cannot be assumed. Because of the processes involved in rock and strata formation involving sedimentation, compression and igneous flows, measurements can demonstrate strong trends in one particular direction or plane, but weak trends in an orthogonal direction. Leapfrog provides tools to account for this anisotropy when modelling, including:

- Global Trends
- Structural Trends
- Variable Orientation
- Variography

Global Trends

The most basic anisotropy tool is the global trend. As the name suggests, this applies the anisotropic trend globally. It is suitable for use in situations where the underlying geology suggests that the anisotropy is planar and continuous over a large area. The global trend sets a constant trend that will favour grade continuity in one direction. When calculating interpolants and modelling, the application of this global trend will reflect the favouring of the trend direction.

Where an object includes a **Trend** tab in its settings, you can directly specify the **Dip**, **Dip Azimuth** and **Pitch** directions, as well as the **Maximum**, **Intermed** and **Minimum** ellipsoid ratios.

The global trend is expressed in the form of ratios in three orthogonal directions, described as the major ("**Maximum**"), semi-major ("**Intermed**") and minor ("**Minimum**") axes of an ellipsoid. When the same value is used for each axis, the ellipsoid is spherical and the global trend is isotropic. Reducing the ratio in the minor axis direction relative to the major and semi-major axes produces an oblate discus-shaped anisotropic trend that de-emphasises the minor axis direction. This sort of global trend is typical for modelling structures that have undergone compression.

Increasing the ratio value in the major axis direction, while having a lower ratio for the semi-major axis and smaller still for the minor axis, further emphasises the trend in the **Maximum** direction. This sort of global trend is typical for modelling structures formed from flows. When the geology is modelled, the **Maximum** direction of the trend is favoured over the other directions, and the **Minimum** direction is de-emphasised.

When the semi-major and minor axes have the same value and the major axis is larger, this emphasises the trend in only in the **Maximum** direction. This results in a prolate cigar-shaped anisotropic trend.

Leapfrog does not enforce that the ratios for the global trend axes are such that the values for **Maximum** > **Intermediate** > **Minimum**. As such, it is possible to create an ellipsoid that has a trend strongest in, say, the **Minimum** direction. This should be avoided as it will likely produce confusion, especially for others endeavouring to understand the geology modelled in the project.

The global trend ellipsoid can be oriented in any direction other than the x, y and z axes of the model by rotating it using **Dip**, **Dip Azimuth** and **Pitch** controls.

You can use the **View Plane** button to add a moving plane to the scene and use the handles on the moving plane to adjust the **Dip**, **Dip Azimuth** and **Pitch** which will be updated when the **Set From Plane** button is clicked. The moving plane indicates the orientation of the major-semimajor axis of the

trend ellipsoid, with the **Maximum** trend direction in the direction of the green **Pitch** arrow. Ellipsoid ratios cannot be set from the moving plane.

The Ellipsoid Ratios determine the relative shape and strength of the ellipsoids in the scene, where:


- The **Maximum** value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The Minimum value is the relative strength in the direction orthogonal to the plane.

Often the easiest way to apply a trend is to click on the **Draw plane line** button (27) and draw a plane line in the scene in the direction in which you wish to adjust the surface. You may need to rotate the scene to see the plane properly. Once you have adjusted the plane to represent the trend you wish to use, click the **Set From Plane** button to copy the moving plane settings.


The **Set to** list contains a number of different options Leapfrog Works has generated based on the data used in the project. **Isotropic** is the default option used when the surface was created. Settings made to other surfaces in the project will also be listed, which makes it easy to apply the same settings to many surfaces.

Anisotropic or Ellipsoidal Distance

When a trend is applied during modelling, distances between points are scaled proportionally to the ellipsoidal trend, creating a concept called the anisotropic distance or ellipsoidal distance. When interpolating to calculate a value at a specific point, measured data points closer to that point will have more influence in the interpolation calculation. When a trend is applied, the anisotropic distance is used instead of the actual distance. In the trend's **Maximum** direction we want the measured data points to have more influence, so the anisotropic distance is smaller than the actual distance. We divide the actual distance by the **Maximum** axis ratio, so if the ellipsoid **Maximum** ratio is 4, the anisotropic distance to a point in the maximum direction is ¼ the actual distance, significantly increasing the influence of a measured point in that direction. If the Intermediate ratio is 2, the anisotropic distance to a point in that direction is ½ the actual distance, again increasing the influence of a measured point in that direction is 1/2 the actual distance, again increasing the influence of a measured point in that direction is 1/2 the actual distance again increasing the influence of a measured point in that direction, though not as significantly as in the **Maximum** direction. Consider this diagram demonstrating how points equidistant from a central point are treated when an anisotropic trend is applied, with the ratios **Maximum** = 4, **Intermediate** = 2 and **Minimum** = 1.



It may be useful to think of the ellipsoidal trend as warping spacetime, making the apparent anisotropic distance or ellipsoidal distance shorter in emphasised directions. Still, it is not normally necessary to envisage things by anisotropic distances. More intuitively, interpolated surfaces modelled using trends clearly demonstrate the emphasis indicated by the trend ellipsoid proportions and orientation.




When you have the Contaminants extension, the trend can also be visualised in the scene as an ellipsoid. For more information, see <u>The Ellipsoid Widget</u>.

Where the underlying geology shows that it cannot be assumed that the anisotropy is planar and continuous over a large area, Leapfrog provides additional tools.


Structural Trends

When there is a gradual shift in the direction of the grade continuity, perhaps due to flows, a global trend will not suffice to model the geology. In this case, Leapfrog's structural trend tool is more appropriate. A structural trend localises trend modelling to indicate changes in direction of continuity. A selected surface or structural data is used as an indicator to locally align the trend direction. The result is that for any given point of interest, the trend orientation is specific and appropriate to that location.



When displayed in the scene, the structural trend is rendered as a grid of oblate ellipsoids. The grid has regular 10x10x10 spacing which enclose the extents of the structural trend's inputs. The orientation of the disk gives the direction of the anisotropy. The size of a disk is proportional to the anisotropy strength. Where there are no disks (or the size is very small) the trend is isotropic.

Note that when a structural trend is used in an interpolation, the locations of the depicted ellipsoids are not the only locations influenced by the structural trend. They are discrete points used to visualise the continuous structural trend effect. If you would like to study a specific area in closer detail, make a copy of the source mesh and select the mesh extents to clip the area of interest. Create another structural trend using this smaller mesh, and you will get a higher-resolution visualisation of the structural trend in that area.



The above scenes depict the result when the **Trend Type** is set to **Non-decaying**. In these illustrations, a mesh has been selected and added to **Trend Inputs** and a trend **Strength** specified. Because the strength of the trend does not decay, all the ellipsoid disks are the same size but may point in different directions.

Creating a Structural Trend


To create a new structural trend, right-click on the **Structural Trends** folder (in the **Structural Modelling** folder) and select **New Structural Trend**. The **Structural Trend** window will appear:

Structural Trend					×
Structural Trend	Global Mean <u>T</u> rend				
Trend Typ <u>e</u>					
Non-decaying				\sim	
Compatibilit <u>y</u> :	Version 2			\sim	
Trend Inputs					
Input			Strength	Range	
÷ 🛍	\$				
Name: Structural Tr	end				5
?		<u>C</u> ancel		<u>0</u> K	

Structural trends can be created from surfaces and from structural data. Click **Add** to select from the suitable inputs available in the project. The list of inputs will be displayed:


Structural Trend	Select Trend Inputs X
Structural Trend Glo	✓ Topography
Trend Typ <u>e</u> Non-decaying Compatibility: Vers	 □ ♣ Topography ✓ □ Meshes □ ☆ Leda_Topo □ ☆ Hypothesis 1
Trend Inputs Input	Hypothesis 2 Hypothesis 3 Structural Trend Mesh
	Comparison of the second seco
+ i >	 ✓ @ GM ✓ □ @ GM: Boundary □ @ GM: Topography
Name: Structural Trend	✓ m Surface Chronology □
?	<u>C</u> ancel <u>OK</u>

Tick the box for each input required, then click **OK**. The selected inputs will be added to the **Structural Trend** window:



The **Non-decaying** option can be used when it can be assumed that the strength of the trend does not decay as you get further away from the mesh. This is useful when the geology has a fairly constant trend across the model, but with some directional shift. The **Strength** parameter describes how many times stronger the trend is in the maximum and intermediate plane than in the minimum direction. Note that when using a structural trend, the maximum and intermediate directions use the same strength value, so the depicted ellipsoids will always be oblate spheroids and cannot be prolate.

Where a trend is isolated to a region near a structure and the influence away from the structure decreases, an effect **Range** can be specified in conjunction with the **Trend Type** option **Strongest along inputs**. Where the trend approaches an isotopic trend, no ellipsoid is visualised.




Away from the structural trend, you can specify the overall global trend that the model should tend towards. The **Global Mean Trend** tab lets you set this as for a global trend, with **Maximum**, **Intermed** and **Minimum** ellipsoid ranges, and **Dip**, **Dip Azimuth** and **Pitch** directions. To set this, click on the **Global Mean Trend** tab.


😵 Structural Trend				×
Structural Trend	Global Mean <u>T</u> rend			
Global Trend				
	Dip	Dip Azimuth	Pitch	
Directions:	0	, 0	, 90	
	Maximum	Intermed.	Minimum	
Ellipsoid R <u>a</u> tios:	1	, 1	, 1	
<u>V</u> iew Pla	ne Set	From <u>P</u> lane	<u>S</u> et to \lor	
Name: Strongest Alo	ng Inputel			
Mame. Strongest Alo	ng mpata			
?		<u>C</u> ancel	<u>0</u> K	

You can enter the trend manually or add the moving plane to the scene and set the trend using the moving plane, as described in <u>Global Trends</u>.

For instance, here a **Strongest along inputs** trend has been added to a global mean trend that goes in a very different direction.



Complex trend interactions can be modelled using structural trends by describing the trend components for each structure. Select **Blending** as the **Trend Type**, then add each input mesh to the **Trend Inputs** list, specifying an appropriate **Strength** and **Range** for each. The **Blending** option requires multiple meshes and blends them according to their individual strength settings. A trend with higher strength makes a stronger impact on the blending. The blended trend is a decaying type, and its strength weakens further away from the mesh. Leapfrog Geo will blend the trends at the places they interact. Because of the strength blending, some of these ellipsoids may end up prolate, but each of the component trend strengths can still only be configured using the same strength value for the maximum and intermediate directions. The **Global Mean Trend** tab can also be used to add an overall trend magnitude and orientation to the model.



Compatibility

Structural Trends includes an option to select the Compatibility as Version 1 or Version 2. Version 2 is the default and preferred option for all new models, as Version 1 is deprecated and retained for compatibility with existing, older models. Version 2 employs an improved strategy to ensure small changes such as the addition of a few new data points does not trigger a significant recalculation of the whole model. Both strategies use clusters of data with similar locations and trend orientations. These


clusters are interpolated separately using the average trends across each cluster and then the interpolants are combined, smoothed with a weighed average. **Version 1** recalculated the clusters whenever new data was added, potentially causing significant model changes from a small data change. **Version 2** retains the clusters and only the clusters immediately surrounding the new data are updated, limiting the effect of the change.

Variable Orientation

For Kriging and other estimations, structural trends do not provide the needed control over the anisotropy ratios, among other considerations. For this purpose, **Variable Orientation** can be used.

This feature is only available when you have the Contaminants extension.

Variable orientation provides a similar control over the changing direction of anisotropy for the purposes of improving local value estimates, orienting the search space and variogram according to local characteristics. Variable orientation is visualised using lines or, as in this illustration, flat disks with a line indicating the orientation of the maximum axis direction for each search space local to each centroid. Here the disks have also been coloured reflecting the **Dip** direction.




For a full description of this feature, please see Variable Orientations.

Variography

This feature is only available when you have the Contaminants extension.

Variography is the analysis of spatial variability of grade within a region. This is an intrinsic part of the estimator functions available as part of the Contaminant extension. Understanding how sample grades relate to each other in space is a vital step in informing grades in a block model. A variogram is used to quantify this spatial variability between samples. A theoretical variogram is developed as a hypothesis attempting to describe this spatial variability, and experimental variography tools are used to visualise and test this hypothesised variogram



For more information on the variography capabilities in the Contaminant extension, see <u>Experimental</u> Variography and Variogram Models.


Polarity in Leapfrog Works

Polarity refers to which side of an object is considered the "inside" or "outside", or the "younger" or "older" side. When used correctly, polarity is a useful tool for controlling structurally complex surfaces, defining how custom boundaries are applied to models or controlling how meshes are clipped during mesh operations. Object polarity can cause unexpected or confusing results if the polarity of an object is different to what was intended or expected.


Polylines, surfaces and structural data all have polarity in Leapfrog Works.

Polarity and Polylines

When a polyline is drawn on a two-dimensional plane such as the slicer, the orientation of the polyline will be consistent. When a polyline is drawn on a three-dimensional object, however, each segment in the polyline will have a different "in" and "out" orientation. To see the line polarity, and the polyline to the scene and increase the **Ribbon width** so a clear ribbon extends away from the polyline. This will help you to see not only how a line changes direction, but also how it twists. You can view the **Surface ribbon** (**P**) as shown here:



Or you can choose the **Normal ribbon** (=), which depicts the ribbon at the normal (or, right angles to) the **Surface ribbon** view:




Invert Polyline Polarity


If the whole line has the wrong polarity, you can select the line then click the **Flip selected objects** button (\mathbb{M}).

Adjust Polyline Polarity Using Tangents


To adjust a portion of a polyline, one tool you might choose is the **Add or set tangents at the selected points, from the current viewing angle** button (**S**). Click on the line where you would like the tangent inserted, then click the (**S**) button. This will add a tangent pointed directly away from the current viewing perspective, and whole line will be twisted so the surface ribbon is aligned in the direction of the viewing angle also, up to the point that some other part of the ribbon has an existing tangent set (if any).



To achieve the desired result, you may need to reposition the viewing angle and set additional tangent points.



Imported polylines can often have inconsistent polarity across different parts of the polyline, which can limit their usefulness until the polarity issues are addressed. Observe how a inverted polarity direction in one part of a polyline can affect a mesh built from the polyline:




If you are editing a surface with a polyline and you get an unexpected result such as the one shown above, check the polarity of your polyline disks.


Polarity and Surfaces

Almost every mesh added to the scene in Leapfrog Works, including meshes from the **Meshes** folder or surfaces from a geological model, will have one colour on one side of the surface and a different colour on the other side. This represents the polarity of the surface, identifying what is considered the 'outside' and the 'inside' of the surface. Note that numeric model isosurfaces and form interpolant surfaces do not have polarity.

When a surface from the **Meshes** folder is added to the scene, by default the colouring is red for the inside and blue for the outside of the mesh.




When a surface from a geological model is added to the scene, the colours reflect the relevant unit colours defined by the drillhole data, and the polarity represents the "younging" side. Here a couple of surfaces separating some stratigraphic layers are revealed, and the colour of each side of the surface is consistent with the stratigraphic layer it contacts.



Polarity and Structural Data


The polarity of structural data is also indicated by the colouring of the disk sides. The orientation of a structural data disk is initially set when it is drawn, according to the direction the mouse was dragged after clicking on the place to insert the disk:




Then the tilt of the disk is set in the **Planar Structural Data** window. Note also the **Flip Polarity** button to invert the orientation of the disk if the disk was accidentally drawn in the wrong way.

		1/	48°	_	/		
	Planar Struct	ural Data		×			
	Point:	6					
	East (X):	10629.355657272272		0			
	North (Y):	100680.42531516719		0			
	Elev. (Z):	699.6210013338024		0			
	Dip:	46		0			
	Dip <u>A</u> zimuth:	201.99		0	0		1/
5							V
1						46°	1
-					•		12
		<u>F</u> lip Polarity				A A	7
		D <u>e</u> lete Point					×
				-			
~	_		-	-/-			7.1
						54°	
			"EE	0			
			22				-

Consistency of polarity is important to get a consistently oriented surface created from the structural data, a surface with a clear 'inside' and 'outside'.



Where structural data has been placed with inconsistent polarity, any resulting surface will have a contorted and inappropriate shape due to unclear 'inside' and 'outside' directions. If you are editing a surface with structural data and you get an unexpected result such as the one shown below, check the polarity of your structural data disks.



Boundaries in Leapfrog Works Projects

This topic discusses boundaries in Leapfrog Works. It is divided into:

- The Clipping Boundary
- Object Extents
- Extending a Surface

A newly-created project has only a basic set of X-Y-Z coordinates, and the coordinate system used by the project is determined by the data imported to the project. It is not necessary to specify what coordinate system is used; however, it is necessary to ensure that data you import into the project uses the same coordinate system.

Often the best way to set the coordinates for the project as a whole is to import a map or aerial photo. Adding georeference data to a map will set the location of the map in three-dimensional space and set the coordinates for the project. See <u>Importing a Map or Image</u> for more information.

An important consideration in defining the project space is setting the clipping boundary. See <u>The</u> <u>Clipping Boundary</u>.

It is not necessary to define a topography to model in Leapfrog Works, but a defined topography can be used as an upper boundary for all models built in the project. See <u>Defining a Topography</u>.

Part of creating many objects in Leapfrog Works is defining the basic rectangular boundary that defines the object's extents. See <u>Object Extents</u>.

You can modify the extents of geological models and interpolants using surfaces created from different types of data. See <u>Modifying a Geological Model's Boundary</u> and <u>Modifying an RBF Interpolant's</u> Boundary With Lateral Extents.

The Clipping Boundary


An important consideration in defining the project space is setting the clipping boundary.

The default clipping boundary in a new project file encompasses everything in the project and grows as more data is added to the project. It is not necessary to set the clipping boundary. However, the clipping

boundary defines the limits of the X-Y coordinates for the region in which data will be imported and models built and so defines the region in which calculations are made. Restricting the size of the clipping boundary limits the area in which calculations are made and is especially important if you are working with a large dataset.

The best way to set the clipping boundary is using an imported map or aerial photo, as this provides a visual reference that is helpful in working with data added to the project in the future. GIS data or borehole data can also be used to set the clipping boundary.

To set the clipping boundary, add to the scene the objects you wish to reference in setting the boundary. Right-click on the **Topographies** folder or on the **GIS Data, Maps and Photos** folder and select **Set Clipping Boundary**. The **Set Clipping Boundary** window will be displayed, together with controls in the scene you can use to resize the clipping boundary:




There are three ways to define the rectangular clipping boundary:

- Enter the coordinates.
- Select **Enclose Object** and choose from the list of objects in the project. The clipping boundary will be updated using the selected object.
- Use the controls that appear in the scene. The orange handle adjusts the corner of the clipping boundary and the red handles adjusts its size.


When you have finished adjusting the clipping boundary, click **OK**.

If you are going to import elevation data and use it to create a topography, it is important to set the clipping boundary before creating the topography. For example, here a map has been imported and a topography (yellow) has been created from an elevation grid. The map is displayed draped on the topography:



The red arrows and orange handle show the clipping boundary, which has been allowed to expand to encompass all data imported to the project. Because the topography was created before the clipping boundary was set, all the data in the imported elevation grid has been used and the resulting topography is larger than might be practical. Clearly, if the intention is to model within the area on the map, the clipping boundary should be limited to the region indicated by the map.


If the map is the only object in the project, it can easily be used to set the clipping boundary by selecting **<Everything>** from the **Enclose Object** list:





This results in a clipping boundary that is limited to the extents of the map:

Once the clipping boundary has been set, further data imported into the project will be clipped to it. For example, importing an elevation grid and using it to create a topography only after the clipping boundary has been set to the map extents will result in a topography (with the map draped) that looks like this, with only a narrow yellow boundary:



Object Extents

Part of creating many objects in Leapfrog Works is defining the basic rectangular boundary that defines the object's extents. There are generally two options for defining an object's extents:

- The first option is to define extents that are independent of other objects in the project. You can do this by entering coordinates or adjusting controls in the scene to set the size and shape of the extents. The new object's extents are fixed to the specified size. This is a good choice if, for example, you are building a geological model from a map and wish to define the model extents based on information on the map.
- The second option is to define extents based on other objects in the project. This is done by selecting the other object from the **Enclose Object** list that appears in many Leapfrog Works screens.

For both methods, the new object's extents are fixed to the selected size. Using the **Enclose Object** list does not link the two objects; it is simply using the X-Y-Z coordinates of the original object as the basis for the new extents.

For example, here, a geological model's extents could be defined using the lithology segments used as the base lithology:

🎉 New Geolog	jical Model		×
General			
Base litholo	ogy column:	🎼 Ro	cktype 🗸
<u>F</u> ilter data:		<none< th=""><th>•</th></none<>	•
Surface res	olution:	400.0	🗘 🗌 <u>A</u> daptive
Model Extent	s		
	Minimu	ım	Maximum
X (East):	1492257.3	1614 ()	1499808.49134 🗘
Y (North):	5216102.14	1260 : 🗘	5219516.21746: 🗘
<u>Z</u> (Elev):	-37.66	¢	1370.66 🗘
			Enclose Object V
Name: GM			Clipping boundary
Marrie. Givi			✓ 🗀 Borehole Data
			V Boreholes
?	<u>C</u> ancel		collar
			litho N
GIS Data:	a Geolog	ical Map	🚄 structures
Iitho			✓ ☐ Points
			Topography_vertices
			✓ 🗀 Meshes
			🔗 Topography

When creating some objects, you have the option of sharing extents with another object. This is the case with editable meshes ((a)), where you can choose whether the mesh has its own extents or shares extents with other objects in the project. Shared extents are updated when the original object's extents are updated.

If you are unsure about relationships between objects, expand them in the project tree to view more information. Here, two meshes have been defined from the same set of points. The first mesh has its own extents that are not updated by other objects in the project, whereas the second mesh shares its extents with those of the RockType geological model.




Geological models and interpolants are created with a basic set of rectangular extents that can then be refined by adding extents created from other data in the project. Creating extents is a useful way of restricting modelling to a particular area of interest. For example, modelling can be restricted to a known distance from borehole data by applying a distance function as a lateral extent. See <u>Modifying a</u> <u>Geological Model's Boundary</u> for more information.

Extending a Surface

Geological models created in a Leapfrog Works project automatically use the defined topography as an upper boundary. If a model is defined that extends outside the topography, an error will occur. A similar error occurs when surfaces used in geological models do not extend outside the model's extents. In all cases, Leapfrog Works cannot process the surface and an error will be displayed.

In this example, an error has occurred during the process of creating a geological model because the model extents (pink) do not fall completely inside of the topography:



In order for Leapfrog Works to be able to divide the model into separate volumes, the topography needs to be extended to enclose the model's boundary or the model's boundary needs to be restricted so it falls inside the topography.

The solutions proposed will depend upon the data used to create the surfaces that conflict, but fall into three broad categories:

- Reduce the size of the model's or interpolant's extents. Click the **Edit Extents** button. This will open the object's **Boundary** window and you can change the boundary.
- Enlarge the topography by manually adjusting it. Click on the **Edit Topography Extents** button. This option is only available when the topography has been created from more than one data source. See <u>Adding Height Data to the Topography</u> and <u>Changing Topography Settings</u>.
- Use the surface's vertices to create the boundary or contact with extents large enough to be used in the model or interpolant. Click the **Use Vertices** button to create a new vertices object and use it as the source data for the boundary or contact.


If you have a solution to the problem that is not covered by the options presented, click **Do Nothing**. For example:

• If the topography is not large enough, there may be additional data available. If it is not already in the project, import the data and add it to the topography as described in <u>Adding Height Data to the</u>

Topography.

• If a surface being used to define a contact surface or boundary in a geological model or interpolant is not large enough, you can add additional data to the surface.

Using vertices to create the boundary or contact results in the creation of a new points object that will be saved in the **Points** folder. For example, here the geological model uses vertices to create the "Topography" used as an extent:



Using topography vertices can take some time to process.

An additional disadvantage to using vertices is that the vertices object created is not linked to the original object, and when the object used to create the vertices changes, the vertices will not be updated.

Central Integration

Central's integration with Leapfrog Works lets you work in different project revisions, publish models to the server, view documents and annotations and reply to annotations. Projects shared within Central can be downloaded and worked on locally in Leapfrog Works. When you have finished working on a project, select the objects you wish to publish to Central and add notes about the revision. New projects can be added to Central by building them from scratch or by uploading an existing project.

The rest of this topic describes how to connect to Central from within Leapfrog Works. It is divided into:

- Enabling Central Connectivity
- Switching to Using Seequent ID
- Connecting to Central
- Troubleshooting Connectivity Issues

To learn more about Central, see the <u>Central 4.0 help</u>.

Enabling Central Connectivity

To enable Central, open the **Settings** window by clicking on the **Leapfrog Works** menu. Select **Central** and tick the box to enable Central. A **Central Projects** tab will appear in the main window, with a list of Central servers you have access to.

See <u>Central Settings</u> for more information on the other Central-related settings in the **Settings** window.

Switching to Using Seequent ID

If your organisation is switching to using Seequent ID to connect to Central, you may be prompted to change your Central settings when you attempt to connect to your Central server. To do this:

- 1. Click on the **Leapfrog** menu and open the **Settings** window.
- 2. Click on **Central**.
- 3. Enable the Use Seequent ID option.
- 4. Close the Settings window.
- 5. Restart Leapfrog.

The Central servers you have access to via your Seequent ID will be listed in the **Central Projects** tab.

Connecting to Central

The **Central Servers** panel in the **Central Projects** tab shows all the Central servers you have access to. The Central servers you connect to are set up via your Seequent ID.

Projects	Central Proje	ects (Offline)	Scene View	
Central Servers	→ り	New Central Proje	ect	
Select the refresh button to update the server	list		roject	
Central Server - Demodata demodata.central.leapfrog3d.com:8884		Import open p	roject	
Central Server - Help help-beta.central.leapfrog3d.com:8885				
Central Beta beta.central.leapfrog3d.com:8880		Central Server:	Central Beta	 ✓ Offline

If a server you expect to see does not appear in the list, click the refresh button (\bigcirc) .

Click on a server description to connect to it.

Leapfrog Works version 4.0 is compatible with Central Server version 4.0. If you get a message saying that the version of Leapfrog Works you are using is not compatible with the Central Server you are trying to connect to, follow the instructions in the message, then try connecting again.

Troubleshooting Connectivity Issues

Seequent Start checks to see if your network will support the connection of Seequent web-based services to your desktop applications. If you are having trouble with your connection to Central, see <u>Checking Connectivity With Seequent Start</u>.

Central Projects

This topic describes how to work with Central projects in Leapfrog Works. It is divided into:

- Viewing a Project's History
- Sharing Projects
- Downloading a Local Copy of a Project
- New Central Projects

The **Central Servers** panel in the **Central Projects** tab shows all the Central servers you have access to. The Central servers you connect to are set up via your Seequent ID.

Projects	Central Proje	ects (Offline)	Scene View	
Central Servers	→ ೨	New Central Proj	ect	
Select the refresh button to update the server	list	<u>C</u> reate blank p	project	
Central Server - Demodata demodata.central.leapfrog3d.com:8884		Import open p	roject	
Central Server - Help help-beta.central.leapfrog3d.com:8885				
Central Beta beta.central.leapfrog3d.com:8880		Central Server:	Central Beta	 ✓ Offline

If a server you expect to see does not appear in the list, click the refresh button (\bigcirc) .

Click on a server description to connect to it.

Leapfrog Works version 4.0 is compatible with Central Server version 4.0. If you get a message saying that the version of Leapfrog Works you are using is not compatible with the Central Server you are trying to connect to, follow the instructions in the message, then try connecting again.


When you are connected to a Central server, there is an **Open Portal** button that will open the Central user portal in a browser window:

Central Projects	
New Central Project Create blank project Import open project	
Central Server - Help Open Portal	-
Utimate Wolfpass	Wolfpass Canada

Viewing a Project's History

See <u>Projects, Revisions, Branches and Nodes</u> in the <u>Central 4.0 help</u> for an overview of how Central projects are organised.

Once you're connected to a Central server, the **Central Projects** tab shows thumbnails of all the projects you have access to. Use the search bar to narrow down the list of projects displayed.



Projects will be organised by location if there are multiple projects at a given location; otherwise projects will simply appear in a list. If a project you expect to see is not listed, click the **Refresh** button (①) in the **Central Servers** part of the **Central Projects** tab. This will refresh the list of projects for the server you are connected to.

A project's location is set in the Central Portal. You cannot change its location from Leapfrog Works.

Click on a project to view its history, which will open in a new tab.

Central projects are organised into revisions and branches:

- Different points in the modelling process are captured as revisions, which are specific points in time.
- A revision can be the basis for a new branch, exploring an alternative hypothesis.

These are displayed visually in a project's history tab, with local copies of projects shown in the panel at the top of the tab:

\checkmark	Rojects		Scene V	/iew	© c	entral Projects		C Wolfpass	×
.ocal co	pies								
	pen Branc		Ī	Open		2 G d: Unchanged default			
Project h	nistory								0
Graph	ID L	Locked Project	Size	,p Name	App Version	Project Stage	Branch	Date	User
9	701 1	8	110.0	Leapfrog Geo	5.0.3	Peer review	Geo 5.0	22/01/2020	Alex Roci
•	700	• •	1 .0MB	Leapfrog Geo	5.0.3	Peer review	default	29/11/2019	Emerson
	698			Leapfrog Geo	5.0.1	Peer review	default	27/11/2019	Emerson
ł	697			Leapfrog Geo	5.0.1	Peer review	default	27/11/2019	Emerson
ļ.	693			Leapfrog Geo	5.0.1	Peer review	default	28/10/2019	
•	614	8	110.0MB	Leapfrog Geo	4.5.0	Peer review	default	17/04/2019	
	533 2	8	66.0MB	Leapfrog Geo	4.4.0 beta		default	5/10/2018	
	473	8	67.0MB	Leapfrog Geo	4.3.0 beta	Experimental	default	22/05/2018	

Each local copy is numbered so that it can easily be seen what versions have local copies in the **Local** column. The number in the column corresponds to the project in the **Local copies** panel. You can also:

- Click a thumbnail to open a local copy.
- Click the branch/copy number button ()¹) to identify the parent version of the local copy in the project history.
- Click the **Publish** button (6) to publish the copy being edited to Central.
- Click the **Delete** button (¹) to delete a local copy, if the project is not open.

In the **Project history**, revisions are displayed chronologically, from the most recent down to the oldest. In the **Graph**, offshoots from a revision are branches where an alternative hypothesis has been investigated. Changes made in a branch do not appear in other branches; branches effectively diverge from the base revision. The dots on the graph line up with the revision information.


To view more information about a revision, click on it in the history.

Locking Branches

When working on a branch in Leapfrog Works, the branch can be locked so no other Central users can make changes to it. This is useful for letting others users know that a model is being worked on.


The **Locked** column indicates whether or not the branch is available to be worked on. If a branch is locked, hold the cursor over it to see who locked it and when it will be available once again.

To lock a branch, right-click on it in the project history and select **Lock branch**:



In the window that appears, set the **Lock duration** and add any comments. The lock can be set for as little as one day; when the lock expires or when a new publish is completed, the branch will be unlocked for other users. While the branch is locked, other users are still able to download projects, create new branches and publish to branches that are not locked.

If you locked a branch, you can unlock it before the lock expires by right-clicking on it and selecting **Unlock branch**:



You can also ask your Central administrator to unlock a branch.

Project Included

The **Project** column indicates whether or not the Leapfrog Works project was included when the revision was published. If there is no icon displayed, then no project was uploaded when the revision was published. You can view the revision in the Central Browser, but you cannot work on it in Leapfrog Works.


When Leapfrog Works projects are included in a revision, they can be published in a **Complete** state (\blacksquare) or in an **Unprocessed** state (\blacksquare). The difference between the two is whether or not stored modelling calculations are included in the published project. Removing stored modelling calculations can make the upload/download size of a revision considerably smaller and is useful when internet connectivity is poor. The tradeoff is that when the project is downloaded by a Leapfrog Works user, the project will have to be reprocessed before they can use it. This may take some time.

Project Stages

The **Project Stage** is useful for promoting projects through an organisation's procedures. For example, your organisation may have project stages defined that include "Experimental", "Ready for Peer Review" and "Ready for Production". Different stages are displayed in different colours so it is easy to see at a glance what revisions belong to each stage.

Comments and Attachments

With comments, Central Browser and Leapfrog Works users can carry out conversations about specific aspects of the model. Comments include a scene. If you already have the project downloaded and open in Leapfrog Works, you can load the current version of the object referred to by the comment. Click on the scene; you will be prompted to load all the objects or only the unchanged objects:




If the selected scene has a geotag, it will be added to the shape list and displayed in the scene.



Central Browser users can also attach files, which can be downloaded in Leapfrog Works.

Sharing Projects

If you are a project's owner, you can share it with other Central users by clicking the **Share Project** button in the project's history tab:



C 0	CENTRAL	≡			
90 00	Projects	Projects / Wolfpass / Users Wolfpass		OVERVIEW USERS FILES	HISTORY EVENTS
ව්	Users	Users		Si	earch Users Q
ŝ	Integrations	Name	Email	Permissions	,
••	Events				0
J.	Maintenance	Enter Email Address	×	Viewer 🗸 🗌 Export	2+ Assign Users
		Avery Marl	avery.marl@seequent.com	Viewer 🗸 🔲 Export	\otimes
		Brooke Gneiss	brooke.gneiss@indirana.com	Editor 🗸	\otimes
		Emerson Cliff	emerson.cliff@seequent.com	Owner 🧹	\otimes
		Jamie Clay	jamie.clay@indirana.com	Owner 🧹	\otimes
		Pat Shale	pat.shale@seequent.com	Editor 🗸	\otimes

Clicking Share Project opens the Central Portal, displaying the list of users for that project:

You may need to sign in to the Portal.

You can select from the other users in the system or enter a user's email address, then assign their permissions.

There are four levels of project permissions in Central: **Owner**, **Editor**, **Viewer+Export** and **Viewer**. An **Owner** can:

- Assign other users as the owner. A project can have more than one owner.
- Configure and add an integration to a project they own.

A user who uploads a new project to Central is automatically assigned as the project owner.

Editor access allows a user to work in a project in Leapfrog.

Viewer+Export access allows a user to open a project in the Central Browser and export data from the project.

Viewer access allows a user to open a project in the Central Browser and make annotations. They cannot export data from the project.

Downloading a Local Copy of a Project

Select a revision and then click **Download** to download a local copy of the project. The project will be downloaded to the location on your local drive specified in the **Settings > Central** window. A new revision of the project will be created in the history, as an unpublished project.

Click the **Open** button in the **Local copies** panel to open the project:

V 🔒 Pr		C Central	Projects	C Wolfpass	×	Scene View	
ocal copies							
	l H 🛛	6		Mary	۲ 2 6	Î	
EDITING	Modified: 15 Sep 2 Branch: Geo 5.0	2020		Open	Modified: 15 Sep 2020 Branch: Geo 5.0		

Work in the project as you would any other Leapfrog Works project.

New Central Projects


There are two options for putting a project into Central:

- Create a new Central project.
- Put an existing project into Central.

Creating a New Central Project

Use this option to create a new Leapfrog Works project and put it into Central. In the **Central Projects** tab, click **Create blank project**. Enter a name for the project and click **OK**. A new Leapfrog Works project will be created and saved in the location on your local drive specified in the **Settings > Central** window.

Work in the project as you would any other Leapfrog Works project. When you are ready to publish the project to Central, click on the Central button in the lower left-hand corner of the screen and select **Publish**:



Adding a Project to Central

Use this option to add an existing project to Central.

Open the project you wish to import, then in the **Central Projects** tab, click **Import open project**. Enter a new name for the project, if you wish, then click **OK**. The project will be opened and copied to the location on your local drive specified in the **Settings > Central** window.

Work in the project as you would any other Leapfrog Works project. When you are ready to publish the project to Central, click on the Central button in the lower left-hand corner of the screen and select **Publish**.

Publishing to Central

See <u>Projects, Revisions, Branches and Nodes</u> in the <u>Central 4.0 help</u> for an overview of how Leapfrog Works projects are organised into revisions when they are published to Central.

When you publish a revision to Central, there are different choices you can make as to what objects are included and whether or not a Leapfrog Works project is uploaded as part of the revision.

• When you select objects to publish to Central, the objects will be available for visualisation in the Central Browser and the Central Portal. You can choose to publish all objects in a project, but if your team's discussion is limited to, for example, a subset of data or one or two models, it might be best to publish only those objects relevant to the discussion.

• When you choose to include a Leapfrog Works project, other Leapfrog Works users who have access to the project via Central can download a copy of the project and work in it.

When you are ready to publish your project to Central, you can start the publishing process by clicking on the Central button in the lower left-hand corner of the screen and selecting **Publish**:

Log Out	
Settings	
Publish	
€ Logged In ∨	ှို Dacite Fold

You can also select the **Publish** button (**S**) in the **Local copies** panel:

T.


Y 🐣 Pr	ojects		Central F	Projects		C Wolfpas	8	×	Scene View
ocal copies									
M. A. Barrenser	F D	6	Î		Magner	부 2		Û	
Open	Modified: 11 Aug 2 Branch: Geo 5.0	020			EDITING	Modified: 15 S Branch: Geo 5	Publis	h	

The rest of this topic describes the steps in publishing a project to Central. These are:

- Unfinished Publish Events
- Selecting Objects
- Setting the Project Workflow Stage
- Including the Project
- Adding Revision Information and Branching
- Preparing the Package
- Uploading the Package

Unfinished Publish Events

When you click **Publish**, you may receive a message saying there is an unfinished publish event:




This occurs when a previous publish event was interrupted. Choose from the options presented. If the publish event was abandoned, it can be removed via the Central Portal.

Selecting Objects

Select the objects you wish to publish from those available in the project.

Most data types in Leapfrog Works projects can be published to Central. If a data object is not listed in the **Publish** window, then the publishing of that data type is not yet supported.

When you publish a project revision to Central from Leapfrog Works and wish to make a data object available for use in other projects, make sure you select that object from those in the project:



For example, in the project above, the data objects that will be available for use in other projects on the same Central server are:

- The Topography mesh
- The surfaces in the Lithology geological model
- The surfaces in the AG_gpt and AS_ppm numeric models

Unticked objects such as the Distance to collar mesh, the topography inside Distance to collar mesh and the AU_gpt numeric model will not be available.

Click **Next** to choose options for how the project will be uploaded.

Setting the Project Workflow Stage

Project stages are useful for advancing projects through an organisation's processes. If the project is ready to be moved on to a different stage, select a different **Project Workflow Stage** from the list. Project stages can later be changed in the Central Browser.

Including the Project

Select whether or not to include the Leapfrog Works project. There are three options:

- No. The Leapfrog Works project will not be published. Other Central users will not be able to download the project and work on it in Leapfrog Works. They will, however, be able to review the published objects and their history in the Central Browser.
- **Complete**. This option publishes the complete Leapfrog Works project, including stored modelling calculations. Other Central users will be able to download the project and work on it in Leapfrog Works without reprocessing the project.

• **Unprocessed**. An unprocessed project has a smaller upload/download size because stored modelling calculations are removed. When an unprocessed project is downloaded again, all of the modelling calculations will need to be reprocessed from the underlying data. Other Central users will be able to download the project and work on it in Leapfrog Works. Depending on the size of the project, reprocessing may take some time.

Click Next.

Adding Revision Information and Branching

Enter information about the new revision. If you want to create a new branch, click the **New Branch** button and enter a name for the branch.

Once you branch from a timeline, you cannot merge back into it. There's no reason, however, that you can't keep working in a branch and start considering that the main branch, if that's the conclusion you and your team reach.

Preparing the Package

Click **Next** to begin the processes of packaging the project for publication.

Uploading the Package

Once the project has been packaged, there are two options for starting the upload:

- If you want the upload to begin automatically once the package has been prepared, tick the **Auto upload** box.
- If you want the option to cancel the upload once it has been packaged, leave the **Auto upload** box unticked. Once the project has been packaged, click **Publish** to upload the project to Central.

If for some reason you need to stop the upload, click on the Central button in the lower left-hand corner of the screen and select **Stop Upload**:

Saved Sce	nes and Movies
Log Out	ions and Contours
Settings	dients
Stop <u>U</u> pload	\$
C Uploading 27	%√ ¦l² default

You can resume the upload by clicking **Publish** in the project history. You will be prompted to resume the unfinished publish event, as described in <u>Unfinished Publish Events</u> above.

If the upload is interrupted because the connection to the server is lost, you will be prompted to finish the publish event the next time you log in to Central.

If you exit Leapfrog Works while a publish event is in progress, you will be warned that a publish event is in progress. You can:

- Cancel exiting Leapfrog Works, in which case the publish event will continue.
- Confirm that you wish to exit Leapfrog Works. The next time you connect to this Central server or publish from this project or from another project on the same server, you will be prompted to the

resume the interrupted publish event. You can complete the interrupted publish event, if you wish, or ignore it.

Importing Data From Central

When you are working on a Central project, you can import some data types from other projects on the same server. In this way, you can easily share data between projects and, if the data object is out-of-date, you can reload it from Central.

Data types that can be imported from Central are:

- Meshes
- Borehole data
- Points
- Polylines
- Planar structural data
- 2D grids
- OMF files

Borehole data and data in OMF files can only be imported from a project's data room. Although borehole data can be published to Central, that is for the purpose of visualising the data in the Central Browser and the Central Portal. Published borehole data cannot be imported into other Leapfrog Works projects.

Geological models and refined geological models can also be imported from Central. Geological models and refined models are imported as static geological models. See <u>Creating a Static Copy of a Geological</u> <u>Model</u> for information on how to work with static geological models.

The rest of this topic describes how to import and reload data from Central. It is divided into:

- Object Availability
- Importing Central Data Objects
- Updating Out-of-Date Objects
- Appending Rows and Adding Columns to Data Tables

Object Availability

With the exception of borehole data and OMF files, data objects that can be imported from Central are those that have been:

- Published to Central as part of a revision via Leapfrog. These appear in the **Import From Central** window in the **Project History** tab.
- Uploaded to the project's Data Room via the Central Portal. These appear in the **Import From Central** window in the **Files** tab.

roject H	listory Files				🥔 Import N	🏄 Import Mesh From Central - Wolfpass							
Graph	Project Stage Peer review Peer review Peer review Peer review Peer review Experimental Experimental Experimental Peer review Peer review Peer review Peer review Peer review	Branch Geo 5.0 default default default default default default default default default default default default default default default	Date 22/01/2020 29/11/2019 27/11/2019 27/11/2019 28/10/2019 5/10/2018 22/05/2018 22/05/2018 10/11/2017 6/07/2017 8/02/2015 23/01/2015	 Colours Topog Meshes Distar topog topog Geologica Eithol Numerici A.Ggi A.Spr A.Ugi CUpd 	ra Project	file to import from Central History Files	Type Folder Folder Folder Folder Folder Folder 1s .ts	Size - - - - - - - - - - 9.0MB 7.0MB 5.3MB	Date	User - - - - - - - - - - - - - Alex Rock Alex Rock			
				<u>C</u> ancel	Suppo	rted formats: *.ara, *.dgn, *.dwg, *.dxf, *.m	sh, *.obj, *.tri, *.ts						

For more information on publishing data to Central, see Publishing to Central in this help system.

When you publish a project revision to Central from Leapfrog Works and wish to make a data object available for use in other projects, make sure you select that object from those in the project:

Publis	h
Select t	he objects to publish
Central I	Browser users will be able to view, track and export the selected object:
\sim C] Meshes
>	Central meshes (current)
>	Central meshes (out-of-date)
>	Meshes with textures
>	Project meshes
	Distance to collar: 1,250
	A topography inside Distance to collar: 1,250
	🔽 🚕 topography
C C	Geological Models
	🗹 🎲 Lithology
\sim	Numeric Models
	🗹 🧿 AG_gpt
	🗹 🖲 AS_ppm
	🗌 🕘 AU_gpt
Publish	to Central
	er: Central Help
Proje	ect: Wolfpass
\bigcirc	Cancel Previous Next

For example, in the project above, the data objects that will be available for use in other projects on the same Central server are:

- The Topography mesh
- The surfaces in the Lithology geological model
- The surfaces in the AG_gpt and AS_ppm numeric models

Unticked objects such as the Distance to collar mesh, the topography inside Distance to collar mesh and the AU_gpt numeric model will not be available.

Importing Central Data Objects

To import data objects from Central, first make sure you are already connected to Central. Then rightclick on the folder for the data type you wish to import and select the **Import From Central** option. In the window that appears, select one of the projects in the repository.

Project H	listory Files					
Graph	Project Stage	Branch	Date	`	- [Topography
•	Peer review	Geo 5.0	22/01/2020			💣 Topography
	Peer review	default	29/11/2019	,	- 0	Meshes
¥ -	Peer review	default	27/11/2019			Distance to collar: 1,250 (click to load)
+	Peer review	default	27/11/2019			Topography (click to load)
+	Peer review	default	28/10/2019			topography inside Distance to collar: 1,250 (click to
+	Peer review	default	17/04/2019			2
+	Experimental	default	5/10/2018			Geological Models
+	Experimental	default	22/05/2018			🎲 Lithology (click to load)
+	Experimental	default	22/05/2018	`] Numeric Models
+	Peer review	default	10/11/2017			 AG_gpt (click to load)
+	Peer review	default	10/11/2017			 AS_ppm (click to load)
+	Peer review	default	6/07/2017			AU_gpt (click to load)
+	Peer review	default	8/02/2015			CU_pct (click to load)
+	Peer review	default	23/01/2015			
<u> </u>	Door review	dofoult	14/01/2015			

In the next window, there are two options, the **Project History** tab and the **Files** list:

In the **Project History** tab, select a revision to view its published objects, then click on a model to load its list of objects. The list displayed will depend on the type of data object you are importing. Here, the surfaces in the project are displayed:

roject	History Files				
Graph	Project Stage	Branch	Date	User	✓ ☐ Geological Models
	Peer review	Geo 5.0	22/01/2020	Alex Rock	V 🙀 Lithology
9	Peer review	default	29/11/2019	Emerson C	🗸 🤪 Boundary
	Peer review	default	27/11/2019	Emerson C	a 250m distance buffer
	Peer review	default	27/11/2019	Emerson C	a topography
	Peer review	default	28/10/2019		Surfaces
	Peer review	default	17/04/2019		
	Experimental	default	5/10/2018		Unknown - Recent contacts
	Experimental	default	22/05/2018		Recent contacts
	Experimental	default	22/05/2018		🛞 Dyke B
	Peer review	default	10/11/2017		🛞 Dyke A
	Peer review	default	10/11/2017		🛞 Dyke C
	Peer review	default	6/07/2017	peter.joynt	👔 Intermineral Diorite
	Peer review	default	8/02/2015	Neville	Early Diorite
	Peer review	default	23/01/2015	Neville	> C Volumes
	Peer review	default	14/01/2015	Neville	
	Peer review	default	8/01/2015	peter.joynt	
9	Peer review	Cover re-model	29/10/2014	john	AG_gpt (click to load)
	Peer review	Cover re-model	16/10/2014	mike	AS_ppm (click to load)
	Peer review	Cover re-model	16/10/2014	peter.joynt	 AU_gpt (click to load)
					CU_pct (click to load)

The **Files** tab shows any files that have been uploaded to the Central project's Data Room:


~											
R											
	Name	Type Size		Date		User					
	Drilling	Folder -				-					
	GIS Data	Folder -									
	Images	Folder -									
	CU_pct - 0.5 - 0.8.ts	.ts									Alex Roc
	CU_pct - 0.8 - 1.0.ts	.ts C	=								Alex Roo
	CU_pct - 1.0 - 1.5.ts	.ts	Pro	ojects / W	olfpass	/ Files					
	Dyke A.msh	.msh		/olfpas					OVERVIEW	USER. FILES	HISTORY EVEN
₽	Dyke B.msh	.msh 🕮									
Ð	Dyke C.msh	.msh		Files						_	
	wp-topo.msh	.msh				March Recycle Bin			Search All Files	🔍 💿 New Folder	<u>↑</u> Upload Files
Support	ted formats: *.ara, *.dgn, *.dwg, *.dxf, *.msh, *.obj, *.tri	i,*.ts			Name		Туре	File Size	Modified On	Modified By	
		E Star									
)		Cancel				Drilling	Folder		Mar 10, 2020	-	
, 		Tauca				GIS Data	Folder		Mar 10, 2020		
						Images	Folder		Mar 10, 2020		
						CU_pct - 0.5 - 0.8.ts	ts	9 MB	Oct 09, 2020	Alex Rock	
					B	CU_pct - 0.8 - 1.0.ts	ts	7 MB	Oct 09, 2020	Alex Rock	
						CU_pct - 1.0 - 1.5.ts	ts	5.3 MB	Oct 09, 2020	Alex Rock	
						CU_pct - 1.0 - 1.5.ts Dyke A.msh	ts msh	5.3 MB 306.2 KB	Oct 09, 2020 Oct 09, 2020	Alex Rock	

Whether you wish to import files from a revision or from the Data Room, use the Shift and Ctrl keys to select as many objects as required. Click **Import** to import the objects, which will be saved into the project tree. Objects imported from Central are displayed using a different icon. For example, here the meshes in the Central meshes (current) folder are marked with the Central logo (O), whereas the meshes in the Project meshes folder are not (O):

V Meshes	
Central meshes (current)	
🔗 Dyke A	
🔗 Dyke B	
> 🔗 Intermineral Diorite	
> 🔗 wp-topo.msh	
> Central meshes (out-of-date)	
✓ □ Project meshes	1
🔗 Dyke A	
🛞 Dyke B	
> 🛞 wp-topo	

Updating Out-of-Date Objects

Leapfrog Works also checks to see if the object imported from Central is the latest version of that object. If a newer version of an object is available, the object's icon will be marked as out-of-date (a):



The options for reloading an out-of-date object depend on whether you imported the object from a project's Data Room or from a project's history.

When you have imported an object from a project's Data Room, you have two options for updating outof-date objects:


- **Reload Latest File Version** imports the newest version of the object available in the Data Room the object was originally imported from.
- **Reload From File History** displays the file's history so you can choose which version you want to use.

Right-click on a data object and choose one of these options.

When you have imported an object from a project's history, you have two options for updating out-ofdate objects:

- **Reload Latest on Branch** imports the newest version available on the branch the out-of-date object was imported from.
- **Reload From Project History** displays the project's history and you can choose any point in time on any branch.

If you have selected multiple out-of-date objects from the project's history, you can reload them all at once by right-clicking on them and selecting **Reload Latest on Branch**:



Appending Rows and Adding Columns to Data Tables

Data tables imported from the Central Data Room also have options for appending new data rows and adding data columns.

See <u>Adding and Updating Data for Existing Tables</u> in the <u>Working With Data Tables</u> topic for a discussion of the differences between reloading data, appending data and adding new data columns.

When you want to append new rows to a table, right-click on the table and select the **Append from Latest File Version** option. You will be prompted to select the project and file. Once you have selected the data source, the process is the same as described in <u>Adding New Rows to Existing Data Tables</u>.

When you want to add new columns to a table, right-click on the table and select either **Import Column** from Latest File Version or Import Column from File History. The from Latest File Version option will display the file and you can select additional columns to import, whereas the from File History option lets you select from the file history. In each case, the file's contents will be displayed and you can select additional columns to import, as described in Importing Additional Columns to a Data Table.

Settings

Open the **Settings** window by clicking on the **Leapfrog Works** menu and selecting **Settings**:

🖉 Leapfrog Works	
$= \sum_{- \vee} \underline{\mathbf{L}}$ eapfrog Works	
(*) New Project	1
Den Project File	ľ
Save a <u>C</u> opy	
Save a <u>Z</u> ipped Copy	I
Compact This Project	I
OM <u>F</u> ≻	
Render Image	
💥 Settings 🔓	
Diagnostics >	I
Works Forum	
MySeequent	
(i) About	
→ Quit Ctrl+Q	

The settings available in this window are described below:

- Display and Navigation Settings
- Overlay Settings
- Colour Scheme
- Lighting Settings
- Processing Settings
- User Interface Settings
- <u>Central Settings</u>
- Usage Policy Settings
- Network Settings
- Help Settings

To close the **Settings** window and leave settings unchanged, click the **Revert** button, then click **Close**.

Display and Navigation Settings

In the Settings window, click on Scene to change scene display and navigation settings.

3D Acceleration Mode

Leapfrog Works can run in one of three acceleration modes. Click the **Acceleration mode** button in the **Settings > Scene** window to use a different mode. The modes available are:

- **Software Rendering** uses software only, for maximum compatibility with any hardware. This option can be very slow displaying all but the simplest scenes, and is provided as a fall-back if display issues cannot be resolved with either of the other two options.
- Partial Acceleration uses hardware acceleration that has been provided on graphics cards for many generations. In this mode, Leapfrog Works renders scenes using "fixed function pipeline" hardware acceleration features that have been superseded in modern graphics cards by programmable shaders, but this legacy capability is widely supported and offers performance advantages over software rendering. Using Partial Acceleration can sometimes fix anomalies or problems encountered in Full Acceleration mode that may be due to bugs in old drivers, and it should work with even old or lower-featured hardware.
- **Full Acceleration** is the best option, assuming you have good hardware and up-to-date drivers. Because it makes use of programmable shaders provided by modern graphics cards, it is the fastest of the three modes and uses your available graphics memory more efficiently. It is the mode you should use, if your system supports it.

First, try using **Full Acceleration** and see how it renders scenes. If you seem to be having issues with how data is displayed in the scene, see <u>Running the Graphics Test</u> for information on testing your computer's graphics capabilities. Note that especially when graphics cards are new on the market, there may be a number of driver versions released to address anomalies, so the use of a recent driver version is important. If using a laptop with dual graphics cards, use it with the power supply connected, and select the **Performance Graphics** option over the **Power Saving** option.

If that doesn't resolve the graphics problems, then try **Partial Acceleration** mode. If possible, avoid using **Software Rendering** as it can be very slow.

If your current hardware is unable to support **Full Acceleration** mode, it may be worth considering upgrading your graphics card. Medium- to high-end home PC and gaming graphics cards are sufficient. High-end workstation grade cards also work very well, but you will also be paying for further capabilities that are not utilised by Leapfrog Works.

The acceleration mode can also be changed by clicking the button at the bottom of the Leapfrog Works main window:

🔗 <no code=""></no>	Full Acceleration	T-Scale 1.0	19 hours to go


Font Size

This setting is the size of text used to display information on the grid and axes.

Z Axis Scale

The **Z-axis scale** setting lets you set a value greater than 1.0 for the z-axis relative to the x- and y-axes. This is useful when the area under study is very planar and extends over a wide area. In such cases, scaling the z-axis can accentuate the distribution of data along the z-axis. If you have a project open when you change this setting, the change will be reflected in the scene so you can experiment with different values before choosing the one that best accentuates the distribution of data.

The z-axis setting can also be changed by clicking the **Z-Scale** button at the bottom of the Leapfrog Works main window. The **Scale Z Axis** window will appear:



Note that each project saves the z-axis scaling setting when the project is closed. In addition, when saving scenes (see <u>Saved Scenes</u>), the z-axis scale is saved as part of the scene.

Rotation Settings

The **Geographic rotation** and **Free rotation** settings determine whether or not the model displayed in the scene window can be "rolled". With the **Geographic rotation** option, the azimuth and elevation can be varied, but the z-axis is constrained to be vertical. With the **Free rotation** option, however, the rotation of the model is not fixed to any axis and the model can be freely rolled around any axis. Select the option you prefer. When Leapfrog Works is installed, **Geographic rotation** is set as the default option as it is the most commonly used.

The **Rotate with left button** and **Rotate with right button** settings determine how the mouse is used to rotate the scene:

- When **Rotate with left button** is selected, you can rotate the scene by holding down the left mouse button and dragging in the scene. Clicking and holding the right mouse button zooms in and out of the scene.
- When **Rotate with right button** is selected, holding down the right mouse button and dragging rotates the scene. However, zooming and rotating functions are not swapped. Instead, the left

mouse button can only be used for clicking on different objects in the scene. Select this option if you tend to accidentally move the scene when you intend to click.

Camera Settings

The **Orthographic projection** and **Perspective projection** settings determine the view of the model in the scene window.

If **Perspective projection** is selected, you can change the **Perspective angle** using the slider. This is similar to adjusting the zoom setting on a camera. Higher angles make nearby objects larger and more distant objects smaller. Lower angles will compress the scene. Experiment with the settings to see the effect on objects in the scene.

Select the option you prefer.

Overlay Settings

In the **Settings** window, click on **Scene > Overlays** to change what objects are included in the scene.

Changes you make to these settings are automatically updated in the scene so you can easily experiment to see what overlays you prefer.

Select **Revert** to return to the settings in place when the **Settings** window was first opened.

Screen Grid Settings

The **Show screen grid** setting determines whether or not the screen grid is displayed. Select the option you prefer. The **Loose Spacing**, **Normal Spacing** and **Fine Spacing** options determine the spacing of the grid.

Axis Lines Settings

The **Axis Lines** settings determine how X-Y-Z coordinates are displayed in the scene. When axis lines are enabled, the axes indicate the extent of data currently displayed in the scene.

- Enable Show axis lines to display the east (red), north (green) and elevation (blue) axis lines.
- Enable **Put numbers on axes** to display scale ticks along the grid. These are automatically adjusted to fit the extent of the data and the current zoom setting.
- Enable **Show whole box** to display the axis lines as a box that encloses the current data set.

Other Overlay Settings

The scale bar, compass ball and viewing angle text are the navigation aids in the lower right-hand corner of the scene window.

When the slicer is in the scene and the slice is aligned with the x-, y- or z-axis, text describing the slicer position can be displayed in the lower left-hand corner if the scene. To do this, enabled the **Slicer position text** option.

When drawing polylines, tooltips are displayed. If you do not wish to view these tooltips, untick the box for **Polyline help text**.

Colour Scheme

In the **Settings** window, click on **Scene > Colour Scheme** to change the colour scheme used in the scene. The options that can be changed include:

- The background colour used in the Scene View tab
- The colour and width used to display borehole traces
- The colour and width of mesh edges, together with the width of the line used when a mesh is sliced and the highlight colour used when mesh parts are selected in the scene
- The colours used for displaying the x, y and z axes
- Grid line width, style and colour
- Axes box line width, style and colour
- Slicer edge width, style and colour

Leapfrog Works is installed with three colours schemes: **Default**, **Black Background** and **White Background**. The scheme selected in the **Schemes** list will be used for all new Leapfrog Works projects and for existing projects when they are next opened.

- Experiment with the settings to see how they affect the scene window. The scene will be updated as you make changes.
- Select **Revert** to return to the settings in place when the **Settings** window was first opened.
- To create a new scheme, click on an existing scheme. This is the scheme that will be used as a basis for defining the new scheme. Next, click the **New Scheme** button and change its settings.
- Click **Factory Reset** to revert to the colour schemes defined when Leapfrog Works was first installed.

Clicking on **Factory Reset** to revert to the original colour schemes deletes any custom colour schemes.

Lighting Settings

In the **Settings** window, click on **Scene > Lighting** to change how visual effects are displayed in the scene window. You may be able to use these settings to emphasise significance in the data displayed in the scene.

- The Ambient level setting determines the overall brightness of the scene.
- The **Specular brightness** and **Specular shininess** settings determine how light appears to fall on the surfaces in the scene. The **Specular brightness** setting has a stronger effect when **Specular shininess** is soft.

You can have up to four light sources defined for a project. By default, two light sources are defined.

Changes made to these settings are automatically applied to the scene.

- Click Revert to return to the settings in place when the Settings window was first opened.
- Click **Factory Reset** to revert to the lighting sources and settings defined when Leapfrog Works was first installed.

Processing Settings

In the **Settings** window, click on **Processing** to change how background processing is used to run changes to data and models. The **Automatic** option creates one process for each physical CPU core on your computer or one for every 2.5 GB of RAM, whichever is smaller. However, there is an upper limit of 8 processes.

You can manually set the number of **Background processes** you would like to commit resources to. For example, you might want to use all but one process for Leapfrog Works and reserve one for other application use.


Select **Revert** to return to the settings in place when the **Settings** window was first opened.

User Interface Settings

In the **Settings** window, click on **User Interface** to change project tree and scene toolbar options and to enable uploading to View.

Show Tree Lines

Ticking the box for Show Tree Lines displays objects in the project tree with lines:



Enable this option if you find it useful for displaying relationships between objects in the project tree.

Show Save Scene Button

Ticking the **Show Save Scene** box adds an extra button to the scene toolbar:

Look V	680	- · 🗟 🖉 💋		
F	ettings Scene Overlays Colour Scheme Lighting Processing User Interface Central	Project Tree ☐ Show tree lines Scene Toolbar ♥ Show save scene ♥ Show View uploa ♥ Show render image Tabs	d ge	×
l	Jsage Policy Network Help	New tab position:	Where the last tab was moved to	~

Click this button to save the current scene.

You can also change the scene toolbar by right-clicking on it and selecting **Customise**.

Upload to View

Ticking the box for **Show View upload** displays the **View** button (**W**) in the **Scene View** toolbar:

	Scene View		Central Projects	C Wolfpass	×	Â	Q Alex Rock
8	Settings				×		6 16
	Scene	Project Tree				v (Z)	
	Overlays	Show tree lines					
	Colour Scheme	Scene Toolbar					
	Lighting	Show save scene				500	
	Processing	 Show View uploa Show render ima 					
	User Interface	Tabs					
	Central	New tab position:	Where the last tab was	moved to	~		
	Usage Policy					000	
	Network						
	Help						

Tab Position

Some Leapfrog Works windows open in separate tabs that can be used either docked or detached. The position in which tabs open is determined by the **New tab position** setting:

- Open all tabs in the main window.
- Open all tabs in separate windows.
- Tabs can open where the last tab was moved to. This setting can be used for creating a window in which all tables and dockable windows open, with the scene window, project tree and shape list in another window.

Central Settings

To enable Central, open the **Settings** window by clicking on the **Leapfrog Works** menu. Select **Central** and tick the box to enable Central. A **Central Projects** tab will appear in the main window.

If the **Use Seequent ID** option is enabled, Central integration is automatically enabled and cannot be disabled.

When you connect to Central, you can download projects and work on them locally. To change the location where projects are saved, click the **Change** button under **Project Files** and navigate to where you want to save projects:

Settings	
Scene	Project Files
Overlays	Location: C:\Users\Geologist\Central Change
Colour Schem	Used Space: 0.00 GB Free Space: 52.62 GB
Lighting	
Processing	Publishing Cache
User Interface	Location: C:\Users\Geologist\AppData\Local\Seequent Change
Central	Used Space: 0.00 GB Free Space: 52.61 GB
Usage Policy	Empty Cache
Network	
Help	Connection
	✓ Use Seequent ID
	Central 3.0 and above requires a Seequent ID to connect to Central. <u>Click here for</u> help
	Default request timeout: 60 🗘 seconds
	Large request timeout: 600 🗘 seconds
	✓ Upload chunk size: 10
	Check file consistency after upload
2)	Revert Close
9	

The **Publishing Cache** settings determine where Central data is stored while publishing to Central. If you have a small local drive and use network storage for most of your data, you can change where temporary publishing data is stored. To do this, click on the **Change** button and navigate to the required location.

The **Empty Cache** button clears the publishing cache folder for the connected Central Server. This button is only active when you are connected to a Central server and should only be used if you are having problems publishing to Central.

The Connection settings determine how you connect to the Central server.

Seequent is in the process of transitioning to using Seequent ID to connect to Central. The **Use Seequent ID** setting determines whether your connections to Central are automatically configured via your Seequent ID or whether you need to manually set up connections to Central servers.

- If your organisation is using Central 3.0 or later, you will need to connecting using Seequent ID. Enable this setting.
- If your organisation has not yet upgraded to Central 3.0, you will need to connect manually using the information provided by your administrator. Leave this setting disabled.

You will be prompted to restart when you change this setting.

The Large request timeout is used for publishing, uploading attachments and getting a revision. All other communication with the Central server uses the **Default request timeout**. The **Default request timeout** and **Large request timeout** should only be adjusted upward if you have problems with a poor connection. The default values are 60 seconds and 600 seconds.

The **Upload chunk size** setting is useful if you have a poor connection. It determines the size of the chunks used to upload large files. For example, if the **Upload chunk size** is 10MB and you are uploading a 100MB file, the file will be uploaded in 10 chunks. If your connection is poor and you are experiencing issues, you can decrease the value of the **Upload chunk size**.

There is an option for checking the integrity of a revision after it has been uploaded. If you wish to do this, enable the **Check file consistency after upload** option.

Usage Policy Settings

When the **Idle time-out** setting is enabled, Leapfrog Works will prompt you after a period of inactivity. Follow the instructions in the message displayed.

Leapfrog Works can use reference codes to track work on specific projects. The number of days associated with each reference code is included in your organisation's monthly usage report. In the **Settings > Usage Policy** window, you can define reference codes on a per-project or per-computer basis. Click the **Add New Code** button to add a code for either the computer or the currently open project.

The other two settings can be used to ensure that you are regularly prompted to update the reference code.

- **Prompt at project start up** ensures that a prompt is displayed for selecting a reference code whenever a project is opened or a new project is created.
- Always required ensures that Leapfrog Works is not used without a reference code being selected. <No Code> is not an option.

Network Settings

If your organisation uses a proxy server to connect to the internet, you can set this up in the **Settings > Network** window.

If you choose the **Autodetect proxy server** option, Leapfrog Works will detect the authentication type, server address and port; there are no further settings for you to change.

If **Autodetect proxy server** does not work or if you need to switch between proxy servers in different network environments, choose the **Manually configure proxy server** option and enter the information provided by your IT department. The advanced settings are optional and you should only change them from the default values if you have been instructed to do so by your IT department.

You can manually configure more than one proxy server. Click the **New** button to add a new profile and enter the required settings. When you want to swap from one proxy server to another, simply select a **Profile** from those already defined.

If you have multiple Seequent products running on your computer, you only need to configure network proxy settings once. Once you have, for example, configured the proxy for Leapfrog Works, the same settings will be used for the Central Browser.

Help Settings

If you are working on a slow connection, you can download a copy of the help that can be saved to your hard drive. To do this:

- Click here to download a copy of the help.
- Once you have downloaded a copy of the help and installed it, select **Settings** from the **Leapfrog Works** menu.
- Click on the **Help** tab and then select **Local folder**.

Leapfrog Works help is updated at each release. If you are using a downloaded copy, you will need to download a new copy each time you update Leapfrog Works.

Reporting a Problem

If Leapfrog Works encounters an error, the **Leapfrog Works Problem** window will be displayed. Enter as much information as you can about the problem, then click **Send**.


Getting Support

Technical support is available by visiting https://my.leapfrog3d.com/support/new-request.

Checking Connectivity With Seequent Start

Seequent Start checks to see if your network will support the connection of Leapfrog web-based services to your desktop applications.


To run Seequent Start, either click the **Test Web Services** button in the **Settings > Network** window or click on the **Leapfrog Works** menu and select **Diagnostics > Test Web Services**:



Supplying Your Licence Details

When contacting technical support, please include your licence number and a full description of the problem or query, including any information provided in system error messages.

You can access your licence information by selecting **About** from the **Leapfrog Works** menu:



You may also be asked to provide a copy of the log files. To find out where these are stored, select **About** from the **Leapfrog Works** menu, then click on the **System Info.** tab. Click on the link to open the folder that contains the log files:

About Lea	pfrog Works					>
About	Permissions	Copyright	Disclaimer	System Info.	OpenGL Extensions	
Open Loo	is Folder					
lm		_				
Leapfr	og Works version	: 4.0.0				
Buil	d	0.0.7.53	034			
Buil	d date	2020-10)-2009-02-27			
Mai	ntenance date	2020-10)-20			
Summ	ary					
Sys	tem					
	Operating system	Window	s 10 (10.0.1904	1) - AMD64		
	Total system memor	y 16242 M	ИB			
Gra	phics in use by Leap	frog				
	Vendor	NVIDIA	Corporation			
	Renderer	GeForce	e GTX 1050/PCI	e/SSE2		
	OpenGL version	4.6.0 N	/IDIA 391.25			
	GLSL version	4.60 NV	IDIA			
	3D Acceleration	Full				

Data Types

Leapfrog Works has tools for importing, creating and working with many different types of data, including:

- GIS Data, Maps and Images
- Borehole Data
- Design Models
- Points Data
- Geophysical Data
- Structural Data
- Meshes
- Polylines

For an introduction to importing data into the project tree, working with data tables, correcting errors in data tables and creating query filters, see the following topics in the <u>Getting Started</u> part of the help:

- The Project Tree
- Working With Data Tables
- Correcting Data Errors in Leapfrog Works
- Query Filters

GIS Data, Maps and Images

Often the first data imported into a new project is information that sets the coordinates for the project as a whole. This includes GIS data, maps and aerial photos.

You can view the attribute table for most GIS data objects by right-clicking and selecting **Attribute Table**. You can also create query filters that can be used when displaying the GIS object. See the <u>Query</u> <u>Filters</u> topic for more information.

If, during the course of a project, GIS data changes, it can be reloaded and models that are dependent on that data will automatically be updated.

Displaying GIS Data

In Leapfrog Works, there are three ways of viewing GIS data:

- In its "native" form, as it was imported to the project. Add the GIS data object to the scene as you would any other object.
- On the topography. GIS data objects added to a project are automatically projected onto the topography and saved in the **Topographies > Draped GIS Objects** folder. Add the draped GIS object to the scene.
- Combined with other data draped on the topography. See Custom Topography Views below.

The reason for having different ways of displaying GIS data is the difficulty posed by inconsistent height data. Not all height data is correct or wanted. In practice, it is important for all the data to be consistent. For this reason, a single elevation field is defined as part of the topography and available data is assigned heights from this object. The native height information is available and can be used to define the height of layers in the models.

Custom Topography Views

In Leapfrog Works, topography can be displayed with any of the GIS data and images available in the project. With a custom view, you can display multiple GIS data objects, maps and aerial photos.

To create a custom view, add the topography object to the scene. Select **Views > Edit views** from the **GIS data** list:

0	📥 Topogra	aphy X	<	🔷 E 🗸 📃 🜌 🛄	•• 🕨 🚺
	GIS Data:	Select 🗸			
		None			
		⊻iews	>	Edit views	
		Maps and Photo	s >	3	
		GIS objects	>		

The **Edit GIS Views** window will appear. Click **New** to create a new view. Enter a name for the new view and click **Create**:


Edit GIS Views		:
GIS <u>v</u> iews:		Rename New
Ayallable layers:	Current layers:	
(?)		Revert All Close

The new view will be created in the **Edit GIS Views** window, together with a list of **Available layers**. Use the arrows to move layers into the **Current layers** list and organise them:

😽 Edit GIS Vie										×
Edit GIS Vie	2WS									^
GIS views:	Maps with contours					~	Renam	e <u>N</u>	ew 🔟	
Available lay	rers:		Current layers:							
lake_b	dy		or Topography contour:	Elevation 🗸	Elevation \smallsetminus		width:	2.0	•	
🧾 North	boundary		krea map						•	
🧟 river_b	ody									
🧟 river_c	s									
🔝 lake_s	eed	<								~
river_s	seed	/								\sim
🔊 lake_p	oly	<								\sim
Niver_p	poly									Ť
scree_	poly									
No. shingl										
Rarmla 🔤										
🔜 Tekap	0									
~						_				_
?							Rever	All	Clos	ie

Use the transparency and point and line size controls to emphasise data.

Click **Close**. The topography will be displayed in the scene with the new view applied:



Importing Vector Data

Vector data formats Leapfrog Works supports include:

- Shape Files (*.shp)
- MapInfo Files (*.tab, *.mif)
- ESRI Personal GeoDatabase Files (*.mdb, *.accdb)

You can also import data from MapInfo and ESRI databases. See <u>Importing a MapInfo Batch File</u> and <u>Importing Data from an ESRI Geodatabase</u> for more information.

To import vector data, right-click on the **GIS Data, Maps and Photos** folder and select **Import Vector Data**. Navigate to the folder that contains the GIS data and select the file. You can select multiple files using the Shift and Ctrl keys.

Click **Open** to begin importing the data.

If you are importing a single file, the **Import GIS Vector Data** window will show a summary of the data in the selected file:

2	Import	GIS Vector Data			×
	S vecto C:\Users'		frogte	orial\GIS data\lake_l	bdy.shp
Fie	elds to in	nport			
	Import	Column	Туре	Import As	
	\checkmark	shapelD	int	shapelD	
	\checkmark	WATER_CONF	string	WATER_CONF	
	\checkmark	ELEVATION	real	ELEVATION	
	Elevatior		ION		
	Everythir	ng <u>w</u> ithin: 0			-
	of the <u>b</u> o	ounding box:	lipping	Boundary	•
Na	ame: la	ke_bdy			
	<u>Не</u>	lp		Cancel	<u>о</u> к

You can choose what field in the data to use for the **Elevation Field** from the list.

If you are importing multiple files, all files being imported are listed in the **Import GIS Vector Data** window and no summary of each file is displayed:

🥂 Import GIS Vector Data		×
Files to be imported		
🔀 lake_bdy		-
lake_poly	1	
lake_seed		
🔀 river_bdy		
🔀 river cl	•	•
✓ <u>F</u> ilter data		
Everything within: 0		
of the <u>b</u> ounding box: Cl	ipping Boundary 🔻	
<u>H</u> elp	Cancel Cancel]

Data is automatically clipped to the clipping boundary, but you can change how the data is filtered to suit any bounding box that exists in the project. If you do not wish to clip the data, untick the **Filter data** box.

Click **OK** to add the data to the project. The object or objects will appear in the project tree under the **GIS Data, Maps and Photos** folder. If a topography has been defined for the project, the imported GIS data objects will automatically be projected onto the topography and saved in the **Topographies > Draped GIS Objects** folder.

You can then view an object's attributes by right-clicking on it and selecting Attribute Table.

When importing files, you may be prompted to select whether or not to filter elevation data. If you wish to use another data source for your elevation data, select **Filter data**. For example, if you import a GIS line that has suspect elevation data, you can discard the elevation data and set the elevation from the topography, as described in Setting Elevation for GIS Objects and Images.

If data changes outside the project, it can be reloaded as described in <u>Reloading GIS Data</u>.

Importing a MapInfo Batch File

You can import a collection of GIS data exported from MapInfo. The MapInfo file can include points, lines, polygons, images and elevation grids.

To import GIS data in this way, right-click on the **GIS Data, Maps and Photos** folder and select **Batch Import > from MapInfo**. In the window that appears, navigate to the folder that contains the MapInfo batch file, which is an XML file. Click **Open**.

The data that can be imported will be displayed and you can select which files to import:

✓	Name	Туре	
\checkmark	🐱 nz-ross-dependency-cliff-edges-ant-150k	Lines	
\checkmark	🔀 nz-ross-dependency-coastlines-ant-150k	Lines	
\checkmark	nz-ross-dependency-geographic-names-ant-150k	Points	
\checkmark	nz-ross-dependency-glacial-lake-polygons-ant-150k	Polygons	
\checkmark	nz-ross-dependency-iceberg-polygons-ant-150k	Polygons	
\checkmark	nz-ross-dependency-island-polygons-ant-150k	Polygons	
\checkmark	nz-ross-dependency-lake-polygons-ant-150k	Polygons	
\checkmark	🗷 nz-ross-dependency-melt-stream-centrelines-ant-150k	Lines	
\checkmark	nz-ross-dependency-moraine-polygons-ant-150k	Polygons	
\checkmark	nz-ross-dependency-sinkhole-points-ant-150k	Points	
\checkmark	contourheightbuf_g2i	Image	
\checkmark	heightpointsRoss_g2i	Image	
Filte	er data		
	thing within: 0		
Ethe	bounding box: Clipping Boundary		

You can select multiple files using the Shift and Ctrl keys.

Data is automatically clipped to the clipping boundary, but you can change how the data is filtered to suit any bounding box that exists in the project. If you do not wish to clip the data, untick the **Filter data** box.

Click **OK** to import the selected files, which will be added to the **GIS Data, Maps and Photos** folder as a group (<), with the exception of elevation grids, which will be added to the **Meshes** folder.

Points, lines and polygons can be reloaded on an individual basis, which is described in <u>Reloading GIS</u> <u>Data</u>.

Importing Data from an ESRI Geodatabase

You can import points, lines and polygons from an ESRI geodatabase. However, the import of raster data is not supported.

To import GIS points, lines and polygons in this way, right-click on the **GIS Data, Maps and Photos** folder and select **Batch Import > from ESRI Geodatabase**. In the window that appears, navigate to the folder that contains the database and click **Open**.

Leapfrog Works imports uncompressed ESRI geodatabases.

The data that can be imported will be displayed and you can select which files to import:

\checkmark	Name	Туре	Projection	Units
\checkmark	🗵 Roads	MultiLineString	NAD83 / UTM zone 12N	metre
\checkmark	🔀 Streams	MultiLineString25D	NAD83 / UTM zone 12N	metre
\checkmark	🔀 Trails	MultiLineString	NAD83 / Utah South (ftUS)	US survey foo
\checkmark	Springs	Point25D	NAD83 / UTM zone 12N	metre
\checkmark	Park_boundary	MultiPolygon	NAD83 / UTM zone 12N	metre
\checkmark	Research_areas	MultiPolygon	NAD83 / UTM zone 12N	metre
\checkmark	📕 tirangle	MultiPolygon	unknown	unknown
\checkmark	Tracts	MultiPolygon	NAD83 / UTM zone 12N	metre
-	er data thing <u>wi</u> thin: 0			
	(
	e bounding box: C	lipping Boundary		~

You can select multiple files using the Shift and Ctrl keys.

Data is automatically clipped to the clipping boundary, but you can change how the data is filtered to suit any bounding box that exists in the project. If you do not wish to clip the data, untick the **Filter data** box.

Click **OK** to import the selected files, which will be added to the **GIS Data, Maps and Photos** folder as a group (<a>). Data in the group can be reloaded individually or as a group, which is described in <a>Reloading GIS Data.

Reloading GIS Data

If during the course of a project GIS points, lines and polygons change, they can be reloaded and dependent models will automatically be updated. Objects originally imported as part of an ESRI database (

Although the GIS data will be overwritten, any elevation data set in Leapfrog Works will be retained.

Reloading Points, Lines and Polygons

To reload a GIS point, line or polygon, right-click on it in the project tree and select **Reload Data**. Navigate to the folder containing the GIS file and select the file. Click **Open**.

The process is the same as importing GIS data. Click **OK** to reload the data. The original data will be overwritten and dependent objects will be updated to reflect the new data.

Reloading an ESRI Database

To reload an ESRI database, right-click on it in the project tree and select **Reload Data**. In the window that appears, select the layers to reload, then click **OK**.

Points, lines and polygons imported as part of an ESRI database can also be reloaded on an individual basis.


Importing a Map or Image


Image formats Leapfrog Works supports include:

- PNG Files (*.png)
- JPEG Files (*.jpg, *.jpeg)
- TIFF and GeoTIFF Files (*.tiff, *.tif)
- Windows Bitmap Files (*.bmp)
- Graphics Interchange Format Files (*.gif)

If images being imported contain georeference data, that information is assumed to be correct. You can, however, edit the information if you need to.

In Leapfrog Works, three markers (\Box , \odot , \diamond) are used to display the georeference data for imported images. You can see these markers in the scene when you double-click on an imported image, which opens a tab that has tools for cropping the image and editing its georeference data:





When you switch back to the scene, you can see the georeferencing markers:

The rest of this topic describes how to work with imported images in Leapfrog Works. It is divided into:

- Importing a Single Image
- Importing Multiple Images
- Cropping Images
- Manually Georeferencing Images
- Overriding Georeference Data
- Exporting a Georeferenced Image

Importing a Single Image

To import a single image, right-click on the **GIS Data, Maps and Photos** folder and select **Import Map**. Navigate to the folder that contains the image, select the file and click **Open**.

- If the image contains georeference data, it will be imported into the **GIS Data, Maps and Photos** folder.
- If the image does not contain georeference data, the Import Map window will be opened so you can add the georeference data. See <u>Manually Georeferencing Images</u> below. Once you have georeferenced the image, click Import. The image will be imported into the GIS Data, Maps and Photos folder.

Importing Multiple Images

There are two ways to import multiple images:


- Right-click on the **GIS Data, Maps and Photos** folder and select **Import Map**. Navigate to the folder that contains the files you wish to import. Select the images and click **Open**. The images will be imported and added to the **GIS Data, Maps and Photos** folder.
- In the File Explorer, select all the files you wish to import. Drag and drop them into the **GIS Data**, **Maps and Photos** folder in Leapfrog Works.

All images will be imported and added to the **GIS Data, Maps and Photos** folder. If an image does not contain georeference data, you will need to open the image and add the information manually, as described in <u>Manually Georeferencing Images</u> below.

Cropping Images

Images larger than 16384 by 16384 pixels will be scaled down. Reducing your images in size below this limit will avoid scaling. You can scale down images in an external image editor, or you can crop imported images in Leapfrog Works.


Cropping an image to only the area of interest will reduce video RAM usage and may improve graphics performance. To crop an image, double-click on the image in the project tree. In the window that appears, select the **Crop Image** button (1, and then drag around the part of the image you wish to use.



Click on the **Remove Crop** button (¹_b) to clear the cropping.

Manually Georeferencing Images

If an image does not contain georeference data, you will need to add it manually by adding the three reference markers (\Box , \odot , \diamond) to the image. To select a marker, click on its marker button (**Marker 1**, **Marker 2** or **Marker 3**), then move it to the required location on the image using the mouse or the arrow keys.




Once each marker is correctly positioned, enter the real-world X and Y coordinates for each marker:

There are two ways to do this:

- Enter the coordinates for each marker in the **East (X)** and **North (Y)** fields. As you enter the coordinates, the positions of the markers will be displayed in the scene.

The second method is useful when you already have other objects correctly georeferenced in the project. For example, if you have a larger map in the project and wish to import a more detailed map, you can copy the coordinates from the georeferenced map to the detailed one. To do this, move the image's tab so you can see enough of the scene to work in both windows:



Next:

- In the **Import Map** tab, position the marker (\Box , \odot , \diamond) on the image being imported.
- Click the corresponding copy coordinates marker (¹, ¹, ¹), ¹).
- Zoom in to the point in the scene window where you wish to place the marker and click.

The coordinates in the scene will be copied to the **Import Map** tab.

Overriding Georeference Data

If an image being imported contains georeference data, the image will automatically be imported and added to the **GIS Data, Maps and Photos** folder. To edit its georeference data, double-click on the image to open it and tick the **Override georeference data from image** box. Edit the information as described in <u>Manually Georeferencing Images</u> above.

Exporting a Georeferenced Image

Leapfrog Works exports georeferenced images as GeoTIFFs. To do this, right-click on it in the project tree and select **Export**. You will be prompted for a filename and location. Click **Save**.

Setting Elevation for GIS Objects and Images

You can set the elevation for GIS objects and images by:

- Using a fixed elevation
- Using the elevation data from one of the object's attributes

• Using the elevation data from a surface in the project

The options available depend upon the type of object.

	Fixed Elevation	From Attribute	From Surface
GIS lines	Х	Х	Х
GIS points	Х	Х	Х
2D grids	Х	-	Х
GIS lines drawn in Leapfrog Works	Х	-	-
GIS lines extracted from polylines	Х	-	Х
Images	Х	-	-

To set the elevation for a GIS object or an image, right-click on it in the project tree and select **Set Elevation**. The **Set Elevation** window will appear, displaying the available options. Select the option required and click **OK**.

Creating a New GIS Line

There are three ways to create a new GIS lines object in Leapfrog Works:

- If you do not have GIS data for a topographical feature you wish to use in model building, you can draw a new GIS line. See <u>Drawing a New GIS Line</u>
- If you have two surfaces that intersect, you can generate a new GIS line from their intersection. You can use any surface in the project, including those that are generated in building models. See <u>Creating a New GIS Line from Intersecting Meshes</u>.


To view new GIS line draped on the topography, select the object from the **GIS data > GIS objects** list, as described in <u>Topography Display Options</u>.

Drawing a New GIS Line

GIS lines can be drawn on the slicer or on a surface.

Right-click on the **GIS Data, Maps and Photos** folder and select **New GIS Line > From New Drawing**. In the window that appears, enter a name for the new object and click **OK**.

The object will be created in the project tree and added to the shape list. The scene view will change to view the objects in the scene from above and tools for drawing polylines will appear. Click on the **Draw lines** button () and start drawing in the scene, as described in Drawing in the Scene.



When you have finished drawing, click the **Save** button (\square). The new line (\blacksquare) will be saved in the project tree.

You can edit the GIS line by right-clicking on it in the project tree and selecting **Edit**. If it is in the shape list, you can edit it by clicking on the **Edit** button (\mathcal{O}).

Creating a New GIS Line from Intersecting Meshes

You can create a new GIS line from two intersecting meshes. You can use any surface in the project, including those that are generated in building models.

To create a new GIS line from two intersecting meshes, right-click on the **GIS Data, Maps and Photos** folder and select **New GIS Line > From Intersecting Meshes**. In the window that appears, select the meshes to use, enter a name for the new object and click **OK**.

The new line () will be saved in the project tree. It is not linked to the meshes used to create it and will not be updated when the meshes are updated.

Exporting GIS Data

To export GIS data, right-click on the GIS data object in the **GIS Data, Maps and Photos** folder and select **Export**. The **Export GIS** window will be displayed:

😰 Export GIS	×
Exporting West boundary	
✓ Use 2.5D format with elevations from	
○ <u>I</u> opography	
<u>G</u> IS object	
Help & Cancel]

Select whether elevation information will come from the topography or from the GIS object itself, or untick the **Use 2.5D format with elevations from** box to export the object without elevation information.

Click **Export**. You be prompted for a filename and location.

Borehole Data

Borehole data forms the basis for creating models in Leapfrog Works. Because borehole data often contains errors that reduce the reliability of a model, Leapfrog Works has tools that help you to identify and correct errors and work with the data.


Borehole data defines the physical 3D shape of boreholes. It is made up of:

- A collar table, containing information on the location of the borehole.
- A survey table, containing information that describes the deviation of each borehole.
- At least one interval table, containing information on measurements such as lithology, date or any numeric or textual values. An interval table must also include collar IDs that correspond to those in the collar table and sample start and end depth.

You can also import downhole points.

When a project is first created, the only options available via the **Borehole Data** folder are for importing data. See <u>Importing Borehole Data</u> for more information on these options.

Once data has been added to the project, a **Boreholes** object will be created that serves as a container for the tables imported:



You can open each table by double-clicking on the table (IIII). The table will be displayed and you can make changes. See <u>Working With Data Tables</u>. When there are errors in the data, the relevant table will be marked with a red exclamation mark (IIII). See <u>Correcting Data Errors in Leapfrog Works</u> for more information on fixing borehole data errors.

In addition to the imported borehole tables, the **Boreholes** object also has two objects that help in visualising and analysing borehole data. These are:

- The Borehole traces object. See Displaying Borehole Traces.
- The Borehole Graphs object. See Displaying Borehole Graphs.

To delete a lithology or numeric data table, right-click on the table in the project tree and select

Delete. You will be asked to confirm your choice.

When you right-click on the borehole or collar table object in the project tree and select **Delete**, the resulting action will also remove all lithology and numeric data tables from the project. You will be asked to confirm your choice.


The rest of this topic discusses options for displaying boreholes and viewing statistics on borehole data tables. It is divided into:

- Displaying Boreholes
- Viewing Borehole Data Table Statistics

Displaying Boreholes

Viewing borehole data in the scene is an important part of refining borehole data and building a geological model. Therefore, Leapfrog Works has a number of different tools for displaying borehole data that can help in making borehole data processing and modelling decisions. Display borehole data in the scene by dragging the **Boreholes** object into the scene. You can also drag individual tables into the scene.


Once borehole data is visible in the scene, click on a borehole to view the data being displayed. You can also display the data associated with each interval by clicking on the **Show text** button (A) in the shape list. Here, data display is enabled for two interval tables:




The **Show trace lines** button (**!!!**) in the shape list displays all trace lines, even if there is no data defined for some intervals. The **Filter trace lines** option in the shape properties panel displays only trace lines for boreholes selected by a query filter. See the <u>Query Filters</u> topic for more information.

Displaying Boreholes as Lines or Cylinders

You can display boreholes as lines or cylinders. You can also display the data associated with each segment. Here, the boreholes are displayed as flat lines:




The width of the lines is set in the shape properties panel.



When the **Make lines solid** button (¹⁰) is enabled, the borehole data is displayed as cylinders and the property that can be controlled is the **Line radius**:


When numeric data is displayed, there is an additional option, to use a data column in the table for the cylinder radius:



When the log button (\square) is enabled, the log of values is used for the radius.

Hiding Lithologies


When lithology tables are displayed, you can hide some of the lithologies to help make better sense of the information in the scene. Click on the **Edit Colours** button in the shape list. In the window that appears, use the **Show/Hide** buttons (⁽⁽⁾⁾) to determine what segments are displayed:



To select multiple lithologies, use the Shift or Ctrl keys while clicking. You can then change the visibility of all selected lithologies by clicking one of the visibility (⁽²⁾) buttons.

Hiding lithologies in this way only changes how the data is displayed in the scene. Another way of limiting the data displayed is to use a query filter (see the <u>Query Filters</u> topic), which can later be used in selecting a subset of data for further processing.

Displaying a Legend



To display a legend in the scene, click the **Show legend** button (**II**) for the table:

The legend in the scene will be updated to reflect lithologies that are hidden in the scene when you click **Edit Colours** and hide some lithologies.

To reorder the legend, click the **Edit Colours** button in the shape list to open the **Legend** window. Click on an item in the list, then use the arrows to move it up or down. The legend shown in the scene will be updated when you close the **Legend** window.

Changing Colourmaps


To change the colours used to display lithologies, click on the **Edit Colours** button in the shape list. In the window that appears, click on the colour chip for each lithology and change it as described in <u>Single</u> Colour Display.

Use the Shift or Ctrl keys to select multiple lithologies. This is useful for changing multiple colour chips to a single colour or for moving multiple lithologies up and down in the list.

You can also import a colourmap, which is described in <u>Importing and Exporting Colourmaps</u>.

Viewing Multiple Interval Tables

When viewing multiple interval tables, use the line and point size controls and the transparency settings to see all the data at once. For example, here, the geology table has been made transparent to show the contaminant intervals inside:



Selecting from Multiple Columns

When an interval table has more than one column of data, select the column to view from the view list:


0	M_Assays	\times	🔢 Au 🗸 🚺 Au 🗸 💶 🔟 🛠 🚺 🛦 🗐	M_Geology	
0	M_Geology	×	K Sim Edit Colours	Slice mode:	Unsliced ~
			♣ Flat colour	Query filter:	No Filter 🗸
			NockType	Filter trace	lines
			Nimple_RockType	Line radius:	8.00 🗘
			Neathering_Zone		
					Format Display Text

Some columns are editable, in which case you can click on the **Edit** button (\mathcal{P}) to start editing the table:

0	M_Assays		\times	Au	~	Au	\sim		+ 	A 🗄	M_Geology		
\odot	M_Geology	Ø	\times	🙀 Gro 🕔	~	Edit Colours			ŧ÷ŧ .	A 🗄	Slice mode:	Unsliced	\sim
											Query filter:	No Filter	~
		Т									Filter trace	lines	
											Line radius:	8.00	¢
												Format Display Text	

Displaying Interval Data in the Scene

Boreholes can be displayed with the data associated with each segment. For example, in the scene below, contaminant values are displayed along the borehole:



To view data in this way, select the table in the shape list, then click on the **Format Display Text** button. In the **Text Format** window, click **Insert Column** to choose from the columns available:

٢	Contaminant Text Format X	🔢 Contaminant	
Ø		Slice mode:	From Scene V
٢	Insert Column	Query filter:	No Filter 🗸
	tei>	Filter trace	lines
	Mean	Value filter:	0.0 0 - 14.0 0
		Line radius:	15.00 🗘
		Radius values:	Fixed Radius ~
	(?) Cancel OK	Decimal places:	2
	(?) <u>Cancel</u> <u>O</u> K		Format Display Text

You can display multiple columns and add text:

📽 Contaminant Text Format		×
Insert Column 🗸 🔟		
Con Contaminant 2 Mean Mean 2		
?	Cancel	<u>о</u> к

Click **OK** to update the formatting in the scene. You can conceal the formatting in the scene by clicking on the **Show text** button (A) in the shape list:

0	Contaminant	\times	Co 🗸	Contaminant 🗸		∞		📆 Contaminant	
Ø	Geology	×	🎎 Lith 🗸	Edit Colours	•		HI A Show te	Clice mode:	From Scene V
٢	collar	\times	🖕 Flat 🗸				A	Query filter:	No Filter 🗸
								Filter trace	lines
							Τ.	Value filter:	0.0 0 - 14.0 0
								Line radius:	15.00 🗘
								Radius values:	Fixed Radius 🗸 🔟
								Decimal places:	2
									Format Display Text

Clear text formatting by clicking on the **Format Display Text** button, then on the **Delete** button (\square).

Displaying Borehole Traces


Adding the **Borehole traces** object (*M*) to the scene can be useful in visualising the extent of drilling. You can change the colour used to display the traces, and they can be displayed as lines or cylinders. You can also display depth markers in the scene. To do so, click on the traces in the shape list and enable the **Show depth marks** option:



Depth markers can be displayed with or without text. Enable the **Show text** option ((A)) to display the depth values. This option also displays the hole ID, which can be displayed at the start or the end of the borehole.

Displaying Borehole Graphs

Downhole numeric data can be displayed in the scene as a bar graph and downhole points data can be displayed as a line graph. To display downhole data in this way, add the **Borehole Graphs** object (⁽¹⁾) to the scene. The **Borehole Graph Style Manager** will be displayed, showing the data columns available:



Data can be displayed to the right or the left of the borehole trace. Use the sliders to change the **Scale** and the **Offset** from the trace.

Data can be clamped, e.g. all values above the set maximum value will be set to the maximum value.

If there are negative values in the data, they will be displayed on the graph with a value of zero.

Downhole points can be displayed as a line, and you can change the **Colouring**, **Scale** and **Offset** of the line:

📽 Borehole Graph Style Manager		×	
Ayailable columns: LF_Demo_Assay Fe_new Composites Fe_composited Fe_new Fe_composited_5 Fe_new Fe_new Composited_5 Fe_new Demo_Geophysical_Data Density	Position and Size Display left of trace Display right of trace Scalg: Offset: Line width: T Colouring Flat colour:		
Gamma	Numeric Display Range		
	Clamp Values		
	Minimum: 26.273		
	Maximum: 143.236		
	Log transform		
?	<u>C</u> lose		Borehole Graphs Slice mode: From Scene
💿 🛛 💣 Demo Model 1: Aas	🗙 À Lit 🗸 📒	 	Query filter: No Filter ~

All changes made in the **Borehole Graph Style Manager** are automatically updated in the scene so you can experiment with the settings. Once you have closed the window, you can also change the **Scale** and **Offset** by clicking on the **Borehole Graphs** object in the shape list:


	₿ Slicer	\times	i 🖉 🜒	۱	Ô	÷\$4		👫 Borehole Graphs
0	Borehole Graphs	×	Alt	Alteration	\sim			Slice mode: From Scene V
0	Alteration	×	Alt 🗸	Alteration	\sim		🔟 🤲 👫	Query filter: No Filter ~
0	🍘 GM	\times	🍘 GM 🔍	Edit Colours				Scale:
								Offset:

To select a different column to display, open the style manager by double-clicking on the **Borehole Graphs** object in the project tree or select a new column from the shape list.

If you are working in a new project into which you have just imported boreholes, the **Borehole Graph Style Manager** will open when you add it to the scene. If the **Borehole Graph Style Manager** does not open when you add the **Borehole Graphs** object to the scene, it is because the styles have already been set, perhaps by another user. You can change them by double-clicking on the **Borehole Graphs** object.

Viewing Borehole Data Table Statistics

To view statistics on an interval table, right-click on the table in the project tree and select **Statistics**. The following options are available:



See the Analysing Data topic for more information on each option:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots

The **Interval Length Statistics** graph is a univariate graph, so for more information on the options available, see <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic.

Right-click on a numeric column and select **Statistics** to open a univariate graph for that column.

Importing Borehole Data

Leapfrog Works can import borehole data from the following sources:

- Files stored on your computer or a network location. To start, right-click on the **Borehole Data** folder and select **Import Boreholes**.
- From a Central project's Data Room. See Importing Drilling Data From the Central Data Room.

- From any database that runs an ODBC interface. See <u>Selecting the ODBC Data Source</u>.
- From OpenGround Cloud. See Connecting to an OpenGround Cloud Database.

For each of these options, once the data source is selected, the process of importing borehole data is the same. See <u>Importing Data Tables and Mapping Data Columns</u> for an overview of how to map data columns in files to the format Leapfrog Works expects.

Once Leapfrog Works has imported the data, it will appear in the project tree under a new **Boreholes** object.

The rest of this topic discusses the data format required for importing borehole data. It is divided into:

- Expected Borehole Data Tables and Columns
- AGS Format Borehole Data

Expected Borehole Data Tables and Columns

Required table types for importing borehole data are:

- A collar table
- At least one interval table

Downhole points tables can also be imported, but are optional.

A screens table can be imported, if you have the Hydrogeology extension.

The following formats are supported:

- CSV Text File (*.csv)
- AGS Files (*.ags)
- ASCII Text File (*.asc)
- Plain Text Files (*.txt)
- Data Files (*.dat)
- TSV Text Files (*.tsv)

For data imported in CSV, ASCII, TXT, DAT and TSV formats, separate files are required for each type of table. For data imported in AGS format, a single file is imported that contains each type of table and a summary of the relevant data is presented at each stage of the importation process so you can select from the available groups of data.

The Collar Table

The collar table should contain five columns:

- A borehole identifier
- The location of the borehole in X, Y and Z coordinates
- The maximum depth of the borehole

A collar table can also contain a trench column, and collars marked as trenches will be desurveyed in a manner different from other boreholes. See <u>Borehole Desurveying Options</u> for more information.

Leapfrog Works expects a 0 for a normal hole and a 1 for a trench. If there is no trench column in the collar table, Leapfrog Works will create one.

The borehole ID is used to associate data in different tables with a single borehole. The ID for a borehole must be identical in all tables in order for data to be associated with that borehole. Inconsistencies in the way boreholes are identified are common sources of errors.

The maximum depth column is optional. If it is present, is used to validate the data imported for the interval tables. The maximum depth specified is often a planned quantity, whereas the interval table records actual measurements. For this reason, Leapfrog Works has an option for fixing the maximum depth value in the collar table to match the data in an interval table.

If maximum depth information is not included in a collar file, Leapfrog Works will determine it from the maximum depth sampled as indicated by data in the interval tables.

Boreholes in AGS format may also include a Project ID column that can be used to identify boreholes that have the same hole ID but are actually from different projects.

The Survey Table

For the survey table, Leapfrog Works expects a minimum of four columns:

- A borehole identifier
- Depth, dip and azimuth values

By default, Leapfrog Works assumes that negative dip values point up. If this is not the case, tick the **Negative survey dip points down** option.

Boreholes in AGS format may also include a Project ID column that can be used to identify boreholes that have the same hole ID but are actually from different projects.

See <u>Borehole Desurveying Options</u> for more information on the borehole desurveying algorithms used in Leapfrog Works.

The Screens Table

A screens table can only be imported if you have the Hydrogeology extension.

For the screens table, Leapfrog Works expects a minimum of four columns:

- A borehole identifier
- Start/from and end/to depths
- A value column

Boreholes in AGS format may also include a Project ID column that can be used to identify boreholes that have the same hole ID but are actually from different projects.

Interval Tables

For interval tables, Leapfrog Works expects, at minimum, four columns:


- A borehole identifier
- Start/from and end/to depths
- A column of measurements

If a borehole ID in an interval table does not correspond to one in the collar table, the table can still be imported but the interval table will contain errors.

Supported column types are:

- Lithology columns containing lithologic data, which can be used for geological modelling.
- Numeric columns containing numeric values, which can be used for interpolating data.
- Category columns, which is text representing categories such as company, geologist, or mineralisation.
- Text columns containing text data that is not categorical, such as comments. Text columns are not validated when imported.
- Date columns containing date data. Custom date and timestamps formats are supported.
- URL columns. Use the prefix file:/// to link to local files.

When an interval table is displayed in the scene and an interval is selected, clicking on a link in the URL column will open the link. This is a useful way of linking to, for example, data files or core photo images from within Leapfrog Works:



Boreholes in AGS format may also include a Project ID column that can be used to identify boreholes that have the same hole ID but are actually from different projects.

Points Tables

For downhole points tables, Leapfrog Works expects the following columns:

- A borehole identifier
- Depth

AGS Format Borehole Data

Leapfrog Works supports the importation of borehole data using the Association of Geotechnical and Geoenvironmental Specialists (AGS) format. AGS versions 3.1 and 4 are supported. The process for importing boreholes in AGS format is the same as that for importing data described in the rest of this topic, except that a single file is selected for import.

For each type of table, a summary of the relevant data in the file is presented, allowing you to select groups of data.

The Collar Table

For the collar data group, the HOLE group (v3.1)/LOCA group (v4.0) will automatically be selected. Click **OK** to accept the selection. The selected data will be mapped and you can change how it is mapped as described in Importing Data Tables and Mapping Data Columns.

The Survey Table

For the survey table data group, the HOLE group (v3.1)/HORN group (v4.0) will automatically be selected. Click **OK** to accept the selection.

If there is no survey information in the file, click **OK**, then click the **Skip** button in the **Import Boreholes** window to move on to the interval table data.

Interval Tables

All remaining groups that contain suitable interval data are displayed, although you can display all groups in the file by disabling the **Only show groups suitable for interval data** option.

Only one group can be selected, and typically the GEOL table contains the lithology data. However, if you need to import more groups, there are two options:

- Import the other groups as additional interval tables (see <u>Importing Interval Tables</u>). Select **Import From File** and then select whether you wish to import intervals or points, then select the AGS file again.
- Append the dataset, as described in <u>Adding New Rows to Existing Data Tables</u> in the <u>Working With</u> <u>Data Tables</u> topic.

Depth Points Tables

All remaining groups that contain points data are displayed, although you can display all groups in the file by disabling the **Only show groups suitable for depth points data** option.

Importing Drilling Data From the Central Data Room

Borehole data can only be imported from a project's data room. Although borehole data can be published to Central, that is for the purpose of visualising the data in the Central Browser and the Central Portal. Published borehole data cannot be imported into other Leapfrog Works projects.

See the <u>The Project Data Room</u> topic in the <u>Central 4.0 help</u> for information on how to work with a Central project's data room.

To import borehole data from Central, first make sure you are connected to a Central server. Next, click on the **Borehole Data** folder and select **Import Boreholes via Central**. In the window that appears, select the project you wish to import data from. The **Import Boreholes from Central** window will be displayed. Click the button for **Collar** to navigate the project's data room to locate the collar file you wish to use.


			# Impo	rt Boreh	oles From Central					×
			File Imp Select t	port the file ti	o Import from Central					
🕫 Import B	reholes from Central	(ଜ	0					
Input Files					Name		Туре	Size	Date	User
Collar:	1		0	5	Drilling		Folder			
Survey:	Optional D				Торо		Folder			
	÷									
Intervals	Θ									
Points:	÷									
Eoms.	Θ									
0	<u>Cancel</u> Import									
			Sup	ported t	formats: *.ags, *.asc, *.csv, *.dat, *.tsv, *.txt					
			0			<u>Cancel</u>	Previous			

Select the file and click Import. Work through the files as described in Importing Borehole Data.

Selecting the ODBC Data Source

Leapfrog Works supports database files in Access Database (*.mdb, *.accdb) and glnt Project (*.gpj) formats.

To import borehole data directly from any database that uses an ODBC interface, right-click on the **Borehole Data** folder and select **Import Borehole Data via ODBC**. The **Select ODBC Data Source** window will appear:



Enter the information supplied by your database administrator and click **OK**.

If you are importing from a local database file, click the **Database file** option and then browse to locate the file.

Selecting Tables

In the Select Tables To Import window, select the tables you wish to import.

To add an interval or points table, click the **Add** button (\bigoplus); the list of tables in the database will be displayed. To remove a table from either list, click on it and click the **Remove** button (\bigcirc).

Click **OK** to begin the process of importing the data, which is similar to that described in <u>Importing</u> <u>Borehole Data</u>.

Connecting to an OpenGround Cloud Database

To import drilling data via OpenGround, right-click on the **Borehole Data** folder and select **Import Boreholes via OpenGround Cloud**. In the window that appears, enter your credentials for the database you wish to connect to, then select the instance you will use.

Select OpenGrou	nd Cloud Data					
roject						
Status	Project ID	Project title	^	Latitude	Longitude	General project comm
Open	Hydro Acetone	Hydro Acetone		50° 14' 60.00" N	10° 5' 60.00" W	Acetone sample data
Archive	Project 1	Project 1		53° 48' 44.32" N	2° 49' 53.52" W	
Archive	Project 2	Project 2				
Open	TestProject	Quinley Test Project		52° 36' 32.95" N	2° 0' 14.35" W	Derelict gasworks for
Open	Second	Second				
Archive	Stress Test	Stress Test				
Desk Study	Amended Config Pack	Test Config Pack		50° 4' 9.42" N	6° 53' 13.74" W	

In the next window, select from the projects available, then click **Next**.

Once the project has been opened, select the data columns to map to the **Collar**, **Survey** and **Tables** lists.

Summary Geological Information Field Geological Descriptions Fracture Spacing Interval Stratum Detail Descriptions Hole Construction If Boring-Drilling Progress by Time Interval Coring Information Interval Depth Related Exploratory Hole Information	Select	OpenGround Cloud Data		
Survey: Tables: Import As Row Court Y Summary Geological Information 13 Import As Field Geological Descriptions Interval 14	Input Da	ita		
Tables: Tables Import As Row Court Summary Geological Information Field Geological Descriptions Interval Fracture Spacing Interval Stratum Detail Descriptions Interval Hole Construction Boring-Drilling Progress by Time Interval Coring Information Depth Related Exploratory Hole Information Interval 2 Performation Interval 2	C <u>o</u> llar:	Location Details		
Tables Import As Row Court Summary Geological Information ## Field Geological Descriptions Interval ## Fracture Spacing Interval ## Stratum Detail Descriptions Interval Hole Construction ## Boring-Drilling Progress by Time Interval ## Coring Information Interval ## Depth Related Exploratory Hole Information Interval 2 Performation	Survey:	Crientation and Inclination		
Geological Information Interval 13 Image: Field Geological Descriptions Interval 14	Tables:	Tables	Import As	Row Count
Image: Second		✓ □ □ Summary		
Interval V		✓ □ □ Geological Information		
Interval V Interv		Field Geological Descriptions	Interval 🗸	131
Hole Construction Hole Construction Hole Construction Derige Drilling Progress by Time Interval Depth Related Exploratory Hole Information Interval Depth Related Exploratory Hole Information		Fracture Spacing	Interval 🗸	5
Image: Sering-Drilling Progress by Time Interval V 8 Image: Sering Drop Drilling Progress by Time Interval V 1 Image: Sering Drop Drop Drop Drop Drop Drop Drop Drop		Stratum Detail Descriptions	Interval 🗸	3
Coring Information Interval \sim 1 Coring Information Interval \sim 2		V D Hole Construction		
Depth Related Exploratory Hole Information Interval \sim 2		Boring-Drilling Progress by Time	Interval 🗸	89
		Coring Information	Interval 🗸	15
Depth Related Remarks Interval		Depth Related Exploratory Hole Information	Interval 🗸	28
		Depth Related Remarks	Interval 🗸	3

You can only select one collar table and one survey table, but you can select as many interval and point tables as you need. Change how tables are mapped using the **Import As** dropdown list:


😸 Select	OpenGround Cloud Data		×
Input Da	ta		
C <u>o</u> llar:	Location Details		~
Survey:	Dientation and Inclination		~
<u>T</u> ables:	Tables	Import As	Row Count
	🗸 🧧 🗋 Summary	T T	
	✓ 🗧 🗀 Geological Information	1 1	
	Field Geological Descriptions	Interval	131
	Fracture Spacing	Interval	5
	Stratum Detail Descriptions	Point	3
	✓ □ □ Hole Construction		
	Boring-Drilling Progress by Time	Interval 🗸	89
	Coring Information	Interval 🗸	15

Select only as many columns as you need to work with. You can import additional data columns from the project later.

Once you have selected the columns you wish to import, click **Import** to work through the data tables and add the data to the project tree.

e Da	ta						Column Summary			
	Hole ID 🗸 🗸	Not Imported 🗸	Not Imported 🗸 🗸	East (X) 🗸 🗸	North (Y) 🗸 🗸 🗸	Not Impo	Column	Column type	Import N	ame
1	LocationID	LocationType	Status	Easting	Northing	Latitude	LocationID	Hole ID	✓ Hole ID	
2	BH127	CP		399887.72	301130.66		LocationType	Not Imported	~	
3	BH128	CP		399809.58	301145.9		Status	Not Imported	~	
4	BH129	CP		399802.58	301195.2		Easting	East (X)	✓ East (X)	
5	BH130	CP		399758.58	301221.0		Northing	North (Y)	✓ North (Y)	
6	BH134	CP+RC		399757.08	301268.1		Latitude	Not Imported	~	
7	BH135	CP		399795.91	301272.33		Longitude	Not Imported	~	
8	BH136	CP		399725.18	301339.0					
9	BH137	CP		399671.18	301433.0		Name:	collar		
10	BH138	CP		399657.18	301492.0		_			
11	BH139	CP		399737.18	301399.9		Character encoding:	Auto (Windows-	1252)	
12	BH140	CP		399796.18	301321.1					
13	BH141	CP		399856.18	301245.0		Unique row ID:	None		
14	BH142	CP		399919.28	301165.9		Select header row:	1		
15	BH143	CP		400006.68	301096.5			Imp	ort All Column	s
16	CPT1	SCP		399821.0	301218.0					
17	TP121	TP		399888.16	301085.67		> Date and time for	mats		
18	TP122	TP		399830.26	301036.04		> CSV characters			

The import process is similar to that described in Working With Data Tables.



The data will be added to the project tree in the **Borehole Data** folder:

To import additional tables, right-click on the **Boreholes** object and select **Import from OpenGround Cloud**. Once you choose whether you will import intervals or points, the database will open and you can choose from the tables available.

See <u>Adding and Updating Data for Existing Tables</u> in the <u>Working With Data Tables</u> topic for information on appending and reloading borehole data.

You cannot append or reload data from a different OpenGround project.

Importing Interval Tables

Interval tables that have not been imported during the borehole data import process can be added to the project at any time. To add an interval table, right-click on the **Boreholes** object in the project tree and select from the options available:

- If the interval table is stored in a file on your computer or a network location, select Import From
 File > Interval Values. Leapfrog Works will ask you to specify the file location, and then will display the data in the file in the Import Interval window.
- If the interval table is stored in an ODBC database, select **Import From ODBC > Interval Values**. You will be prompted to select the data source. See <u>Selecting the ODBC Data Source</u>.

Columns required are:

- A borehole identifier
- Start/from and end/to depths
- A column of measurements

See <u>Expected Borehole Data Tables and Columns</u> for more information on the supported column types.

Select the required columns and assign the data type for each column. Click **Finish** to import the file, which will appear under the **Boreholes** object.

Importing Point Values Down Boreholes

To import a set of points on boreholes, right-click on the **Boreholes** object in the project tree and select **Import From File > Point Values** or **Import From ODBC > Point Values**.

When importing from a file, Leapfrog Works will ask you to specify the file location and then will display the data in the file in the **Import Depth Points** window.

When importing from ODBC, you will first be prompted to select the data source. See <u>Selecting the</u> <u>ODBC Data Source</u>.

Columns required are:

- A borehole identifier
- Depth

Select the required columns and assign the data type for each column. Click **Finish** to import the file, which will appear under the **Boreholes** object.

Importing LAS Points Down Boreholes

Leapfrog Works imports LAS points down boreholes in LAS 1.2 and LAS 2.0 formats. An imported set of LAS files appears as one object with its associated data columns plus a **LAS Boreholes** folder that contains a filter for each borehole. Importing the data preserves the metadata from the LAS files, which can be viewed in the **Properties** window for the LAS points object and in the **Properties** window for each borehole.

To import LAS points down boreholes, right-click on the **Boreholes** object and select **Import From File > LAS Data**. Select the files you wish to import and click Open.

Next, the **Import LAS Data** window will appear. The data displayed in this window is combined from the selected files, with blank and invalid values indicated by "nan". For example, if a borehole file does not contain columns that are included in other borehole files, those missing columns will be marked as "nan".

Leapfrog Works expects borehole ID and Depth columns and will attempt to match the data in the files with the expected format. Select the columns to import, then click **Finish**. The files will be added to the project tree as part of the **Boreholes** object, as described above.

To view LAS points, add the LAS points object to the scene. You can also display individual boreholes by adding their filters to the scene.

LAS File Mapping

The **Properties** window for **LAS Boreholes** includes a **LAS Mapping** tab that shows what data files have been used for the selected borehole:

General LAS Mapping Processing The mapping of curves from each file onto the columns of the depth points table									
Filename	lepth	caliper	density	gamapi	gamcps	m			
GS1.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	Μ			
GS2.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	М			
GS4.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	М			
GS5.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	М			
GS6.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	М			
GS7.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	М			
GS8.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	Μ			
GS9.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	М			
GS10.las	DEPT	CALIPER	DENSITY	GAMAPI	GAMCPS	Μ			

This is useful when data for a borehole originates in different files.

LAS File Inconsistencies

When importing LAS files, inconsistencies in the files are handled as follows:

- If there are two files with the same curve values at the same depth, the duplicate values will be added to the existing column and flagged as overlapping segments. See <u>Correcting Data Errors in Leapfrog</u> <u>Works</u> for more information about correcting borehole data errors.
- If there are more than two files with the same curve values at the same depth, Leapfrog Works will not be able to import the files. Note the conflicting files shown in the error message and reimport the files, leaving the conflicting files out.
- If there are multiple logs of the same name in the files, Leapfrog Works will not be able to import the data. Edit the LAS file header outside of Leapfrog Works to change the names.

Importing Downhole Structural Data

Leapfrog Works supports structural measurements in .csv or text formats. This topic describes importing downhole structural data tables. Structural data tables that include location information can also be imported to the **Structural Modelling** folder. See <u>Importing Planar Structural Data</u>.

To import a set of structural data on boreholes, right-click on the **Boreholes** object in the project tree and select **Import From File > Planar Structural Data** or **Import From ODBC > Planar Structural Data**.

When importing from a file, Leapfrog Works will ask you to specify the file location and then will display the data in the file in the **Import Planar Structural Data** window.

When importing from ODBC, you will first be prompted to select the data source. See <u>Selecting the</u> ODBC Data Source.

Leapfrog Works expects columns describing the borehole identifier, the depth and the structural orientation. Structural orientation can be specified using either dip and dip azimuth or alpha and beta.

Match the values in the file to the required column headers, then click **Finish** to import the file. The table will appear under the **Boreholes** object.

If the structural orientation is specified using alpha and beta, the reference line from which the beta is measured can be the bottom or top of the borehole. When the table is imported, the default setting is **Bottom of core**. To change this, double-click on the structural data table in the project tree. Next, click on **Compatibility** to change the **Beta reference mark** setting to **Top of core**:

Z 😤 F	Projects		Scene View	C	Central Project	ts C	Castle Hill Bas	in ×	Structural_data ×
Fix Erro	ors) ?							
⊖ T <u>o</u> ● <u>B</u> o	rence mari p of core ttorn of co	re							
> <u>D</u> ecluste > <u>Q</u> uery		All 8 rows							
Ignored	id	^ holeid	depth	dip	azimuth	polarity	alpha	beta	
	1	Bore 2	430.0			1	30.0	218.0	
	2	Bore 3	95.0			1	20.0	160.0	
	3	Bore 3	50.0			1	10.0	190.0	

Borehole Desurveying Options

Borehole desurveying computes the geometry of a borehole in three-dimensional space based on the data contained in the survey table. Under ideal conditions, the borehole path follows the original dip and azimuth established at the top of the borehole. Usually, though, the path deflects away from the original direction as a result of layering in the rock, variation in the hardness of the layers and the angle of the drill bit relative to those layers. The drill bit will be able to penetrate softer layers more easily than harder layers, resulting in a preferential direction of drill bit deviation.

There are a number of paths a borehole could take through available survey measurements, but the physical constraints imposed by drilling are more likely to produce smoother paths. Selecting the desurveying method that gives the best likely approximation of the actual path of the borehole will ensure that subsequent modelling is as accurate as possible.

Leapfrog Works implements three algorithms for desurveying boreholes:

- The Spherical Arc Approximation Algorithm
- The Raw Tangent Algorithm
- The Balanced Tangent Algorithm

These options are described in more detail below.

Another factor that affects how boreholes are desurveyed is how dip values are handled. When the survey table is imported, Leapfrog Works sets the **Negative survey dip points down** value according to the data in the imported table. When the majority of the dip data in the table is positive, Leapfrog Works assumes all these boreholes will point down and leaves the field **Negative survey dip points down** disabled. When most of the values are negative, the field is enabled. This field can be changed by double-clicking on the survey table to open it and then clicking on **Compatibility** to show the table's desurveying settings:

V Projects Scene V			Scene View	C	Central Projects	${f C}$ Castle Hill Basin $ imes$	survey	×
Fix Errors ⁽²⁾								
Ignored	id ^	holeid	depth	dip	azimuth			
	1	h001	0.0	68.5	7.7			
	2	h002	0.0	76.5	2.3			
	3	h003	0.0	65.6	92.0			

If you are going to change the automatically set value of **Negative survey dip points down**, consider carefully the implications if there is a mix of boreholes pointing down and up.

The other **Compatibility** setting relates to the algorithm used in desurveying the boreholes.

The Spherical Arc Approximation Algorithm

The default algorithm used in Leapfrog Works is spherical arc approximation, which is sometimes referred to as the minimum curvature algorithm. Downhole distances are desurveyed exactly as distances along a circular arc:



The algorithm matches the survey at the starting and end positions exactly and the curvature is constant between these two measurements. At the survey points, the direction remains continuous and, therefore, there are no unrealistic sharp changes in direction.

If you wish to use spherical arc approximation, there is no need to change any settings.

The Balanced Tangent Algorithm

The balanced tangent algorithm uses straight lines but attempts to improve the accuracy of the raw tangent algorithm by assigning equal weights to the starting and end survey measurements:




It is an improvement on the raw tangent algorithm but still suffers from an unrealistic discontinuity in the borehole path. It is, however, a better approximation of the overall borehole path and is reasonably accurate when the spacing between measurements is small.

To use the balanced tangent algorithm, double-click on the survey table in the project tree. Click on **Compatibility** and change the **Desurveying method**.

The Raw Tangent Algorithm

The raw tangent algorithm assumes the borehole maintains the direction given by the last survey measurement until the next new measurement is reached:



This implies that the borehole makes sharp jumps in direction whenever a measurement is taken, which is unlikely, except when the borehole is being used to define a trench.

Collar tables have a **trench** column that indicates whether or not the borehole is from a trench. When the **trench** column is ticked for a borehole, the trench will be desurveyed using the raw tangent algorithm. Double-click on the collar table in the project tree, then tick the **trench** box for the boreholes you wish to desurvey using the raw tangent algorithm.

Processing Borehole Data

Once imported and corrected, borehole data usually requires further processing before any models are built. Use the techniques described in <u>Displaying Boreholes</u> to aid in making decisions on what further processing is required.

Often, selecting a small portion of intervals can be achieved using a query filter (see the <u>Query Filters</u> topic). In some cases, however, you may wish to composite data to focus on a single unit. There may also be issues with how borehole data has been recorded; for example, two units have been catalogued as one, or a single unit may be divided into multiple units.

Leapfrog Works has a number of tools for processing borehole data, including:

- <u>Category Composites</u>. Sometimes unit boundaries are poorly defined, with fragments of other lithologies within the lithology of interest. This can result in very small segments near the edges of the lithology of interest. Modelling the fine detail is not always necessary, and so compositing can be used to smooth these boundaries.
- <u>Majority Composites</u>. Category data can be composited into interval lengths from another table or into fixed interval lengths. The compositing is based on a majority percentage where each interval is assigned a category based on the category that makes up the highest percentage of the new interval.
- <u>Numeric Composites</u>. Compositing numeric data takes unevenly-spaced borehole data and turns it into regularly-spaced data, which is then interpolated. Numeric data can be composited along the entire borehole or in selected regions. You can also set the compositing length from the base interval table.
- <u>Grouping Lithologies</u>. The group lithologies tool lets you define a new unit to which existing units are added. For example, a sandstone deposit might appear in an interval table as poorly-sorted and well-sorted units. The group lithologies tool lets you group both units into a single sandstone unit.
- <u>Splitting Lithologies</u>. Lithology units may be incorrectly grouped, which can become apparent when you display boreholes in the scene. The split lithologies tool lets you create new units by selecting from intervals displayed in the scene.
- <u>Interval Selection</u>. If the lithologies in a column are poorly sorted, you can display the column in the scene and use the interval selection tool to work with all the segments and sort them into new units.
- <u>Overlaid Lithology Column</u>. You may have two versions of an interval column, one that contains draft data and one that contains the final version. The final version may contain gaps, which can be filled in using the draft version. The overlaid lithology tool lets you combine the two columns to create a new column.
- <u>Category Column from Numeric Data</u>. When you have numeric data you wish to use with the lithology and category modelling tools, you can convert the numeric data to a category column.
- <u>Back-Flagging Borehole Data</u>. Evaluating geological models on boreholes creates a new lithology table containing the lithologies from the selected model.

Each of these tools creates a new interval table or creates a new column in an existing interval table, preserving the original data. New tables and columns can be used as the basis for new models in the project and can be incorporated into existing models using **From Other Contacts** options. When a new table is created, you can view it in the scene along with the original table to see the differences between the processed and the unprocessed data.

If you are working with columns in different interval tables, you can create a new merged table that includes columns from these different tables. Columns created in Leapfrog Works can be included in a merged table. See <u>Merged Borehole Data Tables</u>.

Category Composites

Sometimes unit boundaries are poorly defined, with fragments of other lithologies within the lithology of interest. This can result in very small segments near the edges of the lithology of interest. Modelling the fine detail is not always necessary, and so compositing can be used to smooth these boundaries.

In Leapfrog Works, you can composite category data in two ways:

- Composite the borehole data directly. This creates a new interval table that can be used to build models, and changes made to the table will be reflected in all models based on that table. This process is described below.
- Composite the points used to create an object.

The rest of this topic describes compositing borehole data directly.

Right-click on the **Composites** folder, which is in the project tree as part of the **Boreholes** object, and select **New Category Composite**. You will be prompted to select from the category columns available in the borehole data. Next, the **New Composited Table** window will appear, showing the options for sorting intervals in the selected column:

Rew Composited Table	×
Composite on column 'ROCK' on table 'a_lith'	
Query filter: None	~
Primary <u>u</u> nit	
ASH	~
Exterior segments Ignored segments	
COLLV DA E1 E2 E3 EBX1 Treat unspecified intervals as Ignored O Primary O Exterior Compositing	
Convert enclosed ignored segments	
Shor <u>t</u> er than: 1.000	
Eilter primary segments shorter than: 0.000	
Filter exterior segments shorter than: 0.000	
Name: ROCK_composite	
₩ <u>C</u> ancel	€ОК

Compositing category data sorts segments into three categories:

- **Primary**. This is the unit of interest. In the case of compositing on intrusion contact surfaces, this will be the interior/intrusive lithology.
- **Ignored**. These are units that are, generally, younger than the unit of interest and should, therefore, be ignored in generating contact surfaces.
- **Exterior**. These are units that occur outside of the unit of interest. For an intrusive lithology, other lithologies the intrusion contacts should be classified as **Exterior**.

Unspecified intervals can be handled as **Ignored**, **Primary** or **Exterior**.

The additional compositing parameters determine how ignored segments flanked by interior or exterior segments are handled and the length of segments that will be filtered. Each of these settings is discussed below.

Click **OK** to create the table. Once you have created a composited table, you can edit it by right-clicking on it and selecting **Edit Composited Table**.


Converting Ignored Segments

The **Convert enclosed ignored segments** setting determines how ignored segments are handled when they are flanked by either two interior segments or two exterior segments. If **Convert enclosed ignored segments** is enabled, Leapfrog Works will convert enclosed ignored segments to match the surrounding segments. In cases where an ignored segment does not lie between two interior or exterior segments, it will remain ignored.

If you wish to set a maximum size for ignored enclosed segments, tick the **Shorter than** box and set the maximum length.

If **Convert enclosed ignored segments** is disabled, this processing does not occur and ignored segments are never converted. When an intrusive contact surface is created, this setting is disabled by default.

For example, this scene shows two ignored segments that are flanked by the unit of interest. Because **Convert enclosed ignored segments** is disabled, the segments remain ignored:




Enabling **Convert enclosed ignored segments** results in the segments being converted to the **Primary** unit:

😰 Edit Composited Table 🛛 🕹 🕹				ROCK 🛛
Composite on column 'ROCK' on table 'a_lith'	$1 \times X$			Exterior Ignored
Query filter: None 🗸				Primary
Primary <u>u</u> nit				
H V				/
Exterior segments Ignored segments				/
SBX ASH				/
COLLV			6	/
DA E1				/
E2				1
E3 ~				/
Treat unspecified intervals as				/
● Igno <u>r</u> ed ○ <u>P</u> rimary ○ E <u>x</u> terior				
Compositing				
✓ Convert enclosed ignored segments				
Shorter than: 1.000				
Eilter primary segments shorter than: 20.000				
Filter exterior segments shorter than: 0.000		BOCK_con	nposite	
Filter exterior segments shorter than:		Slice mode:	From Scene	~
Name: ROCK_composite		Query filter:	No Filter	×
		Filter tra		
₩ <u>Cancel</u>		Line width:	2.00	0
			(

Enabling **Shorter than** and setting it to 4 results in the shorter segment being converted to the **Primary** unit and the longer segment remaining **Ignored**:

🚱 Edit Composited Table X				terior
Composite on column 'ROCK' on table 'a_lith'	X		Ig Ig	nored
Query filter: None			Pr	imary
Primary <u>u</u> nit				
H				
Exterior segments				
SBX ASH		$\overline{\mathbf{v}}$		
COLLV				
DA E1				
E2		7		
E3 ~				
Treat unspecified intervals as				
● Igno <u>r</u> ed ○ <u>P</u> rimary ○ E <u>x</u> terior				
Compositing				
✓ Convert enclosed ignored segments				
Shorter than: 4.000				
Filter primary segments shorter than: 20.000				
Filter exterior segments shorter than:		👸 ROCK_com	posite	
		Slice mode:	From Scene	~
Name: ROCK_composite		Query filter:	No Filter	· ~
	=	🗌 Filter tra	ce lines	
₩ Cancel 20K		Line width:	2.00	\$
			E 101 E 1	

Zooming out, we can see that the ignored segments at the top of the boreholes have not been converted:




Filtering Short Segments

The **Filter primary segments** and **Filter exterior segments** parameters determine how short a segment must be before it is composited:


- Short Exterior segments flanked by Primary segments will be converted to Primary segments.
- Short **Primary** segments flanked by **Exterior** segments will be converted to **Exterior** segments.

When the value is set the zero, no segments will be converted.

To see how these parameters can smooth the shape of a unit of interest, let's look at a series of boreholes where we wish to create an intrusion boundary based on the red segments. Short segments are highlighted in the intervals that have not been composited:



An intrusion generated from these intervals will have more detail than is necessary for modelling. However, when compositing settings are applied and the short intervals are converted, we can see that the intrusion boundary is more geologically reasonable:



Viewing Category Composite Statistics

Once you have created a composited table, you can view statistics on the table. To do this, right-click on it and select **Statistics**. The following options are available:

😤 Statistics	×
Choose Statistics Type	
Image: Image and the statistics A table of the statistics of multiple attributes, optionally grouped by category.	
Scatter Plot	
Q-Q Plot A quantile-quantile plot of two numeric columns, or one column with two filters.	
Box Plot A box plot of a single numeric column, split by a category column.	
Interval Length Statistics Univariate statistics of the interval lengths.	

See the Analysing Data topic for more information on each option:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots

The **Interval Length Statistics** graph is a univariate graph, so for more information on the options available, see <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic.

Majority Composites


Category data can be composited into interval lengths from another table or into fixed interval lengths. The compositing is based on a majority percentage where each interval is assigned a category based on the category that makes up the highest percentage of the new interval. If two categories are equally represented, the category that occurs further up the borehole (closest to the collar) is assigned. This is useful for comparing lithology and assay data; the intervals from an assay table can be applied to a category column to produce a new lithology column with the shorter intervals typical of assay tables. The majority composite column can then be used to create a merged table containing both lithology and assay data.

Borehole data is composited from the **Composites** folder, which is in the project tree as part of the **Boreholes** object. To create a majority composite, right-click on the **Composites** folder and select **New Majority Composite**. The **New Composited Table** window will appear:


ntervals from:	Fixed Length>			•
Compositing Length: 1	0.0			\$
vailable columns:		Select	ed columns:	
 a	K_Veins	•		
Select <u>A</u> ll <u>S</u> elec	t None			

Select the interval table that will be used to specify the intervals for the new majority composite or specify a fixed **Compositing Length**. Next, select the columns that will be composited. Click **OK** to create the composite. The composite will be added to the **Composites** folder in the project tree. You can edit it by right-clicking on it and selecting **Edit Composited Table**.

Here assay intervals are shown inside the much longer lithology intervals. The selected interval goes from 14.0 to 23.7 metres:



Here a majority composite has been created based on the lithology table using the assay table intervals. The category column displayed in the scene appears similar to the category column used to create it, but selecting an interval in the scene shows that the lithology has been composited into smaller intervals that match the assay intervals:



Viewing Majority Composite Statistics

Once you have created a composited table, you can view statistics on the table. To do this, right-click on it and select **Statistics**. The following options are available:

😤 Statistics 🛛 🗙
Choose Statistics Type
Iable of Statistics A table of the statistics of multiple attributes, optionally grouped by category.
<u></u> <u>S</u> catter Plot A scatter plot of two numeric columns.
Q-Q Plot A quantile-quantile plot of two numeric columns, or one column with two filters.
Box Plot A box plot of a single numeric column, split by a category column.
Interval Length Statistics Univariate statistics of the interval lengths.
Cancel

See the <u>Analysing Data</u> topic for more information on each option:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots

The **Interval Length Statistics** graph is a univariate graph, so for more information on the options available, see <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic.

Right-click on the numeric columns and select **Statistics** to view information about the composited values. See <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic for more information.

Numeric Composites

Compositing numeric data takes unevenly-spaced borehole data and turns it into regularly-spaced data, which is then interpolated. Compositing parameters can be applied to entire boreholes or only within a selected region of the borehole. For example, you may wish to composite Au values only within a specific lithology.

There are two approaches to compositing numeric data in Leapfrog Works:

- Composite the borehole data directly. Compositing parameters can be applied to entire boreholes or only within a selected region of the borehole. This creates a new interval table that can be used to build models, and changes made to the table will be reflected in all models based on that table. This process is described below.
- Composites the points used to create an interpolant. This is carried out by generating an interpolant and then setting compositing parameters for the interpolant's values object. This isolates the effects of the compositing as the compositing settings are only applied to the interpolant.

Intervals that have no data can have a significant effect when compositing data as they are ignored by the compositing algorithm. The effect of these missing intervals can be managed using the **Minimum coverage** parameter, but it's best to assign special values where intervals have no data. For example, intervals that are missing data can be assigned a value of 0 or that of the background mineralisation. See <u>Handling Special Values</u> for more information.

The rest of this topic describes compositing borehole data directly. It is divided into:

- Creating a Numeric Composite
- Compositing in the Entire Borehole
- Compositing in a Subset of Codes
- Using Intervals From Another Table
- <u>Viewing Numeric Composite Statistics</u>

Creating a Numeric Composite

Creating a numeric composite involves the following steps:

- Selecting the compositing region
- Setting the composite length
- Setting coverage
- Setting residual length handling
- Selecting an additional weighting column (optional)
- Selecting the output columns

To start the process of creating a numeric composite, right-click on the **Composites** folder and select **New Numeric Composite**. You will be prompted to select the compositing region. There are three options:

- Entire Borehole. The same compositing parameters are applied to all values down the length of boreholes, regardless of unit breaks. See <u>Compositing in the Entire Borehole</u>.
- **Subset of Codes**. Different compositing parameters can be set for each code down the length of boreholes. See <u>Compositing in a Subset of Codes</u>.

• Intervals from other Table. Interval lengths from another table are used to determine composite lengths. The value assigned to each interval is the length-weighted average value, and there are no further compositing parameters to set. See <u>Using Intervals From Another Table</u>.

Each option requires a different set of compositing parameters, which are described below.

Once you have set up the composite, click **OK** to create the table, which will be saved to the **Composites** folder. Double-clicking on the table displays the data in its columns. Edit the table by right-clicking on it and selecting **Edit Composited Table**. You can view statistics on the table or for each individual column in the table. See <u>Viewing Numeric Composite Statistics</u>.

Compositing in the Entire Borehole

When compositing is carried out using the **Entire Borehole** option, the boreholes are divided into intervals wherever numeric data occurs and the parameters set in the **Compositing** tab are applied to all values down the length of boreholes.

🛿 New Composited Table - Entire Borehole 🛛 🗙 🗙							
Compositing Output Columns							
Compositing length:	10.00						
If residual end length less than:	0.00						
then discard	~						
Minimum coverage:	50 🗘 %						
Additional weighting column:	<none> V</none>						

Compositing Length

The **Compositing length** you set will depend on factors including the deposit style, the sampling method and raw sample length. You can view statistics on the borehole data table to get an idea of the distribution of interval lengths. Right-click on the borehole data table and select **Statistics**. In the window that appears, select the **Interval Length Statistics** option:

😵 Statistics 🛛 🗙
Choose Statistics Type
Iable of Statistics A table of the statistics of multiple attributes, optionally grouped by category.
A scatter Plot
Q-Q Plot A quantile-quantile plot of two numeric columns, or one column with two filters.
Box Plot A box plot of a single numeric column, split by a category column.
Interval Length Statistics Univariate statistics of the interval lengths.
Cancel

Another consideration in selecting the composite length is choosing a length that will not split units. For example, if most intervals are 2m long, choosing a length of 1m or 5m will split some intervals so that an interval with a single value will be represented more than once in the composite intervals. If intervals are

mostly 2.5m long, then a composite length that is 2.5m or a multiple of 2.5m would ensure that units are not split.

Note that the actual length of intervals in the composited table may be longer than that set by the **Compositing length**. This arises from residual segments at the ends of boreholes and where there is data missing down a borehole; the length of these residual segments will, in certain conditions, be added to the composite intervals further up the borehole. See <u>Residual End Length Handling</u> below for more information.

Minimum Coverage

The **Minimum coverage** parameter determines whether or not a value will be calculated for a composite interval, based on the data available in the input data table. The **Minimum coverage** is a threshold the input intervals must meet in order for a composited value to be calculated. If, for example, the **Minimum coverage** is 50%, a value will be calculated for a composite interval only when there is data in at least 50% of the borehole that informs the composited interval.

- Setting **Minimum coverage** to 100% will result in composite intervals being assigned values only when there is data for all borehole intervals that inform the composite interval.
- Setting Minimum coverage to 0% will results in all composite intervals being assigned values.

Intervals that have no data can have a significant effect when compositing data as they are ignored by the compositing algorithm. The effect of these missing intervals can be managed using the **Minimum coverage** parameter, but it's best to assign special values where intervals have no data. For example, intervals that are missing data can be assigned a value of 0 or that of the background mineralisation. See <u>Handling Special Values</u> for more information.

Composite values are calculated for each composite interval. This is simply the length-weighted average of all numeric borehole data that falls within the composite interval.

Composite points are generated at the centre of each composite interval from the composite values.

Residual End Length Handling

The full length of each borehole will seldom divide up exactly into a whole number of intervals of the specified **Compositing length**. For this reason, "residual segments" will occur at the end of each borehole and where there is data missing down the length of the borehole. In the **Compositing** tab, you can set a residual end length value, then specify how residual segments that are shorter than that value are handled. There are three options:

- With the **Discard** option, both the length of the residual segment and the **Minimum coverage** threshold determine whether the segment is discarded or retained:
 - Residual segments shorter than the specified length are discarded.
 - Residual segments longer than the specified length that meet the **Minimum coverage** threshold are retained as separate segments at the end of the borehole.
 - Residual segments longer than the specified length that do not meet the **Minimum coverage** are discarded.
- With the **Add to previous interval** option, the **Minimum coverage** is automatically set to zero so that the length of residual intervals is the sole factor in determining whether they are retained as separate segments or added to the previous interval.

- Residual segments longer than the specified length are retained as separate segments.
- Residual segments shorter than the specified length are added to the previous interval. Note that when this occurs, the actual length of that last composited interval will be longer than the **Compositing length** specified.
- With the **Distribute equally throughout borehole** option, the **Minimum coverage** is automatically set to zero so that the length of the residual segments is the sole factor in determining whether they are retained as separate intervals or distributed equally throughout the other intervals.
 - Residual segments longer than the specified length are retained as separate segments.
 - Residual segments shorter than the specified length have their length distributed among the other intervals. Note that when this occurs, the actual length of each composited interval will be longer than the **Compositing length** specified.

Additional Weighting Column

If you use an **Additional weighting column**, the column selected must contain valid (positive) values for all of the composite's output intervals. If this is not the case, you will receive a message saying the table cannot be created. If the column selected as the weighting column is also in the list of output columns, that output column will be composited using length-weighted averaging only.

Compositing in a Subset of Codes

When compositing is carried out using the **Subset of Codes** option, some codes can be excluded from the composited table or the raw data from the **Base column** can be used. When compositing is applied to a code, the same parameters apply as for the **Entire Borehole** option, but different codes can use different **Compositing length** and **Minimum coverage** parameters.

	(
<u>B</u> ase column:	M GM			~
Additional <u>w</u> eighting colum	n: None>			~
Lithology	Action	Length	Min. coverage	e %
Default	Composite	10	50	
Alluvial gravel	Composite	10	50	
clay	Composite	10	50	
Granodiorite	Composite	10	50	
Sandy gravel	Composite	10	50	
Schist	Composite	10	50	
Silt	Composite	10	50	
Water	Composite	10	50	
lf <u>r</u> esidual end length less tha	in: 0			
then: discard	~			
me: numeric_composite				

For the **Action** column, select from:

- **Composite**. Numeric data that falls within the selected code will be composited according to the parameters set.
- No compositing. Numeric data is not composited within the selected code. The raw data will be

used in creating the new data table.

• Filter out. Numeric data within the selected code will excluded from the new data table.

See <u>Compositing in the Entire Borehole</u> above for an explanation of the **Length**, **Minimum coverage**, **If residual end length** and **Additional weighting column** parameters.

Once you have set the compositing parameters, click on the **Output Columns** tab to select from the available columns of numeric data. Click **OK** to create the table.

Using Intervals From Another Table

When compositing is carried out using the **Intervals from other Table** option, first select the **Base table**. This is the table that will that will be used to determine the interval lengths in the composited table.

😵 New Composited Table - In	tervals from Table	×
<u>B</u> ase table:	Lake_Aura_Geology	~
Additional weighting column:	<none></none>	~
Output columns Available columns:	S <u>e</u> lected columns:	
▼ ☐ Lake_Aura_RQD	*	
Select <u>A</u> ll Select No	pne	
<u>N</u> ame: numeric_composite		
Help	🤾 Cancel 🦪	<u>о</u> к


The value assigned to each interval will be the length-weighted average value, and you can use an **Additional weighting column**. This column must contain valid (positive) values for all of the composite's output intervals. If this is not the case, you will receive a message saying the table cannot be created. If the column selected as the weighting column is also in the list of output columns, that output column will be composited using length-weighted averaging only.

There are no further compositing parameters to set. Click **OK** to create the table.

Viewing Numeric Composite Statistics

Once you have created a composited table, you can view statistics on the table or for each individual column in the table.

To view statistics for the table, right-click on it and select **Statistics**.




See the Analysing Data topic for more information on each option:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots

The **Interval Length Statistics** graph is a univariate graph, so for more information on the options available, see <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic.


Right-click on the table columns and select **Statistics** to view information about the composited values.

The first option displays statistics on the composited values; see <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic for more information. The other two options display statistics comparing data before and after compositing.



Compositing Comparison

The double histogram, one displaying the distribution of the raw data and one displaying the distribution of the composited data, enables comparison of the two distributions of the same element before and after the compositing transformation. Impacts on the symmetry of distributions will be evident.



In the **Histogram** settings, **Bin width** changes the size of the histogram bins used in the plot. **Percentage** is used to change the Y-axis scale from a length-weighted scale to a percentage scale.


The **Box Plot** options control the appearance of the box plot drawn under the primary chart. The whiskers extend out to lines that mark the extents you select, which can be the **Min/max whiskers**, the **Inner fence whiskers** or the **Outer fence whiskers**. Inner and outer values are defined as being 1.5 times the interquartile range and 3 times the interquartile range respectively.

The Limits fields control the ranges for the X-axis and Y-axis. Select Automatic X axis limits and/or Automatic Y axis limits to get the full range required for the chart display. Untick these and manually adjust the X limits and/or Y limits to constrain the chart to a particular region of interest. This can effectively be used to zoom the chart.

The bottom left corner of the chart displays a table with a comprehensive set of statistical measures for the data set.

Compositing Interval Lengths

This graph shows a double histogram of distributions of the interval lengths before and after compositing.



In the **Histogram** settings, **Bin width** changes the size of the histogram bins used in the plot. **Percentage** is used to change the Y-axis scale from a length-weighted scale to a percentage scale.

The **Box Plot** options control the appearance of the box plot drawn under the primary chart. The whiskers extend out to lines that mark the extents you select, which can be the **Min/max whiskers**, the **Inner fence whiskers** or the **Outer fence whiskers**. Inner and outer values are defined as being 1.5 times the interquartile range and 3 times the interquartile range respectively.

The Limits fields control the ranges for the X-axis and Y-axis. Select Automatic X axis limits and/or Automatic Y axis limits to get the full range required for the chart display. Untick these and manually adjust the X limits and/or Y limits to constrain the chart to a particular region of interest. This can effectively be used to zoom the chart.

The bottom left corner of the chart displays a table with a comprehensive set of statistical measures for the data set.

Grouping Lithologies

The group lithologies tool lets you define a new unit to which existing units are added. For example, a sandstone deposit might appear in an interval table as poorly-sorted and well-sorted units. With the group lithologies tool, you can group both units into a single sandstone unit.

When you group lithologies, the original lithology column is preserved and a new lithology column is added to the interval table. You can then select the original lithology column or the new one when displaying data and creating models.

To start grouping two or more lithologies, right-click on the interval table in the project tree and select **New Column > Group Lithologies**. The **New Lithology Column** window will appear:

😤 New Lithold	ogy Column	×
<u>B</u> ase Column:	👰 Lithology	-
<u>N</u> ame:	GroupedLithologies	
Help	Cancel	(

Select the lithology column you wish to use from the **Base Column** list, then enter a **Name** for the new lithology column. Click **OK**.

A window will appear displaying all lithologies in the base lithology column:

😰 Lithology Column - GroupedLit	hologies			×
Ungrouped Lithologies		Groups		
(ID) Code	Colour	Columnation	ode	Colour
Alluvium				
Aluvium				
Aquifer Miocene Alluvium				
Basement Granite				
Coarse Sand				
 Glacial Till 				
Gravel				
Lower Gravel				
Auto Group	w Group			Delete Groups
Help			X Can	cel <u>@Q</u> K

In this example, two spellings of Alluvium have been used and these lithologies should be combined into a single lithology.

The most straightforward way to group lithologies is to select the first of the lithologies, then click **New Group**. A group will be created for the selected lithology with only that lithology as a member:

-	rouped Lithologies		Group	15	
	Code	Colour	Ð	Code	Colou
B>	Aluvium		▼ @	Alluvium	
	Aquifer Miocene Alluvium			Alluvium	
5>	Basement Granite				
	Coarse Sand				
	Glacial Till				
	Gravel				
Ð	Lower Gravel				

ing	rouped Lithologies	_	Group	1		
۲	Code	Colour	۲	Code		Colour
۲	Aluvium		V .0	Allunium		
٩	Aquifer Miocene Alluvium			Aluviu		
٩	Basement Granite					
Ð	Coarse Sand					
Ð	Glacial Till					
Ð	Gravel					
Ð	Lower Gravel					
	Auto Group	w Group			Delet	e Groups

Next, click on a lithology in the **Ungrouped Lithologies** pane and drag it onto the group:

Grouping lithologies creates a new lithology column and any lithologies left in the **Ungrouped Lithologies** pane will be excluded from the new column. For this reason, once you have grouped the required lithologies, move all remaining lithologies to the **Groups** pane by clicking on each lithology, then on the **New Group** button. This will make each remaining lithology a new group with a single member:

ng	rouped Lithologies		Group	5	
	Code	Colour	۲	Code	Colour
				Alluvium Alluvium Aluvium Aquifer Miocene Alluvium Basement Granite Coarse Sand Glacial Till Gravel Lower Gravel	
6	Auto Group	<u>N</u> ew Group		Cancel	e Groups

When you are finished, click **OK** to create the new lithology column. It will appear in the project tree as an additional lithology column in the interval table.

Select the new column from the shape list to display it:

👁 🗾 Lithology	/ 🛛	Groupe Edit Colours	
		🐣 Flat colour	
		A GroupedLithologies	
		hs hs	
		👰 Lithology	

Click on the **Edit** button (\checkmark) to start editing the selected column.

The other way to group lithologies is to let Leapfrog Works create the lithology groups.

Automatic Lithology Groups

Leapfrog Works can automatically create lithology groups. To do this, create a new lithology column, as described above. Click the **Auto Group** button to reveal more options:

ngi	rouped Lithologies		Grou	ps		
۲	Code	Colour	•	Code		Colour
۲	Alluvium					
۲	Aluvium	=				
۲	Aquifer Miocene Alluvium					
۲	Basement Granite					
۲	Coarse Sand					
۲	Glacial Till	-				
Gro	up Values By:					
(● <u>F</u> irst 1 ↓ letter(s)					
(⊖ <u>L</u> ast 1 _ letter(s)					
(One group per <u>v</u> alue	Group				
	Auto Group	New Group]		B Del	ete Groups

The **First letter(s)** and **Last letter(s)** options let you create groups according the names of the existing lithologies. Click **Group** to create the new groups.

Here, the first two letters have been used to created a new set of lithologies:

Ingrouped Lithologies			Groups		
Ð	Code	Colour	۲	Code	Colou
				Co	
				Gr	
			▼ @	Lo	
				Lower Gravel	
			▼ @	· Al	
				Alluvium	
				Aluvium	
				Ва	
	Auto Group	New Group			Delete Groups

The two alluvium lithologies have been added to a single group.

The **One group per value** option creates a group for each original lithology. You can then drag and drop lithologies into different groups, move lithologies you do not wish to group back into the **Ungrouped Lithologies** pane and use the **Delete Groups** options to remove any empty groups.

Splitting Lithologies

With the split lithologies tool, you can create new units from a single unit by selecting from intervals displayed in the scene. When you split lithologies, the original lithology column is preserved and a new lithology column is added to the interval table. You can then select the original lithology column or the new one when displaying data and creating models.


The difference between the interval selection tool and the split lithologies tool is that with splitting lithologies, you are limited to selecting intervals from a single lithology. If you wish to select intervals from multiple lithologies, see <u>Interval Selection</u>.

To start splitting a lithology, first add the borehole data to the scene. Then right-click on the interval table in the project tree and select **New Column > Split Lithologies**. The **New Lithology Column** window will appear:

😤 New Lithol	ogy Column	×			
<u>B</u> ase Column:	A Lithology	~			
<u>N</u> ame:	SplitLithologies				
Help X Cancel					

Select the lithology column you wish to use from the **Base Column** list, then enter a **Name** for the new lithology column. Click **OK**.


The **Lithologies and Splits** window will appear, together with a set of tools that will help you to select intervals in the scene:



Alluvium (gold) appears both above and below Coarse Sand (blue) and so should be split into two separate lithologies.

The first step is to select the lithology that will be split in the **Lithologies and Splits** window. In the example above, Alluvium is already selected.

Next, click on the **Select Intervals** tool () and click the **Add Intervals** tool (). In the scene, draw a line across each interval you wish to select.



To change the width of the line used to select intervals, click on the **Change line width** button (\square) and enter a new value. You can keep the **Set Line Width** window open while you select intervals so you can change the line width as required:

📕 🍢 % 💽 I 🕐 I 🥱 🦑 🛅 🗙
💋 Set Line Width 🛛 🗙 🗶
Selection line width: 19
Close

Note that the current line width is indicated by the **Change line width** button.

Selected intervals are highlighted in the scene. If you accidentally select the wrong interval, either:


- Click the **Remove intervals** button (⁴) and draw across the interval once again.
- Hold the **Ctrl** key while drawing across the interval.

You can also:


- Select all visible intervals by clicking on the **Select all** button (¹) or by pressing Ctrl+A.
- Clear all selected intervals by clicking on the Clear selection button (⁴⁶) or by pressing Ctrl+Shift+A.

Swap the selected intervals for the unselected intervals by clicking on the **Invert selection** button (
 Or by pressing Ctrl+I.


Once you have selected some segments, click on the **Assign to** button in the **Lithologies and Splits** window and select **Create New Split**:



The **New Split** window will appear:



Enter a **Name** for the new lithology, then click **OK**. The new lithology will be created and the scene updated to reflect the changes:



Once you have created a new lithology, you can add to it by selecting intervals, then selecting the lithology from the **Assign to** list.

When you are finished, click the **Save** button (and close the **Lithologies and Splits** window. The new lithology column will appear in the project tree as an additional lithology column in the interval table. Select the new column from the shape list to display it:

👁 🗾 Lithology	1 🖉	A SplitLit Edit Colours		
		🐣 Flat colour		
		👰 GroupedLithologies		
		👰 Lith		
		👰 Lithology		
		A SplitLithologies		
		W	-	

Click on the **Edit** button (\checkmark) to start editing the selected column.

Interval Selection

When you wish to select a small portion of intervals or you don't have suitable parameters to use a query filter, you can select intervals from boreholes displayed in the scene to create a new lithology column. The original lithology column is preserved and a new lithology column is added to the interval table. You can then select the original lithology column or the new one when displaying data and creating models.

The difference between the interval selection tool and the split lithologies tool is that with splitting lithologies, you are limited to selecting intervals from a single lithology. With interval selection, you can choose intervals from any lithology displayed in the scene.


To start selecting intervals, first add the borehole data to the scene. Then right-click on the interval table in the project tree and select **New Column > Interval Selection**. For a merged table, right-click on it and select **Interval Selection**.

The New Lithology Column window will appear:

😰 New Lithol	ogy Column	×
<u>B</u> ase Column:	👰 Lithology	~
<u>N</u> ame:	Selected Intervals	
Help	Cancel 🦪 Q	к

Select the lithology column you wish to use from the **Base Column** list, then enter a **Name** for the new lithology column. Click **OK**.

The Interval Selection window will appear, together with a set of tools that will help you to select intervals in the scene. To select intervals, click on the Select Intervals button () and click the Add Intervals button (). In the scene, draw a line across each interval you wish to select:




Selected intervals are highlighted in the scene. If you accidentally select the wrong interval, either:

- Click the **Remove intervals** button (⁴) and draw across the interval once again.
- Hold the **Ctrl** key while drawing across the interval.

You can also:


- Select all visible intervals by clicking on the **Select all** button (2/2) or by pressing Ctrl+A.
- Clear all selected intervals by clicking on the Clear selection button (⁶) or by pressing Ctrl+Shift+A.
- Swap the selected intervals for the unselected intervals by clicking on the **Invert selection** button (I) or by pressing Ctrl+l.

To change the width of the line used to select intervals, click on the **Change line width** button (^(C)) and enter a new value. You can keep the **Set Line Width** window open while you select intervals so you can change the line width as required:



Note that the current line width is indicated by the **Change line width** button.


When you have selected at least one interval, click on the **Assign to** button, then either select an existing lithology or create a new lithology by selecting **Create New Lithology**:



Enter a Name for the new lithology, then click OK:


Ð	Name	Colour
Þ	Alluvium	
Þ	Aquifer Miocene Alluvium	
Þ	Basement Granite	
Þ	Coarse Sand	
Þ	Glacial Till	
Þ	🕼 😵 New Lithology	×
Ð		
	Name: Above Gravel	
	Colour	
	Cancel Cancel	

The new lithology will be created and the scene updated to reflect the changes:



Once you have created a new lithology, you can add to it by selecting intervals, then selecting the lithology from the **Assign to** list.

When you are finished, click the **Save** button (a) and close the **Interval Selection** window. The new lithology column will appear in the project tree as an additional lithology column in the interval table. Select the new column from the shape list to display it:



Overlaid Lithology Column

You may have two versions of an interval column, one that contains draft data and one that contains the final version. The final version may contain gaps, which can be filled in using the draft version. The overlaid lithology tool lets you combine the two columns to create a new column.

Both columns must be part of the same interval table. If they are not, use the merged table tool to create a new table that contains both columns. See <u>Merged Borehole Data Tables</u>.

To create an overlaid lithology column, right-click on the interval table in the project tree and select **New Column > Overlaid Lithology Column**. For a merged table, right-click on it and select **Overlaid Lithology Column**.


The New Overlaid Lithology Column window will appear:

primary column w	ithology Column vill contain values from the hen the value is present, and in when the primary value is	× I from
Primary column:	Ma RockType	•
<u>F</u> allback column:	A Simple_RockType	•
<u>N</u> ame:	RockType with Simple_Roo	ckType
Help	<u>X</u> ancel C <u>r</u> ea	ate

For the **Primary column**, select the column that you wish to have precedence. Data in the **Fallback** column will be used when no data is available from the **Primary column**.

Click **Create** to create the new column. The new column will appear in the project tree.

You can display borehole data with the new column by selecting it from the shape list:



Category Column from Numeric Data

When you have numeric data you wish to use with the lithology and category modelling tools, you can convert the numeric data to a category column. To do this, right-click on the numeric data column and select **New Column > Category From Numeric**. In the window that appears, select the **Base Column**, then enter a name for the new column. Click **OK**.

The next step is to sort the numeric data into categories:

	<u> </u>	Open <u>S</u> tatisti	ics Tab	
at <u>eg</u> ories: Category Name	≤	Value	Colour	Matches
.ow	≤	0.331		5505
Mid	≤	11.923		10937

Leapfrog Works automatically assigns three categories calculated from the distribution of data. To add a new category, click the **Add** button and enter the required value. Click the **Open Statistics Tab** button to view the distribution of data, which will help in deciding what categories to define. See <u>Univariate</u> <u>Graphs</u> in the <u>Analysing Data</u> topic for more information on using this tab.

Click **OK** to create the new column, which will appear in the project tree as part of the original interval table.

Back-Flagging Borehole Data

Evaluating geological models on boreholes creates a new lithology table containing the lithologies from the selected model. This is useful for validating models created from borehole data as you can generate statistics for the correlation between modelled geology and drilling data.

To created a back-flagged borehole data table, right-click on the **Boreholes** object in the project tree and select **New Evaluation**. The **New Evaluation** window will appear:

Select model:	RockType GM course res	~
Evaluation type:	Output Volumes	\ \
<u>C</u> olumn name:	RockType_GM_course_res	
<u>T</u> able name:	RockType_GM_course_res_Ev	alua

Select the model to use and enter names for the column and table.

When the selected model is a faulted model, the **Evaluation Type** setting determines whether the model's output volumes, faulted output volumes or fault blocks are evaluated.

Click **OK** to create the new table, which will appear in the project tree as part of the **Boreholes** object. The new table contains From, To and Lithology columns defined using the intersection between the model's output volumes and the boreholes. For output volume evaluations, you can view the correlation between modelled geology and actual logged borehole segments. To do this, right-click on the table and select **Statistics**. In the **Correlation Statistics** window, you can compare model values to drilled lithologies or vice versa.

See:

- <u>Comparing Modelled Values to Drilling Lithologies</u>
- <u>Comparing Drilling Lithologies to Modelled Values</u>
- Refining the Geological Model to Improve Correlation Statistics

You can export the information displayed in the **Correlation Statistics** window in CSV format for use in other applications. To do this, click **Export**.

Comparing Modelled Values to Drilling Lithologies

Comparing **model values to drilling lithologies** shows how accurately drilling lithologies are modelled in the selected geological model. High matching percentages for drilling lithologies in the left-hand side of the window mean the model closely matches the drilling data for that lithology:


olumn RockType ve	rses model Roo	kType GM co	ourse res			Model values matching drilli D2	ng inniology	Exp
Drilling Lithology	Drilling Length	Matching Length	Matching Percent	Non Matching Length	Non Matching Percent	Model Value	Length ∨	Percent
D2	13213.3	11919.147	90.21%	1294.153	9.79%	D2	11919.147	90.21%
11	12538.5	12172.988	97.08%	365.512	2.92%	Outside Model	1145.321 72.232	8.67% 0.55%
D3	11903.5	10001.807	84.02%	1901.693	15.98%	D3	47.728	0.35%
D4	2424.0	1760.288	72.62%	663.712	27.38%	D1	28.872	0.30%
12	2275.5	2168.805	95.31%	106.695	4.69%		20.072	0.2270
D1	1382.0	1218.86	88.2%	163.14	11.8%			
D5	75.0	61.523	82.03%	13.477	17.97%			

The right-hand side of the window shows the composition of the modelled values for the selected **Drilling Lithology**. Here, D1 in the geological model corresponds to D1 in the lithology data for 88.2% of the length of the borehole:

ompare: model val			ourse res			Model values matching drillin D1	g lithology	🔓 Ехро
Drilling Lithology	Drilling Length	Matching Length	Matching Percent	Non Matching Length	Non Matching Percent	Model Value	Length ∨	Percent
D2	13213.3	11919.147	90.21%	1294.153	9.79%	D1 Outside Model	1218.86	88.2% 9.44%
11	12538.5	12172.988	97.08%	365.512	2.92%	D2	32,739	2.37%
D3	11903.5	10001.807	84.02%	1901.693	15.98%	02	32,739	2.5770
D4	2424.0	1760.288	72.62%	663.712	27.38%			
12	2275.5	2168.805	95.31%	106.695	4.69%			
D1	1382.0	1218.86	88.2%	163.14	11.8%			
D5	75.0	61.523	82.03%	13.477	17.97%			

D1 in the model is actually D2 for 2.37% of the length of the boreholes, and 9.44% of the drilled D1 values fall outside of the boundary of the geological model.


In the images that follow, we will look at the correlation between the D5 drilling lithology and modelled D5. Here, two borehole data tables are displayed with the D5-D4 contact surface from the geological model:



The inner boreholes show the original borehole data. The outer boreholes show the geological model back-flagged onto the borehole data table. In the highlighted borehole, we can see there is a discrepancy between the actual lithology data and that modelled. When we view correlation statistics for this model, we can see that this discrepancy is explained by the fact that 17.97% of the D5 drilling length is modelled as D4:

olumn RockType ve		thologies v				Model values matching de D5	rilling lithology	Export
Drilling Lithology	Drilling	Matching	Matching	Non Matching	Non Matching	Model Value	Length ∨	Percent
	Length	Length	Percent	Length	Percent	D5	61.523	82.03%
D2	13213.3	11919.147	90.21%	1294.153	9.79%	D4	13.477	17.97%
11	12538.5	12172.988	97.08%	365.512	2.92%			
D3	11903.5	10001.807	84.02%	1901.693	15.98%			
D4	2424.0	1760.288	72.62%	663.712	27.38%			
12	2275.5	2168.805	95.31%	106.695	4.69%			
D1	1382.0	1218.86	88.2%	163.14	11.8%			
D5	75.0	61.523	82.03%	13.477	17.97%			

You might consider this an acceptable match, but if it is too low, there are several ways to refine the geological model so that the geological model more closely reflects the original boreholes, which are discussed below. For this example, we will adjust the resolution of the geological model. The modelled segment now corresponds more closely to the original borehole data:



Viewing the correlation statistics shows that 99.62% of modelled boreholes now match the original data:

Drilling Lithology	0.101					D5		
initing clanology	Drilling Length	Matching Length	Matching Percent	Non Matching Length	Non Matching Percent	Model Value	Length ∨	Percent
	13213.3	12048.174	91.18%	1165.126	8.82%	D5	74.716	99.62%
	12538.5	12310.02	98.18%	228.48	1.82%	D4	0.284	0.38%
D3 1	11903.5	10108.977	84.92%	1794.523	15.08%			
D4 2	2424.0	1772.028	73.1%	651.972	26.9%			
12 2	2275.5	2271.957	99.84%	3.543	0.16%			
D1 1	1382.0	1242.729	89.92%	139.271	10.08%			
D5 7	75.0	74.716	99.62%	0.284	0.38%			

Comparing Drilling Lithologies to Modelled Values

Comparing **drilling lithologies to model values** shows the lithological composition of modelled values. Again, high matching percentages in the left-hand side of the window mean the model closely matches the drilling data for that modelled lithology:

Compare: drilling lithe	-					Drilling lithologies matchin 11	g model value	Export
Model Value	Model Length ~	Matching Length	Matching Percent	Non Matching Length	Non Matching Percent	Drilling Lithology	Length ∨ 12172.988	Percent 98.37%
I 1	12375.126	12172.988	98.37%	202.138	1.63%	D2	72.232	0.58%
D2	12086.7	11919.147	98.61%	167.553	1.39%	D3	63.24	0.51%
D3	10132.004	10001.807	98.71%	130.197	1.29%	12	61.868	0.5%
Outside Model	3915.749	0.0	0.0%	3915.749	100.0%	D4	4,798	0.04%
12	2191.361	2168.805	98.97%	22.556	1.03%		41150	010470
D4	1795.438	1760.288	98.04%	35.15	1.96%			
D1	1250.794	1218.86	97.45%	31.934	2.55%			
D5	64.628	61.523	95.2%	3.105	4.8%			

The non-matching percentage indicates how much of the modelled lithology is not the borehole lithology. You can see in the right-hand side of the window the lithologies that make up the non-matching portions of the modelled value.

In the images that follow, we will look at the correlation between the D5 drilling lithology and modelled D5 once again. The non-matching percentage is 4.8, and on the right-hand side of the window, we can see that this is exclusively drilling lithology I2:

ompare: drilling lith	ologies to mo	1000				Drilling lithologies matching D5	g model value	Expo
Model Value	Model ~		Matching Percent	Non Matching Length	Non Matching Percent	Drilling Lithology	Length ∨	Percent
	Length	Length 12172.988			1.63%	D5	61.523	95.2%
11	12375.126		98.37%	202.138		12	3.105	4.8%
D2	12086.7	11919.147	98.61%	167.553	1.39%			
D3	10132.004	10001.807	98.71%	130.197	1.29%			
Outside Model	3915.749	0.0	0.0%	3915.749	100.0%			
12	2191.361	2168.805	98.97%	22.556	1.03%			
D4	1795.438	1760.288	98.04%	35.15	1.96%			
D1	1250.794	1218.86	97.45%	31.934	2.55%			
D5	64.628	61.523	95.2%	3.105	4.8%			

Adjusting the resolution of the geological model improves the matching percentage to the point where only 0.09 percent of the D5 modelled value is drilling lithology I2:

ompare: drilling lithe	ologies to mor ses model Ro					Drilling lithologies matchin D5	g model value	Expor
Model Value	Model Length	Matching Length	Matching Percent	Non Matching Length	Non Matching Percent	Drilling Lithology	Length ∨	Percent
11	12325.4	12310.02	99.88%	15.38	0.12%	D5	74.716	99.91% 0.09%
D2	12074.351	12048.174	99.78%	26.177	0.22%	12	0.07	0.09%
D3	10122.208	10108.977	99.87%	13.231	0.13%			
Outside Model	3915.749	0.0	0.0%	3915.749	100.0%			
12	2272.93	2271.957	99.96%	0.973	0.04%			
D4	1775.087	1772.028	99.83%	3.059	0.17%			
D1	1251.289	1242.729	99.32%	8.56	0.68%			
D5	74.786	74.716	99.91%	0.07	0.09%			

Refining the Geological Model to Improve Correlation Statistics

If the matching percentages are too low for the lithologies of interest, there are several ways to refine the geological model so that the geological model more closely matches the boreholes:

- Reduce the resolution of the geological model or of its contact surfaces. See <u>Surface Resolution for a</u> <u>Geological Model and Surface Resolution in Leapfrog Works</u>.
- Add more data to the model's surfaces. See Adding Data to Surfaces.
- Snap surfaces to the data used to create them. See Honouring Surface Contacts.

Merged Borehole Data Tables

When you have more than one borehole interval table in a project, you can create a new table using selected columns from existing interval tables. You can include columns created by, for example, grouping or splitting lithologies or compositing.

To create a merged table, right-click on the **Boreholes** object in the project tree and select **New Merged Table**. The **New Merged Table** window will appear showing all interval columns available in the project:

vailable columns:	Selected columns:	
▼ □ Lake_Aura_Geology		
/A GM ▼ 🛄 Lake_Aura_RQD		
∧ RQD	\$	
Select <u>A</u> ll <u>S</u> elect None		
ame: Merged_Table_1		

You can change the columns included once you have created the table.


Select the columns you wish to include in the new table and click **OK**. The new table will appear in the project tree as part of the **Boreholes** object.

You can create query filters for a merged data table, as described in the <u>Query Filters</u> topic. You can also select intervals (see <u>Interval Selection</u>) and create an overlaid lithology column (see <u>Overlaid Lithology</u> <u>Column</u>). You cannot, however, use the group lithologies and split lithology tools on a merged table.

To edit the table, right-click on it and select **Edit Merged Table**.


Core Photo Links

Leapfrog Works can link borehole data to ALS Webtrieve, Coreshed and Imago core photo databases. When you have added a core photo link to a project, a core photo link will be displayed when intervals are clicked on in the scene:




You can click on the link to open the corresponding core photo in your browser.

Adding a core photo link also adds a button to the toolbar that allows for rapid viewing of core photos:



Once you are logged in to your core photo database, enable this mode, then click on intervals in the scene to view core photos in the browser. To disable rapid viewing mode, click on another tool in the toolbar.

When borehole data has been linked to a core photo database, a photo link object will appear in the project tree:



You can only have one type of core photo link associated with the borehole data.


To add a link, right-click on the **Boreholes** object and select **Add Core Photo Link**. In the window that appears, select the core photo provider and click **OK**:

😰 Core Photo Provider 💦 🖓	<
Choose your core photo provider:	
● <u>A</u> LS CoreViewer™	
○ 🚯 C <u>o</u> reshed	
🔿 🔕 Imago	
₩ Lelp]

For information on setting up and using the different core photo links, see:

- The ALS CoreViewer Interface
- The Coreshed Core Photo Interface
- The Imago Core Photo Interface

An alternative to linking to a core photo database is to link to files stored locally or on a network drive. This can be achieved by having a URL column in an interval table. When the interval is selected in the scene, you can click the link to view the file:



Use the prefix file:/// to link to local files.

The ALS CoreViewer Interface

This topic describes how to set up and use the ALS core photo interface. It is divided into:

- Setting Up the ALS CoreViewer Interface
- Using the ALS Interface
- Removing the ALS Link


Setting Up the ALS CoreViewer Interface

Before you can view core photos, you must first set up the ALS CoreViewer interface. To set up the interface between Leapfrog Works and the ALS database, right-click on the **Boreholes** object and select **Add Core Photo Link**. In the window that appears, select **ALS CoreViewer** and click **OK**. The **ALS Core Photo Settings** window will appear. The **Project Name** is required to set up the link, although the **Encryption Key** is optional.

For **Application depths measured in**, ensure that the units used for depth match in Leapfrog Works and ALS.

For **Open selection in new browser**, choose whether each core photo will be opened in a separate browser **Window** or **Tab**.

Click **OK** to save the information. If login is successful, the **ALS Core Photo Link** button (^(A)) will appear in the toolbar:




A link will also appear in the project tree as part of the **Boreholes** object:



You can edit the link by double-clicking on it.

Using the ALS Interface

To view core photos, click on a borehole in the scene, then click on the **ALS Core Photo Link** button in the window that appears:



Your browser will be launched and you will be prompted to log in to the ALS database. Enter the **User Name** and **Password**, which are case-sensitive. Remember to allow the browser to save the details so that you will not be prompted to log in each time you wish to view a photo.

Your browser settings may require that you install a plugin or make changes to settings in order to view core photos. If you are not able to access the ALS database from Leapfrog Works and have ensured your **Project Name**, **Encryption Key**, **User Name** and **Password** have been entered correctly, contact Customer Support as described in <u>Getting Support</u>.

The **ALS Core Photo Link** button (♠) in the toolbar allows you to view core photos in your browser in rapid succession. To do this, first make sure you are already logged into the database. Then click on the **ALS Core Photo Link** button (♠) to enable the rapid viewing mode. Each time you click on an interval in the scene, the core photo link will open in your browser.

Position your browser window alongside the Leapfrog Works scene window to view borehole data in Leapfrog Works alongside the core photo data.

To disable rapid viewing mode, click on another tool in the toolbar.

Removing the ALS Link

To remove the ALS link, right-click on it in the project tree and select **Delete**.

The Coreshed Core Photo Interface


This topic describes how to set up and use the Coreshed core photo interface. It is divided into:

- Setting Up the Coreshed Interface
- Using the Coreshed Interface
- Removing the Coreshed Link

Setting Up the Coreshed Interface

Before you can view core photos, you must first set up the Coreshed interface. To do this, right-click on the **Boreholes** object and select **Add Core Photo Link**. In the window that appears, select **Coreshed** and click **OK**. The **Coreshed Photo Settings** window will appear. Enter the information required and select whether each core photo will be opened in a separate browser **Window** or **Tab**.

Click **OK** to save the information. The **Coreshed Photo Link** button (⁽⁶⁾) will appear in the toolbar:




A link will also appear in the project tree as part of the **Boreholes** object:

Borehole Data
 III Boreholes
 collar
 survey
 Borehole traces
 Borehole Graphs
 assay
 lithology
 Correshed Photo Link

You can edit the link by double-clicking on it.

Using the Coreshed Interface

To view core photos, click on a borehole in the scene, then click on the **Coreshed Photo Link** button in the window that appears:



Your browser will be launched and you will be prompted to log in to the Coreshed database. Enter the **Username** and **Password**, which are case-sensitive. Remember to allow the browser to save the details so that you will not be prompted to log in each time you wish to view a photo.

Your browser settings may require that you install a plugin or make changes to settings in order to view core photos. If you are not able to access the Coreshed database from Leapfrog Works and have ensured your **Username** and **Password** have been entered correctly, contact Customer Support as described in <u>Getting Support</u>.

The **Coreshed Photo Link** button (⁶) in the toolbar allows you to view core photos in your browser in rapid succession. To do this, first make sure you are already logged into the database. Then click on the **Coreshed Photo Link** button (⁶) to enable the rapid viewing mode. Each time you click on an interval in the scene, the core photo link will open in your browser.

Position your browser window alongside the Leapfrog Works scene window to view borehole data in Leapfrog Works alongside the core photo data.

To disable rapid viewing mode, click on another tool in the toolbar.

Removing the Coreshed Link

To remove the Coreshed link, right-click on it in the project tree and select **Delete**.

The Imago Core Photo Interface

This topic describes how to set up and use the Imago core photo interface. It is divided into:

- <u>Setting Up the Imago Interface</u>
- Using the Imago Interface
- Removing the Imago Link

Setting Up the Imago Interface

Before you can view core photos, you must first set up the link between Leapfrog Works and the Imago database. To do this, right-click on the **Boreholes** object and select **Add Core Photo Link**. In the window that appears, select **Imago** and click **OK**. The **Imago Settings** window will appear. Select whether each core photo will be opened in a separate browser **Window** or **Tab**. All other parameters are optional.

Click **OK** to save the information. The **Imago Link** button (^(I)) will appear in the toolbar:




A link will also appear in the project tree as part of the **Boreholes** object:

Borehole Data
 III Boreholes
 collar
 survey
 Borehole traces
 Borehole Graphs
 assay
 Iithology
 Composites
 Imago Link

You can edit the link by double-clicking on it.

Using the Imago Interface

To view core photos, click on a borehole in the scene, then click on the **Imago Link** button in the window that appears:



Your browser will be launched and you will be prompted to log in to the Imago database. Remember to allow the browser to save the details so that you will not be prompted to log in each time you wish to view a photo.

The **Imago Link** button (•) in the toolbar allows you to view core photos in your browser in rapid succession. To do this, first make sure you are already logged into the database. Then click on the **Imago Link** button (•) to enable the rapid viewing mode. Each time you click on an interval in the scene, the core photo link will open in your browser.

Position your browser window alongside the Leapfrog Works scene window to view borehole data in Leapfrog Works alongside the core photo data.

To disable rapid viewing mode, click on another tool in the toolbar.

Removing the Imago Link

To remove the Imago link, right-click on it in the project tree and select **Delete**.

Exporting Borehole Data

Changes made to the borehole data in Leapfrog Works only affect the Leapfrog Works database, not the original data files. You can export Leapfrog Works borehole data, which is useful if you wish to keep a copy of borehole data outside the project.

You can:

- Export all data. See Exporting All Borehole Data.
- Export all data in IFC format. See Exporting Borehole Data in IFC Format.
- Export only a single data table. See Exporting a Single Borehole Data Table.

These export options export the borehole data tables using To and From values to indicate location information. If you wish to export data with X-Y-Z values, extract points data using one of the following options:

- Extracting Contact Points from Borehole Data
- Extracting Intrusion Values from Borehole Data
- Extracting Interval Midpoints from Borehole Data


Then export the data object as described in Exporting Points Data.

Exporting All Borehole Data

To export all borehole data, right-click on the **Boreholes** object and select **Export**. The **Export Borehole Data** window will appear:

💋 Export Borehole Data		×
Export Boreholes Export Options		
<u>A</u> ll rows in table Changed ro <u>w</u> s only <u>V</u> alid rows only	Use <u>o</u> riginal column names Add changed flags Invert <u>dip</u> values Export <u>t</u> rench column	Add interval start points Add interval mid points Add interval end points
?	Cancel	<u>E</u> xport

Once you have selected how you wish to export the data, click **OK**. The **Export Borehole Data Files** window will appear:



The list shows the files that will be created, one for each data table. Choose the **Folder** where the files will be saved, then enter a **Base file name**, which will be added to the front of each file name.

Click **Export** to save the files.

Exporting Borehole Data in IFC Format

To export borehole data in IFC format, right-click on the **Boreholes** object and select **Export > Export** to IFC. In the window that appears, select the objects you wish to include, then enter a filename.

🖉 Export Borehole Data	a		×
Select <u>O</u> bjects			
Objects		Colouring	
V 🗋 Borehole Data	8		
V 👭 Boreholes	3		
🗸 🥢 Bo	rehole traces		
V 🔽 🔛 La	ke_Aura_Geo		
v 🎼	(GM	🌇 GM	~
🗸 🔽 🔛 La	ke_Aura_RQD		
v 🏭	RQD	RQD	~
Export Options			
Combine outputs in	nto ifczip archiv	e	<u>U</u> nits
Folder: C:\Users\Geo	logist\Exports		
Filename:			
?	<u>C</u> ancel		<u>E</u> xport

When an object has more than one colouring option available, you must choose which one you wish to export.

You can also:

- Combine all outputs into a single archive, in ifczip format
- Change the units used to export the data

Click **Export** to save the files.

Exporting a Single Borehole Data Table

To export a single borehole data table, right-click on that table and select **Export**. The **Export Borehole Data** window will appear:

💋 Export Borehole Data		×
Export Lake_Aura_Get Export Options	blogy	
<u>A</u> ll rows in table Changed ro <u>w</u> s only <u>V</u> alid rows only	 ✓ Use <u>o</u>riginal column names Add changed <u>f</u>lags 	Add interval start points Add interval mid points Add interval end points
?	Cancel	Export

Once you have selected how you wish to export the data, click **OK**. You will be prompted for a filename and location.

Design Models

This topic describes how to import and work with designs and alignments in Leapfrog Works. It is divided into:

- Designs
- Alignments

Designs

Leapfrog Works imports designs in the following formats:

- DGN(*.dgn)
- DWG(*.dwg)
- DXF (*.dxf)

This includes Autodesk Civil 3D objects in *.dwg format.

For DGN files:

- Xrefs are not supported and the externally referenced data will need to be imported into Leapfrog Works separately.
- For files that contain 'Complex Elements', it may be necessary to first 'Drop Elements' in the Bentley design software before importing it into Leapfrog Works.

When you are importing Civil3D objects, note that some object types can be imported into Leapfrog Works directly, while others must be exploded before they can be imported.

Object	Imported As	Notes
Alignments	Design line	
Corridors	Design mesh	
Feature lines	Design line	
Fittings	Design mesh	Needs to be exploded in Civil3D
Intersections	Design line	
Parcels	Design line	
Match lines	Design line	
Pipes	Design mesh	Needs to be exploded in Civil3D
Pressure pipes	Design mesh	Needs to be exploded in Civil3D
Sample lines	Design line	
Structures	Design mesh	Needs to be exploded in Civil3D
Surfaces	Design mesh	Needs to be exploded in Civil3D


To import a design, right-click on the **Designs** folder and select **Import Designs**. In the window that appears, navigate to the folder where your design is stored and select the files you wish to import. You can use the Shift and Ctrl keys to select multiple files. Click **Open**.

All models and layers available in the selected files will be displayed. Here three files have been selected for import, FLYOVER_Tunnel, Tunnel and visualization_-_apt_block:

2	i Im	port Designs	×
	Laye	ers to be imported	
	\sim	FLYOVER_Tunnel	
		✓ 0	
	\sim	Tunnel	
		 Alignment 	
		 Extent 	
		Tunnel Design	
	\sim	visualizationapt_block	
		✓ 0	
		*ADSK_SYSTEM_LIGHTS	
	Coor	rdinate system: World Coordinate System	~
	?	<u>C</u> ancel <u>Q</u> K	

Select the layers you want to import. If the files contain information on more than one coordinate system, select the system you want to use from the **Coordinate system** list. Click **OK** to import the selected objects.

The model will be added to the project tree; expand it to see the different layers. For example, here a Tunnel file has been expanded in the project tree, showing the different layers:



The layer colours are saved in the **Layer colour** object (), which you can double-click on to change the colours used.

The meshes and lines in the model can be used as inputs to geological models and cross sections.

Reloading Designs

To reload a design, right-click on it in the project tree and select **Reload**. Navigate to the folder containing the design file and select the file. Click **Open**.

The process is the same as importing the model file. Click **OK** to reload the data. The original data will be overwritten and dependent objects will be updated to reflect the new data.

Displaying Designs

Drag the different layers of the design into the scene to display them. Meshes can be displayed using a **Flat colour**, the **Face dip** or the **Layer colour**. Design lines can be displayed using the **Layer colour**. Double-click on the **Layer colour** object (E) in the project tree to change the colours used:

✓ ☐ Designs	
> B FLYOVER_Tunnel	22 Legend for Layer colour X
V 📷 Tunnel	
Layer colour	Code Colour
✓ I Alignment	
Alignment 😜	Alignment
V 📷 Extent	Extent
💓 Extent	Tunnel Design
🗸 🃷 Tunnel Design	
🍿 Tunnel Design	
V B visualizationapt_block	
Layer colour	(?) <u>Cancel</u> <u>OK</u>
*ADSK_SYSTEM_LIGHTS	
> 🎫 0	
Depints	💿 🌒 Tunnel: Extent X 🔶 La V
Polylines	💿 🥡 Tunnel: Tel Design X À La 🗸 📃 💶 🕨 🚺
Geophysical Data	💿 📦 Tunnel: Alignment 🗙 À La 🗸 🔲
> 🗀 Structural Modelling	

Moving Designs

If all or part of the design are in the wrong location, you can move the entire design or part of it. Rightclick on the object you want to move and select the **Move** option. The **Move Design** window will appear, together with tools in the scene for making changes. Select the part of the model you wish to move from the **Select Design Object** list. Here the whole model has been selected and there is one set of **Offset** values displayed in the **Move Design**:


💋 Move Design		×
Select Design Object		
ge funde	[Reset All
Design Object Offset		
Desig <u>n</u> : 0	, 0 , 0	
?	Cancel	ОК

Click on one of the arrows in the scene to move the design; you can only move in one plane at a time. Updated values will be displayed in the **Move Design** window. To move just part of the model, select it from the dropdown list. The controls in the scene will adjust only the location of the selected layer and its contents:

Move De	sign sign Object		>	
	el: Extent		~	
Design Ob	ject Offset		<u>R</u> eset All	
Desig <u>n</u> :	0	, 0	, 0	
Layer:	0	, 0	, 0	
Mesh:	143.81884734	, -123.62064891	, 75.290968874	
?		<u>C</u> ancel	<u>о</u> к	

Click the **Reset All** button to return all location values to 0,0,0.

Click **OK** to close the **Move Design** window and save the new values. All parts of the model that have been moved will be marked in the project tree with moved sign (\oplus). For example, here only the extent has been moved:



You can edit the offset values by opening the **Move Design** window once again.

Working With Design Meshes

You can also carry out standard operations on the design meshes, including the options available for working with meshes described in <u>Cleaning Up a Mesh</u>. Double-click on a design mesh in the project tree to view the options available. Right-click on a mesh to see the other options available.

See Meshes for more information on working with meshes in Leapfrog Works.

A mesh marked with an exclamation mark (\widehat{a}) is not closed.

Editing Design Lines

If you need to edit a design line, right-click on it and select **Extract Polyline**. The new polyline object will appear in the **Polylines** folder. You can then edit the polyline and use it as an input to models and cross sections.

Exporting Designs

Leapfrog Works can export designs and design lines in Drawing file (2013/LT2013) (*.dwg) and Bentley Drawing Files (v8) (*.dgn) formats.

Leapfrog Works can export design meshes in the following formats:

- Leapfrog Files (*.msh)
- DXF Files (11/12 [AC1009]) (*.dxf)
- DXF Polyface Files (11/12 [AC1009]) (*.dxf)
- Alias Wavefront Object Files (*.obj)
- AutoCAD Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

Alignments

Leapfrog Works imports LandXML alignments as 3D alignments. The types of LandXML alignment objects that can be imported are lines, curves and the following spiral types:

- Clothoid
- Bloss
- Cubic parabola
- Cubic (JP)
- Sine half-wavelength diminishing tangent curve

The file should have, at a minimum, a horizontal alignment. Chainage information in the imported alignment is taken from the horizontal alignment.


- If the file contains a profile, that will appear in the project as a 3D alignment.
- If the file contains a surface, that will appear as a projected alignment. An alignment can have multiple projected alignments.

To import an alignment, right-click on the **Designs** folder and select **Import Alignments**. In the window that appears, navigate to the folder where the alignments file is stored, select the file you wish to import and click **Open** to start importing the file. If there is more than one alignment in the file, you will be prompted to select which ones to import. Otherwise, the alignment will be imported and added to the **Designs** folder.

Alignments are organised in the project tree by the imported file. For example, here two files have been imported into Leapfrog Works. The first, 100kmAlignment.xml, contains a single alignment, whereas the file Alignments.xml contains three separate alignments:




The alignments in the parent file object can be expanded to show the separate parts. Here the file imported contains a single alignment, which is made up of a horizontal alignment, a 3D alignment and a projected alignment:



The **Projected Alignments** folder contains any CAD projections of the alignment that were included in the imported file.

Reloading Alignments

To reload an alignment, right-click on its file in the project tree and select **Reload**:




Navigate to the folder containing the alignment file and select the file. Click **Open**. You will be prompted to select which alignments to reload:

😰 Sele	ct Alignments to reload		×
Alian	ments to be reloaded		
	Name		Status
~	Alignment 2		RELOAD
~	Alignment 8		NEW
~	Alignment 3		RELOAD
	ments in the existing design tha	t cannot be matched with aligr	iments in the file
Nan			
Alig	Inment 1		
?)		Cancel	<u>О</u> К


Click **OK** to reload the data. The original data will be overwritten and dependent objects will be updated to reflect the new data. If there are new alignments in the file, they will be added to the existing parent alignment.

Displaying Alignments

When an alignment is displayed, you can change how the chainage values are displayed using the **Tick spacing** and **Label occurrence** controls in the properties panel. To hide the chainage values in the scene, disable the text control () in the shape list.



The colour options in the shape list control the alignment colour and the tick mark and chainage values colour:



When the chainage values are displayed, there is also an option in the properties panel for showing the curve points.




Using Alignments in the Project

Alignments can be used as the basis for alignment serial sections:


😹 New Alignment Seri	🗸 New Alignment Serial Section 🛛 🗙			
Alignment Opriel Ope	Vien From			
Alignment Serial Sec				
New Polyline	Existing Line			
Z Tunnel align	ment 2D Geometry	~		
Bas				
Tunnel	- Alignment			
🛛 🛛 🗸 Tu	nnel alignment			
2	Tunnel alignment 2D Geometry			
2	Tunnel alignment			
) Projected Alignments			
Alie	Civil3D DEM			
-				
Start Chainage: 0		~		
Offset Sections				
Entire Line	○ Line Section			
Chainage Spacing:	10	¢		
Line Section Star <u>t</u> :	0			
Line Section End:	2080			
Name: Tunnel align	nment 2D Geometry			
?	<u>C</u> ancel <u>O</u> K			

The **Start Chainage** value used in the **New Alignment Serial Section** window is taken from the alignment selected, and the **Chainage Spacing** value is taken from the **Tick spacing** property in the properties panel:



Note that the link between the alignment's display properties and the alignment serial section is not dynamic; changing the **Tick spacing** value does not update the value for the section.

Alignments can be evaluated onto sections as lines:



Points Data

Points are sets of X-Y-Z coordinates, with or without associated values. In Leapfrog Works, points are used to define surfaces and for interpolation. You can use the **Points** folder to:

- Import points data
- Extract contact points, intrusion values and interval midpoints from borehole data
- Create guide points
- Create grids of points that can be evaluated against geological and numeric models and exported for use in other modelling

The rest of this topic describes importing and exporting points, setting elevation for points and evaluating points. It is divided into:

- Importing Points Data
- Reloading Points Data
- Appending Points Data
- Importing a Column
- Setting Elevation for Points
- Evaluating Points Data
- Displaying Points
- Viewing Points Table Statistics
- Exporting Points Data

Importing Points Data

Leapfrog Works supports the following file types for points data:

- CSV files (*.csv)
- ASCII text files (*.asc)
- DXF files (*.dxf)
- Leapfrog Works 3D Point Data files (*.pl3, *.ara)

Points data can be imported from:

- Files stored on your computer or a network location. Right-click on the **Points** folder and select **Import Points**. You will be prompted to select a file.
- From any database that runs an ODBC interface. Right-click on the **Points** folder and select **Import Points via ODBC**. See <u>Selecting the ODBC Data Source</u> below.

For each of these options, once the data source is selected, the process of importing the data is the same.

The expected data columns are:

- A borehole identifier
- Depth

You can also import a holeID column, although this is optional.

When importing a file that has multiple features, you will be prompted to select which ones to import. You can also choose to:

- Import the features as separate objects. Each feature will appear in the project tree as a separate object.
- Flatten all features into one object. Leapfrog Works will treat all features as a single object.

Once imported, the file will be added to the **Points** folder. If there are errors in the data, the errors can be corrected as described in <u>Correcting Data Errors in Leapfrog Works</u>.

To view the imported data, double-click on the object that has been added to the **Points** folder.

Once points data has been imported to the project, it can be modified and evaluated against geological and numeric models, as described in <u>Evaluating Points Data</u>.

Selecting the ODBC Data Source

When importing points data from an ODBC database, you will need to specify the ODBC data source. Enter the information supplied by your database administrator and click **OK**.

Once the data source is selected, the import process is similar to that described above.

Reloading Points Data

Reloading data is necessary when the imported data is modified externally. Points data can be reloaded by right-clicking on the table and selecting **Reload Data**.

Reloading points data overwrites all data in the existing table. If you have data you wish to add to the project without overwriting existing data, use the **Append Data** option.

The process is similar to that for importing the original table.

Appending Points Data

If points data is stored in multiple files, you can import these files into the project and add them to existing points data. To do this, right-click on the object you wish to append and select **Append Data**. You will be prompted to select a file.

Next, the Import Tables For Appending window will be displayed.

Check the data to ensure that the correct information will be imported, then click **Finish** to add the new file.

Importing a Column

Columns of points data that were not imported when the original data was imported or that are stored in a separate file can be added to the table at any time. To do this, right-click on the points table in the project tree and select **Import Column**.

The process is similar to importing the original table; select the file and map the columns you wish to import.

Setting Elevation for Points

You can set the elevation for points tables by projecting them onto a surface. This overwrites elevation values in the z column of the points table, using the data from the selected surface. If the surface does not intersect vertically with all points, you can choose how the z values for those unprojected points will be handled.

To set the elevation for points from a surface, right-click on the points object in the project tree and select **Set Elevation**. The **Set Elevation** window will appear:

💋 Set Elevation from Surface				
Set elevation for 'points' <u>S</u> elect surface:	bhy	~		
Unprojected points For points that cannot be projected onto the surface:				
<u>Assign elevation values to:</u> 0				
 Leave elevation values empty Leave unchanged 				
? <u>C</u> ancel	<u>0</u> K			

Select from the surfaces available in the project.

Next, select how unprojected points should be handled. There are three options:

- Assign elevation values to sets the z values to a fixed elevation for all unprojected points.
- Leave elevation values empty clears the z values for all unprojected points.
- Leave unchanged makes no changes to the z values for unprojected points.

Click **OK** to set elevation values.

Evaluating Points Data


Once points data has been imported to the project, it can be modified and evaluated against geological and numeric models, as described in Evaluations.

In the case of geological models, you can also combine two or more models to evaluate the points data and set the priority used for evaluation. To do this, click on the **Combined Evaluation** button in the **Select Models To Evaluate** window. In the window that appears, select the evaluations to combined, then set their priority. Click **OK** to create the combined evaluation, then click **OK** in the **Select Models To Evaluate** window. The combined evaluation will be available from the colour list.

To delete a combined evaluation, click on the **Delete Combined** button in the **Select Models To Evaluate** window.


Displaying Points

Points data can be displayed using a single flat colour, using a colour gradient or using the points values. You can also import a colourmap, which is described in <u>Colour Options</u>. As with boreholes, points data can be displayed as flat points or as spheres. When **Make points solid** button (¹) is enabled for points data, the data points are displayed as spheres. Here, the values are displayed as flat points:



You can restrict the range of values displayed using the Value filter in the properties panel.

When using the spheres option, the points can be displayed using the values. To do this, the **Radius** values list displays the columns available:




Select the column that will be used to determine the point size.

The **Point radius** control then determines the maximum point size displayed in the scene.

Viewing Points Table Statistics

To view statistics on points data tables, right-click on a points table and select **Statistics**. The following options are available:



See the <u>Analysing Data</u> topic for more information on each option:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots

Exporting Points Data

To export points data, right-click on the points data object in the project tree and select **Export**. For many points objects, you can select whether the exported file includes all rows, only changed rows or only valid rows. You can also apply a query filter, if any have been defined for the table.

Points data can be exported in the following formats:

- CSV Files (*.csv)
- DXF Files (11/12 [AC1009]) (*.dxf)
- Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

Additional export options are available for some types of points, which are described below.

Once you have selected how you wish to export the data, click **Export**. You will be prompted for a filename and location.

Exporting Intrusion Values

Intrusion values can be extracted from borehole data as described in <u>Extracting Intrusion Values from</u> Borehole Data.

There are two options for exporting intrusion values:

- Export only the contact points. To do this, right-click on the intrusion values object and select **Export**. If you choose this option, you can export the points in CSV format (*.csv), DXF format (*.dxf) or DWG format (*.dwg).
- Export all the points used in creating an intrusion. To do this, right-click on the intrusion values object and select **Export Volume Points**. If you choose this option, you can only export the points in CSV format (*.csv).

In both cases, you will be prompted for a filename and location.

Exporting Interval Midpoints

Interval midpoints can be extracted from borehole data, which is described in <u>Extracting Interval</u> <u>Midpoints from Borehole Data</u>. You can also export midpoints directly from an RBF interpolant, which is described in <u>Exporting Numeric Model Midpoints</u>.

To export interval midpoints, right-click on the points data object in the project tree and select **Export**. Interval midpoints can be exported in the following formats:

- CSV text file (*.csv)
- Snowden Supervisor CSV file (*.csv)
- Isatis 3D points file (*.asc)

The values exported are the midpoints of each segment, the X-Y-Z values and the hole ID. The Snowden Supervisor and Isatis 3D points formats also include the interval length.

In each case, you will be prompted for a filename and location.

Extracting Points from Borehole Data

This topic describes extracting different types of points from imported borehole data. It is divided into:


- Extracting Contact Points from Borehole Data
- Extracting Intrusion Values from Borehole Data
- Extracting Interval Midpoints from Borehole Data

If you wish to save and export points data with X-Y-Z information, use these options, then right-click on the data object to export the data as described in <u>Exporting Points Data</u>.

Extracting Contact Points from Borehole Data

Contact points define the boundary between two lithology layers. You can extract contact points from interval tables to create a new points object in the **Points** folder. The values extracted are the x-y-z values of the contact points.

To extract contact points from an interval table, right-click on the **Points** folder and select **New Contact Points**. A window will appear listing the lithology and category columns available in the project:



Select the required column and click OK.


Next, the New Contact Points window will appear:

Lithology Cor	mpositing			
Contact in Colum	nn 'RockType' on Tat	ole 'M_Geolog	IY'	
Query filter: None			~	
Select primary li	thology			
D 5				~
Use contac Contacting lith	ts <u>a</u> bove O Use cor iologies:	ntacts <u>b</u> elow	O Use both Ignored lithologies:	
D4 (1)			D1 (0)	
I2 (1)			D2 (0)	
			D3 (0)	
			11 (0)	
Treat unspecifie	d intervale ac			
	Primary O Contac	ting		
Reference Plane				
Horizontal				
Dip:				
Dip azimyth				
View Plan	ne <u>S</u> et From P	lane		
Name: D5 con	tacts			

Select the lithology required from the **Select primary lithology** list, then select the adjacent lithologies you wish to extract in the **Contacting lithologies** list.

Unspecified intervals are intervals that have no data. By default, unspecified intervals are ignored when creating new contact points, but you can also treat them as the primary lithology or as contacting lithologies.

For complex geologies, the up and down directions for the surface may not be clear. If this is the case, untick the **Horizontal Plane** box. A reference plane will appear in the scene, with the up-facing surface labelled A and the downward-facing surface labelled B:



When you disable the **Horizontal plane** option for the **Reference Surface**, the number of contacts is longer displayed in the lithologies lists, as the number of contact points is not updated when the reference surface used changes.

Controlling the position of the reference plane is similar to controlling the position of the moving plane:

- Use the handles in the scene window to move the plane.
- Set the **Dip** and **Dip Azimuth** values in the **New Contact Points** window. The reference plane will be updated in the scene.

Once the reference plane is correctly oriented, click the **Set From Plane** button.

A reference plane set for contact points in the **Points** folder will be applied wherever the contact points are used.


Click **OK** to create the points, which will appear in the project tree under the **Points** folder. To edit the points, double-click on them.

Extracted contact points can be exported as described in Exporting Points Data.

Extracting Intrusion Values from Borehole Data

You can extract intrusion points from interval tables to create a new points object in the **Points** folder.

To extract intrusion values from an interval table, right-click on the **Points** folder and select **New Intrusion Values**. A window will appear listing the lithology and category columns available in the project:



Select the required column and click **OK**.

Next, the **New Intrusion** window will appear:

Intrusion in column 'RockType' on table	e 'M_Geology'	
Query filter: None		~
Select interior lithology		
1 1		~
Exterior lithologies:	Ignore (Younger lithologies):	
D1		
D2		
D3		
D4		
D5		
12		
Treat unspecified intervals as		
Ignore O Interior O Exterior		
Name: I1		

Select the intrusion lithology, then move any younger lithologies to the **Ignore** list.

Unspecified intervals are intervals that have no data. By default, unspecified intervals are ignored when extracting intrusion values, but you can also treat them as the interior lithology or as exterior lithologies.

The settings in the **Compositing** tab are described in <u>Category Composites</u>.

Click **OK** to create the new points object, which will appear in the project tree under the **Points** folder. To edit the points, double-click on the points object (**!!!**) in the project tree. See <u>Intrusion Point</u> <u>Generation Parameters</u> below.


When you view the intrusion points in the scene, you can display only the contact points or all the points used determining the extrusion values. To display all points, click on the points object in the shape list and tick the box for **Show volume points**:

٢	11	×	. v	11	\sim	-	₩	A 🗄	<u>11</u> II		
									Slice mode:	From Scene	~
									Show volume	points	
								· · ·	Query filter:	No Filter	~
									Value filter:	-560.6390690000 🗘 - 560.6390690000	¢
									Point size:	5	0

Extracted intrusion points and values can be exported as described in Exporting Points Data.


Intrusion Point Generation Parameters

To change the way intrusion values are generated, double-click on the points object in the project tree:



The Edit Intrusion window will appear, displaying the Point Generation tab.

Here, the surface and volume points are displayed to show the effects of the **Surface offset distance** and **Background fill spacing** parameters:



The **Surface offset distance** parameter sets the top and bottom ends of the interval and affects how a surface behaves when it approaches a contact point. A smaller distance restricts the angles that an approaching surface can take. Another factor that affects the angles a surface will take is whether or not a trend has been applied to the surface.

The **Background Fill Spacing** parameter determines the approximate length of segments in the remaining intervals. If the remaining interval is not a multiple of the **Background Fill Spacing** value, Leapfrog Works will automatically adjust the spacing to an appropriate value. A smaller value for **Background Fill Spacing** means higher resolution and, therefore, slightly smoother surfaces. However, computation can take longer.

Extracting Interval Midpoints from Borehole Data

You can extract interval midpoints from raw or composited numeric and category tables to create a new points object in the **Points** folder. The extracted points will be dynamically linked to the original borehole segments and can be evaluated against other data in the project. The values extracted are the midpoints of each segment, the X-Y-Z values and the hole ID.

If you are exporting points data for use in Snowden Supervisor, use this option for extracting points from borehole data. If you wish to export midpoints from an interpolant, see <u>Exporting Numeric</u> <u>Model Midpoints</u>.

To extract midpoints from an interval table, right-click on the **Points** folder and select **New Interval Mid Points**. In the window that appears, select the required **Source table**, then select which data columns to use:

🖉 New Interva	I Mid Points			×
Source table:	Merged_Table_1			~
Query filter:	<none></none>			~
Select Colum	ns:			
Available C	olumns:		Selected Columns:	
			Au	
			🎼 RockType	
		>		
		<		
Select 4	II Select None			
Name: Mer	ged_Table_1 midpoints			
?			<u>C</u> ancel	<u>о</u> к

Apply a query filter, if required, then click **OK**. The new points object will appear in the project tree under the **Points** folder. To edit the points, double-click on the points object in the project tree.

Changes made to the source data table, such as changes to compositing parameters or special values rules, will be reflected in the extracted points object.

Extracted interval midpoints can be exported as described in Exporting Points Data.

Creating Guide Points

Guide points can be created from any category point data in the project and added to surfaces. Category data that can be used to create guide points includes:

- Downhole category point data
- LAS points
- Category data on imported points
- Interval midpoints

Guide points are classified into interior or exterior, and each guide point is assigned a distance value that is the distance to the nearest point on the opposite side. Interior values are positive and exterior values are negative.

Guide points are a good way of using blasthole data to control surfaces: create the guide points from the downhole points, then add the guide points to the surface.

To create guide points, right-click on the **Points** folder and select **New Guide Points**. A window will appear listing the category columns available in the project:

💋 New Guide Points		×
Category column:		~
Query filter: None		
Select codes:		
Interior:	Exterior:	Ignor <u>e</u> :
Maple Fault	Basement Crown Fault Dacite Early Diorite Fault Recent	Unspecified
Ignore distant values: 100		
Name Split_Faults Guide Points		
?		<u>C</u> ancel <u>O</u> K

Select the categories to assign to Interior (the positive side) and Exterior (the negative side).

You can also filter out distant values by ticking the **Ignore distant values** box and entering a value. Often distant values have little effect on a surface and filtering out these values can improve processing time.

Click **OK**. The guide points will appear in the project tree under the **Points** folder. To edit the points, double-click on them.

Guide points can be exported as described in Exporting Points Data.

Categorising Points

When you wish to select a small portion of points and you don't have suitable parameters to use a query filter, you can select points in the scene and assign them to categories. This adds a new column to the points object, preserving the original data.

To start categorising points, right-click on the points object in the project tree and select **New Category Selection**.

The New Category Selection window will appear:

😢 New Category S	election	×
Copy categories fr	om	
Source Column:	<none></none>	•
<u>Name:</u> Selection		
Help	Cancel	:

If you select an existing column as the **Source Column**, you can assign selected points to the existing categories or create new categories. If you select **<None>** for the **Source Column**, you will have to define each category manually.

When you click **OK**, the points object will be added to the scene, along with a set of tools for selecting points. To select points, click on the **Select Points** button () and click the **Add Points** button (). In the scene, draw a line across each point you wish to select:

🔻 🔡 Projects 🌒 Central Projects 🛛 🌒 Ultimate Wolfpass 🗙	🗊 Scene View	🖉 Alex Rock 🔻
🧬 Look 🕶 💥 🔪 🦸 🖽 🖛 😓 🔪 🧍	🔰 🥡	😃 🔚 🖓 🏹 🌠 🗇 🔅 🗔 🗶 🔹 🎕
Category Selection - Selection ×		·
● Name Colour		
Dacite [Editing]	🥂 🗶 🆄	Selection - Edit Colours - V 🔛 🗛 🗐 🏘 Dacite


Selected points are highlighted in the scene. If you accidentally select the wrong point, either:

- Click the **Remove points** tool (¹/₁) and draw across the point once again.
- Hold the **Ctrl** key while drawing across the point.

You can also:


- Select all visible points by clicking on the **Select all** tool (2) or by pressing Ctrl+A.
- Clear all selected points by clicking on the **Clear selection** tool (⁴/₆) or by pressing Ctrl+Shift+A.
- Swap the selected points for the unselected points by clicking on the **Invert selection** tool () or by pressing Ctrl+I.

To change the width of the line used to select intervals, click on the **Change line width** button (\Box) and enter a new value. You can keep the **Set Line Width** window open while you select intervals so you can change the line width as required:




Note that the current line width is indicated by the **Change line width** button.

When you have selected at least one point, click on the **Assign to** button, then select **Create New Lithology**:



Enter a **Name** for the new category, then click **OK**.



The new category will be created and the scene updated to reflect the changes:

Once you have created a new category, you can add to it by selecting further points, then selecting the category from the **Assign to** list.

When you are finished, click the **Save** button (and close the **Category Selection** window. The new category column will appear in the project tree as an additional column in the points table. Select the new column from the shape list to display it.

Geophysical Data

The types of geophysical points and grids that can be imported into Leapfrog Works are:

- 2D Grids
- UBC Grids
- GOCAD Models

2D Grids

Leapfrog Works imports the following 2D grid formats:

- Arc/Info ASCII Grid (*.asc, *.txt)
- Arco/Info Binary Grid (*.adf)
- Digital Elevation Model (*.dem)
- Intergraph ERDAS ER Mapper 2D Grid (*.ers)
- ESRI .hdr Labelled Image (*.img, *.bil)
- SRTM .hgt (*.hgt)
- Surfer ASCII or Binary Grid (*.grd)
- Grid eXchange File (*.gxf)
- Geosoft Grid (*.grd)

MapInfo files can be imported into the **GIS Data, Maps and Photos** folder. 2D grids in these files will be saved into the into the **GIS Data, Maps and Photos** folder. See Importing a MapInfo Batch <u>File</u> for more information.

To import a 2D grid, right-click on either the **Geophysical Data** folder and select **Import 2D Grid**. Navigate to the folder that contains grid and select the file. Click **Open** to begin importing the data.

The **Import 2D Grid** window will appear, displaying the grid and each of the bands available. Select the data type for each band and set the georeference information, if necessary. See <u>Importing a Map or</u> Image for information on georeferencing imported files.

Once the grid has been imported, you can set its elevation, which is described in <u>Setting Elevation for</u> GIS Objects and Images.

When you display the grid in the scene, select the imported bands from the shape list:

0	💏 ersgrid	\times	🛄 – 🍃 📕 Au_ppm	-•	B#		式 ersgrid			
			A Flat colour				Slice mode:	From Scene		\sim
			Au_ppm				Value filter:	0.003429	11.503758	
			Cu_ppm							
			Mo_ppm			1				
			Pb_ppm							
			Zn_ppm							

Grids can be displayed as points (^[]]]) or as cells and the values filtered, as described in <u>Displaying Points</u>.

UBC Grids

Leapfrog Works imports UBC grids in *.msh format, together with numeric values in properties files in *.gra, *.sus, *.mag and *.den formats. UBC grids can be evaluated against geological and numeric models, which can then be exported with the grid.

Importing a UBC Grid

To import a UBC grid, right-click on the **Geophysical Data** folder and select **Import UBC Model**. In the window that appears, click **Browse** to locate the file to be imported. Click **Add** to add any properties file, although these are not required.

For any properties file, click the **Inactive Value** field to mark cells as inactive. Doing so does not change the data but ensures that cells with the inactive value can be hidden when the grid is displayed in the scene. If you do not set this value when importing the grid, you can set it later by double-clicking on the grid in the project tree.

Click **Import**. The grid will appear in the **Geophysical Data** folder.

Evaluating UBC Grids

UBC grids can be evaluated against geological and numeric models as described in <u>Evaluations</u>. However, UBC grids cannot be evaluated against fault blocks and mutli-domained RBF interpolants, although they can be evaluated against the parent geological model and the parent numeric model.

Mapping Category Evaluations

When a UBC grid is exported with a category evaluation, category data is mapped to an editable numeric value. You can edit this by double-clicking on the grid in the project tree, then clicking on the **Export Mappings** tab:

B	External UBC Model: Wo	fpass		×
ſ	General Export Maj	opings		_
	Geo&logical Evaluation:	🟫 Geological model	~	
	Categories	Value		
	Basement	0		
	Cover	1		
	Dacite	2		
	Early Diorite	3		
	Intermineral diorite	4		
	Value to be assigned to	mesh blocks having no lithology: -1		
Ī	Name: Wolfpass			
				_
	?		<u>Cancel OK</u>	

Change the numeric value assigned to each lithology, if required. You can also change the value assigned to blocks that have no lithology.

The **Export Mappings** tab does not appear for UBC grids that have no geological model evaluations.

Exporting a UBC Grid

To export a UBC grid, right-click on it in the project tree and select **Export**. Select the evaluations to export with the grid, then select a folder. Click **OK** to export the grid.

A UBC grid can also be exported as points to a CSV file. To do this, right-click on the grid and select **Export as Points**. You will then be prompted to select a file name and location. Once you have clicked **Save**, select the CSV export options for null values and numeric precision, then click **OK**.

The CSV file will contain:

- X, Y and Z columns, which represent the centre of each grid block
- I, J and K columns, which is the grid block index. I is in the range 1 to NI, J is in the range 1 to NJ and K is in the range 1 to NK, where NI, NJ and NK are the grid dimensions.
- One or more data columns

GOCAD Models

To import a GOCAD model, right-click on the **Geophysical Data** folder and select **Import GOCAD Model**. Leapfrog Works will ask you to specify the file location. Click **Open** to import the file.

In the window that appears, set the **Subsample Rate** and enter a **Name** for the model. Click **OK** to import the model, which will appear under the **Geophysical Data** folder.

You can then evaluate geological models, interpolants and distance functions in the project on the model. In the case of geological models, you can also combine two or more models to evaluate on the model. To evaluate a model, right-click on the model object in the project tree and select **Evaluations**. See <u>Evaluations</u> for more information.

A GOCAD model can be exported as points to a CSV file. To do this, right-click on the grid and select **Export as Points**. You will then be prompted to select a file name and location. Once you have clicked **Save**, select the CSV export options for null values and numeric precision, then click **OK**.

The CSV file will contain:

- X, Y and Z columns, which represent the centre of each grid block
- I, J and K columns, which is the grid block index. I is in the range 1 to NI, J is in the range 1 to NJ and K is in the range 1 to NK, where NI, NJ and NK are the grid dimensions.
- One or more data columns

Structural Data

In Leapfrog Works, you can create and edit planar structural data tables directly or from other objects in the project. Structural data can also be used to create and edit many surfaces. Downhole planar structural data and lineations can also be imported, although structural data imported in this way cannot be edited.

This topic describes how to work with structural data in Leapfrog Works. It covers:

- Creating New Planar Structural Data Tables
- Importing Planar Structural Data
- Importing Lineations
- Displaying Structural Data
- Viewing Statistics on Structural Data
- Assigning Structural Data to Categories
- Editing the Orientation of Planar Structural Data
- Declustering Planar Structural Data
- Setting Elevation for Structural Data
- Estimating Planar Structural Data

See <u>Stereonets</u> and <u>Form Interpolants</u> for information on tools for analysing structural data.

Leapfrog Works calculates strike using the American right-hand rule; when looking in the strike direction, the plane should dip to the right.


Creating New Planar Structural Data Tables

There are two ways to create a new planar structural data table in Leapfrog Works:


- Create a new table as part of creating or editing another object. See <u>Editing Surfaces With Structural</u> Data.
- Create a new table using the Structural Modelling folder. Use this technique when, for example, you are creating structural data points from a map or image. Right-click on the Structural Modelling folder and select New Planar Structural Data. In the window that appears, enter a name for the new table and click OK.


Before creating the new data table, add the map, image or data object you wish to work from to the scene and orient the scene for drawing the new data points.

When a new structural data table is created, it will be added to the scene. The **Planar Structural Data** window will open, together with a set of tools for adding structural data points:



Click on the **New Structural Data Point** button (*i*) and click and drag along the strike line in the scene to add a new data point:





You can adjust the data point using the controls in the **Planar Structural Data** window:

Importing Planar Structural Data

Leapfrog Works supports planar structural measurements in .csv or text formats. This topic describes importing structural data tables that include location information. Downhole structural data can also be imported, as described in <u>Importing Downhole Structural Data</u>.

Structural data containing location information can be imported from:

- Files stored on your computer or a network location. Right-click on the **Structural Modelling** folder and select **Import Planar Structural Data**. You will be prompted to select a file.
- From any database that runs an ODBC interface. Right-click on the Structural Modelling folder and select Import Planar Structural Data via ODBC. See <u>Selecting the ODBC Data Source</u> below.

😰 Import Planar Structural Data all structural_data File Data Column Summary East (X) 🛛 🔻 North (Y) ▼ Dip ▼ Dip Azimuth ▼ sequence ▼ Polarity Column Import As Import Name 1 polarity East (X) dip dip-azimuth sequence x z 5949400.0 30.0 North (Y) 2463950.0 487,212 218.0 Mangles Formation 1 y 2 3 2463770.0 5949380.0 523.235 25.0 209.0 Mangles Formation z Elev (Z) 1 dip Dip dip Mangles Formation 4 2463360.0 5949280.0 629.657 30.0 207.0 1 202.0 Trig A Member dip-azimuth Dip Azimuth 2463340.0 5948940.0 708.05 20.0 sequence Category sequence 2453690.0 5948780.0 301.417 15.0 76.0 6 181.0 Matiri Formation 1 polarity Polarity 7 2462690.0 5948570.0 472.69 40.0 Longford Formation 1 2456640.0 5948550.0 630.398 70.0 99.0 Matiri Formation 2465350.0 5948480.0 60.0 273.0 263.619 9 Mangles Formation 1 10 2456130.0 5948460.0 502,537 45.0 301.0 Matiri Formation 11 2456830.0 5948390.0 709.944 70.0 103.0 Matiri Formation 12 2463000.0 5947990.0 363.28 30.0 222.0 Longford Formation 1 Name: all_structural_data 2463200.0 5947820.0 463,785 227.0 13 30.0 Longford Formation 1 14 2446060.0 5947780.0 811.985 35.0 51.0 Maruia Formation 11 Character encoding: Auto (Windows-1252) v 15 2453600.0 5947660.0 289,452 30.0 98.0 Matiri Formation Unique Row ID: None . 16 2463080.0 5947590.0 366.224 40.0 218.0 Longford Formation 1 Select Header Row: 1 -17 2454080.0 5947550.0 287.808 35.0 305.0 Tutaki Member 1 18 2459020.0 5947530.0 547.226 40.0 114.0 Mangles Formation 1 Import All Columns 120.0 19 2459040.0 5947530.0 545.951 40.0 Mangles Formation 1 ▶ Date and <u>T</u>ime Formats 20 2449160.0 5947460.0 599.725 20.0 334.0 Maruia Formation 1 ▶ CSV characters Help X Cancel

For each of these options, once the data source is selected, the process of importing the data is the same. Leapfrog Works will display the data and you can select which columns to import:

Leapfrog Works expects **East (X)**, **North (Y)**, **Elev (Z)**, **Dip** and **Dip Azimuth** columns. The **Polarity** column is optional. The **Base Category** column can be used for filtering data once it has been imported.

Click **Finish** to import the data. The structural measurements will appear in the **Structural Modelling** folder.

Once the data has been imported, you can add new columns and rows and reload the data, which is described in the <u>Working With Data Tables</u> topic.

Selecting the ODBC Data Source

When importing planar structural data from an ODBC database, you will need to specify the ODBC data source. Enter the information supplied by your database administrator and click **OK**.

Once the data source is selected, the import process is similar to that described above.

Importing Lineations

Lineations containing location information can be imported from files stored on your computer or a network location in .csv or text formats. To do this, right-click on the **Structural Modelling** folder and select **Import Lineations**. You will be prompted to select a file.


Leapfrog Works expects **East (X)**, **North (Y)**, **Elev (Z)**, **Trend** and **Plunge** columns. The **Polarity** column is optional. The **Category** column can be used for filtering data once it has been imported.

Click **Finish** to import the data. The lineations will appear in the **Structural Modelling** folder.

Once the data has been imported, you can add new columns and rows and reload the data, which is described in Adding and Updating Data for Existing Tables in the Working With Data Tables topic.


Displaying Structural Data

Planar structural data is displayed as disks and lineations are displayed as cones. There are several ways to change how this data is displayed. In the scene below, planar structural data is displayed using the **Flat colour** option, with positive (red) and negative (blue) sides shown:



You can change the colours used to display the positive and negative sides using the controls in the shape list. You can also display the data points as **Thick** disks, **Flat** disks or as **Outlined flat** disks. You can change the **Disk radius** and the **Disk size** using the controls in the shape properties panel.


Another way of displaying planar structural data is to display the categories as different colours:



You can change the colours used to display the different categories by clicking on **Edit Colours** in the shape list. In the window that appears, click on the colour chip for each category and change it as described in <u>Single Colour Display</u>.


To set multiple categories to a single colour, use the Shift or Ctrl keys to select the colour chips you wish to change, then click on one of the colour chips. The colour changes you make will be made to all selected categories.

The categories displayed can also be filtered by other columns in the data table, as described in <u>Filtering</u> Data Using Values and Categories.



In the scene below, lineations are displayed using the **Flat colour** option in green:


Click the colour chip to change the colour used to display the cones in the shape list or select one of the table's columns:



The length of the cones displayed in the scene is set in the properties panel. This can be a **Fixed Length**, defined by the **Cone length** setting, or it can be scaled using the values from one of the table's columns:

👁 🛕 Topography	💥 🔒 Flat col 🗸 🗾 🖉 📰 💷 👘 🍐 🌽	Plunge_Da	ta_Fold_Axis
GIS data: Select -		Slice mode:	From Scene 💌
👁 🏹 Plunge_Data_Fold_Axis	💥 🐣 Flat col 🗸 🔤 👘 🖉	Query filter:	No Filter 🗸 🔻
		Cone length:	1000.000
		Scale values:	Fixed Length
		F	Fixed Length
		L	🐴 plunge
			🍫 polarity
			ks trend

Another way of displaying lineations is to display the categories as different colours:




You can change the colours used to display the different categories by clicking on **Edit Colours** in the shape list. In the window that appears, click on the colour chip for each category and change it as described in <u>Single Colour Display</u>.

To set multiple categories to a single colour, use the Shift or Ctrl keys to select the colour chips you wish to change, then click on one of the colour chips. The colour changes you make will be made to all selected categories.

The categories displayed can also be filtered by other columns in the data table, as described in <u>Filtering</u> Data Using Values and Categories.

Viewing Statistics on Structural Data

To view statistics on structural data and lineations, right-click on a table and select **Statistics**. The following options are available:



See the <u>Analysing Data</u> topic for more information on each option:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots

Bingham Analysis

The **Bingham Analysis** option shows the value, trend and plunge for each of the eigenvectors, along with the Bingham mean plane and best-fit great circle:

📔 Export 🔲 Copy 🔻 📎 ጵ	🔀 Help										
Duery filter:	Category	Count		Value	Trend	Plunge		Strike	Dip	Dip Az.	
Query filter: None>	All Data	127	e1:	0.604	287.0	82.9	Mean plane:	17.0	7.1	107.0	
			e2:	0.358	99.7	7.0	Best fit great circle:	279.8	89.1	9.8	
			e3:	0.037	189.8	0.9					
	🔻 換 Bedding										
	Base	52	e1:	0.900	39.2	86.5	Mean plane:	129.2	3.5	219.2	
			e2:	0.077	186.7	2.9	Best fit great circle:	6.7	88.1	96.7	
			e3:	0.023	276.7	1.9					
	Bedding1	37	e1:	0.613	277.2	23.8	Mean plane:	7.2	66.2	97.2	
			e2:	0.387	97.6	66.2	Best fit great circle:	97.3	89.9	187.3	
			e3:	0.000	7.3	0.1					
	Bedding2	26	e1:	0.633	107.0	12.5	Mean plane:	197.0	77.5	287.0	
			e2:	0.367	287.0	77.5	Best fit great circle:	287.0	90.0	17.0	
			e3:	0.000	197.0	0.0					
	Bedding3	12	e1:	0.828	270.6	31.6	Mean plane:	0.6	58.4	90.6	
			e2:	0.160	104.2	57.6	Best fit great circle:	94.4	83.8	184.4	

You can select specific rows and copy them to the clipboard or copy all data to the clipboard. You can also export the data in *.csv format.

Fisher Statistics

The **Fisher Statistics** option shows the Fisher mean plane and confidence for the data in the selected table:


Projects Central Proj			-							_
🔓 Export 🕞 Copy 🔻 📎	• 🖾 🗠 🗙	Help								
		Category	Count	R-value	Kappa	Mean Strike	Mean Dip	Mean Dip Az.	Mean Trend	Mea
Query filter:	▼	All Data	127	0.742	3.841	18.4	4.2	108.4	288.4	
		🗸 👰 Bedding								
		Base	52	0.946	18.202	139.3	3.4	229.3	49.3	
		Bedding1	37	0.640	2.701	6.5	8.7	96.5	276.5	
		Bedding2	26	0.584	2.310	197.0	0.8	287.0	107.0	
		Bedding3	12	0.685	2.915	359.2	40.4	89.2	269.2	
		🗸 👰 Selection								
		cat1	35	0.987	74.498	110.4	4.0	200.4	20.4	
		No Value	92	0.652	2.839	359.1	7.1	89.1	269.1	

You can select specific rows and copy them to the clipboard or copy all data to the clipboard. You can also export the data in *.csv format.

Assigning Structural Data to Categories


There are two ways to initiate structural data selection: from the data object in the project tree/shape list and from a stereonet. The advantage of initiating structural data selection from a stereonet is that the data will be displayed both on the stereonet and in the scene window. This provides the most flexibility for analysing what data belongs to what category. See <u>Selecting Data in the Stereonet</u> and Using the Scene Window With the Stereonet for more information.

If you wish to assign planar structural data points or lineations to categories, right-click on the data table in the project tree and select **New Category Selection**. First, select the **Source Column**. If you select an existing column as the **Source Column**, you can assign selected data points to existing categories or create new categories. If you select **<None>** for the **Source Column**, you will have to define each category manually.



Select points by clicking on the **Select points** tool (), then drawing over those points in the scene:

Once you have selected points, you can assign them to existing categories or create new ones. To create a new category, click on the **Assign to > Create New Category** button:



Enter a name for the new category and click **OK**.


When you have finished selecting points and adding them to categories, close the **Category Selection** window to close the editor.

Editing the Orientation of Planar Structural Data

If you need to edit the orientation of planar structural data points, you can do so in two ways:

- Edit the data in the table directly by double-clicking on the structural data table in the project tree. See <u>Working With Data Tables</u>.
- Edit the structural data orientation in the scene.

To edit the structural data in the scene, right-click on the table in the project tree and select **Edit Orientation in Scene**. If the table is displayed in the scene, in the shape list, click on the **Edit** button (*(*). The **Planar Structural Data** window will appear in the scene, together with controls for editing the data points. To edit a data point, click on it. Information about the selected point will be displayed in the **Planar Structural Data** window, together with controls in the scene you can use to adjust the point:



You can also add new data points in the same manner described in <u>Creating New Planar Structural Data</u> <u>Tables</u>.

Declustering Planar Structural Data

If a planar structural data table contains multiple duplicate or near-duplicate measurements, you can create a declustered structural data set that will make the table easier to work with. Declustering is intended to work with large, machine-collected data sets rather than smaller sets that might be edited manually.

Declustering preserves the original data table and creates the set as a "filter" by applying two parameters: the **Spatial search radius** and the **Angular tolerance**.

- The **Spatial search radius** determines the size of the declustering space. All points inside the **Spatial search radius** are compared searching for duplicates.
- The **Angular tolerance** measures whether points have the same or similar orientation. The orientation of all points inside the **Spatial search radius** is measured and the mean taken. If a

point's orientation is less than the **Angular tolerance** from the mean, then the point is regarded as a duplicate. The point that is retained is the one that is closest to the mean.

When a structural data set has a numeric column that gives some indication of the measurement's uncertainty, this column can be used to prioritise values. Select the **Priority column** and set how the values should be handled.

Another factor in declustering the points is the category columns selected. When you choose multiple category columns, all criteria must match for points to be regarded as duplicates. What this means is that points will be kept if they have different category values in just one column, even if they meet the criteria for duplicates established by the **Spatial search radius** and the **Angular tolerance** and match in other columns. For example, in this table, assume that applying the **Spatial search radius** and the **Angular tolerance** parameters without using the Lithology category results in three points. However, including the Lithology column results in five points, indicated by the colours:

Dip	Dip-azimuth	Lithology
25	334	А
25	334	А
25	334	В
25	139	С
25	139	С
25	139	С
15	114	В
15	114	В
15	114	А

The more columns you select, the lower the likelihood that points will be regarded as duplicate.

The declustered set can be used like an ordinary structural data table. However, it is a filter on a planar structural data table and can be used as such when the parent table is displayed in the scene. For example, here the filters available for the planar structural data table include the query filters (∇) defined for the table as well as the declustered set (\leq):

👁 🤗 LongfBase 🧷 💥 🔒 Flat col 🛛 🗾 🖉 👘 Thick 🔹	Congford_Base		
	Slice mode:	From Scene 🔹	
	Query filter: Disk radius: Disk sides:	No Filter No Filter V Longford_Base: Base V Longford_Base: Bedding1 V Longford_Base: Bedding2 Longford_Base: Bedding3 Congford_Base_declustered	
E.	🧾 Full A	cceleration 100+ FPS \$Z-Scale 1.0	

To create a declustered structural data set, right-click on the **Structural Modelling** folder and select **New Declustered Structural Data**. Select the source data table and a query filter, if required. Set the parameters and the columns you wish to use, then click **OK**. The declustered set will be added to the **Structural Modelling** folder.

Edit the set by right-clicking on it in the project tree and selecting Edit Declustered Structural Data.

Setting Elevation for Structural Data

You can set the elevation for planar structural data points or lineations by projecting the data onto a surface. Any elevation data in the data table will be overwritten by the elevation values from the selected surface.

To set the elevation for planar structural data points or lineations, right-click on the table in the project tree and select **Set Elevation**. The **Set Elevation from Surface** window will appear:

😢 Set Elevation from Surface	×
Set elevation for 'Fault_F1'	
Select surface:	▼
Unprojected points	
<u>Empty elevation field</u>	
• Assign elevation value:	0
Marning: This will over	write all the Z values in the points table
U Help	<mark>∭ C</mark> ancel <u>€ O</u> K

Select from the surfaces available in the project.

Unprojected points are data points that do not vertically intersect the selected surface. There are two options for handling these points:

- Leave the elevation field empty.
- Assign a fixed elevation value.

Click **OK** to set elevation values.

Estimating Planar Structural Data

You can generate a set of planar structural measurements from points, polylines and GIS lines. To do this, right-click on the points or lines object in the project tree and select **Estimate Structural Data**. In the window that appears, enter a name for the structural data table, then click **OK**. The new structural data table will appear in the project tree and you can view and edit it as described in <u>Displaying Structural</u> <u>Data</u> and <u>Editing the Orientation of Planar Structural Data</u>.

Meshes

In Leapfrog Works, meshes are used to represent surfaces in the form of vertices and triangles that define the 3D shape of the surface. Meshes can be open or closed. Meshes are generated as part of the model-building process, but can also be imported into a project or created directly in the project. Leapfrog Works has several tools for adjusting meshes.

The **Meshes** folder contains all meshes imported into Leapfrog Works and created in Leapfrog Works outside of the model building process.

Two types of meshes are stored in the **Meshes** folder:

- Non-editable meshes ((>>) are meshes imported into Leapfrog Works and meshes created in Leapfrog Works from the moving plane, **Meshes > Mesh Operations** tools and by extracting mesh parts from other surfaces in the project.
- Editable meshes (a) are created in Leapfrog Works from data objects such as points data, GIS data and polylines. Editable meshes can be refined by adding more data. Editable meshes can be interpolated meshes (using FastRBF) or triangulated meshes (using Delaunay triangulation). Interpolated meshes can also be created from structural data and values objects.

The rest of this topic is divided into:

- Cleaning Up a Mesh
- Importing a Mesh
- Reloading a Mesh
- Displaying Surfaces
- Exporting Meshes

Cleaning Up a Mesh

There are several options for cleaning up a mesh that can be applied to meshes imported into Leapfrog Works and to non-editable meshes created in Leapfrog Works.

To clean up a mesh, double-click on the mesh in the **Meshes** folder or right-click on the mesh and select **Open**. The **Cleanup Mesh** window will be displayed:

💋 Cleanup Mesh - Topography X
Perform the following steps:
Combine identical vertices
Remove self-intersections for volumes
Consistently orient faces
<u>Remove non-vertex points</u>
Remove degenerate faces
Orient concentric parts
Invert mesh orientation
Remove vertical edges
Rotate locations about X axis
 Rotate 90 degrees clockwise
 Rotate 90 degrees anticlockwise
Move mesh
0 0 0
? <u>Cancel</u> <u>OK</u>

The Cleanup Mesh window will also be displayed when you import meshes.

The first option, **Combine identical vertices**, is intended for snapping cases where vertices occupy the exact same point in space. When enabled, vertices that have the exact same coordinates will be merged.

When enabled, **Combine identical vertices** occurs before the other processing actions in the **Cleanup Mesh** window.

The next option, **Remove self-intersections for volumes**, retriangulates self-intersecting triangles and trims away remaining open surfaces, whether they lie inside or outside the mesh. Before applying the **Remove self-intersections for volumes** option, check whether the mesh is open or closed. To do this, right-click on it in the project tree and select **Properties**. **Closed** should be True:

Import Filenam Imported On:	e:	
Vertices:	1,366	
Triangles:	2,728	
Volume:		
Area:	1,522,300	
Parts:	1	
Closed:	True	
Consistent:	True	
Manifold:	True	
Mesh extents:		
Min Corner:	3790.96, 7096.99, 180	
Max Corner:	4839.2, 7883.63, 726.693	

A mesh may appear to be closed in the scene but the **Closed** property will be false. Such a mesh may be made up of open parts that do not join up perfectly to make a closed mesh. If **Remove selfintersections for volumes** is enabled for such a mesh, it may disappear when it is trimmed.

Remove self-intersections for volumes should not be enabled for surface-like open meshes.

You may wish to enable **Remove self-intersections for volumes** if a mesh is reporting as open but is more volume-like than surface-like. Such a mesh may have a single open part that needs to be removed, or it may have open parts that line up perfectly and can be retriangulated to form a closed mesh.

The next four options are automatically applied to meshes created in or imported into Leapfrog Works:

- Consistently orient faces ensures that a mesh can be used for inside/outside testing.
- **Remove non-vertex points** removes points that are not used by any triangles.
- Remove degenerate faces removes triangles with duplicate vertices.
- Orient concentric parts ensures that internal parts have the correct orientation.

Other options are:

- Invert mesh orientation reverses the polarity of the mesh.
- **Remove vertical edges** removes any vertical faces from the mesh boundary.
- Rotate locations about X axis lets you rotate the mesh 90 degrees clockwise or anticlockwise.
- Move Mesh lets you offset the mesh by a vector. Tick the Move Mesh box and enter the required values. The offset values can be changed by opening the **Clean Mesh** window once again.

Select the options required, then click **OK**.

The mesh will be added to the project tree under the **Meshes** folder.

Importing a Mesh

Mesh formats Leapfrog Works supports include:

- Leapfrog Works Attribute Binary Mesh Formats (*.msh, *.ara)
- DXF Polyface Files (11/12 [AC1009]) (*.dxf)
- Alias Wavefront Object Files (*.obj)
- Leapfrog Model Files (*.lfm)
- Bentley Drawing Files (v8) (*.dgn)
- AutoCAD Drawing Files (2013/LT2013) (*.dwg)

Once a mesh has been imported to the project, you can evaluate it against any interpolant or distance function in the project. See <u>Evaluations</u> for more information.

To import a mesh, right-click on the **Meshes** folder and select **Import Mesh**. Navigate to the folder that contains the mesh file and select the file. You can select multiple files using the Shift and Ctrl keys. Click **Open** to import the file.

The **Cleanup Mesh** window will be displayed. See <u>Cleaning Up a Mesh</u>. Select the options required, then click **OK**.

The mesh will be added to the project tree under the **Meshes** folder.

Meshes imported into Leapfrog Works may exhibit geometries that cannot be used computationally by Leapfrog Works. See <u>Visualising Issues With Imported Meshes</u> for information on how to identify issues with imported meshes.

Meshes With Textures

- PNG Files (*.png)
- JPEG Files (*.jpg, *.jpeg)
- TIFF and GeoTIFF Files (*.tiff, *.tif)
- Windows Bitmap Files (*.bmp)
- Graphics Interchange Format Files (*.gif)

The texture is automatically imported when the mesh is imported and will appear in the project tree under the mesh.

Reloading a Mesh

Meshes imported into Leapfrog Works and created from extracting mesh parts can be reloaded. To do this, right-click on the mesh in the project tree and select **Reload Mesh**. Navigate to the file that should be used and click **Open**.


Displaying Surfaces

Leapfrog Works assigns different colours to each side of a surface.

A basic mesh will have an inside (coloured red) and an outside (coloured blue):

<	⊙ ∂`	Topography	×	À Flat c	-	v		
						_		

In the case of contact surfaces, each side will be assigned a lithology. "Unknown" will be used if multiple lithologies are contacted. Contact surfaces can be displayed using the assigned lithologies or the younging direction:



When a contact surface is displayed by its younging direction, the younger side of the surface will be displayed in green and the older side in brown.

Surfaces that are part of a geological model or interpolant are, by default, displayed clipped to the model boundary:

0	🛞 Geological model: Dyke 1	×	🖕 Flat c 🗸 📕		▶ 🕩 ▷ 🚮 😥 🛞 Dyke 2
0	🛞 Geological model: Dyke 2	\times	À Flat c 🗸 📕		Show unclipped surface
0	🕥 Geological marly Diorite	\times	À Lithol 🗸 📕		Fill Slicer
0	🛞 Geological meral diorite	\times	À Lithol 🗸 📕		
٢	🏈 Geologicaler contacts	\times	À Lithol 🗸	-•	

Disable the **Clipped surface** button (\checkmark) to view the surface unclipped.

Draping an Image on a Mesh

You can drape images on any mesh in the **Meshes** folder. To do this, right-click on the mesh in the **Meshes** folder and select one of the **Drape Image** options.

- For the **Import Image** option, you will be prompted for a file location. Navigate to the folder containing the image you wish to drape, select the file and click **Open**. Set georeferencing information for the image, if required, then click **OK**. See <u>Importing a Map or Image</u> for more information on georeferencing images. The imported image will appear in the project tree under the mesh.
- For the **Select Existing Image** option, select from the images available in the project and click **OK**. A hyperlink to the image will appear in the project tree under the mesh.

You can drape as many images as required. When the mesh is displayed in the scene, you will be able to select any draped images from the list of display options.

When you import and georeference an image, you can then export it as a GeoTIFF. To do this, rightclick on it in the project tree and select **Export**. You will be prompted for a filename and location. Click **Save**.

Exporting Meshes

Leapfrog Works exports meshes in the following formats:

- Leapfrog Files (*.msh)
- DXF Files (*.dxf)
- Alias Wavefront Object Files (*.obj)
- Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

You can export single meshes or batch export meshes from the **Meshes** folder or from individual models. Each of these is described below:

- Exporting a Single Mesh
- Exporting Multiple Meshes from the Meshes Folder
- Exporting Multiple Meshes from Models

Exporting a Single Mesh

To export a mesh, right-click on the mesh and select **Export**. The **Export Mesh Parts** window will appear:

8	xport Me	sh Parts	:	×
Pa	rts to Exp	ort		
		Volume 🗸	Area	
	~	409,320,000	4,347,700	
		215,230,000	3,254,300	
		138,620,000	2,012,700	
		1,141,900	93,185	
		205,220	17,560	
		22,874	7515.8	
		0704.0	1107.0	
	<u>S</u>	elect All	Remove Inside-Out	
	Re	move All	Remove Below Current	
	Flip Me	esh		
(\mathcal{D}	<u>C</u> ancel	<u>E</u> xport	
		L		

An **Export clipped mesh** option is available for meshes that are clipped to a boundary:


😸 Exp	ort Me	h Parts	
Parts	to Exp	ort	
\checkmark	Export	clippe <u>d</u> mesh	
	_	Volume	√ Area
	~	205,220	17,560
		4973.7	1470.3
		Open	2,932,500
		-261.7	224.76
	<u>S</u> e	elect All	Remove Inside-Out
	Ro	move All	Remove Below Current
	IVC.	HOVE AII	Remove Delow Ourrent

If the quality of the mesh produced is not acceptable, clip the mesh as described in <u>Clipping a Mesh</u>, then export the mesh.


Select the **Parts to Export**, then click **OK**. You will be prompted for a filename and location.

When exporting a mesh that has multiple parts, you can distinguish between the different parts by clicking on them in the **Export Mesh Parts** window. Here, the mesh was added to the scene before the

Export Mesh Parts window was opened. Clicking on a mesh part in the list selects that part in the scene:



If the mesh is not in the scene when the **Export Mesh Parts** window is opened, selecting a part in the list will display it in the scene without reference to the other parts of the mesh:



Use the Shift and Ctrl keys to select and view multiple mesh parts in the scene:

Export Me		:	×				
	Volume 🗸	Area					
_	409,320,000	4,347,700					
~	215,230,000	3,254,300					
~	138,620,000	2,012,700					
~	1,141,900	93,185			Elev (Z)		
~	205,220	17,560					
~	22,874	7515.8	5		+3000		
-	0704.0	1107.0	North (Y)	8			
5	elect All	Remove Inside-Out	N	494500			
R	emove All	Remove Below Current		494000		8 2	
Flip M	esh			+49	000 000 000 000 000 000 000 000	+445500 • East (X)	
				· · · · · · · · · · · · · · · · · · ·	+445000 +45000 +45000 +45000	+ "	Plunge +20
?	Cancel	<u>E</u> xport					Azimuth 030
	L						0 250 500

Exporting Multiple Meshes from the Meshes Folder

To export multiple meshes from those in the **Meshes** folder, right-click on the **Meshes** folder and select **Export Meshes**. In the window that appears, select the meshes you wish to export:

💋 Export Meshes	×
Select Objects	
Objects	Names
✓ ☐ Meshes	
> Component surfaces: Intermineral diorite	
✓ ☐ GM Surfaces	
🗌 쉱 GM: Boundary	
GM: EArly Diorite	EarlyDiorite
🗌 🔗 GM: Lateral Extent	
> Intermineral diorite surfaces	
✓ ☐ Merge Meshes	
🗌 쉱 Торо	
🗆 🛞 Pit	
🗌 🚕 Merged Mesh	
Select All Select None	
Export Options	
Format: Leapfrog Model Files (*.lfm)	~
Combine outputs into zip archive	
Folder: D:\Data\Castle Hill Basin	
File <u>n</u> ame: Meshes	
?	<u>Cancel</u> <u>Export</u>

The filename that will be used for each mesh is shown in the **Filenames** column. To change the filename for any of the meshes, click on its name in the **Filenames** column.

Next, select the format required and where to save the exported meshes. Available formats are:

- Leapfrog Model Files (*.lfm)
- Industry Foundation Classes Format 4 (*.ifc)
- Leapfrog Files (*.msh)
- DXF Files (*.dxf)
- Alias Wavefront Object Files (*.obj)
- Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

Click **Export** to save the meshes.


Exporting Multiple Meshes from Models

You can export multiple meshes from individual geological models, numeric models, combined models and static models. To export meshes in this way, right-click on a model or interpolant and select **Export**. In the window that appears, select the volumes and surfaces you wish to export:

😹 Export Mo	del - Geological model		×
Select Obje	cts utput ⊻olumes		
Objects		Names	
🗸 🍘 G	eological model		
\[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\] \[\[\] \[\] \[\] \[\[\] \[\] \[\[\] \[\[\] \[\[\] \[\[\] \[\[\[\] \[\] \] \] \] \]	Output Volumes		
	🔽 🌰 Cover	Geological model - Cover	
	🔽 🌰 Dacite	Geological model - Dacite	
	🔽 췕 Intermineral diorite	Geological model - Intermineral diorite	
	🔽 ┢ Early Diorite	Geological model - Early Diorite	
	🔽 ┢ Basement	Geological model - Basement	
Select <u>/</u> Export Optic			
<u>F</u> ormat:	Leapfrog Model Files (*.lfm)		~
	Combine outputs into zip arcl	hive	
Folder:	D:\Data\Castle Hill Basin		
File <u>n</u> ame:	Geological model		
?		Cancel	<u>E</u> xport

For geological models, if you wish to export surfaces other than the output volumes, untick the **Only Output Volumes** option.

For faulted geological models, you also can select from the faulted volumes by ticking the **Faulted Volumes** box:



The filename that will be used for each mesh is shown in the **Filenames** column. To change the filename for any of the meshes, click on its name in the **Filenames** column.

Next, select the format required and where to save the exported meshes. Available formats are:

- Leapfrog Model Files (*.lfm)
- Industry Foundation Classes Format 4 (*.ifc)
- Leapfrog Files (*.msh)
- DXF Files (*.dxf)
- Alias Wavefront Object Files (*.obj)
- Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

For any of the export options other than Leapfrog Model Files format and Industry Foundation Classes format, you can save the meshes as a zip file.

The Leapfrog Model File format exports a single *. If m file. If the file is imported into the **Meshes** folder, each output volume will appear as a single mesh.

Click **Export** to save the meshes.

Visualising Issues With Imported Meshes

Meshes imported into Leapfrog Works may exhibit geometries that cannot be used computationally by Leapfrog Works. For example, problems often arise when a mesh has holes, self-intersections or is non-manifold, and such problematic meshes need to be fixed before they can be used in Leapfrog Works. Leapfrog Works can identify and work with certain situations, such as non-manifold meshes with shared edges with an even number of adjoining triangles, and for other cases Leapfrog Works provides some tools that may fix some meshes. Note that blindly utilising these tools can result in undesirable side effects, so it is best to have a good understanding of the precise nature of the problems prior to selecting and utilising any repair options. Alternatively, understanding the location and nature of the problem may permit manual intervention in the tool generating the mesh that is being imported to Leapfrog Works. This topic describes how to identify issues in imported meshes. It is divided into:

- Examining Mesh Properties
- Visualising Self Intersections
- Visualising Borders
- Options for Handling Mesh Issues

Examining Mesh Properties

After importing a mesh, right click on it in the project tree and select **Properties**. Information in the **General** tab can give some insight into any problems with the mesh. These are the **Properties** window for an open mesh (left) and a closed one:

<u>G</u> eneral <u>P</u> r	ocessing		 <u>General</u> <u>Proces</u>	sing <u>E</u> rrors
Import Filenam Imported On:		ne\Desktop\Bad Meshes\test_meshes\omesh.msh 6:17:28.219000	Import Filename: Imported On:	D:\Jeremy\Documents\GeoProjects\testmeshes\closed_mesh.ms 2020-10-26 14:36:18.686755
Vertices:	36		Vertices:	54,474
Triangles:	34		Triangles:	108,944
Volume:	0		Volume:	7,335,900,000
Area:	29,975,000		Area:	28,524,000
Parts:	1		Parts:	1
Closed:	False		Closed:	True
Consistent:	True		Consistent:	True
Manifold:	True		Manifold:	False
Borders:	1		Mesh extents:	
Edges:	36		Min Corner:	2.7974e+06, 6.2907e+06, -2200
Length:	150,670		Max Corner:	2.8001e+06, 6.294e+06, -673.714
Mesh extents:				
Min Corner:	2.46789e+06,	5.73464e+06, -300	Surface intersects if	tself
Max Corner:	2.48997e+06,	5.75752e+06, 100	See Errors tab for d	etails

The **Closed**, **Consistent** and **Manifold** properties are shown for all meshes:

- A "closed" mesh is one for which no borders have been detected.
- A mesh is regarded as "consistent" when its inside can be distinguished from its outside.
- A manifold mesh is a closed mesh for which Leapfrog Works can calculate a volume. If there are issues with parts of the mesh and the volume cannot be calculated, the mesh will be flagged as "non-manifold", which, in Leapfrog Works, is a general term for geometry issues that limit a mesh's use.

Some non-manifold meshes can be utilised such as meshes with shared edges that have an even number of adjoining triangles.

Information about **Borders**, **Edges** and **Length** is shown for open meshes:

- "Borders" are boundary edges that are not connected to another triangle.
- "Edges" indicates the number of triangle edges that make up the border.
- "Length" is the total length of all border edges.


When Leapfrog Works detects errors in the mesh, additional information is provided in an Errors tab.

Properties - closed_mesh		×
General Processing Errors		
This surface is non-manifold, its inside can not be distinguished from its outside so its use within your project will be limited. - This mesh has self-intersecting triangles: 108587, 108588, 108586, 59389, 108440, 108441, 108439, 59421 108601, 108602, 108600, 57691, 107636, 59541, 59543, 59542 107634, 107440, 59584, 59583, 107439, 107881, 57955, 57960 107879, 107820, 57971, 57970, 107819, 107834, 57986, 57985 107833, 107296, 107295, 107294, 59618, 107326, 107327, 107325 59641, 107103, 59679, 59678, 59677, 107102, 107116, 59735 59736, 107115, 107254, 59800, 59799, 59798, 59797, 59796 107253, 59808, 107402, 107401, 59807, 108049, 59270, 59271 108048, 108180, 59278, 59280, 108179, 108280, 59261, 59265 59264, 108279, 107790, 59209, 59208, 107789, 107856, 107855 107874, 58020, 107764, 58073, 58078, 107762, 107429, 107428 107427, 58100, 58101, 58109, 107278, 106986, 58132, 58131 58130, 106985, 107274, 107273, 107272, 58176, 107288, 107287 107286, 58185, 58977, 58978, 106342, 106341, 58979, 58968 58972, 58967, 106333, 106270, 106271, 106269, 58267, 58498 58495, 58492, 58497, 105972, 58569, 58572, 105723, 106123 59068, 59067, 106122, 59047, 105816, 59046, 59040, 59045 59041, 105815, 105950, 59022, 105551, 59021, 105249, 58917 58916, 58914, 58913, 58912, 106055, 106042, 58813, 58813 106041, 58857, 106122, 59047, 105816, 59046, 59040, 59045 59041, 105815, 105950, 59022, 105551, 59024, 58593 58592, 108166, 108425, 58551, 58549, 108424, 58544, 58553 58513, 58841, 1060985, 58455, 106242, 58544, 58525 58513, 58841, 1060985, 58459, 108425, 58574, 58474, 58526 58525, 58524, 108415, 58481, 58481, 58480, 58478, 58476, 58479		
?	<u>C</u> lose	


Visualising Self Intersections

A mesh with self-intersections is often regarded as open, which limits the mesh's use in Leapfrog Works. The **Errors** tab in the **Properties** window provides a full list of each self-intersection triangle, but this is not useful for visualising where the self-intersections occur. There are three options for visualising self-intersections, which can be used alone or together.

The first option is to add the mesh to the scene and display it by its self intersections, which is one of the colouring options available in the shape list:



The self intersections may be so tiny that visualising them in this way is not useful. You could then use the second option for displaying self-intersections: Using the self intersections object in the project tree. The self intersections object is a sub-mesh that replicates the parts of its parent mesh that have the problematic self-intersections. Its like a copy of the mesh with the valid parts filtered out, and it can be displayed in the scene in the same manner as other meshes. Remove the whole mesh from the scene and add only the self intersections object:




Make sure **Show faces** (\triangleright) is on and **Smooth faces** ($\square \bullet$) is off. Pick front and back face shading colours that contrast with your chosen background colour, pale shades on dark backgrounds, dark shades on pale backgrounds.


The problematic triangles can be invisibly small. Pressing the Home button and zooming in to fill the screen can work well if triangles are few and close together.

Use the scroll wheel to quickly zoom in and out, and click-and-drag the left-and-right mouse buttons to pan.

If, however, the self intersections are spaced at opposite ends of the original mesh, you probably still won't be able to see them, in which case, the third option for displaying self intersections may be useful. This involves using the **Extract Mesh Parts** window to view different parts of the mesh. To do this, clear the scene. Next, right-click on the mesh (not the **self intersections** sub-object) and select **Extract Mesh Parts**:




In the window that appears, you can sort the mesh parts by either their volume or area and view only the smaller volumes, those likely to be the self intersections, one by one:



Whichever row is selected will appear in the scene behind, as seen above. There are buttons to **Select All** and **Remove All** that tick or untick all the mesh parts. **Remove Inside-Out** will untick any selected meshes that have a different 'sign' from the first mesh part in the list. If the first mesh part is positive, the button will untick selected negative -volume meshes; if the first mesh part is negative, the button will untick selected positive-volume meshes. **Remove Below Current** will untick all mesh parts below the currently selected mesh part.

Tick the mesh parts you want to extract and click OK to have a new object added to the project tree that contains only the extracted mesh parts. Now you can add only the selected mesh parts into the scene.

Once you've identified the areas of interest, add the whole mesh to the scene. Because you will have the mesh itself and its self intersections displayed, you can independently control the visibility of each. On the whole mesh, change the colouring selector to self intersections and the mesh will show hot colours where the mesh is intersected. Try turning **Show faces** () off but **Show edges** () on to see just the wireframe of the mesh. You can also adjust the opacity of the mesh to make the whole mesh into a pale background so that the self intersection mesh stands out. To get a better picture of the geometry of the mesh around the self-intersecting triangles, move the scene around to see the shape better in 3D. Click the middle mouse button (scroll wheel button) on a self-intersecting triangle to set the centre of rotation on that triangle. Then click-and-drag the scene up and down and left and right and around to orbit around the point of interest. This will help you visualise the context better.



The self-intersecting triangles can at times look very simple, but zooming in very close to the corners, edges and contacts between triangles may reveal some very small triangles you hadn't previously noticed.



You can choose to **Export** the **self intersections** mesh sub-object, which will only offer the mesh parts that Leapfrog Works has identified as self intersections. Right click the **self intersections** mesh sub-object and select **Export**. You will get a similar mesh part selection window to the one described above, but with the addition of a **Flip Mesh** option to invert the inside/outside identification of the mesh surfaces.

The **Cleanup Mesh** window has a **Remove self-intersections for volumes** option that can be useful in fixing some self intersections:

😵 Cleanup Mesh - closed_me	sh		×			
Perform the following steps:						
Combine identical vertices						
Remove self-intersections for volumes						
Consistently orient face	Consistently orient <u>f</u> aces					
Remove non-vertex poin	nts					
Remove <u>d</u> egenerate fac	ces					
Orient concentric parts						
Invert mesh orientation						
Remove <u>v</u> ertical edges						
Rotate locations about	X axis					
Rotate 90 degrees of the second se	Rotate 90 degrees clockwise					
Rotate 90 degrees a	anticlockwise					
Move mesh						
0	, 0	, 0				
?	<u>C</u> ancel		<u>о</u> к			

The **Cleanup Mesh** window can be opened by double-clicking on an imported mesh in the project tree. See <u>Cleaning Up a Mesh</u> for more information.


The **Remove self-intersections for volumes** repair option re-triangulates self-intersecting triangles and trims away remaining open surfaces, whether they lie inside or outside the mesh.

- Before applying the Remove self-intersections for volumes option, check whether the mesh is open or closed. A mesh may appear to be closed in the scene but the Closed property will be false. Such a mesh may be made up of open parts that do not join up perfectly to make a closed mesh. If Remove self-intersections for volumes is enabled for such a mesh, it may disappear when it is trimmed.
- Remove self-intersections for volumes should not be enabled for surface-like open meshes. You may wish to enable Remove self-intersections for volumes if a mesh is reporting as open but is more volume-like than surface-like. Such a mesh may have a single open part that needs to be removed, or it may have open parts that line up perfectly and can be re-triangulated to form a closed mesh.


If you enable this option, check the resulting mesh's properties and that is appears in the scene as you expect.

Visualising Borders

Leapfrog Works may regard a mesh as open when it appears to be closed. Here a mesh that appears to be a closed volume is displayed in the scene:




To visualise where the borders are on the mesh, add the **border edges** mesh sub-object to the scene. Here a green line highlights where the small border is, representing a tear in the mesh:




You can right click the **border edges** sub-object in the project tree and select **Export** to export Leapfrog Works polylines in *.LFPL format.

Visualising Non-Manifold Edges

Non-manifold edges are a common reason that a volume cannot be calculated for the mesh. This mesh is reporting a non-manifold mesh problem :



To visualise where the non-manifold edges are on the mesh, add the **non-manifold edges** mesh subobject to the scene. Here a green line highlights where the non-manifold edge is:



You can right click the **non-manifold edges** sub-object in the project tree and select **Export** to export Leapfrog Works polylines in *.LFPL format.

Options for Handling Mesh Issues

Key questions to ask with regard to mesh issues are:

- Can the mesh be fixed in the application of origin?
- Do you need to use the affected part of the mesh?
- Can you extract the parts of the mesh you need to work with?

The best option for issues with an imported mesh is to fix the issues in the application of origin, and diagnosing the issues in Leapfrog can be of some help in doing so. But when fixing the mesh outside Leapfrog Works is not possible, there are mesh repair options available through the **Cleanup Mesh** window. This is opened when meshes are imported, but you can also open it by double-clicking on a mesh:

Cleanup Mesh - open_mesh_appears_closed	×				
Perform the following steps:					
Com <u>b</u> ine identical vertices					
Remove self-intersections for volumes					
Consistently orient faces					
Remove non-vertex points					
✓ Remove <u>d</u> egenerate faces					
✓ Orient concentric parts					
Invert mesh orientation					
Remove vertical edges					
Rotate locations about X axis					
Rotate 90 degrees clockwise					
 Rotate 90 degrees anticlockwise 					
Move mesh					
0 0 0					
<u>Cancel</u> <u>OK</u>					

However, some options can have unexpected results and so it is best to have a good understanding of the precise nature of the problems prior to selecting and utilising any repair options. The **Cleanup Mesh** window can be opened by double-clicking on an imported mesh in the project tree. See <u>Cleaning Up a</u> Mesh for more information.

When these mesh repair options cannot fix the problems, consider whether you need to use the problem part of the mesh. It could be that the issues you have identified lie outside the are in which you are modelling. If Leapfrog Works does not limit the use of this mesh in your model, using the mesh might not be an issue.

If you do not need to use the problem part of the mesh but Leapfrog Works limits your use of the mesh due to the errors identified, you could use the **Extract Mesh Parts** tool to extract the parts of the mesh you want to work with, leaving out the parts that have issues.

If you cannot resolve issues with a mesh, contact support as described in <u>Getting Support</u>. When doing so:

- Include a zipped copy of the project that includes the mesh.
- Identify the source of the mesh.

Non-Editable Meshes

Leapfrog Works provides you with several tools for creating non-editable meshes:

- Mesh from the Moving Plane
- <u>Combining Meshes</u>
- Clipping a Volume
- Clipping a Mesh
- Merging 2D Meshes
- Extracting Mesh Parts

These tools produce non-editable meshes (\bigotimes).

Mesh from the Moving Plane

When a vertical wall, flat fault plane or other flat geological surface is required, the moving plane can be used to create a simple mesh.

To create a new mesh from the moving plane, first display the plane in the scene by clicking on the **Show Plane** button (\mathcal{Q}). Use the controls in the scene to position the plane, then right-click on the **Meshes** folder and select **Mesh From Moving Plane**. The **Mesh From Plane** window will appear:

😤 Mesh Fron	n Plane	×
<u>R</u> esolution:	150.0	\$
<u>N</u> ame:	plane	
Help	<u>X</u> Cancel	<u>ер</u> к

Set the **Resolution** for the mesh, enter a name and click **OK**. The new mesh will appear in the **Meshes** folder.

See Surface Resolution in Leapfrog Works for more information on the resolution setting.

Combining Meshes

To create a new mesh from two existing closed meshes, right-click on the **Meshes** folder and select **Mesh Operations > Boolean Volume**. The **Boolean Volume** window will appear:

😵 Boolean Volume	>
A <u>v</u> ailable meshes:	Selected meshes:
▼ Meshes	
local extracted from	=
🛡 🛅 Geological Models	
🔻 🊺 GM	
Boundary	
🔻 🎒 GM fault block 1	
Fault Block Bou	
Output Volumes	
🎯 Fault Block	
🎯 Fault Block	
🔻 🞒 GM fault block 2	
Fault Block Bou	
🛡 📄 Output Volumes	
🎯 Fault Block	
E-wik Dia ala	<u> </u>
Select <u>A</u> ll <u>S</u> elect None	
Operation: Intersect	▼
Name:	
	Cancel @QK

The **Available** list shows all closed meshes available in the project. Select a mesh by double-clicking on it or by clicking on it, then on the arrow.

The **Operation** type can be **Intersect** or **Union**.

Click **OK** to save the new mesh, which will appear in the **Meshes** folder. To edit the mesh, double-click on it. The **Boolean Volume** window will appear.

When any of the meshes used to create the volume is modified, the volume will be updated.

Clipping a Volume

To clip a closed mesh using another mesh, right-click on the **Meshes** folder and select **Mesh**

Operations > Clip Volume. The **Clip Volume** window will appear. Select the meshes you wish to use and whether to retain the inside or outside of the clipped mesh.

Click **OK** to save the new mesh, which will appear in the **Meshes** folder. To edit the mesh, double-click on it.

When either of the meshes used to create the clipped volume is modified, the clipped volume will also be updated.

Clipping a Mesh

This option creates a new mesh that consists of the parts of a **Clip** mesh that are inside, outside or overlap with the **Using** mesh. To clip one mesh using another mesh or boundary in this manner, right-click on the **Meshes** folder and select **Mesh Operations > Clip Mesh**. The **Clip Mesh** window will appear:

😤 Clip I	Mesh)
Clip:	🁆 Select Mesh	
<u>U</u> sing:	👌 Select Mesh	
<u>R</u> etain:	Inside	
	Include overlap	
Name:		


Select the meshes to use, then choose whether to retain the inside or the outside of the clipped mesh. Tick the **Include overlap** box to include the overlap between the two meshes as part of the new mesh.

Click **OK** to save the new mesh, which will appear in the **Meshes** folder. To edit the mesh, double-click on it. The **Clip Mesh** window will appear.

When either of the meshes used to create the clipped mesh is modified, the clipped mesh will be updated.


Merging 2D Meshes

This option creates a new mesh from two or more open meshes and specifies the priority in which input meshes will be used to create the final mesh. This is useful when, for example, a single mesh is required that represents the topography (with less detail) and the area around a site (with more detail). To merge 2D meshes, right-click on the **Meshes** folder and select **Mesh Operations > Merge Meshes 2D**. In the window that appears, select the meshes you wish to use.



If you use more than one detailed mesh or base mesh, the meshes higher in the list will have higher priority over those lower down in the list.

The **Buffer distance** value determines the zone in which the selected meshes are merged and the **Resolution** setting determines the resolution of that zone. For example, here the **Buffer distance** is 250:



Click **OK** to save the new mesh, which will appear in the **Meshes** folder. To edit the mesh, double-click on it.

When any of the meshes used to create the merged mesh are modified, the merged mesh will be updated.

Extracting Mesh Parts

To extract the triangles from a mesh and create a new mesh, right-click on the surface and select **Extract Mesh Parts**. The **Extract Mesh Parts** window will appear:

😵 Extract	🗱 Extract Mesh Parts				
Parts To	Extract				
	Volume 🗸	Area			
~	293,030	36,099			
	54,719	18,192			
	54,120	14,826			
	27,419	8125.4			
~	24,456	9,023			
~	19,572	7589.4			
~	17,899	7753.5			
	13,991	6282.5			
	13,322	5754.9			
	13,110	5274.7			
	00057	4500.0			
	Select All	Remove Inside-Out			
E	emove All	Remove Below Current	t		
<u>N</u> ame:	extract self-inters	sections			
?	<u>C</u> ancel	<u>0</u> К			

The **Extract clipped mesh** option is only available for meshes that are clipped to a boundary. The largest part is initially selected. You can sort the mesh parts by **Volume** or by **Area** by clicking the heading of the respective column. Other options are:

- Select all parts by clicking the **Select All** button. To de-select all parts click the **Remove All** button.
- Some mesh parts may have a negative volume. If the first mesh part has a negative volume, clicking the **Remove Inside-Out** button will untick mesh parts with positive volumes; if the first mesh part has a positive volume the **Remove Inside-Out** button will untick mesh parts with negative volumes.
- To remove parts smaller than a given size, first click the **Select All** button. Select the last item you want to keep and click the **Remove Below Current** button.

Click **OK** to save the new mesh, which will appear in the **Meshes** folder. The mesh generated is a noneditable mesh (O).

Meshes created in this way are not connected to the mesh they were created from. Changes to the original mesh will not be reflected in the selected parts.

If the quality of the mesh produced is not acceptable, clip the mesh as described in Clipping a Mesh.

Interpolated Meshes

An interpolated mesh is a type of editable mesh (ﷺ). An interpolated mesh uses FastRBF to fit and interpolate surface data. The FastRBF is useful for creating meshes from sparse datasets or when data has large areas where there are no points. Interpolated meshes can be created from points data, GIS data, polylines, structural data and values objects.

Interpolated meshes can be edited by adding more data to the mesh and changing settings.

This topic describes creating and working with interpolated meshes. It is divided into:

- Creating an Interpolated Mesh
- Refining an Interpolated Mesh
 - Surface Resolution Settings
 - Snap Settings
 - Other Options

Creating an Interpolated Mesh

The steps for creating a mesh from data in the project are similar, regardless of the data used to create the mesh. The exception is creating an offset mesh, which requires additional parameters. See <u>Offset</u> <u>Meshes</u> for more information.

To create an interpolated mesh from data in the project, right-click on the **Meshes** folder and select from the **New Mesh** options.

Here, a new mesh is being created from points:

😤 New Mesh		×			
Points: 🏘 D2 - [01 contacts	•			
Extents					
Shared with	n: 🔷 Zn_pc in BM	13: Do 💌			
Own extent	ts				
Surface resolution: 80.0					
Name: D2 - D1 contacts					
Help	<u>X</u> Cancel	€ <u>о</u> к			

Select the required object from the list.

When defining the mesh's extents, you can set the extents to be independent of other objects in the project (**Own extents**) or you can use the extents of another object (**Shared with**). When you select the **Shared with** option, the mesh will be updated when the extents object it shares is updated.

Leapfrog Works automatically sets the surface resolution based on the data available in the project. You can experiment with the surface resolution and adaptive settings once you have created the mesh. See <u>Surface Resolution in Leapfrog Works</u> for more information on the effects of these settings.

Enter a name for the new mesh and click **OK**.

If you are creating the mesh from a polyline, you will be prompted to select an existing polyline or draw a new one. If you draw a new polyline, it will not be able to be used elsewhere in the project unless it has been shared. To share the polyline, expand the mesh in the project tree, right-click on the polyline and select **Share**.

The new mesh will appear in the **Meshes** folder. Expand the mesh in the project tree to see how it was made. As further refinements are made to the mesh, that information will also be added to the mesh in the project tree.

Refining an Interpolated Mesh

Editable interpolated meshes () can be refined by adding data, as described in <u>Adding Data to</u> <u>Surfaces</u>. The options available depend on how the mesh was created.

To add data to an editable mesh, right-click on it and select one of the options from the **Add** menu. A list of objects available in the project will be displayed. Select the required object and click **OK**. The mesh will be updated and the object used to modify it will appear under it in the project tree.

You can also refine editable interpolated meshes by changing the trend, transforming values, adjusting the interpolant and changing the boundary. To do this, double-click on the mesh. The **Edit Mesh** window will be opened:

Genera	Boundary	Trend	Value Transform	Interpolant	
Surfac	e <u>r</u> esolution:	50.0	\$ [Adaptive	
<u>S</u> nap t	o data: All d	ata			•
Maxim	ium snap <u>d</u> ist	ance:			25.00
Snap	Input				
1	速 GIS line				
	🖗 D2 - D1 c				
	🖗 D2 conta	cts			
	points				
\checkmark	Contacts				
<u>N</u> ame:	D2 - D1 cor	tacts			

See Offset Meshes for the options available for meshes from offset points.

Surface Resolution Settings

See <u>Surface Resolution in Leapfrog Works</u> for more information on the **Surface resolution** settings in the **General** tab.

Snap Settings

The mesh can be set to snap to the data objects used to create it. There are four options:

- Off. The mesh does not snap to the data.
- All data. The mesh snaps to data within the Maximum snap distance.
- **Drilling only**. The mesh snaps only to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data. For example, the mesh will honour points data derived from borehole data, but not points data imported into the **Points** folder.
- Custom. The mesh snaps to selected data objects within the Maximum snap distance.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

When **Snap to data** is set to **Custom**, you can then set whether or not **Snap** is enabled for the objects used to create the mesh, as discussed in <u>Honouring Surface Contacts</u>. **Custom** is the most flexible options as you can select the specific data objects the mesh will or will not snap to.

If you will be exporting the mesh for use in another application, you may wish to adjust the snap settings.

Data used to create the mesh will appear in the **Input** list. When you add more data to the mesh, those objects will also be listed. You can remove those additional objects by expanding the mesh in the project tree, then right-clicking on the data object and selecting **Remove**.

Other Options

In the **Boundary** tab, you can change whether the mesh boundary is independent of other objects in the project (**Own extents**) or you can use the extents of another object (**Shared with**). When you select the **Shared with** option, the mesh will be updated when the extents object it shares is updated.

Options available in other tabs are similar to those available for interpolants. See:

- Structural Trends
- Clipping and Transforming Values for an RBF Interpolant

For information on the parameters in the **Interpolants** tab, see the <u>Interpolant Functions</u> topic.

2D Interpolant Meshes

A 2D interpolant can be created using any points object in the project. A 2D interpolant is built using the same algorithm as the project's topography surface (see <u>Defining a Topography</u>). This often this gives a smoother result in less time than when using the same data to build a 3D interpolated mesh. A 2D interpolant can work with vertically-oriented data such as fault planes, whereas building a topography is meant to work with primarily horizontal data.

To create a 2D interpolant, right-click on the **Meshes** folder and select **New 2D Interpolant Mesh**. In the window that appears, select from the points objects available in the project.

Extents			
Shared with the second seco	th: 🛆 Topograph	y `	/
Own exter	nts		
	Minimum	Maximum	
<u>X</u> (East):	444061.047527	446939.668430	< >
Y (North):	492061.471866	494939.923247	~ >
<u>Z</u> (Elev):	-1852.0	5252.0	< >
		Enclose Object N	
Reference Plan			
	_		
✓ Automatic	5		
✓ Automation Dip:	0.0		
	0.0 🗘		
D <u>i</u> p:	0.0 🗘	Set From <u>D</u> ata	
D <u>i</u> p:	0.0 ¢ uth: 0.0 ¢ Set From Plane	Set From Data	ve

The mesh's extents can be independent of other objects in the project or you can use the extents of another object. Surface resolution can be adaptive or non-adaptive. You can set a reference plane to set the direction of the best fit through the data; this is useful when working with data that is not primarily horizontal.

Offset Meshes

You can create a new interpolated mesh by offsetting an existing mesh with any points object in the project. To do this, first ensure the points and mesh you wish to use are already in the project. Next, right-click on the **Meshes** folder and select **New Mesh > From Offset Points**. In the window that appears, select the **Mesh** and **Points** to use:

😤 New Me	esh from Offset Points	×			
<u>M</u> esh:	👌 Select				
<u>P</u> oints:	b Select				
Distance li	imits				
🗌 Mir	nim <u>u</u> m 0	*			
🗌 Maj	<u>x</u> imum 0	- -			
Extents					
● <u>S</u> ha	ared with: 🔷 Zn_pc in BM3: Do	•			
O Ow	n extents				
Surface <u>r</u> esolution: 18.00					
<u>N</u> ame:					
E	elp 🔀 Cancel 🦺 OK				

When the mesh is created, it will automatically snap to the points, and points outside the **Distance Limits** will be ignored. These settings can be changed once the mesh has been created.

An offset mesh may be distorted if points used to offset the mesh lie too far outside the mesh extents. If this occurs, set a **Maximum** distance to exclude points far away from the mesh extents.

Enter a name for the new mesh and click **OK**. The new mesh will appear in the **Meshes** folder. To edit the mesh, double-click on it. The **Edit Offset Mesh** window will appear:

General Boundary	
<u>M</u> esh	
BM3	
Surfacing	
Surface resolution:	60.0 🗘 🗋 🖸 <u>A</u> daptive
Snap to data:	All data 🔹
Maximum snap <u>d</u> istance:	30.00
Snap Input	
points	
Distance limits	
Minim <u>u</u> m 0	4 V
Maximum 2650	÷
- [

The mesh can be set to snap to the data objects used to create it. There are four options:

- Off. The mesh does not snap to the data.
- All data. The mesh snaps to data within the Maximum snap distance.

- **Drilling only**. The mesh snaps only to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data. For example, the mesh will honour points data derived from borehole data, but not points data imported into the **Points** folder.
- Custom. The mesh snaps to selected data objects within the Maximum snap distance.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

When **Snap to data** is set to **Custom**, you can then set whether or not **Snap** is enabled for the objects used to create the mesh, as discussed in <u>Honouring Surface Contacts</u>. **Custom** is the most flexible options as you can select the specific data objects the mesh will or will not snap to.

If you will be exporting the mesh for use in another application, you may wish to adjust the snap settings.

Data used to create the mesh will appear in the **Input** list. When you add more data to the mesh, those objects will also be listed. You can remove those additional objects by expanding the mesh in the project tree, then right-clicking on the data object and selecting **Remove**.

You can modify an offset mesh by adding data, as described in <u>Refining an Interpolated Mesh</u>.

It is not possible to add structural data or polylines with orientation information to an offset mesh. If you edit an offset mesh with a polyline, your options for editing the polyline will be limited.

You can also edit the mesh's boundary, but you cannot apply a trend, clip and transform values or adjust the interpolant as you can for other interpolated editable meshes.

Triangulated Meshes

A triangulated mesh is a type of editable mesh ((a)). A triangulated mesh uses Delaunay triangulation to create the mesh and can handle more points than an interpolated mesh. Triangulated meshes can be created from points data, GIS data and polylines. Large datasets representing horizontal surfaces can be used to create a triangulated mesh.

The steps for creating a mesh from data in the project are similar, regardless of the data used to create the mesh. To create a triangulated mesh from data in the project, right-click on the **Meshes** folder and select from the **New Triangulated Mesh** options.

Here, a new triangulated mesh is being created from points:


😢 New Triangulated Mesh 🛛 🗧 🗧	×				
Points: GM_Main_Thrust_vertices 🔹	ן ן				
Extents					
● <u>Shared with:</u> ◆ <i>Zn_pc in BM3</i> : Do ▼					
Own extents					
□ <u>U</u> se error threshold					
<u>D</u> istance: 0.000]				
Name: GM_Main_Thrust_vertices					
Help X Cancel]				

Select the required object from the list.


When defining the mesh's extents, you can set the extents to be independent of other objects in the project (**Own extents**) or you can use the extents of another object (**Shared with**). When you select the **Shared with** option, the mesh will be updated when the extents object it shares is updated.

The **Use error threshold** setting lets you exclude data points that fall within the threshold. This can be useful if you are using a large dataset and you require a more coarse surface that omits some data. When **Use error threshold** is disabled, the mesh will follow all the data.

Here, a mesh created from points has the **Use error threshold** disabled. The mesh follows all the points:



Here, a mesh has been created with the **Distance** set to 20. The mesh ignores points that fall outside the threshold:



You will be able to change the **Use error threshold** setting once the mesh has been created.

Enter a name for the new mesh and click **OK**.

If you are creating the mesh from a polyline, you will be prompted to select an existing polyline or draw a new one. If you draw a new polyline, it will not be able to be used elsewhere in the project unless it has been shared. To share the polyline, expand the mesh in the project tree, right-click on the polyline and select **Share**.

The new mesh will appear in the **Meshes** folder and you can edit its settings by double-clicking on it.

To add data to a triangulated mesh, right-click on it and select one of the options from the **Add** menu. A list of objects available in the project will be displayed. Select the required object and click **OK**. The mesh will be updated and the object used to modify it will appear under it in the project tree.

It is not possible to add structural data or polylines with orientation information to a triangulated mesh. If you edit a triangulated mesh with a polyline, your options for editing the polyline will be limited.

Elevation Grids

Leapfrog Works imports and exports elevation grids in common formats.

Importing an Elevation Grid

Elevation grid formats Leapfrog Works supports include:

- Arc/Info ASCII Grid Files (*.asc, *.txt)
- Arc/Info Binary Grid Files (*.adf)
- Digital Elevation Model Files (*.dem)
- Surfer ASCII or Binary Grid Files (*.grd)
- SRTM Files (*.hgt)
- ESRI.hdr Labelled Image Files (*.img, *.bil)
- GeoTIFF Image Files (*.tiff, *.tif)

There are two ways to import an elevation grid:

- Import the grid to the **Meshes** folder. Right-click on the **Meshes** folder and select **Import Elevation Grid**.
- Import the grid as part of creating a topography. Right-click on the **Topographies** folder and select **New Topography > Import Elevation Grid**.

Navigate to the folder that contains the elevation grid file and open the file. The **Import Elevation Grid** window will be displayed:

Import Elevation Grid					
Surface resolution:	100.0	•			
Clipping					
	r be applied to grids rtical on the map.				
✓ Clip data to b	oounding box				
<u>B</u> ounding box:	Clipping Boundary	•			
<u>M</u> argin:	0	* *			
No Data Handling					
<u> <u> Leave</u> a gap </u>					
O <u>R</u> eplace with		* *			
Name: Topo Golden					
E Import					

Leapfrog Works automatically sets a **Surface resolution** based on the information in the file, but you can change the value if you wish. A lower value will produce more detail, but calculations will take longer. See Surface Resolution in Leapfrog Works for more information.

When importing an elevation grid, note that the resolution cannot be changed once the file has been imported.

Data is automatically clipped to the clipping boundary, but you can change how the data is filtered to suit any bounding box that exists in the project. If you do not wish to clip the data, untick **Clip data to bounding box**.

The Margin value determines how far outside the selected Bounding box the elevation grid will extend.

The **No Data Handling** option determines whether NoData values are displayed as gaps or at a fixed elevation setting.

Click **Import**. If you are creating a new topography, you will then be prompted to enter a name for it and click **OK**.

The elevation grid will be added to the **Meshes** folder. If you imported the grid as part of creating a topography, a hyperlink to the grid in the **Meshes** folder will appear as part of the defined topography.

Exporting an Elevation Grid

For any mesh in a project, you can export an elevation grid for use in other software. Formats Leapfrog Works can export are:

- ARC/Info ASCII Grid (*.asc)
- ESRI.hdr Labelled (*.bil)
- ENVI Raster Image (*.img)
- Surfer ASCII Grid (*.grd)

To export an elevation grid, right-click on the mesh and select **Export Elevation Grid**. The **Export Grid** window will appear:

😢 Export Gri	d		×			
Exporting Topography Grid Spacing:						
X (E <u>a</u> st):	0.00 🗘 Y (Nort	:h): 10.00	•			
Covering:						
	Minimum	Maximum				
<u>X</u> (East):	2225.9999999999	6074.00000000	-			
<u>Y</u> (North):	\$728.0	9472.0	-			
	Enclose <u>O</u> bject 🔻	Snap to Grid				
Help	Cancel	<u>Export</u>				

The **Snap to Grid** option changes the extents of the exported grid so that they coincide with the elevation grid spacing.

Enter the information required, then click **Export** to enter a filename and choose a location and format for the file.

Thickness Grids

For any mesh in a project, you can export a grid made up of the area between two surfaces. Formats Leapfrog Works can export are:

- ARC/Info ASCII Grid (*.asc)
- ESRI.hdr Labelled (*.bil)
- ENVI Raster Image (*.img)
- Surfer ASCII Grid (*.grd)

To export a thickness grid, right-click on the mesh and select **Export Thickness Grid**. The **Export Thickness Grid** window will appear:

😢 Export Thi				×
· · · · ·	ickness between e: A-B contacts			
- Second S <u>u</u>	face:			•
Grid Spacing	:			
X (E <u>a</u> st): 1	0.00	Y (Nort	h): 10.00	+
Covering:				
	Minimum		Maximum	
<u>X</u> (East):	3479.2096107113343	\$	5204.727499479282	-
Y (North):	6636.90732749469	•	8375.975398437135	-
	Enclose <u>O</u> bject 🔹		Snap to Grid	
Help			<mark>∭ C</mark> ancel	kport

Select the surfaces required from the lists.

Enter the information required, then click **Export**. You will be prompted for a filename and location.

Polylines

Leapfrog Works imports many common polyline formats and also has tools for drawing and exporting polylines. This topic describes:

- <u>Creating Polylines</u>
- Displaying Polylines
- Sharing and Unsharing Polylines
- Importing Polylines
- Reloading Polylines
- Exporting Polylines

See <u>Drawing in the Scene</u> for information on drawing and editing polylines.

Creating Polylines


There are three ways to create polylines in Leapfrog Works:

- Create a new polyline using the **Polylines** folder. These polylines are stored in the **Polylines** folder.
- Create a new polyline as part of working with another tool. For example, a polyline can be drawn to create a lateral extent in a geological model. These polylines are stored in the tool used to create them and cannot be used elsewhere in the project unless they have been shared. To share a polyline, right-click on it and select **Share**. The polyline will be moved to the **Polylines** folder and can be used elsewhere in the project.
- Create a new polyline from a GIS line. To do this, right-click on the GIS lines object (a or) in the GIS Data, Maps and Photos folder and select Extract Polyline. The new polyline object will appear in the Polylines folder. It is not linked to the original GIS lines object.

See <u>Drawing in the Scene</u> for information on drawing and editing polylines.

Displaying Polylines


When polylines are displayed in the scene, you can control the colour of the positive and negative surfaces of the line and of the line itself. In this example, the positive side of the polyline is red, the negative side is blue and the polyline itself is green:



For contact surfaces, the colour of the positive and negative sides of a ribbon will be determined by the lithologies or categories assigned to either side of the surface.

With the **Node size** and **Point size** controls in the properties panel, you can change the size of nodes and points in the scene to make working with the polyline easier.

Polylines have a **Surface ribbon**() and **Normal ribbon**() to help you to determine the orientation of the polyline in the scene. The surface ribbon reflects the orientation of the polyline and the normal ribbon is perpendicular to the surface ribbon. For example, click on the **Surface ribbon** button () to determine which side of the polyline is positive (red) and which side is negative (blue):




If you are having trouble seeing the ribbons, you can change their size using the **Ribbon width** control in the properties panel.

Other aspects of polyline display are useful when creating and editing polylines. See <u>Drawing in the</u> <u>Scene</u>.

Sharing and Unsharing Polylines

Some polylines are created as part of working with other objects and are not available elsewhere in the project. An example of this is a polyline drawn as part of creating a model boundary. To share the polyline, right-click on the object in the project tree and click **Share**. The shared polyline will be copied to the relevant location in the project tree and a hyperlink added to the object it was shared from.

Polylines that have been shared can be unshared by making a local copy of the polyline. To do this, right-click on the shared polyline and select **Create Local Copy**:



The polyline in the **Polylines** folder remains, but a local copy of it is made and the hyperlink to the **Polylines** folder copy is deleted. This means you can now work on, for example, the **Polylines** folder copy without changes to it affecting the geological model's copy.

Importing Polylines

Polyline formats Leapfrog Works supports include:

- Drawing Interchange Polylines (*.dxf)
- Old Leapfrog Polylines (*.lfpl)
- Leapfrog Polylines (*.csv, *.txt)
- AutoCAD Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

There are two ways to import a polyline:

- Right-click on the **Polylines** folder and select **Import Polyline**. In the **Import Polyline** window, navigate to the location where the polyline file is saved and select it. Click **Open**.
- Drag and drop polyline files directly into Leapfrog Works.

If the polyline file is in Leapfrog, Gocad or DXF formats, the importing will start immediately. For all other formats, the **Polyline Import** window will appear. If the polyline file is in one of the standard formats listed above, the default settings can be used. Click **Import** to finish the process. If, however, you wish to specify polyline import parameters, two pieces of information are required:

- The columns the polyline vertex coordinates are in
- How the polyline sections are separated in the file

Select the vertex coordinate columns by clicking on the heading at the top of a column and selecting one of East (X), North (Y) or Elev (Z) from the list.

When importing a file that has multiple features, you will be prompted to select which ones to import. You can also choose to:

- Import the features as separate objects. Each feature will appear in the project tree as a separate object.
- Flatten all features into one object. Leapfrog Works will treat all features as a single object.

The polyline will be imported and added to the project tree under the **Polylines** folder.

See Drawing in the Scene for information on drawing and editing polylines.

Reloading Polylines

Reloading data is necessary when the imported data is modified externally. To reload a polyline, rightclick on it in the project tree and select **Reload Data**.

Reloading a polyline overwrites any changes you have made to the polyline. Any dependent objects will be updated, which can take some time.

Select the file to be reloaded and click **Open**. The polyline will be updated, as will any dependent objects.

Exporting Polylines

Export a polyline by right-clicking on it and selecting **Export**. Leapfrog Works exports polylines in the following formats:

- Leapfrog Polylines (*.lfpl)
- Leapfrog Polylines (*.csv)
- Drawing Interchange Polylines (*.dxf)
- Drawing File (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)


Open Mining Format (OMF) Export and Import

Open Mining Format is a convenient format for exchanging data with other applications because multiple geosciences objects can be moved as a single file. Leapfrog Works supports the export and import of Open Mining Format v0.9.

This topic describes how to export and import OMF data. It is divided into:

- OMF Export
- OMF Import
- Importing OMF Files From the Central Data Room

OMF export and import are available from the **Leapfrog Works** menu:




OMF Export

When you export objects in OMF format, you can select from the list of objects in the project. You can also select the objects that are currently in the scene, and so setting up a scene before initiating the export of an OMF file is a useful way of selecting a subset of data for export.

To export data from a project in OMF format, click on the **Leapfrog Works** menu and select **OMF > Export**. A list of objects in the project that can be exported in OMF format will be displayed:

Ø OMF Export		×
Select items t	o export:	
🗸 🗀 Торо	graphy	•
v 🤞	Topography	
∨ [] D	raped GIS Objects	
~	🙈 Alignment (On Topography)	
~	🉈 Alluvial Fan (On Topography)	
~	🍰 Granodiorite Contact (On Topography)	
~	🍰 Gravel Schist contact (On Topography)	
~	🍰 Gravel Water (On Topography)	
~	🍰 Lake Aura Bathymetry (On Topography)	
~	🍰 Sandy Gravel Schist contact (On Topography)	
Select <u>A</u> ll	Select None Select Objects in Scene	
<u>T</u> itle:	Lake Aura Demo	
Description:		
File <u>n</u> ame:	C:\Users\Geologist\Scenes\Lake Aura Demo.omf	
?	<u>C</u> ancel <u>O</u> K	

If you have information in the project tree's **Notes** object, it will be added to the **Description** field in the **OMF Export** window:



Select the objects you wish to export, then specify the file name and the folder where it will be saved. Click **OK** to export the file.

Exporting the file may take some time if you have selected a large number of objects.

OMF Import

To import data from an OMF file, click on the **Leapfrog Works** menu and select **OMF > Import**. In the window that appears, select the file you wish to import and click **Open**. The objects in the file will be displayed, organised into folders:

💋 OMF Import X						
Select items to import: > Select items to import: > Select items > Select items > Select items > Select items to import: >						
Select All Select None Title: LA_objects						
Description:						
(?)	Cancel	<u>о</u> к				

How the objects in these folders will be organised in the Leapfrog Works project tree is as follows:

- Points objects will be added to the **Points** folder.
- Lines objects will be added to the GIS Data, Maps and Photos folder.
- Meshes will be added to the **Meshes** folder.
- Block models will be added to the **Block Models** folder.
- Colourmaps on imported objects will be added to the **Colour Gradients** folder.

Select the objects you wish to import and click **OK**.

Importing OMF Files From the Central Data Room

See the <u>The Project Data Room</u> topic in the <u>Central 4.0 help</u> for information on how to work with a Central project's data room.

In order for OMF files to available for import to Central users, upload the OMF file to a Central project's data room. Here an OMF file in the Ultimate Wolfpass project's data room can be imported into Leapfrog projects on the same Central server:

С	=		Alex Rock ADMIN
je ₽	Projects / Ultimate Wolfpass / Files Ultimate Wolfpass	OVERVIEW USERS FILES HISTORY EVENTS	PROPERTIES
(B) (B)	Files	Search All Files Q To New Folder <u>1</u> Upload Files	Utimate Wolfpass.omf Type: OMF File Size: 169.9 MB Storage Use: 169.9 MB
11 }	Name Type	File Modified On Modified By	Versions: 1 Created On: 23 Oct 2020 Modified On: 23 Oct 2020
		Import OMF Project Files From Central - Ultimate W File Import Seicet the file to import from Central Name Name Utimate Wolfpass.omf Supported formats: *.omf	offpess X
		3	<u>Q</u> ancel <u>Previous</u> Import

To import data from an OMF file stored on Central, first make sure you are connected to a Central server. Next, click on the **Leapfrog Works** menu and select **OMF > Import from Central**. In the window that appears, select the project you wish to import data from. The OMF files stored in the project's data room will be displayed:

							2 OMF Impo	rt X
File Import	IF Project Files From Central - Ultimate Wolfpass e to import from Central			-	×	<	Select items	
	Name Ultimate Pit.omf	Type	Size 639.1KB	Date 23/10/2020 17:36:59	User			
	Ultimate Wolfpass.omf	.omf	169.9MB	23/10/2020 17:30:39	-		Select <u>A</u> ll Title:	Sglect None Uttimate Pit
Supporte	Supported formats: *.omf						Description:	Mesh from the Ultimate Wolfpass project
							?	<u>Cancel</u> <u>QK</u>

How the objects in these folders will be organised in the Leapfrog Works project tree is as follows:

- Points objects will be added to the **Points** folder.
- Lines objects will be added to the GIS Data, Maps and Photos folder.
- Meshes will be added to the **Meshes** folder.
- Block models will be added to the **Block Models** folder.
- Colourmaps on imported objects will be added to the **Colour Gradients** folder.

Select the objects you wish to import and click **OK**.

Objects imported from OMF files cannot be reloaded.

Analysing Data

Leapfrog Works has a number of tools that help you to analyse your data.

- The most basic information about an object is contained in the object's **Properties** window, which is specific to the type of object. Right-click on the object in the project tree and select **Properties**. See <u>Object Properties</u> in the <u>The Project Tree</u> topic for more information.
- Viewing statistical information about objects helps you to analyse your data. This is described further below.
- Visualising data using the shape list and the shape properties panel is an important part of interpreting and refining data and making modelling decisions. The tools available depend on the type of object being displayed, and many objects can be displayed evaluated on other objects.
- Stereonets are useful for visualising structural data and identifying trends in 2D. Errors in categorisation of structural data can also become apparent when the data is viewed on a stereonet.
- Form interpolants are useful for visualising structural data and identifying broad trends in 3D. The form interpolant's meshes can then be used to control other surfaces in the project.
- With the borehole correlation tool, you can view and compare selected boreholes in a 2D view. You can then create interpretation tables in which you can assign and adjust intervals and create new intervals. Interpretation tables are like any other interval table in a project and can be used to create models.
- You can plan boreholes, view prognoses for models in the project and export planned boreholes in .csv format.

The rest of this topic describes the different statistics visualisations available in Leapfrog Works.

Statistics

The statistics options available in Leapfrog Works depend on the type of object. Common statistics visualisations are described below:

- Table of Statistics
- Scatter Plots
- Q-Q Plots
- Box Plots
- Univariate Graphs

Variations of these are described relative to the data objects for which they are relevant.

Leapfrog Works uses fixed 25%/75% quartiles.

Table of Statistics

For many data tables, you can view a table of statistics for multiple attributes. If the table has one or more category columns, data can, optionally, be grouped by category. To open a table of statistics, right-click on a data table then select **Statistics**. In the window that appears, select the **Table of Statistics** option.


In this example, we have the initial table of statistics for a merged table that has two category columns and four numeric columns, plus an **Interval Length** column. However, nothing is displayed in the table because data columns have not yet been selected.

V 🛞 Projects	Scene View	Central Projects	Σ Statistics: Merged_Ta \times	Alex Rock
Query filter: <pre></pre>	~			
Statistics weighting: Length-weighted	✓	s selected		
Group by category				
Group by numeric item				
<u>Categories:</u>				
\oplus \ominus				
Hide empty categories				
Hide inactive rows				
Numeric items:				
AG_gpt				
AU_gpt				
CU_pct				
ECOV				
🗌 🥠 Interval Length				
Select All Select None	e			

Select from the **Numeric items** available for the table. In this case, all columns have been selected, including the **Interval Length** column:

V 🐣 Projects	Scene View	Central Proj	ects	Statistics: Merged	_Ta ×	Alex Ro	ck
⊉ №~ 12 ≫ ≪ ?)							
Query filter: <pre></pre>	Name 🗸	Count	Length	Mean	Std. dev.	Coeff. var.	Variance
Statistics weighting: Length-weighted	AG_gpt	9,187	16,930.8	3.778	15.688	4.153	246.115
Group by category	AU_gpt	9,187	16,930.8	0.831	1.420	1.709	2.016
⊖ Group by numeric item	CU_pct	9,187	16,930.8	0.898	0.916	1.020	0.839
Categories:	RECOV	9,187	16,930.8	1.886	0.417	0.221	0.174
	🥠 Interval Length	9,316	n/a	2.775	12.713	4.581	161.613
(\pm) $(=)$							
\oplus Θ							
Hide empty categories							
Hide inactive rows Numeric items:							
AG_gpt							
V Processor							
CU_pct							
 Market Strength 							
Select All Select None							

Click the **Add** button to select from the category columns available in the table. An entry will be added to the **Categories** list. Click on the arrow to select from the available category columns:



Statistics for the selected category column will be displayed in the table. You can change what categories are displayed by clicking on the second button and enabling or disabling categories:

V 🐣 Projects	🌒 Sc	ene View 🥲 🤅	Central Projects	St.	atistics: Merged_Ta $ imes$	\triangle	Q Alex Rock	
<u>→</u> °°~ 12 × ×	≈ ?							
Query filter: <pre></pre>	e> ~	Name 🗸 🗸	Count	Length	Mean	Std. dev.	Coeff. var.	Vari
Statistics weighting: Lengt	h-weighted 🗸	V ASH	63	197.4				
Group by category	_	AG_gpt	53	75.9	1.420	7.411	5.220	54
Group by numeric item		AU_gpt	53	75.9	0.060	0.383	6.388	0.1
Categories:		CU_pct	53	75.9	0.036	0.070	1.931	0.0
Level 1: 🏾 🦺 ROCK 🗸	ASH, CRLSS	RECOV	53	75.9	0.164	0.484	2.946	0.3
	All	🥠 Interval Length	63	n/a	3.134	5.545	1.769	30
	None	COLLV	106	299.1				
	ASH	AG_gpt	96	187.6	5.196	7.522	1.448	56
\square \bigcirc		AU_gpt	96	187.6	0.348	0.826	2.374	0.
\oplus \ominus	DA	CU_pct	96	187.6	0.207	0.308	1.491	0.0
Hide empty categories	✓ E1	RECOV	96	187.6	0.818	0.903	1.104	0.
Hide inactive rows	✓ E2	🥢 Interval Length	106	n/a	2.821	4.976	1.764	24
Numeric items:	E3	- 📕 DA	533	1,423.7				
AG_gpt	EBX1	AG_gpt	510	922.3	1.851	8.051	4.349	64
AU_gpt	EBX2	AU_gpt	510	922.3	0.414	0.588	1.419	0.
CU_pct	H	CU_pct	510	922.3	0.304	0.292	0.961	0.0
RECOV	✓ 11	RECOV	510	922.3	1.986	0.086	0.043	0.0
🔽 🥠 Interval Length	✓ 12	🥠 Interval Length	533	n/a	2.671	5.049	1.890	25
	IBX	E1	159	375.3				
	SAPR	AG_gpt	158	288.5	3.564	3.304	0.927	10
Select All	SBX	All ant	158	288.5	1.629	1.251	0.768	1.9

If there is more than one category column, you can set lower levels. Here there are two category columns displayed in the table, "ROCK" and "Domain":

V 🐣 Projects		Scene View	Central Project	ts	Statistics: Merg	ed_Table_1 \times		ex Rock
<u>→</u> 🔤 🛛 🔡 📎	∕ ጵ ?							
Query filter:	None> ~	Name 🔨	Count	Length	Mean	Std. dev.	Coeff. var.	Variance
Statistics weighting:	ength-weighted	V ASH	63	197.4				
Group by category		AG_gpt	53	75.9	1.420	7.411	5.220	54.917
Group by numeric item		AU_gpt	53	75.9	0.060	0.383	6.388	0.146
Categories:		CU_pct	53	75.9	0.036	0.070	1.931	0.005
Level 1: 🎼 ROCK	ASH, CNCRLSS	RECOV	53	75.9	0.164	0.484	2.946	0.234
Level 2:	n 🗸 🛛 Ore, waste	🥢 🥠 Interval Length	63	n/a	3.134	5.545	1.769	30.745
		Ore 🖉	23	38.8				
		AG_gpt	23	38.8	2.644	10.653	4.029	113.484
		AU_gpt	23	38.8	0.033	0.113	3.427	0.013
\oplus \ominus		CU_pct	23	38.8	0.039	0.065	1.679	0.004
Hide empty categories	3	RECOV	23	38.8	0.271	0.622	2.293	0.387
Hide inactive rows		🛛 🧳 🥠 Interval Lengtl	1 23	n/a	1.685	2.522	1.496	6.359
umeric items:		✓ waste	30	37.2				
AG_gpt		AG_gpt	30	37.2	0.144	0.898	6.255	0.807
AU_gpt		AU_gpt	30	37.2	0.088	0.541	6.151	0.292
U_pct		CU_pct	30	37.2	0.034	0.078	2.327	0.006
RECOV		RECOV	30	37.2	0.052	0.292	5.584	0.086
🔽 🥠 Interval Length		🥢 Interval Lengti	n 30	n/a	1.239	1.458	1.177	2.127


You can hide empty categories (those with a count of zero) and inactive rows using the options below the **Categories** list:

Group by Group by Group by I	cat <u>eg</u> ory n <u>u</u> meric item	
Categories:		
Level 1:	nock 🗸 🗸	ASH, CNCRLSS/
Level 2:	🌇 Domain 🗸	Ore, waste 🔍
A		
\bigcirc		
Hide emp	ty categories	
Numeric item		
- 	_gpt	
🔽 🏥 AU.		
🔽 🏭 CU.		
REC		
🔽 🥠 Inte	erval Length	

Group by category and Group by numeric item provide further options for the table organisation. Here the Group by numeric item option has been selected:

Projects	Scene View	Centra Centra	l Projects	Statistic	cs: Merged_Table_1 \times	\triangle	Q Alex Rock	
⊉ №~ 12 🛛 🛠 🔍 🕐								
Query filter: <pre></pre>	Name N	Count	Length	Mean	Std. dev.	Coeff. var.	Variance	1
Statistics weighting: Length-weighted	AG_gpt	9,187	16,930.8	3.778	15.688	4.153	246.115	
Group by category	ASH	53	75.9	1.420	7.411	5.220	54.917	
Group by numeric item	COLLV	96	187.6	5.196	7.522	1.448	56.582	
categories:	DA	510	922.3	1.851	8.051	4.349	64.814	
Level 1: 🎼 ROCK 🗸 ASH, CNCRLS	S/ E1	158	288.5	3.564	3.304	0.927	10.919	
	E2	953	1,752.1	3.164	4.121	1.303	16.983	
	E3	633	1,166.0	4.360	9.261	2.124	85.770	
	EBX1	145	277.5	3.595	2.245	0.624	5.039	
\oplus \ominus	EBX2	2,035	3,858.9	4.994	23.922	4.790	572.267	
$(\pm) (\ominus)$	н	1,382	2,587.9	2.492	7.944	3.188	63.108	
Hide empty categories	📕 I1	914	1,747.1	3.516	4.368	1.242	19.077	
Hide inactive rows	12	297	552.7	3.156	2.549	0.808	6.499	
umeric items:	IBX	1,259	2,456.2	3.308	15.013	4.539	225.380	
AG_gpt	SAPR	265	429.3	5.808	6.858	1.181	47.032	
AU_gpt	SBX	176	302.0	6.543	40.991	6.265	1,680.227	
	SGNCRLS	S 266	239.0	8.642	43.383	5.020	1,882.104	
RECOV	*Inactive	45	87.6	2.827	3.261	1.154	10.637	
🔽 🥠 Interval Length	V 🛄 AU_gpt	9,187	16,930.8	0.831	1.420	1.709	2.016	

You can filter the data using any **Guery filter** defined for the data table. Statistics for interval tables can be unweighted or weighted by interval length.



Change the columns displayed in the table by clicking on the **Edit table columns** button (**B**):

Once you have set up a table of statistics on a particular table, its settings will be saved so you can easily review the statistics and export the table using the same settings.

To export the table in CSV format, click on the **Export** button in the toolbar (\mathbf{D}) .

Click rows to select them, and select multiple rows by holding down the Shift or Ctrl key while clicking rows. You can then copy rows by clicking the **Copy** button (), which allows you to copy the selected row(s) or all rows in the table.

The arrow buttons quickly expand (>) or collapse (\land) rows.

Scatter Plots

Scatter plots are useful for understanding relationships between two variables. An additional variable can be introduced by setting the **Colouring** option to a data column. The example below plots the two variables lead and zinc against each other, with gold being indicated by the colouring. You can make either axis a log scale with the **Log scale in X** and **Log scale in Y** options. A **Query filter** may also be applied.

The appearance of the chart can be modified by adjusting the **Point size**, **Point shape**, and **White background** settings.

Enable **Show X = Y line** to aid in assessing how far off equal the distributions are.

When you select **Show linear regression**, a regression line is added to the chart and a function equation is added below the chart title.

Show conditional expectation plots a line that attempts to find the expected value of one variable given the other. The X axis is divided into a number of bins specified by **Bin count**, and the data in each bin is used to predict the expected Y value.



By default, the limits of the chart are automatically set to range between zero and the upper limit of the variable data. You can adjust this by turning off **Automatic X axis limits** and/or **Automatic Y axis limits** and specifying preferred minimum and maximum values for each axis.

There are three select tools at the top of the window:

\checkmark	Reprojects	Scene View	© c	entral Projects	Z Scatter: Leda_assay	/ ×
	🗠 🧾 🍢 👘 🕄 🔅] (?				
Data				S	catter graph of Pb_pc	vs Zn_pc
X colum	n: In Zn_pc	~		Weighted linear r	egression: y = 0.361459 >	(+ 0.125255 R ² =
	Log scale in X			+		
Y colum	n: Pb_pc	~				/
	Log scale in Y		- 3			
Query filt	ter: <none></none>	~			Ŋ	


With these tool, you can select or deselect points on the graph.

- Use the **Replace** button (\blacksquare) to select points. This tool clears any previous selection.
- Use the Add button (^{IIII}) to add more points to an existing selection.
- Use the **Remove** button (^E) to deselect points.

There are three ways to use each tool:

- Click on individual points to select/deselect them.
- Drag the cursor across points to select/deselect them.
- Draw around a set of points to select/deselect them.


For example, here, using the **Replace** button (\blacksquare) to draw a loop around points selects those points:



You can also:

- Select all visible points by clicking on the **Select All** button (1997) or by pressing Ctrl+A.
- Clear all selected points by clicking on the **Clear Selection** button (10) or by pressing Ctrl+Shift+A.
- Swap the selected points for the unselected points by clicking on the **Invert Selection** button (I) or by pressing Ctrl+l.

Selected points can be filtered in the scene by selecting the scatter plot from the **Query filter** options in the shape properties panel.




Q-Q Plots

Quantile-Quantile plots are useful for validating your assumptions about the nature of distributions of data. Select the data columns to show on the X Axis and Y Axis (which can optionally be set as log scales). You can also select an X filter and/or Y filter to limit the values used from the data columns.

Enable **Show X = Y line** to plot the mirror line for the chart, which may not always be obvious when the X and Y axis have different scales.

Show quartile line draws a line through two points on the chart, the lower quartiles and the upper quartiles for each of the axes.



Box Plots

The box plot (or box-and-whisker plot) provides a visualisation of the key statistics for a data set in one diagram.


Select a **Numeric column** to display, enabling **Log scale** if it helps to visualise the data more clearly. If the table includes category data, set the **Category column** to one of the category columns to help visualise the data. Select which categories to include from the **Categories** list.

You can also use a pre-defined **Query filter** to limit the data included in the chart.


Note these features of the plot:

- The mean is indicated by the red diamond.
- The median is indicated by the line that crosses the inside of the box.


- The box encloses the interquartile range around the median.
- The whiskers extend out to lines that mark the extents you select, which can be the **Min/Max** whiskers, the **Outer fence whiskers** or the **Inner fence whiskers**. Outer and inner values are defined as being three times the interquartile range and 1.5 times the interquartile range respectively.



Univariate Graphs




There are several different visualisation options. **Histogram** shows a probability density function for the values, and **Cumulative Histogram** shows a cumulative distribution function for the values as a line graph:



There are three options that show the charts with a log scale in the X-axis:

• Select **Histogram** and enable **Histogram of the log** to see the value distribution with a log scale X-axis.

• Select **Cumulative histogram** and enable **Histogram of the log** to see a cumulative distribution function for the values with a log scale X-axis.



• Log probability is a log-log weighted cumulative probability distribution line chart.

Percentage is used to change the Y-axis scale from a length-weighted scale to a percentage scale.

Bin width changes the size of the histogram bins used in the plot.

The **Box Plot** options control the appearance of the box plot drawn under the primary chart. The whiskers extend out to lines that mark the extents you select, which can be the **Min/max whiskers**, the **Inner fence whiskers** or the **Outer fence whiskers**. Inner and outer values are defined as being 1.5 times the interquartile range and 3 times the interquartile range respectively.

Some univariate graphs may include a **Filtering** option containing where a **Query filter** defined for the data set can be selected.

The Limits fields control the ranges for the X-axis and Y-axis. Select Automatic X axis limits and/or Automatic Y axis limits to get the full range required for the chart display. Untick these and manually adjust the X limits and/or Y limits to constrain the chart to a particular region of interest. This can effectively be used to zoom the chart.

The bottom left corner of the chart displays a table with a comprehensive set of statistical measures for the data set.

Borehole Correlation Tool

With the borehole correlation tool, you can view and compare selected boreholes in a 2D view. You can then create interpretation tables in which you can assign and adjust intervals and create new intervals. Interpretation tables are like any other interval table in a project and can be used to create models. You can also save and export correlation set layouts and styles that can be exported and used in other Leapfrog Works projects.


This topic describes creating correlation sets and creating interpretation tables. It is divided into:

- Selecting Collars
- The Correlation Set Window
- Correlation Column Layouts
- Managing Styles
- Interpretation Tables

Selecting Collars

To select collars, you need to create a borehole correlation set, which you can do from the scene. First, add the collars you wish to work with to the scene. A useful way of limiting the number of collars displayed is to draw a slice in the scene and set it to a thick slice () and set the slice width to hide collars on either side of the slice.

Next, right-click on the **Borehole Correlation** folder and select **New Borehole Set**. The new set will be created and opened, but is empty until you select collars. Click the **Select Collars** button () to switch to the scene and begin selecting collars:



The line in the scene indicates the order in which collars will appear in the set.

- To select collars one-by-one, click on the Select collar button (^(A)), then on the Add collar button (^(A)). Click on a collar to add it to the nearest end of the set. Hold down the Ctrl key while clicking to remove a collar from the set.
- To temporarily switch to the **Select** button ($\$), hold down the Shift key while clicking.
- To select all collars visible in the scene, click on the **Select all collars** button (
- To remove a collar from the selection, click on the **Remove collar** button (³/₆), then click on the collar you wish to remove from the set.
- To clear the selection, click on the **Clear collar selection** button (**%**).

If you want to change the order, you can easily do so in the set tab once you have selected collars.

Once you have selected the required collars, click the **Save** button (🛅). The selected collars will be added to the set window:

🚴 Layout	: <none></none>	~		< 6 ₽	0			
EM_73	EM_72	JM_086	JM_085	EM_68	JM_084	EM_71	EM_70	JM_083
Depth	Depth	Depth	Depth	Depth	Depth	Depth	Depth	Depth
0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
10.0	0.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0
20.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0
30.0 📲	20.0 30.0 40.0	30.0	30.0	0.0 10.0 20.0 30.0 40.0	30.0	20.0	30.0	30.0
40.0	40.0	40.0	40.0	40.0	40.0	40.0	40.0	40.0
0.0	50.0	0.0 Image: Constraint of the second sec	0.0	50.0	0.0 funning 10.0 20.0 30.0 40.0 50.0 60.0 70.0 80.0	50.0	0.0 []]] 10.0 []]] 20.0 []]] 30.0 []]] 40.0 []]] 50.0 []]] 60.0 []]]] 70.0 []]]	50.0
60.0	60.0	60.0	60.0		60.0	60.0	60.0	60.0
70.0	60.0 70.0	70.0	70.0	60.0 70.0 80.0	70.0	70.0	70.0	70.0
		80.0	80.0		80.0	80.0		80.0
		90.0	90.0	90.0	90.0	50.0		0.0 Image: Constraint of the second sec
		100.0	90.0	=	90.0	=		I
		110.0	110.0					

The Correlation Set Window

Remove collars from the correlation set by either editing the set in the scene, as described in <u>Selecting</u> Collars above, or right-click on a the borehole name in the column header and select **Remove collar**:

\searrow	Drillhole Set	×		
🚴 Layout:	<none></none>	~	B 🖗 🖗 🕅	₽?
EM_73	EM_72	JM_086	1M 0.85 FM_68	3 JM_08
Depth	Depth	Depth	Collar <u>d</u> etails Depth	Depth
0.0	0.0	0.0 -	Remove collar 0.0	3 0.0
10.0 20.0	10.0	10.0	10.0 10.0	10.0
20.0	20.0	20.0	20.0 20.0	20.0
30.0	30.0	30.0	30.0 30.0	30.0
30.0 40.0	0.0 10.0 10.0 10.0 10.0 10.0 10.0 10.0	10.0	30.0 30.0 40.0 40.0	10.0 10.0 20.0 30.0 40.0

You can change how data is displayed by right-clicking below the borehole name in the column header, then selecting **Format**:


\searrow	Drillhole Set	×						
🚴 Layout:	<none></none>	~	🔣 🛇 🕼	2 6 2	?			
EM_73 Depth	EM_72 Depth	JM_086 Depth	JM_085	EM_68 Depth	JM_084 Depth	EM_71 Depth	EM_70 Depth	JM_083 Depth
0.0	0.0	0.0	Eormat	0.0	0.0	0.0	0.0	0.0
10.0	10.0	10.0	10.0	0.0	10.0	0.0	0.0	10.0
20.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0	20.0
30.0	30.0	30.0	🤹 🦉 Depth A	xis Display Style		×	20.0 mm 30.0 mm 40.0 mm	30.0
40.0	40.0	40.0	2 Depth axis	,				40.0
0.0	0.0 Ганиниристиристиристиристиристиристиристир	50.0		, interval: 1.00		Û	50.0 fo.0	0.0 ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
60.0	60.0	60.0	6				60.0	60.0
70.0	70.0	70.0	?	<u>C</u> ancel		<u>о</u> к	70.0	70.0
	3	80.0	8					80.0
		90.0	90.0	90.0	90.0	90.0		90.0
		20.0 Implementation 30.0 Implementation 40.0 Implementation 50.0 Implementation 60.0 Implementation 70.0 Implementation 90.0 Implementation 100.0 Implementation	100.0	1	90.0 100.0	E		Ē
		110.0	110.0		4			
		1						

The options available depend on the type of column being formatted.


Click on boreholes and drag them in the correlation set window to change the order in which they appear:

🚴 Layou	t: <none></none>			~			2 6	⊵	(?)							
EM_70	EM_73		EM_72		JM_08	6	JM_08	5	EM_68		JM_0	84	EM_71		JM_08	3
Depth	€Ber	_	Берш		Берш		рерш		рерш		Depui		Depth		Depth	
0.0	0.0		0.0	l	0.0	l	0.0	l	0.0	l	0.0	لسب	0.0	l	0.0	luu
10.0	10.0		10.0	-	10.0	humbu	10.0	-	10.0	-	10.0	mhum	10.0	humhun	10.0	hum
20.0	20.0	mlum	20.0	mhum	20.0	T	20.0	T	20.0	mlum	20.0	mhum	20.0	mhun	20.0	mhum
30.0	30.0	uhuuuhuuuhu	30.0	mhun	30.0	ահատահատահա	30.0	mhum	30.0	mhum	30.0	mhim	30.0	ահատհատոհա	30.0	mhum
40.0	40.0		40.0	T	40.0		40.0	mhim	40.0	mhim	40.0	m	40.0	- Hereit	40.0	mhum
0.0	50.0		50.0	hannalanaa kanalanaa kanalanaa kanalanaa kanalana kanalana kanalana kanalana kanala kanala kanala kanala kanala	50.0	-	50.0	m	50.0	m	50.0	mhini	50.0		50.0	mhun
60.0	60.0	mhundh	60.0	-	60.0	mhuunhuunhu	60.0		60.0		60.0		60.0	-	60.0	mhun
70.0	70.0	m	70.0	- Hora	70.0	1	70.0		70.0		70.0	mhun	70.0	m	70.0	mhum
				3	80.0		80.0	-	80.0	-	80.0	m	80.0	-	80.0	mhum
					90.0	-	90.0	հատահատահատահատահատահատահատահատահատուհ	90.0	հատոհատոհատոհատոհատոհատոհատոհատոհատո	90.0	mlim	90.0		90.0	
	1				100.0		100.0			Ξ	100.0			3		=
					110.0	mhim	110.0	ų								

Add columns to the set by dragging them from the project tree into the set window. Here, four columns have been added to the set. From right to left they are a lithology column, an assay data column, a points data column formatted as a line and a points data column formatted as points:



You can then format the columns to get a better view of relationships between them. Format columns by right-clicking on their headers and selecting **Format**:



The styles used to display columns can be used by other sets in the project and can be exported to other projects. See Managing Styles below.

You can also drag some types of columns on top of other columns, although it is not possible to display category data on top of other category data. You can select multiple columns using the Shift and Ctrl keys.


Navigating in the Correlation Set Window

Navigate in the correlation set window using the following mouse and keyboard combinations:

- Use the scroll wheel to move up and down.
- Hold down the Shift key while scrolling to move right and left.
- Hold down the Ctrl key while scrolling to zoom in and out.
- Hold down the Alt key while scrolling to stretch the data vertically.

Correlation Column Layouts

Once you have organised data columns and how they are displayed, you can save this information as a column layout that can be applied to other correlation sets. To do this, click the **Layout** button in the toolbar and select **Save Current Layout** from the list:



You will be prompted for a name. Click **OK** to save the layout, which can then be applied to other correlation sets by selecting the layout from the list.

To view the layouts available in the project, right-click on the **Borehole Correlation** folder in the project tree and select **Layout Manager**. In the window that appears, you can easily see what columns are used for each layout and apply a layout to all correlation sets in a project:

2 Column Layouts	×
Layouts	Columns in selected layout
Demo Template Fe_Logging_Reinterp	Demo_Geophysical_Data.Gamma Demo_Geophysical_Data.Density LF_Demo_Assay.Fe_new LF_Demo_Lith_Logging.Proj_Lith_Code
Import Export all	Delete Assign to all
(?)	<u>C</u> lose

You can also export column layouts for use in other projects and import layouts from other projects. Clicking **Export all** exports layouts as a text file.

Managing Styles

The styles used to display data columns can also be exported to other projects. To view the styles used in the project, right-click on the **Borehole Correlation** folder in the project tree and select **Style Manager**:

Table	Column	Label	Style	Text Colour	Edit
IF_Dem	Fe_new	default	Bars		Ø
🔢 LF_Dem	🦺 Proj_Lith	default	Intervals		0
₿ SJB_AII	🌇 SJB_AII	default	Intervals		Ø
SJB_Rei	NA SJB_Rei	default	Intervals		Ø
Fe_com	Fe_new	default	Bars		Ø
Fe_com	Fe_new	default	Bars		Ø
Demo_G	Density	default	Line, width 0.3		Ø
Demo_G	Gamma	default	Points, size 1.0		0
			lr	nport E <u>x</u>	port all

Click **Edit** to change a style, which will update objects that use the selected style throughout the project. Click **Export all** to export the styles in the project as a text file that can be imported into other projects.

Interpretation Tables

With interpretation tables, you can assign and adjust intervals and create new intervals. Interpretation tables are like any other interval table in a project and can be used to create models.


To create an interpretation table, click the **New Interpretation** button in the correlation set window. The **New Interpretation Table** window will be displayed:

EM_70	- Li	JM_083			
Depth	Proj_Lith_Code 0.0 Fe_new 75.7 0.1 by 20.0 26.3 90.0	Depth	Proj_Lith_Code	Fe_new Density Gamma	90.0
0.0 -		0.0	UBF	III 🗱 🛛 🗯 📲	
0.0 -		10.0		*	5
0.0	New Interpretation Table	0.0	EBa		Č.
0.0 -		0.0			4
0.0 -	Column to interpret	10.0 - 10.0 - 0.0 - 0.0 - 0.0 - 0.0 - 0.0 - 0.0 - 0.0 - 0.0 -			
0.0 -	Source Column: 🌇 Proj_Lith_Code 🗸 🗸	0.0			
D.O -	Initial data:	0.0	BX		Ľ.
0.0 -	○ <u>A</u> ll intervals	0.0			
	Name: Interpretation_Table	0.0			
		10.0		- 1945 - 1925 - 1926 -	

There are three options for creating an interpretation table:

- Create the table without using a base table. Each borehole will have an empty legend and a single empty interval from 0 to its maximum depth. Select **<None>** for the **Source Column**.
- Create the table from a base column but have no intervals. This copies the base column's legend but no intervals. Select the **Source Column**, then select **Empty Table**.
- Create a copy of a table. Select the Source Column, then select All Intervals.

Click **OK** to create the table. A new interpretation table will be added to the project tree under the **Boreholes** object and the column will be added to the correlation set window:




Assigning Lithologies

If you have created the interpretation table without using a base table, you will need to assign lithologies to the new table. Do this as part of working with the table in the correlation set window, which is described below.


Modifying the Interpretation Table

In the correlation set window, the blue line that appears as you mouse over the columns is used to create intervals. Position the blue line then right-click on it and select one of the options:




- The Copy from option assigns intervals from the base table.
- The Insert interval option adds an empty interval that overrides any intervals already defined.
- The **Unassign interval** option clears the lithology assigned to the interval.
- The **Assign interval** option opens the legend for the interpretation table so you can select a lithology to assign to the interval. If you need to add lithologies, you can do so in this window.


For example, to create an interval at the top of the table called "High Density", move the blue line near to where you wish to create the interval. You do not need to be precise as you can adjust the interval once you have added it. Right-click and select **Insert interval**:




In the legend window, click the **Add** button and add a lithology called "High Density":



Click **OK** to select the new lithology and close the legend window. The new lithology has been assigned to the interval:



To resize the interval, click and drag the interval end points:



You can move the interval end point and snap it to a data point in another column. To do this:

1. Click on the interval end point and drag it into position without releasing the mouse button.

- 2. Move the mouse across to the data point you wish to snap to.
- **3.** Release the mouse.

You can also snap to points along the depth axis.

Continue making changes to the interpretation table, using the **Undo** button to step backwards if necessary. Save changes to update the table.

Stereonets

Stereonets are useful for visualising structural data and identifying trends in 2D. Errors in categorisation of structural data can also become apparent when the data is viewed on a stereonet.


There are two types of stereonets available in Leapfrog Works: equatorial stereonets and polar stereonets. The process of creating a stereonet is the same for both types; you can change the type of stereonet by clicking the **Options** button in the stereonet window. Both Fisher and Bingham statistics are available for stereonets.

This topic describes how to work with stereonets in Leapfrog Works. It covers:

- <u>Creating a Stereonet</u>
- Displaying the Stereonet in the 3D Scene
- Plot Options
- Data Display Options
- <u>Viewing Stereonet Statistics</u>
- Selecting Data in the Stereonet
- Using the Scene Window With the Stereonet
- Exporting a Stereonet

Creating a Stereonet

Create a stereonet by right-clicking on the **Stereonets** folder (in the **Structural Modelling** folder) and selecting **New Stereonet**. The stereonet is created and opened in a new tab. Click the **Add** button to add any structural data table in the project to the stereonet:




You can also drag and drop structural data objects from the project tree into the stereonet.


See <u>Plot Options</u> and <u>Data Display Options</u> below for information on the different options available for stereonets.

Displaying the Stereonet in the 3D Scene

You can display the stereonet in the 3D scene by dragging the stereonet from the project tree into the scene or by clicking on the **View** button (**S**) in the stereonet window:



You can display planes and poles in the 3D scene, but not contours. In the shape list, you can control whether planes or poles are displayed in the scene:



Otherwise, the appearance of the stereonet in the 3D scene is controlled from the stereonet window. In the scene, you can:

- Resize the stereonet in the scene. Click on it and use the green arrows to resize it.
- Move the stereonet around in the scene. The controls are the same as those for the moving plane.
- Centre the stereonet on its input data. To do this, click on the stereonet in the shape list and then select from its inputs in the **Move to** list.

Plot Options


Click **Options** to change plot options:

🗠 🔡 Projects 🌖 Central Project	ts 🗊 Scene View 🛞 Ste	reonet ×	은 Alex Rock 🗸
Add 🧼 View 🖉 Plot	Bingham G Fisher		
	0°	eld_mapping_structures 184	● Structural Data ② ③ ■ 펌 Colouring ● 子 Fieldctures ② ③ ■ 펌 备 Flat colour • 》
270	Iitle: Image: Constraint of the second type: Equ Projection: © Equ Desample rate: 0.50 Axes Spacing: 10 Label interval: 45 Label offset: 1	atorial () <u>P</u> olar	Query filter: None Displayed statistics: Flat cglour: Pole size: 5.0

There are two types of stereonets available, **Equatorial** and **Polar**. You can also choose between **Equal area** (Schmidt) and **Equal angle** (Wulff) projections.


The **Desample rate** affects how quickly data is displayed by combining points with duplicate orientations, as determined by the **Desample rate** value. A low value will filter fewer data points, whereas a higher value will filter out more data. Setting the **Desample rate** to 0 plots all points, which may be slow for very large data sets that have not been declustered. The **Desample rate** applies only to how data is displayed; it does not affect the data in the table.

Note that the settings in **Edit plot options** window only apply to the current stereonet. If you want to create a stereonet "template" for your project, you can create a new stereonet with different plot options and make copies of it in the project tree:



Data Display Options


Planar structural data can be displayed as planes (\bigcirc), poles (\bigcirc) or contours (\bigcirc), using the colouring from any column in the structural data table. Lineations can be displayed as poles (\bigcirc) or contours (\bigcirc). Contour methods available are **Schmidt**, **Exponential Kamb** and **Kamb**, and contours can be displayed filled or outlined.




Click on a line or pole to view information about the data point:

The information displayed includes whether or not there are duplicates of the selected data point in the data set.


Click the mean button (\bigcirc) to view the Fisher mean on the stereonet, which is displayed as a line for planar structural data and as an X for lineations. You can also display the Bingham best-fit plane (0) and eigenvectors e1, e2 and e3:



For planar structural data, you can also display the Bingham mean plane (\bigcirc) :



A legend can be displayed for the stereonet as a whole (\blacksquare) and for the contours (\triangleq). The stereonet's legend is generated from the categories that are visible in the list of colourings. Here, the categories displayed are from the Bedding column:



You can apply query filters from those available in the project.

Declustered data can be viewed on stereonets in two ways:

- Declustered data can be viewed directly on the stereonet. Simply drag the declustered table into the stereonet.
- If the declustered data's parent data table is displayed on the stereonet, the declustered data is available as a filter.

For example, here a structural data table is displayed on a stereonet along with a declustered table. The declustered table is available as a query filter for its parent object:

۲	Structural Data	🕞 🕓 🌒 📕 🖪 Colouring	
۲	S Longfd_Bas	se 🕒 🕓 💽 📕 📰 🐣 Flat colour	- 23
٩	S Longfstele	d 🔘 ઉ 🖲 📕 🗟 Flat colour	• *
Quer	y filter:	None	~
Displ	ayed statistics.	None Support_Base_declustered None	
Flat	: <u>o</u> lour:	Longford_Base: Base	
Pole	si <u>z</u> e:	Longford_Base: Bedding2	
Line	width:	Longford_Base: Bedding3	
Cont	ours		
M	ethod:	Schmidt	~
V] <u>F</u> ill contours		

Viewing Stereonet Statistics

To view statistics on the data displayed on the stereonet, click either the **Bingham** button or the **Fisher** button:

Hadd 🧼 View 🛛 🏠 Pla	ot 💽 Bingham	G Fi	sher	Expor	t 🔽 Co	ру 🔻 👋 ጵ				
Category	Count		Value	Trend	Plunge		•	Structural Dat	a 🕒 🕓 💽 📕	
▼ 🥌 Longford_Base							۲	S Longfd_	Base 🕒 🕓 🕚	🗉 🐣 Flat colour 🔹
Whole Table	127	e1:	0.604	287.0	82.9	Mean plane	۲	S Longfste	ered 🕒 🕓 🔳	🗉 🐣 Flat colour 🝷
		e2:	0.358	99.7	7.0	Best fit great circle				
		e3:	0.037	189.8	0.9					
🔻 👰 Bedding										
Base	52	e1:	0.900	39.2	86.5	Mean plane				
		e2:	0.077	186.7	2.9	Best fit great circle				
		e3:	0.023	276.7	1.9					
Bedding1	37	e1:	0.613	277.2	23.8	Mean plane			111	
		e2:	0.387	97.6	66.2	Best fit great circle	Ou	ery filter:	None	~
		e3:	0.000	7.3	0.1					
Bedding2	26	e1:	0.633	107.0	12.5	Mean plane	Dis	played statistics:		
		e2:	0.367	287.0	77.5	Best fit great circl∈ ≡				J
		e3:	0.000	197.0	0.0		Flat	c <u>o</u> lour:		
Bedding3	12	e1:	0.828	270.6	31.6	Mean plane	Pol	e size:	5.0 🗘	
		e2:	0.160	104.2	57.6	Best fit great circle		-		

You can select specific rows and copy them to the clipboard or copy all data to the clipboard.

Selecting Data in the Stereonet

You can select data in the stereonet and assign it to new categories or existing ones. To do this, click on the data table in the stereonet window and select **New selection** from the colouring list:

✓					\triangle Alex Rock \vee
🕂 Add 🧼 View 🛛 💽 Plot 💽 Bingham 👩 Fisher 🛛 👔 Export	💥 Options 🛛 💢				
	Longford Base 127	۲	Structural Data	6 3 3) 📕 🗐 Colouring
gford_Ba- se (%)	Flat colour: 127	۲	😸 Longfd_Ba	se 🕒 🕓 🔇) 📕 🗐 👶 Flat colour 🔹 💥
					🐣 Flat colour
17.5					換 Bedding
0°					New selection
U					
- 15.0	150				
315°	45			111	
		Que	ery filter:	None	~

The New Category Selection window will appear:

😢 New	Category S	election	×
Copy ca	tegories fr	om	
<u>S</u> ourc	e Column:	<none></none>	~
<u>N</u> ame:	Selection		
	Help		<


The poles will be displayed in the stereonet, if they are not already visible, and the data table will also be added to the scene window, together with tools for selecting points in the scene.

Organising the stereonet tab and the Scene View tab so they are displayed side-by-side can be

useful in working with the data as you can select data in the stereonet or in the scene window. This is described further in <u>Using the Scene Window With the Stereonet</u> below.

If you select an existing column as the **Source Column**, you can assign selected points to the existing categories or create new categories. If you select **<None>** for the **Source Column**, you will have to define each category manually.

When you click **OK**, a set of tools for selecting data will be added to the stereonet window:




There are two tools for selecting data in the stereonet, the polygon tool (4) and the bullseye (6) tool.

- Use the polygon tool (4) to draw around the points you wish to select. Closing the polygon will select the points, and you can click on the vertices to refine the shape of the selection. Click outside of the selection to clear the polygon.
- Use the bullseye tool (🏐) to:
 - Click on points one-by-one.
 - Click and drag around points.

The **Add** button (^{**F**}) and the **Remove** button (^{**F**}) determine whether selected points are being added to or removed from the selection. For example, if you draw a polygon around a set of points with the **Add** button enabled, the points will be added to the selection.


You can also:

- Remove points from a selection while the **Add** button (^{fig}) is enabled by holding down the Ctrl key and selecting points.
- Select all visible points by clicking on the **Select All** button (2/2) or by pressing Ctrl+A.
- Clear all selected points by clicking on the **Clear Selection** button (⁴/₆) or by pressing Ctrl+Shift+A.
- Swap the selected points for the unselected points by clicking on the **Invert Selection** button (I) or by pressing Ctrl+I.
- Show or hide all unassigned points using the **Unspecified Measurements** button (H).




Statistics are shown for the currently selected set of points:


You can choose what type of statistics to display for selected points:



Once you have selected a set of points, click the **Assign to** button in the stereonet window, then select **Create New Category**. In the window that appears, enter a name for the category and assign a colour:



Click **OK**. The new category will be created and the stereonet will be updated to reflect the changes:




The scene window will also be updated.

Once you have created a new category, you can add to it by selecting further points, then selecting the category from the **Assign to** list.

When you are finished, click the **Save** button (\square) and close the category editor. You can make further edits by clicking the **Edit** button ($oldsymbol{?}$) in the stereonet window.

Using the Scene Window With the Stereonet

You can also select points in the scene window by clicking on the **Select points** tool (**I**), then drawing over those points in the scene:



Controls for assigning points to categories will remain in the stereonet window, and both the stereonet window and the scene window will be updated to reflect the selected and assigned points.

Exporting a Stereonet

Stereonets can be exported in the following formats:

- PDF Files (*.pdf)
- Scalable Vector Graphics Files (*.svg)
- PNG Image Files (*.png)

Click the **Export** button. Select a format and navigate to the folder where you wish to save the file. Enter a name and click **Save**.

Form Interpolants

A form interpolant is an RBF interpolant that uses planar structural data to control the RBF gradient. The RBF gradient resembles the geology orientation, which makes form interpolants useful for visualising structural data and identifying broad trends in 3D. The form interpolant's meshes can then be used to control other surfaces in the project.


This topic describes how to work with form interpolants in Leapfrog Works. It covers:

- Creating a Form Interpolant
- The Form Interpolant in the Project Tree
- Form Interpolant Statistics

Once a form interpolant has been created, experiment with different **Distance** values. To do this, double-click on the interpolant in the project tree and click on the **Outputs** tab.

Creating a Form Interpolant

To create a form interpolant, right-click on the **Form Interpolants** folder (in the **Structural Modelling** folder) and select **New Form Interpolant**. In the window that appears, click the **Add** button to add structural data tables to the interpolant:



Data can be filtered using the query filters defined for the selected structural data tables:

nputs	Boundary	Trend	Outp	uts			
Struc	tural Data	Query I	Filter	Use	Polarity	Boun	dary filter
SB	ase_of_Lo	None	T		✓		
		None	h	Ì			
		Base					
		Beddin	ig1				
		Beddin	ig2				
		Beddin	ig3				
	<u>A</u> dd	<u> </u>	move]			

Once you have created the interpolant, you can easily add and remove structural data tables and change the filtering.

When generating the form interpolant, you can use the tangents and polarity or only the tangents. To use both, leave the **Use Polarity** box ticked. To use only the tangents, untick the box.

The **Boundary filter** setting determines how data is handled when it lies outside the interpolant's boundary:

- **Boundary filter** enabled. The interpolant is only influenced by the data that falls inside the boundary.
- **Boundary filter** disabled. The interpolant is influenced by the data both inside and outside the boundary.

Setting a Trend

In the **Trend** tab, you can set a trend using the moving plane or by entering the required values. You can also use the **Set to** list to choose different options used in the project. **Isotropic** is the default option used when the function is created.

The Ellipsoid Ratios determine the relative shape and strength of the ellipsoids in the scene, where:

- The Maximum value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The **Minimum** value is the relative strength in the direction orthogonal to the plane.


Adding Isosurfaces

The isosurfaces generated for the form interpolant are determined by the settings in the **Outputs** tab. If you wish to add more isosurfaces to the interpolant, click the **Add** button and enter the required **Iso Value**. Click on an isosurface and then on the **Remove** button to delete it.

The **Default resolution** setting is used for all new isosurfaces.

The Form Interpolant in the Project Tree

In the project tree, the form interpolant contains objects that represent different parts of the interpolant:




- The Extents object represents the interpolant's boundary settings, from the Boundary tab.
- The **Trend** object describes the trend applied in the interpolant. See <u>Global Trends</u> for more information.

- The structural data object (*s*) contains a link to the data used in generating the interpolant. See Form Interpolant Statistics for more information.
- The **Isosurfaces** folder contains the isosurfaces defined in the **Outputs** tab.

To display the form interpolant:

- Drag the interpolant into the scene.
- Right-click on the interpolant and select View Isosurfaces.



Form Interpolant Statistics

To view information about the data used for the form interpolant, right-click on the structural data object (*s*) under the interpolant and select **Properties**. The **General** tab includes information about how the data has been declustered:

6	🎖 Properties - Form Interpolant Structural Data 🛛 🚽 🗌	×
	General Processing Errors Merged structural data from: Base, of Longford Frm x, section(Query filter: None): 127 points	
	Total merged structural data points: 125 Duplicate structural data points: 126 Adjacent structural data points ignored: 2	
	Note: Duplicate and adjacent points are those structural data points where the separation distance is less than the maximum length of the data bounding box scaled by 1-e8 and 1e-3 respectively. For each group of duplicate or adjacent points, if the normals are identical then the first point is chosen and the remainder ignored, else if the variance between normals for each group of duplicate or adjacent points is less than 1e-3 then the point closest to the mean is selected and the remainder ignored otherwise all points in that group are ignored.	

You cannot change how data is declustered in the form interpolant, but if you wish to have more control over this, create a declustered structural data set and use it as the input for the form interpolant. See <u>Declustering Planar Structural Data</u> for more information.


Planning Boreholes

In Leapfrog Works, planned boreholes are organised into borehole groups. You can evaluate models onto the borehole group and view drilling prognoses for all boreholes in the group.

Planned borehole groups were introduced in Leapfrog Works 2.1. When a project from an earlier version is opened in Leapfrog Works 2.1, all existing planned boreholes will automatically be assigned to groups, based on the phases of each borehole.

If necessary, you can move planned boreholes between groups by opening both groups, then dragging boreholes between the groups. This copies boreholes from group to group, so once copied, you will need to delete the planned borehole from the group it does not belong to.

Planned boreholes are added to a project from a borehole group, and these are stored in the **Planned Boreholes** folder. When displayed in the scene, the planned borehole is made up of a collar point, a target location and a path defined by lift and drift parameters:



The rest of this topic is divided into:

- Adding Planned Boreholes
- Planning Options
- Drilling Prognoses
- Exporting Planned Boreholes
- Importing Planned Boreholes

Adding Planned Boreholes

To plan a borehole, first add the data objects to the scene that you will use in helping to define the borehole, such as the topography and any existing boreholes. Next, right click on the **Planned Boreholes** folder and select **New Borehole Group**. In the window that appears, you can define basic information about the group, including the **Prefix** used for each borehole added to the group:

	Edit	Borehole		Total Depth	-
					=
	Add	Borehole	Prefix:	LAFN	-
	Add) –	LAIN	
-	<u>R</u> emo	ove Selected	J		

Start defining boreholes by clicking the **Add Borehole** button.

anned be	oreholes:			😤 Borehole Plan	ining			
∎> Edit	Borehole	Total Depth	-	Specify:	● Colla <u>r</u> ○ T	arget		
				Collar	1200000	4000000		
				Location:		, 4900000	, 1400	B
				Dip:	90.00	Azimuth:	0.00	
				Target				
				Location:	1200000	, 4900000	, 700	
			=	Dip:	90.00	Azimuth: 0	00 \$	
				Path				
					700.00			
		/		Dep <u>t</u> h:				
				End of hole is:	: [0.00	units past tai	get	
				Description				
				Commen <u>t</u> s:				
Add I	Borehole Prefix:	LAFN		Name:	LAFN001			
-			• 		[=			
<u> </u>	ove Selected			Slice along	Borehole	Move Collar or	to the Topography	🔶 Ne <u>w</u> Ho
ame: [l	AFN							
			Edit Co	ld Help	Defa <u>u</u> lts		💥 <u>C</u> ancel	€ <mark>0</mark> к
			OK -					

You can change whether **Collar** or **Target** is selected when this window is opened by clicking on the **Defaults** button. See <u>Planning Options</u> below.

A name is automatically generated for the new planned borehole based on the **Prefix** defined for the group.

There are three ways to define the borehole collar or target:

Click in the scene to set the collar or target location. First, click on the Select button () for the Collar or Target, then click in the scene to define the Collar or Target. The borehole will appear in

the scene and you can adjust the coordinates using the controls in the **Borehole Planning** window. Click the **Slice along borehole** button to draw a slice in the scene. This is useful in adjusting the borehole path and in defining subsequent boreholes.

- Draw the borehole in the scene. Click on the **Select** button () for the **Collar** or **Target**, then click and drag in the scene to define a basic path for the borehole. If you are defining the borehole from the collar down, click first on or near the topography. Likewise, if you are defining the borehole from the target up, click first at or near the target point.
- Enter the coordinates for the Collar or the Target in the Borehole Planning window.


Clicking the **Move Collar onto the Topography** button adjusts the elevation of the borehole so that it lies on the topography.

Click the **Next Hole** button to create another planned borehole. The new planned borehole will be created at a specific distance from the currently displayed planned borehole using the **Path** settings for the currently displayed borehole and the **Offset To Next Hole** settings in the **Borehole Planning Options** window. See <u>Planning Options</u> below.

Once you have specified the collar or target, adjust the borehole path:

- Lift is how much the borehole deviates upward.
- **Drift** is how much the borehole deviates laterally.
- Leapfrog Works automatically calculates the **Depth** value when the borehole is defined by the **Target** location.
- Adding an End of hole length extends the borehole past the Target location.

Once you have finished defining planned boreholes, click **OK** to return to the **Borehole Group** window.



You can change the automatically generated name by clicking on the borehole in the list and editing the text.

Search for planned boreholes in the list by pressing Ctrl-F. A **Find** window will appear that you can use to search the list.

Click the **Edit** button (\mathcal{O}) to change the settings for a planned borehole, or click **OK** to save the group.

Any model in project can be evaluated on a borehole group, and evaluations can be exported when the group is exported as interval tables. See <u>Exporting Planned Boreholes</u> below. Right-click on the group in the project tree and select **Evaluations**. The **Sample Distance** setting applies to numeric evaluations and determines the spacing between downhole evaluation points.

You can also define filters for a borehole group. A filter makes it easier to select a subset of the borehole when the group is displayed in the scene. To define a filter, right-click on the group and select **New Filter**. Select which boreholes to include in the filter and enter a name for it. The filter will be saved in the project tree as part of the group.

Display planned borehole by dragging the group into the scene. Hide boreholes in the scene using any defined filters or by opening the group and using the show/hide button (@).

You can copy planned boreholes between groups by opening both groups, then dragging boreholes between the groups. For example, here the boreholes selected in the first group are being copied into the second group:

🔮 Boreho	le Group - LAFN	>	<				3 B	oreho	le Group - LAOA		×
Planned b	oreholes:						Plan	ned b	oreholes:		
👁 Edit	Borehole	Total Depth					۲	Edit	Borehole	Total Depth	-
• /	LAFN001	110									
• /	LAFN002	107									
• 🤌	LAFN003	122				Elev (Z)					
• /	LAFN004	122		_							
• 🦯	LAFN005	122		۲	1	LAFN007		1	00 F		
• /	LAFN006	122									
• /	LAFN007	100				1010					
•	LAFN008	80									=
•	LAFN009	80				+0					
•	LAFN010	110				10					
• /	LAFN011	110									
		*			<u>_</u>	-0.5 0 -1					4
	ove Selected	LAFN					2	Remo	Borehole Pre	fix: LAFN	
<u>N</u> ame: L	lAFN	<u>∦ C</u> ancel <u>€ QK</u>					<u>N</u> am	ie: [l	AOA Ip	Cancel	<u>2</u> K

This copies boreholes from group to group, rather than moving them, so once copied, you will need to delete the planned borehole from the group it does not belong to.

Planning Options

Borehole planning options are set on a per-project basis. To change borehole planning options, rightclick on the **Planned Boreholes** folder or on a borehole group and select **Edit Planned Boreholes Defaults**. The **Borehole Planning Options** window will appear:

😰 Borehole Planning Options 🛛 🗙 🗙
Default Planning Mode
Specify: Collar Target
Default Extension
End of hole is: 0.0 🗘 units past target
Offset To Next Hole
Distance: 10 2 Azimuth 0.00 2

Select whether new planned boreholes are specified by the **Collar** or by the **Target**.

The **Offset To Next Hole** values apply when defining multiple boreholes in the **Borehole Planning** window.

Enter the information required and click **OK**. The new settings will be applied to the next new planned borehole added to the project.

Drilling Prognoses

Planned boreholes can be evaluated against any model in the project. To view drilling prognoses for a borehole, right-click on a borehole group in the project tree and select **Drilling Prognoses**. The **Drilling Prognoses** tab will appear:

• 🔟 C	Drilling Pro	gnoses:	LAFN ×	
<u>V</u> iew prog	gnosis for:	🖰 Me	rged Intervals	
Name	From	То	Lake Aura GM	Tunnel
LAFN001	0.0	56.515	Alluvial Gravel	
LAFN001	56.515	110.0	Schist	
LAFN002	0.0	53.352	Alluvial Gravel	Unknowr
LAFN002	53.352	107.0	Schist	Unknown
LAFN003	0.0	48.749	Water	Unknowr
LAFN003	48.749	79.285	Alluvial Gravel	Unknowr
LAFN003	79.285	122.0	Schist	Unknowr
LAFN004	0.0	48.427	Water	Unknowr
LAFN004	48.427	50.836	Clay	Unknowr
LAFN004	50.836	57.902	Silt	Unknowr
LAFN004	57.902	71.696	Sandy Gravel	Unknowr
LAFN004	71.696	122.0	Schist	Unknowr

The dropdown list contains all evaluations on the borehole group, along with a **Merged Intervals** option that combines the information from all evaluations. You can copy the information displayed to your computer's clipboard by selecting rows, then clicking the **Copy** button (^b). The information in the selected rows will be copied as tab delimited text, which can be copied into a spreadsheet application such as Excel.

Exporting Planned Boreholes

There are two ways to export planned boreholes: export their parameters or export interval tables that contain the boreholes.

Export Parameters

Exporting planned borehole parameters exports the boreholes as a *.csv file. To export parameters for planned boreholes, right-click on a borehole group and select **Export Parameters**. In the window that appears, select the boreholes you want to export. The total length will be updated as you add or remove boreholes.

In Leapfrog Works, positive dip points down for planned boreholes. To invert the dip for exported planned boreholes so that negative dip points down, tick the box for **Invert dip on export**.

Click Export. Navigate to where you wish to save the file, then click Save.

Export as Interval Table

To export planned boreholes as an interval table, right-click on a borehole group and select **Export as Interval Table**. Select the evaluations you wish to include, then click **Export**. In the **Export Planned Boreholes** window, the files that will be created are listed, one each for the collar and survey table and one for each selected evaluation. Change the **Base file name**, if required, choose a folder in which to save the files, then click **Export** to save the files.

Importing Planned Boreholes

Leapfrog Works imports planned boreholes from files in CSV format. The columns expected are:

- A borehole identifier
- X-Y-Z coordinates for the planned borehole
- Azimuth
- Dip
- Lift rate
- Drift rate
- Distance
- Extension
- Target Depth
- Comment

When importing planned boreholes, you can import them into a new group or into an existing group. To import planned boreholes, right-click on the **Planned Boreholes** folder or on a group and select **Import Planned Boreholes**. If the IDs in the file are already in the project, you will be prompted to resolve the conflict:

😵 Resolve Naming Conflict - M	×
Names within the imported dat	a are already used. Do you wish to:
	re there is existing data with the same name
O Replace existing data with in	dentically named data being imported
Help	Cancel

You can:

- Rename the imported boreholes. Leapfrog Works will automatically assign new names and import the planned boreholes.
- Exclude planned boreholes that already exist in the project. Planned boreholes will only be imported if they have an identifier that does not already exist in the project.
- Replace existing planned boreholes with the imported boreholes. Use this option if you are importing information previously exported from the project and subsequently updated in an external application.

Click **OK** to process the file.

If there are no conflicts, the planned boreholes will be added to the project.

Calculations and Filters

Calculations and Filters uses data and estimators to derive new values, resource classifications and more. A powerful and versatile tool, it offers a simple and intuitive editor so you do not need to be an expert programmer to make use of its pure functional language to define calculations. Even complex calculations can be developed with ease.

The rest of this topic describes:

- Defining Calculations and Filters for drilling data tables, imported points and some derived points.
- A <u>Catalogue of Metadata, Syntax and Functions</u>. It describes each of the items in the pinnable **Insert** list and includes intentionally trivial examples to illustrate the use of the item, along with an explanation of the effect of the expression.

Defining Calculations and Filters

Some aspects of this feature may be illustrated using examples including block models. Block models are a feature that requires the Contaminant extension in Leapfrog Works. What is described for points objects can also be applied to block models if you have the Contaminants extension.

This topic describes how to define calculations and filters for drilling data tables, imported points and some derived points. It is divided into:

- The Calculations Window
- Creating a New Calculation or Filter
- Understanding Errors Reported in the Errors Pane
- Building Calculations and Filters
- Null Values

The topic that follows, <u>Catalogue of Metadata</u>, <u>Syntax and Functions</u>, details each of the items in the pinnable **Insert** list and includes intentionally trivial examples to illustrate the use of the item, along with an explanation of the effect of the expression.

A printable guide is available that contains this topic and the <u>Catalogue of Metadata</u>, <u>Syntax and</u> <u>Functions</u> topic. The guide is a useful reference to help you get started with the **Calculations and Filters** editor. To download this guide, click <u>here</u>.

The Calculations Window

Right-click on a drilling data table to find the **Calculations** option or on a points table to find the **Calculations and Filters** option.

\sim		Poin	ts			
	~ 1	i s	el	ected_Earthquakes		
				mag_scaled		<u>O</u> pen
			•	magnitude	0	-
			:	time	Q	New Query Filter
	C -1	Poly		es	A	New Category Selection
				vsical Data		Calculations an <u>d</u> Filters
						Eval <u>u</u> ations
>				ral Modelling	Σ_{0}	Statistics
>		Mest				Import Column
		Geol	Dg	ical Models	\oplus	Append Data
		Estin	na	tion	0	<u>R</u> eload Data
		Num	er	ic Models		Set Elevation
		Com	bi	ned Models	8	Estimate Structural Data
		Block	¢1	lodels	~	View Object
>		Save	d	Scenes and Movies		<u>C</u> opy
		Cros	s	Sections and Contou	\uparrow	P <u>r</u> ioritise
		Colo	ur	Gradients	())	Free <u>z</u> e
		Note	s			Rename F2
					Ŵ	Delete Del
					₽	Export
						Export Errors
					Y	Properties
					_	- ·

The **Calculations and Filters** option is not available for all points tables.

When the **Calculations** window is first opened, the **Insert** list is pinned to the right-hand side. You can untick the **Pin Window** box to get more screen space.

Calculations: Selected_Ea ×		
* 🕯 🛨 < 🖌 🖑 👘 🕼 🖉 🕷	≥ < " □ <u> →</u>	
Variables [empty]	Click on either list below to insert that item Existing items:	Syntax and functions:
Calculations [empty] Filters [empty]	METADATA id Row ID 1 to 1.867e+05 x Location X 6.794e+05 to 2.385e+06 y Location Y 4.177e+06 to 6.484e+06 z Location Z -7.5e+05 to 0 IMPORTED mag_scaled 0.01029 to 61.16 magnitude 0.1014 to 7.82 time 1 to 1.926e+05	 ✓ Statements () Brackets if(::) If block ✓ Basic Operators + Add - Subtract * Multiply / Divide
No Errors		% Modulo ^ Power and Logical and or Logical or not Logical not = Equal != Not equal <

You can then select items by clicking on the **Insert** menu.

Calculations: Selected_E ×	_			
* 🕏 🕹 🐟 🕪 👉 🔓 🖪	isert 👔 il 🗄 il 🔄 🥱 🧬	≞ ⊇ ?		
	Click on e ither list below to i		Pi <u>n</u> window	
	Existing items:		Syntax and functions:	
(X) variable \checkmark = pi	METADATA		>= Greater or equal	59265358
	id Row ID	1 to 1.867e+05	✓ Complex Comparisons	
Calculations	x Location X	6.794e+05 to 2.385e+06	lower < n < upper	
[empty]	y Location Y	4.177e+06 to 6.484e+06	Lower <= n < upper	
Filters	z Location Z	-7.5e+05 to 0	lower < n <= upper	
[empty]	IMPORTED	0.01000 to 61.16	lower <= n <= upper	
	mag_scaled magnitude	0.01029 to 61.16 0.1014 to 7.82	x in {a, b,}	
	time	1 to 1.926e+05	x not in { <i>a</i> , <i>b</i> ,}	
	VARIABLES	1101.5200.00	✓ Invalid Values	
No Errors	(x) variable		blank	
			error	
			error('message')	
			is_normal(<i>a</i>)	
			is_blank(<i>a</i>)	
			✓ Mathematics	
			pi Constant	
			e Constant	
			log(n) Base 10	
			log(n. base)	

Items in this list are divided into **Existing items** and **Syntax and functions**. **Existing items** include handy metadata items you can use immediately, e.g. row ID and point location coordinates. It also includes evaluations that can be selected, such as estimators. **Syntax and functions** contains mathematical operators and other calculation elements, along with special values such as 'blank' and 'error' and pre-made functions such as unit conversions and log(n).

If the **Calculations** window is docked as a tab, you can tear the tab off to form a stand-alone window. You might do this when arranging your windows so you can see the **Calculations** window at the same time as the scene. The detached window can be docked again by dragging the tab back alongside the other tabs, as described in <u>Organising Your Workspace</u>.

The toolbar in the **Calculations** window has three buttons that relate to copying, importing and exporting calculations and filters between points objects and projects:



To copy calculations and filters from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems for another **object** button (<a>style="text-align: center;">systems from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems from another points object, click the **Copy items from another object** button (<a>style="text-align: center;">systems for align: <a>style="text-align: center;">syste

To export calculations and filters, click the **Export** button (⊉). You will be prompted for a file name and location. The information is saved in *.Ifcalc format, which is a binary file format. This format cannot be read or written by any other program.

To import calculations, click on the **Import** button (\checkmark) and select a calculations file to import.

The arrow buttons allow you to quickly expand (\checkmark) or collapse (\land) all calculations and filters. You can also individually expand or collapse a calculation or filter by clicking on the = symbol next to the calculation or filter name.

Cut (*), **Copy** (*) and **Paste** (*) buttons provide basic text operations on selected parts of equations.

Undo (>) and **Redo** (<) buttons provide the ability to move back and forward in the edit history for your equations.

Creating a New Calculation or Filter

Click the **New Item** button to add a calculation to the **Calculations** window.



The **New Item** windows gives you the choice of creating a variable, a numeric calculation, a category calculation, or a filter. Select one of these options, enter a name for the new item and click **OK**.

The item will appear in the list on the left-hand side of the **Calculations** window.

Variables	Click on either list below to insert that item				
	Existing items:				
(x) variable v =	METADATA				
Calculations	id Row ID	1 to 1.867e+05			
	x Location X 6.794	e+05 to 2.385e+06			
[empty]	y Location Y 4.1776	e+06 to 6.484e+06			
Filters	z Location Z	-7.5e+05 to 0			
[empty]	IMPORTED				
fembral	mag_scaled	0.01029 to 61.16			

If you want to delete an item, click on it in the list, then select **Delete**:

	(x) variable \checkmark	=
Ci	Collapse Collapse Add Comment Insert Name at Cursor	
Fi	Rename	
1	Move to Top	1011
x	 ✓ Move Do<u>w</u>n ✓ Move to <u>B</u>ottom 	is blank.

Variables

A **Variable** is an expression that is given a name to make it simple to refer to the expression in other parts of the **Calculations** window. Note that 'variable' is a homonym/homograph that in a different context has a different meaning; 'variable' is at times used to refer to a mineral such as gold or silver. In the context of calculations and filters, the meaning is aligned with the use of the word in mathematics and scripting languages.

Using a variable in calculations can make the calculations easier to read and understand. It also makes it simple to reuse an expression multiple times in different places. Any time you find the same expression appearing in different calculations, or in different parts of a calculation, split that expression out into a variable. You can even use a variable to represent a constant value, such as a particular density measure. You can use it to hold a value you want to change as you experiment. If the value is used in multiple places in other expressions and calculations, using a variable in those places means you only need to change the value in one place instead of many.

Numeric Calculations

A **Numeric calculation** is an expression that evaluates to a number, or a number for each point evaluation used as input. A numeric calculation can be viewed in the 3D scene as a points object.

Category Calculations

A **Category calculation** is an expression that evaluates to text, usually used to label a category or classification such as a lithology or grade description. If a points object is used as input, each point will be assigned a text label to categorise it according to the evaluation value. A category calculation can be viewed in the 3D scene as a points object.

Filters

A **Filter** is an expression that limits the data to specified constraints. When viewing a points object in the scene view, filters can be selected in the properties panel's **Query filter** option to constrain which points are displayed.

Understanding Errors Reported in the Errors Pane


Items in the **Existing items** list or in the **Syntax and functions** list can be selected and added to the **Calculations** pane. While a calculation or filter is incomplete, the **Error** pane will identify what is needed to make the calculation valid.

The errors pane will report when the syntax of an expression cannot be validly interpreted. It cannot report when the expression is not correctly structured to do what was intended.

While you are in the process of constructing an expression, errors will be reported when the incomplete expression cannot be validly interpreted:

Variables	
(x) variable \vee =	
1 error	
(x) variable (1)	
(x) variable (1) () Syntax Error: Expression is blank.	

The messages provide the reason the expression is not valid or complete, but it cannot tell you how to complete or correct the equation.



Other errors will be displayed when the type of result doesn't match the sort of calculation selected when it was created. A numeric calculation needs to produce numbers, a category calculation needs to produce text results, and filters need to produce true or false (boolean) results.

Calculations	
👬 number 🗸	= [time] > 0
	3000
1 error	
number (1)	
() Error: Expression type	boolean' doesn't match calculation type 'number'.

Text needs to be identified by enclosing it with quotation marks, so it is not mistaken by the calculation engine as some sort of unspecified constant.

Calculations	
category	Bedrock
1 error	
tategory (1)	onstant with name 'Bedrock'.
() Reference Error: No o	onstant with name 'Bedrock'.

A processing error indicates a problem executing part of the calculation for at least one of the points. The function may be syntactically correct, but the calculation cannot be performed for one or more points for some other reason. In the example below, **number** will not be able to be calculated if magnitude is ever below 3, as that will result in a divide by zero error. Because magnitude ranges from about 0.1 upwards, this does indeed cause a processing error. Not all processing errors will be divide by zero errors. The list of problems that will be reported as processing errors includes:

- divide by zero
- log of zero or a negative number
- log base of 1
- raising a negative number to a fractional power
- sqrt of a negative number
- numeric overflow, producing a number outside the range -1e308 to 1e308
- a null value (blank, outside, without_value) in a set
- multiple instances of the same value in a set
- referencing a column that has been deleted
- referencing a column that contains processing errors

Some processing errors will report that the problem is due to 'above errors', referring to errors higher in the errors list.

Processing errors will include a count of the number of affected blocks. Note that processing errors will only show up in the error list once processing has completed. You may need to unpause process execution and **Run All** processes.

Calculations	
🚺 number 🗸 🗸	<pre>= 1 / floor([magnitude] / 3)</pre>
	10000
1 error	
number (1)	n by zero . On 163,171 of 186,690 rows.

You may have more than one error shown. As a rule of thumb, address the errors at the top first, as this corrective action may address the subsequent error.

$i_{0}^{*} \text{ category } \vee = \text{ if } \left(\begin{array}{c} [id] > 10000 \rightarrow [[x]] \\ \text{ otherwise } \\ [y] \end{array} \right)$
l errors
category (2)
① Error: Expression type 'number' doesn't match calculation type 'text'. Processing Error: The equation cannot be executed due to the above errors.

Building Calculations and Filters


Items in the **Existing items** list or in the **Syntax and functions** list can be selected and added to the **Calculations** pane. Wherever a dotted box appears in the **Calculations** pane, you can add items and operators. Select an insertion point by clicking the dotted box where the item is required. You will see that the colour of the dotted box turns from black to orange to indicate that it is the currently selected entry box. Insert an item from one of the lists by clicking on it.

Variables	Click on either list below to in	nsert that item		Pin window
	Existing items:		Syntax and function	ons:
(x) variable \checkmark = if	METADATA		✓ Statements	
(x) variable • - II otherwise	id Row ID	1 to 1.867e+05	()	Brackets
	x Location X	6.794e+05 to 2.385e+06	if(::)	If block
Calculations	y Location Y	4.177e+06 to 6.484e+06	✓ Basic Operat	ors
[empty]	z Location Z	-7.5e+05 to 0	+	Add
	IMPORTED	0.01020 to 61.16		Subtract
Filters	mag_scaled magnitude	0.01029 to 61.16 0.1014 to 7.82		Multiply
[empty]	time	1 to 1.926e+05	/	Divide
	VARIABLES	1101.9200+05	%	Modulo
	(x) variable		^	Power
	(*) ******		and	Logical and
			or	Logical or
			not	Logical not
100000			-	Equal
1 error			1 =	Not equal
(x) variable (1)			<	Less than
() Syntax Error: If statement is empty.			<=	Less or equal


Select additional operators, constants, evaluations or other items as required, or type in values.



Some items you insert include placeholders that need to be replaced. For example, here, a value needs to be entered at the cursor position and the terms 'lower' and 'upper' need to be replaced with other items.




The if (::) conditional statement can have additional rows added to it. Insert the cursor where you want to insert a row and then click the **Add Row** button (¹/₁) and a row will be added above the selected line.



You can hold the Shift key to add the row below the cursor. To delete the selected row, click the **Delete Row** button (¹⁶).

A calculation or filter can be renamed after it has been created. Click on its name and select **Rename** from the menu that appears:



Examples of Variables

Variables can produce numeric, boolean, or text results. You may create a variable because using a variable in other expressions can make them easier to read and understand, or it can let you change a value in just one place, even though it is used in many expressions.


Variables				
(x) lower-threshold	~	=	4.5	= 4.5
(x) bedrock	\sim	=	"Bedrock"	= 'Bedrock'
(x) filter	\sim	=	[magnitude] > [lower-three	shold]

While producing results similar to numeric calculations, category calculations or filters, variables cannot be viewed on the block model in the 3D scene.

Example of a Numeric Calculation

Numeric calculations must produce numeric results, or an error will be reported.

Calculations



The results of the numeric calculation for the points object can be viewed in the 3D scene by rightclicking on the numeric calculation entry in the project tree and selecting **View Object**.

\checkmark \square Points	
✓ ₿ Selected_Ear	thquakes
mag_sca	aled
magnitu	de
time	
CALCULATION	IS
value	
Polylines	Edit Equation
Geophysical D	View Object
> 🗋 Structural Moc	Σ_{σ} Statistics
> 🗋 Meshes	Rename F2
Geological Mo	Delete Del
Estimation	<u>⊢</u> Export
D Numeric Mode	Colours >
Combined Mo	Properties
Block Models	

Example of a Filter

In this example, one of the selectors from the **Complex Comparisons** options was chosen from the insert list. The value that will be tested is to be added at the insertion point between the comparators, and the placeholder words 'lower' and 'upper' need to be replaced with constants.

Filters		
🖓 historic 🗸 🗸	=	<u>lower</u> <= <u><</u> = upper

Here the numeric column [time] has been specified as the value that will be tested, and lower and upper limits have been specified.



When you select **View Object** for the filter in the project tree, the **Query filter** is set to the selected filter in the shape properties panel.

 Topographies GiS Data, Maps and Photos Drillhole Data Designs Points "" Beketed_Earthquakes " mag.scaled " magnitude " time CALCULATIONS " value " phase RLTERS 	
Contemporary	💿 🥔 Topography X 👌 Fla 🗸 🗖 🖉 📰 🛑 🕨 🎲 Selected_Earthquakes
Polylines	Slice mode: From Scene
Geophysical Data	💿 🎼 Selected_Earthquakes 🛛 🗶 🏥 ma 🗸 🚺 magnitude 🗸 💶 🔐 🔐 👘 🚛 🖓 Query filter: 🖓 historic 🗸
Structural Modelling	💿 💮 Wadati-Benioff zone X 🗞 Fla V 🔳 💷 🕨 🕨 🕼 🏷 🛛 🗹 Value filter: 1.56 🗘 - 2.57 🗘
> D Meshes	©
Geological Models	Radius values: Fixed Radius 🗸 🏠

Example of a Category Calculation

This example uses a category calculation to organise events into quarters for the year 2014 using the if (::) conditional statement.

The if(::) conditional statement contains two lines by default. Note the guiding cues within the dotted entry boxes. The first line describes the test to be performed that, if it evaluates as true, will produce a specified result. The 'otherwise' condition on the second line captures all the tested conditions that did not evaluate as true in the test on the first line, and these all produce an alternate result:





In this case, all the values outside of the range of the filtering expression [Year] = 2014 are outside the period of interest. We add the expression as the 'test' condition, and specify the label "2014" as the first result, and use the label "Not Considered" in the bottom line for the 'otherwise' condition. So the labels are not mistaken by the calculation engine as some sort of unspecified constant, make sure labels are identified using quotation marks:



We need to extend this trivial example for organise the period into quarters, and to do this we can nest if (::) conditional statements. Replace the "2014" label with a new if(::) item:



Now if values pass the filter in the first test, they then get to be sorted using the second if(::) block. This time we will test the month field and if it is less than or equal to 3 we will classify this as "Q1":




Shift-click the **Add Row** button (⁽⁾), and a new conditional row is added below the current one, where we can specify that a Month value less than or equal to 6 will be classified as "Q2". Only values between 4 and 6 will be classified as "Q2" as the first line will have already classified all the values under 4 as "Q1".

Repeat to add another row specifying a Month value less than or equal to 9 to be classified as "Q3".

This leaves the 'otherwise' row in the nested if(::) block to catch values above 9 which are labelled "Q4":



The new 2014_quarter calculation we have constructed can be added to the scene view. Click the **Edit Colours** button in the shape list to select which categories are visible.



Null Values

Leapfrog Works can differentiate between different types of invalid or null values, which are shown in the **Calculations** window:

lick on either	r list below to in	nsert that item		✓ Pi <u>n</u> windo
xisting items:			Synt	tax and functions:
METADATA			\geq	Statements
id	Row ID	1 to 1.867e+05	>	Basic Operators
x	Location X	6.794e+05 to 2.385e+06	>	Complex Comparisons
у	Location Y	4.177e+06 to 6.484e+06	\sim	Invalid Values
z	Location Z	-7.5e+05 to 0	L	blank
IMPORTED				error
mag_s	caled	0.01029 to 61.16		error('message')
📑 magnit	tude	0.1014 to 7.82		
time		1 to 1.926e+05		<pre>is_normal(a)</pre>
CALCULATIO	NS		L	is_blank(<i>a</i>)
🎎 phase			\geq	Mathematics
FILTERS			>	Limits and Rounding
🖓 conterr	nporary		>	Text
🖓 historio	C		>	Date/Time
			>	Unit Conversion

If you are using the Contaminants extension adding block models, you will have additional invalid values:


✓ Invalid Values


```
blank
without_value
outside
error
error('message')
is_normal(a)
is_blank(a)
is_without_value(a)
is_outside(a)
```

You can see how many points or blocks of each normal or invalid status occur in an evaluation by rightclicking on the evaluation in the project tree and selecting **Properties**:

Status counts	
Normal:	1,386
Blank:	0
Without valu	Je: 437
Outside:	313,877
Error:	0
Minimum:	0.490122
Maximum:	20.0376

Invalid values can be displayed in the scene. When a block model is displayed in the scene, you can choose between displaying evaluation values or the **Status**. Highlighted below is a Kriging evaluation, shown displayed on the block model. Next to the Kriging evaluation in the dropdown list is a **Status** option:





When the status option is selected, the model is displayed by block status. Click **Edit Colours** to change what status values are displayed.

With block model statistics, you can view statistics for all evaluations and calculations made on a block mode. Statistics can be broken down into categories and organised by numeric evaluations and calculations. See <u>Viewing Block Model Statistics</u> in the <u>Block Models</u> topic for more information.


Catalogue of Metadata, Syntax and Functions

This catalogue details each of the items in the pinnable **Insert** list for **Calculations and Filters**. Each item includes an intentionally trivial example to illustrate the use of the item, along with an explanation of the effect of the expression.

Some aspects of this feature may be illustrated using examples including block models. Some capabilities are specific to block models. Block models are a feature that requires the Contaminant extension in Leapfrog Works. Unless otherwise stated, what is described for points objects can also be applied to block models if you have the Contaminants extension.

Existing Items

This section covers the items listed in the left-hand side of the pinnable **Insert** list:



To pin these lists to the Calculations tab, enable the Pin Window option:



Metadata

id

This metadata item is available for imported points objects. It is the row ID from the points table.

Example



Explanation

The filter even rows will select for points with a row [id] that has no remainder when divided by 2.

x, y and z

These three metadata items are the variables for locating each point in a points object in X, Y and Z coordinates. Select an item to add it to the expression at the insertion point. Note that whenever one of these metadata items is added to an expression, it is wrapped in square brackets. This is not available for block objects; use xc, xy and xz instead.

Example



Explanation

The numeric calculation YX will be assigned the value of the location of [y] multiplied by the location of [x].

xc, yc and zc

These three metadata items are the variables for locating the centroid of each block, in X, Y and Z coordinates. Select an item to add it to the expression at the insertion point. Note that whenever one of these metadata items is added to an expression, it is wrapped in square brackets. This is not available for points objects; use x, y and z instead.

Example

top \vee = [zc] + ([dz] / 2)

Explanation

The numeric calculation top will be assigned the value of the location of [zc] the altitude of each block centroid from the zero reference, plus half the height of the block.

dx, dy and dz

These three metadata items are the variables for the block dimensions in X, Y and Z coordinates. Select an item to add it to the expression at the insertion point. Note that whenever one of these metadata items is added to an expression, it is wrapped in square brackets. This is not available for points objects.

Example

surface area \vee = ((2*[<i>dx</i>]*[<i>dy</i>]) +	$(2^{*}[dx]^{*}[dz]) +$	$(2^{*}[dy]^{*}[dz])$
-------------------------	-----------------------------------	-------------------------	-----------------------

Explanation

The numeric calculation surface area will be calculated by figuring the area of each face of the block by multiplying the X and Y dimensions, X and Z dimensions and Y and Z dimensions and adding them together.

volume

This metadata item provides the volume for each block. Note that when this metadata item is added to an expression, it is wrapped in square brackets. This is not available for points objects.

Example




Explanation

The numeric calculation density will be assigned the value of the variable [mass] divided by the metadata item [volume].

xi, yi and zi

These three metadata items are the variables for locating each block by X, Y and Z index. Select an item to add it to the expression at the insertion point. Note that whenever one of these metadata items is added to an expression, it is wrapped in square brackets. This is not available for points objects.

Example



Explanation

The numeric calculation remaining will be assigned the value of the block's AU_gpt evaluation, unless [zi] the Z index of the block is greater than or equal to 40, in which case the block status will be set to the invalid value outside.

Evaluations

Each of these items are automatically added to the list whenever an evaluation is added to the object. When added to an expression, the item represents a placeholder in the calculation for an estimated value, as the expression is evaluated for each of the locations in turn.

Note you can expand each evaluation in the list to see the attributes for the estimation evaluation that may also be selected instead of or in addition to the estimated value.

Example

🚦 halved 🗸 🗸	=	[<i>AU_gpt</i>] / 2
--------------	---	-----------------------

Explanation


The numeric calculation halved is defined by the evaluation [AU_gpt] divided by 2. Each location in the object will have its own value for AU_gpt, and this calculation uses those values to create a new value named halved for each location, using the formula above.

Variables, Calculations and Filters

Each time you create a new variable, numeric calculation, category calculation, or filter in **Calculations**, it will also be added to the **Existing items** list. You can select them from this list and they will be inserted into your new expression at the insertion point. Note that whenever one of these named items is added to an expression, it is wrapped in square brackets.



Example



Explanation

This example is only attempting to illustrate how variables, calculations and filters that have already been defined can be referenced by name in new calculations; the calculation highlight is not intended to be useful.

It is good practice to break your calculations down into parts, giving each part a relevant and readily identifiable, unambiguous and easily understood name. This will make your calculations more readable and clear. Using **Variables** to define a constant with a name makes it easy to understand the utility of that particular constant when you use it in a calculation. You may also be able to re-use certain parts such as filters or constant variables, so you do not need to define the same thing repeatedly.

Be careful not to inadvertently name something incorrectly, such as naming a volume as "area", as this could give rise to difficult-to-locate errors in your calculation.

Syntax and Functions

This section covers the items listed in the right-hand side of the pinnable **Insert** list.

ting items:			Sunt	tax and functi	ions:
METADATA			Jay 10	Statements	
id	Row ID	1 to 3591	Ň		
	Location X	2.77e+06 to 2.782e+06		()	
	Location Y			if(::)	lf block
7	Location Z	-7170 to 530	\sim	Basic Opera	itors
IMPORTED	Location 2	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		+	Add
Day		1 to 31		-	Subtract
Days		0.01597 to 364.8		*	Multiply
Depth		-7.17 to 0.53		/	Divide
Event N	No.	8296 to 1.324e+04		%	Modulo
Excel ti	me	4.164e+04 to 4.2e+04		^	Power
Hour		0 to 23		and	Logical and
Mag		0.01 to 3.71		or	Logical or
Minute		0 to 59		not	Logical not
Month		1 to 12		=	Equal
Second	I	0 to 59.98		!=	Not equal
UTC tir	ne			<	Less than
Year		2014 to 2014		<=	Less or equal
VARIABLES				>	Greater than
(x) radius					
(x) denom	inator			>=	Greater or equal
(x) area			2	Complex Co	
CALCULATIO			>	Invalid Valu	
2014_0	Juarter		>	Mathematic	-
FILTERS			>	Limits and I	Rounding
🖓 Y2014			>	Text	
			>	Date/Time	
			>	Unit Conver	rsion

To pin these lists to the **Calculations** tab, enable the **Pin Window** option:

Insert v if	ifer 🗲 🤗	⊢ ?				
Click on eith	her list below to in	sert that item				Pi <u>n</u> window
Existing items	s:		Synt	ax and functio	ns:	
METADAT	A		\sim	Statements		
id	Row ID	1 to 3591		()	Bracket	ts
x	Location X	2.77e+06 to 2.782e+06		if(::)	If block	c i i

Statements

(...) Brackets

Brackets are used to enclose an expression so the operations on the values within the brackets take precedence over operations outside the brackets.

Example

```
(x) BODMAS \vee = 6 / 2 * (1 + 2) = 9
```

Explanation

1+2 will be calculated prior to calculating the result of the expression, following the standard order of mathematical operations.

if(::) If block


The **If block** is used for conditional logic. This allows multiple pathways to results depending on selected conditions, or categorisation based on values.

An **If block** will be evaluated by each test \rightarrow result, row by row, separately and in order downwards by row. Each test has an output that can be 'true', 'false', or an invalid value, either 'error' or 'blank'. Block models can also have the invalid values 'without_value' or 'outside'. The result output is produced by the execution of the result expression. The **If block** output follows these rules:

- If a test output is 'error', the **If block** output is 'error' and no further processing of subsequent rows is done.
- If a test output is 'false', the result expression is not executed, and the next row is considered.
- If a test is 'true', the result expression is executed and the result output is used for the **If block** output and no further processing of subsequent rows is done.
- If all the tests are 'false', the 'otherwise' result expression is executed and its output is used.
- If a test output is an invalid value (without_value, blank, outside) the result expression is not executed and the test output's invalid value is remembered. The subsequent rows are then run.
- If a subsequent test output is 'true' after an earlier one produced an invalid value, the previous test output is discarded and the new row's result expression output is used as the output for the **If block**.
- If all test outputs are invalid status values, the highest priority status of all the remembered invalid statuses is used as the output result. The priority of non-error invalid status values is: outside > without_value > blank.

Additionally, it is possible to choose to produce invalid values as the output of result expressions.


Example



Explanation


Cu_pct is the name of an evaluation applied to all the points in a points object. As the **if(::) If block** calculation is run for each point, the evaluation for each point replaces this variable name in the expression. If the value is greater than the value of the constant pi, the result for that point will be the text string "Blue". Otherwise, if the value is less than or equal to pi, the result will be the string "Red".

Additional rows may be added. Each row follows on from the left-over results of the line before, simplifying the logical expression that may be used.



Note the addition of the line $[Cu_pct] > e \rightarrow "Purple"$. This line can be interpreted to mean: if the value estimated for a point is less than or equal to pi, but greater than e the result shall be "Purple". The part about it being less than or equal to pi is implied because the line follows the previous line $[Cu_pct] > pi \rightarrow "Blue"$.

Note that expression elements before and after the if expression can be entered. This allows the **if(::) If block** to form part of a more complex or extensive expression.



Explanation

The earlier conditional classification has now been embedded within a concatenation function, forming the first part of a two-part string concatenation. The concatenation function is adding the text string "-ish" to whatever is produced by the **if(::) If block**. Thus, if the value of the block being evaluated is 1.2, the result of the colour categorisation calculation will be "Red-ish".

Basic Operators

+ Add

An arithmetic addition operation.

Example



Explanation

next is assigned the value of the current imported points row [id] plus 1.

- Subtract

An arithmetic subtraction operation.

Example

(x) prev \vee = $[id]$ - 1

prev is assigned the value of the current imported points row [id] minus 1.

* Multiply

An arithmetic multiplication operation. Note that implied multiplication, putting factors adjacent to one another, is not supported. The * operator must be explicitly used.

Example



Explanation

product is assigned the value of [x] times [scale].

/ Divide

An arithmetic division operation.

Example

	(x)	quotient	\sim	=	[numerator]	7	[denominator]
--	-----	----------	--------	---	-------------	---	---------------

Explanation

quotient is assigned the value of [numerator] divided by [denominator].

% Modulo

An arithmetic modulo operation. This is an integer division operation that returns the remainder instead of the integer quotient.

Example



Explanation

remainder is assigned the value of [numerator] modulo [denominator], or in other words, [numerator] is divided by [denominator] to produce an integer quotient, the number of times [denominator] goes into [numerator], and a remainder, which is the number returned by this modulo function.

^ Power

A mathematical exponentiation operation where a base is raised to the power of the exponent.

Example

(x) area ~	=	pi * [<i>radius</i>]^2	= 12.5663706143
------------	---	--------------------------	-----------------

area is assigned the value of pi * $[radius]^2$ (because ^2 is interpreted as 'to the power of the exponent 2' or 'squared'). Because [radius] happened to be defined as equalling 2, the result of the expression pi * 2^2 is 12.56637..., as can be seen from the result at the end of the expression.

and Logical and

A logical and operation.

Example

 ∇ topD \vee = ([Geological model] = 'Dacite') and ([z] > 2800)

Explanation

filter will be true if the point is classified in the 'Dacite' part of the geological model AND the [z] coordinate for the point is above 2800; it will be false if either of these conditions are not true.

or Logical or

A logical or operation.

Example

 The second product of the second pr

Explanation

Dacite and ED will be true if the point is classified in the 'Dacite' part of the geological model OR the point is classified in the 'Early Diorite' part of the geological model, but it will be false if neither of these conditions is true.

not Logical not

A logical not operation.

Example

🖓 Not Dacite	\sim	=	<pre>not ([Geological model] = 'Dacite')</pre>

Explanation

Not Dacite will be true if the point is classified in the geological model as anything other than 'Dacite'. The logical operator not inverts the logical expression that follows the operator.

= Equal

A logical equality operator.

Example

Dacite will be true if the point is classified in the 'Dacite' part of the geological model, and will be false for all other values.

!= Not equal

A logical not-equal operator.

Example

🖓 Not Dacite 🗸 🗸	=	([Geological model] != 'Dacite')
U Hot Baoke		([,

Explanation

Not Dacite will be true if the point is classified in the geological model as anything other than 'Dacite', and will be false when it is 'Dacite'.

< Less than

A logical less-than operator.

Example

 \bigtriangledown density under 1 \lor = [density] < 1

Explanation

density under 1 will be true when the variable [density] is less than 1, and false otherwise.

< Less or equal

A logical less-than-or-equals operator.

Example

Explanation

density le 1 will be true when the variable [density] is less than or equal to 1, and false otherwise.

< Greater than

A logical greater-than operator.

Example

 \bigtriangledown density over 1 \lor = [density] > 1

Explanation

density over 1 will be true when the variable [density] is more than 1, and false otherwise.

< Greater or equal

A logical greater-than-or-equals operator.

Example

 \bigtriangledown density ge 1 \lor = [density] >= 1

Explanation

density ge 1 will be true when the variable [density] is more than or equal to 1, and false otherwise.

Complex Comparisons

Lower < n < upper

A pair of comparisons, with a logical result to indicate if the tested value n is between the lower value provided and the upper value provided.

Example

🖓 filter 🗸 🗸	=	5 < [<i>AU_gpt</i>] < 8

Explanation

filter will be true when the point evaluation [AU_gpt] is between the values of 5 and 8 (but not equalling 5 or 8); it will be false otherwise.

Lower <= n < upper

A pair of comparisons, with a logical result to indicate if the tested value n is between the lower value provided and the upper value provided, or equal to the lower value.

Example

🖓 filter 🗸 🗸	=	5 <= [<i>AU_gpt</i>] < 8

Explanation

filter will be true when the point evaluation [AU_gpt] is between the values of 5 and 8 (but not equalling 8); it will be false otherwise.

Lower < n <= upper

A pair of comparisons, with a logical result to indicate if the tested value n is between the lower value provided and the upper value provided, or equal to the upper value.

Example

🖯 filter 🗸	1 -	5 < [41] ant] <= 8
	=	$5 < [AU_gpc] <= 0$

filter will be true when the point evaluation [AU_gpt] is between the values of 5 and 8 (but not equalling 5); it will be false otherwise.

Lower <= n <= upper

A pair of comparisons, with a logical result to indicate if the tested value n is between (or equal to either) the lower value provided and the upper value provided.

Example

🖓 filter 🗸 🗸	=	5 <= [AU_gpt] <= 8

Explanation

filter will be true when the point evaluation [AU_gpt] is greater than or equal to 5 and less than or equal to 8; it will be false otherwise.

x in {a,b,...}

A logical inclusion expression. This will return true if x matches any element of the set of listed items.

Example

filter \vee = [colour] in {'red', 'orange', 'yellow', 'green', 'blue', 'violet'}

Explanation

If [colour] is one of the items in the list within the curly brackets, filter will be true. If [colour] is anything else, filter will be false.

x not in {a,b,...}

A logical exclusion expression. This will return true if x fails to match any element of the set of listed items.

Example

🖓 filter	 <pre>[colour] not in {'red', 'orange', 'yellow', 'green', 'blue', 'violet'}</pre>
U miter	[coooding inde in [red) or dige) year on) green) brace) violee]

Explanation

If [colour] is not one of the items in the list within the curly brackets, filter will be true. If [colour] matches any item in the list, filter will be false.


Invalid Values

Invalid values are different types of results for "numeric" categorisation calculations that need special non-numeric results for certain category results. These have special meanings of their own without having to resort to interpreting negative numbers and zero as having special meaning.

blank means having no value, the value in the imported file is blank or has non-numeric data

without_value is often used to mean the estimator cannot produce a value (specific to blocks) outside is used to indicate the block is outside the boundary of the domain (specific to blocks) error generates an error, and provides an 'error' status value for the affected block or point error('message') is similar to error but includes a custom message.

Multiple case example



Explanation

If the variable [area] is equal to 0, the point will be marked with the special value blank. If the variable [area] is less than 0, the point will be marked with the special value outside. If [area] is greater than 0 and the variable [result] is equal to 0, the point will be marked with the special value without_value. If [area] is greater than 0 and [result] is greater than 0, the point will be will be assigned the value of the variable [result]. If [area] is greater than 0 and [result] is less than 0, the point will be given the special value error and status with the message 'negative result'.

is_normal(a)

A function that tests a to see if it is a normal value or an invalid value. If a is normal, it returns true. If a is invalid, it returns false.

Example

🖓 filter 🗸 🗸	=	<pre>is_normal([number])</pre>

Explanation

If [number] has a normal value, filter will be true for that block. If it produces an invalid value, filter will be false.

is_blank(a)

A function that tests a to see if it is a blank invalid value. If a is blank, it returns true. If a is normal or another invalid value, it returns false.

Example

🖓 filter 🗸 🗸	=	<pre>is_blank([number])</pre>

Explanation

If [number] has a blank status, filter will be true for that block. If it produces any other invalid value or a normal value, filter will be false.

is_without_value(a)

A function that tests a to see if it is a without_value invalid value. If a is without_value, it returns true. If a is normal or another invalid value, it returns false.

Example

🖓 filter	~ =	<pre>is_without_value([number])</pre>

Explanation

If [number] has a without_value status, filter will be true for that block. If it produces any other invalid value or a normal value, filter will be false.

is_outside(a)

A function that tests a to see if it is an outside invalid value. If a is outside, it returns true. If a is normal or another invalid value, it returns false.

Example

🖓 filter 🗸 🗸	=	<pre>is_outside([number])</pre>

Explanation

If [number] has an outside status, filter will be true for that block. If it produces any other invalid value or a normal value, filter will be false.

Mathematics

pi Constant

The constant pi is an existing item you do not need to define yourself. It is defined to 15 decimal places as 3.141592653589793.

Example

(x) area ~	=	pi * [<i>radius</i>]^2	= 12.5663706143
()			

Explanation

area will be calculated as pi multiplied by the square of [radius]. Note that pi is not enclosed in square brackets like user-created variables and constants, as it is an internal constant.

e Constant

The constant e, the base of the natural logarithm, is an existing item you do not need to define yourself. It is defined to 15 decimal places as 2.718281828459045.

Example

🚺 comp 🗸 🗸	=	e^([<i>rate</i>]-1)

Explanation

comp will be calculated as e to the power of ([rate] minus 1). Note that e is not enclosed in square brackets like user-created variables and constants, as it is an internal constant.

log(n) Base 10

The common logarithm, the logarithm with base 10, i.e. $log_{10}(n)$ or lg(n). This function will calculate the common logarithm of the value provided as n.

Example

scaled \vee = log([measure])

Explanation

scaled will be calculated as log₁₀ of [measure].

log(n, base)

The logarithm of a number n to the base base.

Example

scaled \vee = log([measure], 2)

Explanation

scaled will be calculated as log_2 of [measure].

In(n) Natural log, base e

The natural logarithm, the logarithm with base e, i.e. $\log_e(n)$. This function will calculate the natural logarithm of the value provided as n.

Example

scaled \vee = ln([measure])

Explanation

scaled will be calculated as log_e of [measure].

exp(n) Natural exponent

The natural exponent. This function will provide the result of eⁿ.

Example

em v = exp([measure])

Explanation

em will be calculated as e [measure].

sqrt(n) Square root

The principle square root of the provided number n.

Example

sqrtm \vee = sqrt([measure])

Explanation

sqrtmwill be calculated as the square root of [measure].

abs(n) Absolute value

The absolute value of a number is it's value with the sign of the number disregarded. The absolute value of -42 is 42. The absolute value of 42 is also 42.

Example

🚦 absm 🗸 🗸	=	abs([measure])

Explanation

absm will be whatever [measure] is, but without its sign; it will always be positive as a result.

Limits and Rounding

min (n, m, ...)

Returns the lowest of all the values in the set provided.

Example

iii Iow	~ =	min([x], [y], [z])
---------	-----	--------------------

Explanation

low will be the lowest of the three values provided, the metadata items for the X, Y, and Z point coordinates.

max (n, m, ...)

Returns the highest of all the values in the set provided.

Example

high \vee = max([x], [y], [z])

Explanation

high will be the highest of the three values provided, the metadata items for the X, Y, and Z point coordinates.

clamp(n, lower)

This clamp function tests the value n against the threshold lower and if it is less than lower the result will be lower; otherwise the result will be n. The effect is to push all the values below the threshold up to the threshold.

Example

(x) modified \vee	=	clamp([<i>AU_gpt</i>], 0.25)

Explanation

The output for modified will range from 0.25 up to the maximum value of [AU_gpt]. If [AU_gpt] is less than 0.25, the output will be 0.25 instead. Otherwise, the output will be [AU_gpt].

clamp(n, lower, upper)

This clamp function tests the value n against the threshold lower and if it is less than lower the result will be lower; it tests the value n against the threshold upper and if it is more than upper the result will be upper; otherwise the result will be n. The effect is to squish all the values into a box between the lower and upper thresholds.

Example

(x) modified \vee = clamp([AU_gpt], 0.25, 8)

Explanation

The output for modified will range from 0.25 up to 8. If [AU_gpt] is less than 0.25, the output will be 0.25 instead. If [AU_gpt] is more than 8, the output will be 8 instead. Otherwise, the output will be [AU_gpt].

round(n)

This function rounds the input value n to the nearest whole number.

Example

(x) negative \vee	=	round(-12.6789)	= -13
(x) postive ~	=	round(12.6789)	= 13

Explanation

The variable negative will be given the value -13 as the nearest whole number to -12.6789 used as the input to the function. The variable positive will be given the value 13 as the nearest whole number to 12.6789 used as the input to the function.

round(n, dp)

This function rounds the input value n to the number of decimal places specified by dp, a positive integer.

Example

(x) negative \sim	=	round(-12.3456789, 4)	= -12.3457
(X) postive	=	round(12.3456789, 4)	= 12.3457

Explanation

The variable negative will be given the value -12.3457, the value of -12.3456789 rounded to 4 decimal places. The variable positive will be given the value 12.3457, the value of 12.3456789 rounded to 4 decimal places.

roundsf(n, sf)

This function rounds the input value n to the number of significant figures specified by sf, which must be a positive integer >= 1. Rounding to a given number of significant figures is often preferred in scientific applications over rounding to a given number of decimal places, as outputs can be rounded to the same amount of significance as the inputs.

Example

(x) negative	- =	roundsf(-12.3456789, 4)	= -12.35
(x) postive	- =	roundsf(12.3456789, 4)	= 12.35

Explanation

The variable negative will be given the value -12.35, the value of -12.3456789 rounded to 4 significant figures. The variable positive will be given the value 12.35, the value of 12.3456789 rounded to 4 significant figures.

floor(n)

This function removes the fractional part of a real number n and returns the integer number below the real number n. This remains true when n is a negative number.

Example

(x) negative ~	=	floor(-12.3456789)	= -13
(x) postive ~	=	floor(12.3456789)	= 12

Explanation

The variable negative will be given the value -13, the integer below -12.3456789. The variable positive will be given the value 12, the integer below 12.3456789.

ceiling(n)

This function removes the fractional part of a real number n and returns the integer number above the real number n. This remains true when n is a negative number.

Example

(x) negative \vee	=	ceiling(-12.3456789)	= -12
(X) postive ~	=	ceiling(12.3456789)	= 13

Explanation

The variable negative will be given the value -12, the integer above -12.3456789. The variable positive will be given the value 13, the integer above 12.3456789.

truncate(n)

This function simply removes the fractional part of a real number n and returns the integer number without the fractional part. This means that for positive real numbers, the result will be the integer less than the real number n, but for negative real numbers, the result will be the integer greater than the real number n.

Example

(x) negative ~	=	truncate(-12.3456789)	= -12
(x) postive	=	truncate(12.3456789)	= 12

Explanation

The variable negative will be given the value -12, the integer part of -12.3456789. The variable positive will be given the value 12, the integer part of 12.3456789.

Text

'abc' Text value

Use this item to add a text sequence to an expression. Selecting the item will add two single quotation marks with the cursor between, ready for the text sequence to be typed. You can of course simply type the quote marks into the expression yourself. Double quotations marks also work identically to the single quotation marks used by this item. If you need to include a quote mark inside your text sequence, you need to "escape" the character so it is not interpreted as the end of the text sequence, by entering two quotation marks for each quotation mark you want inside the text sequence. Alternatively, you can use a different type of quotation mark as the sequence wrappers; for instance to write Seequent's Region with an internal apostrophe, you might wrap the sequence with double quotation marks: "Seequent's Region".

Example

(x) name1 ~	=	"Seequent's Region"
(X) name2 ~	=	'Seequent''s Region'

Explanation

The text sequence Seequent's Region (note: without the wrapping quotation marks and with only one possessive apostrophe) will be used wherever the variables name1 or name2 are used in expressions. Both techniques for including apostrophes in the text sequence have the same result.

Enter text...

This selection opens a dialog box prompting you for text. After you enter it and click OK, the text will be entered at the cursor, wrapped with quotation marks. This is an easy way to resolve any issues about internal quotation marks, as the dialog box will convert the text into the necessary character sequence required to generate your desired text.

Example

📽 Enter Text Value		×
Text value to insert:	Seequent's Region	
<u>C</u> ancel	<u>о</u> к	ľ

Explanation

This will produce a converted character sequence that produces a valid string and insert it to the expression at the insertion point.

(X) name2 \vee = "Seequent's Region"	(x) name2	- =	"Seequent's Region"
--	-----------	-----	---------------------

concat(t, u, ...)

This concatenates a series of text sequences together.

Example

	(x) name v	=	<pre>concat("Seequent_", [direction], "_Region")</pre>
--	------------	---	--

Explanation

Each of the text sequences in the input are run together and combined. If [direction] is 'North' then name will be Seequent_North_Region. If [direction] is 'South' then name will be Seequent_South_Region.

startswith(t, 'prefix')

This function returns true if the text sequence t starts with prefix, and false otherwise. This is case insensitive; 'prefix' will match 'PREFIX'.

Example

🖓 filter 🗸 🗸	/ =	<pre>startswith([name] ,</pre>	'Seequent')

Explanation

filter will be true if [name] starts with Seequent.

endswith(t, 'suffix')

This function returns true if the text sequence t ends with suffix, and false otherwise. This is case insensitive; 'suffix' will match 'SUFFIX'.

Example

filter \vee = endswith([name], 'Region')

Explanation

filter will be true if [name] ends with Region.

contains(t, 'part')

This function returns true if the text sequence t contains part somewhere within, and false otherwise. This is case insensitive; 'part' will match 'PART'.

Example



Explanation

filter will be true if [name] contains North somewhere within the character sequence.

like(t, 'pattern')

This function returns true if the text sequence t matches pattern, where [pattern] is follows SQL-style LIKE matching rules. This is case insensitive, and pattern must match the whole of t, not just a portion of it. Use _ as a wildcard for a single character, and % as a wildcard for any number of characters (including no characters).

Example

🖓 filter 🗸 🗸	=	<pre>like([name] , '%Seequent_Region%')</pre>

Explanation

filter will be true if [name] matches the pattern %Seequent_Region%. Examples of [name] that will match include:

- SEEQUENT1Region
- SEEQUENT1REGION
- Seequent2region
- NorthernSeequent1Region
- SEEQUENT3regionExtra
- #seequentXregion#

Examples that will not match include:

- Seequent12Region
- SeequentReg1ion
- SeequentRegion

regexp(t, 'pattern')

This function returns true if the text sequence t matches pattern, where [pattern] is follows regular expression matching rules. This is case insensitive.

Example

filter \vee = regexp([name], 'Seequent.Region')

Explanation

filter will be true if [name] matches the regexp pattern Seequent.Region. Examples of [name] that will match include:

- SEEQUENT1Region
- SEEQUENT1REGION
- Seequent2region
- NorthernSeequent1Region
- SEEQUENT3regionExtra
- #seequentXregion#

Examples that will not match include:

- Seequent12Region
- SeequentReg1ion
- SeequentRegion

Date/Time

'*now*' Current timestamp

Use this item to add the current date-and-timestamp at the insertion point.

Example

(x) rightnow ~	~ =	= @2020-09-28 21:37:1

Explanation

While entering an expression, the 'now' selection has been chosen and a date-and-timestamp has been entered at the insertion point.

'today' Current date

Use this item to add the current datestamp at the insertion point.

Example

(a) to down dots		00000 00 00	
(x) todaysdate	~ =	@2020-09-28	

Explanation

While entering an expression, the 'today' selection has been chosen and a date-and-timestamp has been entered at the insertion point.

dateonly(timestamp)

This function takes a date-and-timestamp and cuts off the timestamp to leave just the date.

Example

(x) justdate \vee = dateonly([past])
--

Explanation

While the [past] variable has a full date-and-timestamp, the dateonly function strips the time off and leaves just the date.

Pick timestamp...

This selection opens a dialog box prompting you for a date and a time that will be entered at the insertion point when you click OK.

Example

<		Septer	nber~	2020		>
S	м	т	W	Т	F	S
		1	2	3	4	5
6	7	8	9	10	11	12
13	14	15	16	17	18	19
20	21	22	23	24	25	26
27	28	29	30			
4	5	6		8	9	
Date:	9/28/	20	0			
Time:	12:00:00 am					

Explanation

Use the year picker, month picker, date selector and **Time** field to specify a date and time. If the above date is entered, it will be represented in the expression as @2020-01-22 00:00:00.

Pick date...

This selection opens a dialog box prompting you for a date that will be entered at the insertion point when you click OK.

Example



Explanation

Use the year picker, month picker and date selector to specify a date. If the above date is entered, it will be represented in the expression as @2020-01-22.

Unit Conversion

Mass/weight...

This selection opens a dialog box prompting for the **From Unit** and **To Unit** for the conversion.

🖉 Convert Mass	×
From Unit	To Unit
 Micrograms (µg) 	 Micrograms (µg)
🔿 Milligrams (mg)	O Milligrams (mg)
O <u>G</u> rams (g)	O <u>G</u> rams (g)
 <u>K</u>ilograms (kg) 	C Kilog
 <u>M</u>etric Tonnes 	<u>M</u> etric
Troy Ounces	<u>Troy Ounces</u>
O Pounds	O Pounds
Short Tons	Short Tons
○ <u>L</u> ong Tons	○ <u>L</u> ong Tons

When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(x) grams ~	=	<pre>troy_oz_to_g([troy0z])</pre>

Explanation

The troy_oz_to_g function has been entered by the dialog box, and the variable [troyOz] has been entered as the input. The numeric calculation grams will be given the output of the troy_oz_to_g function.

Distance...

This selection opens a dialog box prompting for the **From Unit** and **To Unit** for the conversion.

🖉 Convert Distance To Unit From Unit Millimetres (mm) Millimetres (mm) Centimetres (cm) <u>C</u>entimetres (cm) Decimetres (dm) Decimetres (dm) Metres (m) O Metres (m) Kilom Metres Kilometres (km) Inches • <u>F</u>eet <u>F</u>eet <u>Y</u>ards Yards Miles Mil<u>e</u>s

When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(x) metres ~	=	<pre>ft_to_m([feet])</pre>

Explanation

The ft_to_m function has been entered by the dialog box, and the variable [feet] has been entered as the input. The numeric calculation metres will be given the output of theft_to_m function.

Area...

This selection opens a dialog box prompting for the From Unit and To Unit for the conversion.

🗸 Convert Area	
From Unit	To Unit
 Square <u>M</u>etres (m²) 	 Square <u>Metres</u> (m²)
<u>H</u> ectares (ha)	 <u>H</u>ectares (ha)
O Square Kilometres (km²)	 Square <u>K</u>ilometres (km²)
Square <u>Feet</u>	O Square <u>F</u> eet
O Square <u>Y</u> ards	O Square <u>Y</u> ards
○ Acres	○ Arces
Square Miles	St ^{ares} s

When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(x) acres ~	=	ha_to_acre([<i>hectares</i>])
× 7		

Explanation

The ha_to_acre function has been entered by the dialog box, and the variable [hectares] has been entered as the input. The numeric calculation acres will be given the output of theha_to_acre function.

Volume...

This selection opens a dialog box prompting for the **From Unit** and **To Unit** for the conversion.

🦉 Convert Volume	
From Unit	To Unit
🔿 Litres (L)	Litres (L)
 Cubic <u>Metres (m³)</u> 	O Cubic Metres (m ³)
 Cubic Inches (in^a) 	O Current Cubic metres
O US <u>G</u> allon	O US
◯ <u>U</u> K Gallon	UK Gallon
 Cubic <u>Feet (ft</u>^a) 	 Cubic <u>Feet</u> (ft^a)
<u>Acre-Inches</u>	<u>A</u> cre-Inches
Acre-Feet	Acre-Feet

When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(x) volm3 \vee = acre_ft_to_m3([acre_ft])

Explanation

The acre_ft_to_m3 function has been entered by the dialog box, and the variable [acre-ft] has been entered as the input. The numeric calculation volm3 will be given the output of theacre_ft_to_m3 function.

Temperature...

This selection opens a dialog box prompting for the **From Unit** and **To Unit** for the conversion.



When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(X) Kelvin \checkmark	=	<pre>degF_to_K([fahrenheit])</pre>
-------------------------	---	------------------------------------

Explanation

The degF_to_K function has been entered by the dialog box, and the variable [fahrenheit] has been entered as the input. The numeric calculation Kelvin will be given the output of thedegF_to_K function.

Pressure...

This selection opens a dialog box prompting for the **From Unit** and **To Unit** for the conversion.

From Unit	To Unit
<u>P</u> ascals (Pa)	<u>P</u> ascals (Pa)
 <u>K</u>ilopascals (kPa) 	〇 <u>K</u> ilopascals (kPa)
0 <u>B</u> ar	⊖ B ar Kilopascals
Atmospheres	
PSI	

When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(x) pressure_kPa ~	=	<pre>psi_to_kPa([pressure_psi])</pre>

Explanation

The psi_to_kPa function has been entered by the dialog box, and the variable [pressure_psi] has been entered as the input. The numeric calculation pressure_kPa will be given the output of thepsi_to_kPa function.

Energy...

This selection opens a dialog box prompting for the From Unit and To Unit for the conversion.

From Unit	To Unit
 Joules (J) 	 Joules (J)
 Kilojoules (kJ) 	 Kilojoules (kJ)
Megajoules (MJ)	 Megajoules (MJ)
 Kilowatt <u>H</u>ours (kWh) 	O Kilowatt Hours (kWh)
Calories	C C Kilowatt hours
 Kilgcalories 	Kingana
 ISO British Thermal Units (Btu) 	 ISO British Thermal Units (Btu)

When you have selected the two units, the dialog box disappears and the conversion function you require will have been inserted into the expression at the cursor, and the cursor repositioned so you can enter the source of the value to be converted.

Example

(𝗶) kiloWatt Hours ∨	=	MJ_to_kWh([<i>MegaJoules</i>])

Explanation

The MJ_to_kWh function has been entered by the dialog box, and the variable [MegaJoules] has been entered as the input. The numeric calculation kiloWatt Hours will be given the output of the MJ_to_kWh function.

Modelling

This section describes how to build models in Leapfrog Works.

- It is not necessary to define a topography to model in Leapfrog Works, but a defined topography can be used as an upper boundary for all models built in the project. A key advantage of defining a topography is that it provides consistent elevation data for objects imported to and created in the project. The quality of elevation information can be poor compared to X- and Y-coordinates, which can create problems when using objects to build a model. A topography can be created from the most reliable elevation data, and other objects can have elevation set from this topography.
- Geological models can be built from lithology data or from any other suitable data in the project. Visualising data in the scene is an important step in determining the model that will be built, and the tools for doing this are described in <u>Visualising Data</u>. Once this has been determined, the next step is to define a basic geological model and refine its boundaries. Modelling contact surfaces and setting their cutting relationships determine how the basic model volume is divided into lithologies. Models can also have a fault system that, once activated, will subdivided the model into fault blocks.
- With the **Numeric Models** folder, you can interpolate downhole numeric data, composited borehole data and points data.
- Combined models use information from up to four geological models, interpolants and distance functions in order to visualise relationships between different types of data in the project.
- With the Hydrogeology extension, geological models created in Leapfrog Works can be used as the basis for MODFLOW and FEFLOW models. You can create flow models directly in Leapfrog Works and assign hydrological/material properties based on the lithologies in the geological model. Flow models can be exported for use in other applications, and you can import existing flow models and use them as the basis for the construction of new models. Flow models can be displayed in the scene, and time-dependent data can also be visualised.

Assigning Attributes to Volumes

For geological models, numeric models and combined models, you can assign attributes to the model volumes. To do this, right-click on the model in the project tree and select **Volume Attributes**. In the window that appears, click the **Add Attribute** button (③) to add a new column.

\checkmark	Projects	Scene View	Central Projects	\blacksquare Attribute Table: \times
*				
Volume	•			
🍐 Gra	anodiorite			
🌰 Wa	ater	🔏 Name	×	
🍐 Cla	ау	Enter a new attribute name		
🍐 Sil	t		<i>.</i>	
🍐 Sa	indy Gravel	Cohesion		
all 🌰	luvial Gravel	Cancel	<u>o</u> ĸ	
🍐 Sc	hist	<u>_</u>	2.4	
	L			

Enter a name for the column and click **OK**. You can then edit the values in the table. When you click in the scene, the values will be included in the information displayed about the selected volume:

			Attribu	te Table: Lake Aura $ imes$		
			* 6 ?			
			Volume	Cohesion (kPa)	Friction angle (min)	Friction angle (max)
			b Granodiorite	42	25	29
			b Sandy Gravel	15	28	34
			b Schist	43	23	33
		00	🌰 Alluvial Gravel	19	26	38
		000	🍙 Silt	22	23	28
		4890000	┢ Water			
899	and the second	×	┢ Clay	15	20	35
🍘 Lake Aura G	M					
Location	1165350.1257, 4890301.5504, 82.1089			1		
Lake Aura GM	Sandy Gravel			EASE SOL		
Volume	114,630,000		AFEAS002 hole008	hole004	hole001	
Area	16,130,000				Holeoor	
Parts	2			5		
Cohesion (kPa)	15					
Friction angle (min)	28					
Friction angle	34					
C Edit Commen	ts					

Attribute information can be exported with IFC geometry.

Attribute information cannot be displayed in the Central Browser.

When you save scenes for viewing in Leapfrog Viewer, manually entered attributes will be displayed when volume information is displayed.

Defining a Topography

It is not necessary to define a topography to model in Leapfrog Works, but a defined topography can be used as an upper boundary for all models built in the project.

A key advantage of defining a topography is that it provides consistent elevation data for objects imported to and created in the project. The quality of elevation information can be poor compared to X-and Y-coordinates, which can create problems when using objects to build a model. A topography can be created from the most reliable elevation data, and other objects can have elevation set from this topography.

An important consideration when defining the topography is ensuring that it is large enough to encompass the models you will be building in the project. If you create a small topography but then later create a model that extends outside the topography, you will need to enlarge the topography, which can result in considerable reprocessing of all objects in the project that use the topography as a boundary. See <u>Extending a Surface</u> for more information.

This topic describes creating and working with a topography. It is divided into:

- Topography From Elevation Grid
- Topography From Surfaces, Points or GIS Vector Data
- Fixed Elevation Topography
- Adding Height Data to the Topography
- <u>Changing Topography Settings</u>
- Topography Display Options
- Setting Elevation for Collar Points

The topography can be created from an imported elevation grid, points data, surfaces and GIS data. It is not necessary to decide on a single source of information, as information can be combined, and you can add and remove data as required.

Once defined, you can export the topography as a mesh or as an elevation grid. See:

- Exporting Meshes
- Exporting an Elevation Grid

Topography From Elevation Grid

There are two ways to create the topography from an elevation grid:

- Right-click on the **Topographies** folder and select **New Topography > Import Elevation Grid**. Import the grid as described in Importing an Elevation Grid.
- Import the grid using the **Meshes** folder and then right-click on the **Topographies** folder and select **New Topography > From Surface**.

Enter a name for the topography and click **OK**. A hyperlink to the elevation grid will appear in the **Topographies** folder under the defined topography.

Once the topography has been defined, additional height data can be added by right-clicking on the topography and selecting from the options available. See <u>Adding Height Data to the Topography</u> for more information.

Topography From Surfaces, Points or GIS Vector Data

To create the topography from a surface, points or GIS data, first import the data into the project.

- Import surfaces into the **Meshes** folder.
- Import borehole data into the project or points data into the **Points** folder.
- Import GIS vector data into the **GIS Data, Maps and Photos** folder.

Next, right-click on the **Topographies** folder and select one of the **New Topography** options. A list of suitable objects available in the project will be displayed. Select the required object and click **OK**. Enter a name for the topography and click **OK**. A hyperlink to the source object will appear in the **Topographies** folder under the defined topography.

Once the topography has been defined, additional height data can be added by right-clicking on the topography and selecting from the options available. See <u>Adding Height Data to the Topography</u> for more information.

See also Changing Topography Settings below.

Fixed Elevation Topography

If you don't have any data suitable for creating a topography, you can set a fixed elevation. To do this, right-click on the **Topographies** folder and select **New Topography > Fixed Elevation**. In the window that appears, enter a value for the elevation and click **OK**. Enter a name for the new topography and click **OK**.

The new topography will appear in the project tree under the Topographies folder.

Once a topography has been defined, the only way to set a fixed elevation is to remove the objects that have been used to define the topography. To do this, right-click on the hyperlinked object and click **Remove**. You will then be able to set a fixed elevation for the topography.

Adding Height Data to the Topography


When creating the topography, it is not necessary to decide on a single source of information, as information can be combined. Once the topography has been defined, additional height data can be added by right-clicking on the topography and selecting from the options available:

Project <u>T</u> ree 0	` 0 (II) Q 📑 Look	~ là 8 Ø 🖸 🔳
🗸 🗋 Topographies		
🗸 🌛 Topography	<u>O</u> pen	Comments
<u>Tekapo DTM</u>	🕂 Add Height Data 📐 👌	Points
✓ ☐ Draped GIS Objects	Adjust Sur <u>f</u> ace	Surface
🗸 🔬 lake_bdy (On Topogra	🦿 E <u>d</u> it	🛃 GIS Vector Data
🥵 lake_bdy	Set <u>E</u> levation	Import Elevation <u>G</u> rid
∨ 🔬 North_boundary (On	Eval <u>u</u> ations	Polylines
S North_boundary	Extract Mesh Parts	
🗸 🔬 Topography contours	Extract Vertices	
orter 1000 1000 1000 1000 1000 1000 1000 10	View Object	
✓ ☐ GIS Data, Maps and Photos	↑ P <u>r</u> ioritise	
🗸 🛃 lake_bdy	(II) Freeze	
MATER_CONF [Empt]	Rename F2	
ELEVATION	Delete Del	
shapelD	<u>→</u> Export	
🗸 🛃 North_boundary	→ Export Elevation Grid	
shapelD	🔄 Colours >	
Area map	Properties	

It is not possible to add structural data or polylines with orientation information to the topography. If you edit the topography with a polyline, your options for editing the polyline will be limited.

For points, surfaces and GIS vector data, you will be prompted to select from the data sources available in the project. For an elevation grid, see <u>Importing an Elevation Grid</u>.

All data objects used to define the topography will appear under the topography, hyperlinked to their parent objects:



When you have added data to the topography, you may need to enlarge the topography extents. See <u>Changing Topography Settings below</u>.

To remove data objects from the topography, either:

- Delete the object from the topography. To do this, right-click on the hyperlinked object and click **Remove**.
- Delete the object from the project. If you choose this option, consider carefully the effects on other objects in the project, as once an object is deleted, it cannot be recovered.

When the topography is defined from multiple objects, you can set the resolution of the topography by double-clicking on it. See <u>Changing Topography Settings</u> below.

Changing Topography Settings

When the topography is created from points or GIS data or when the topography is created by combining data, you can change its boundary and resolution and apply a trend. To do this, double-click on the topography in the project tree. The **Edit Topography** window will appear:

🖉 Edit Topograph	y		×
General	Frend		
Bounding Bo	x		
	Minimum	Maximum	
<u>X</u> (East):	2283181.6433100495	<pre>\$ 2314588.7100257343 </pre>	
Y (North):	5693837.173313726	\$ 5711277.650018381	
Z (Elev):	-200.0		
		Enclose Object 🗸 🗸	
Resolution			
Surface <u>r</u> e	solution: 2000.0	🗘 🗌 Adaptive	
Name: Topogr	aphy		
?		<u>C</u> ancel <u>O</u> K	

Changing the Size of the Topography

In the **General** tab, you can change the topography extents. Use the controls in the scene or enter the required values in the **Bounding Box** fields.

Topography Resolution

The resolution of the topography depends on how it was created.

- When the topography is created from a single mesh, the resolution of the topography is set from the resolution of the mesh and can only be changed when the mesh is imported. If you wish to change the resolution of the topography, you must first add more height data to the topography. See <u>Adding</u> <u>Height Data to the Topography</u>.
- When the topography is created by setting a fixed elevation, the resolution cannot be set.

When the topography is created from points or GIS data or when the topography is created from combining data, you can set its resolution in the **Edit Topography** window.

When you set a specific **Surface resolution** without enabling the **Adaptive** option, the triangles used will be the same size for the whole topography. When you enable the **Adaptive** option, the resolution of the topography will be affected by the availability and density of real data. See <u>Surface Resolution in</u> <u>Leapfrog Works</u> for more information on these settings.

Applying a Trend to the Topography

Edit Topography				
General Tren	d			
	Dip	Dip Azimuth	Pitch	
Directions:	0	, 0	, 90	
	Maximum	Intermed.	Minimum	
Ellipsoid Ratios:	1	, 1	, 1	
View Pla	ne	Set From Plane	Set to	\sim
Name: Topograph	у			
\bigcirc		Cancel		<u>0</u> K


In the **Trend** tab, you can apply a trend to the topography:

See <u>Global Trends</u> for more information.

Topography Display Options

To display the topography in the scene window, either:

- Right-click on the topography in the project tree and select **View Object**.
- Click on the topography object and drag it into the scene.



The topography will be displayed in the scene window and in the shape list:

The topography object in the shape list provides additional controls that can be used to change the way the topography is displayed and highlight features of interest. For example, selecting an imported map from the list results in it being displayed draped onto the topography:

\odot	💣 Topogra	aphy	🗙 👌 Flat 🗸 📃 🗹			👔 No Selectio	n	
	GIS Data:	Select 🗸						
		None						
		<u>V</u> iews						
		Maps and Photos	🛛 🔤 Area map					
		GIS objects	Farmland detail					
			Tekapo					
		122775	77.74, +5082502.54, +3720.13	🔗 <no code=""></no>	Full Acceleration	90 FPS	Z-Scale 1.0	19 hours to go

The list is organised into:

- Views. This contains options for creating and editing custom topography views and also lists any views already defined. With custom topography views, you can view multiple GIS objects, maps and contours. See Custom Topography Views for more information.
- Maps and Photos. This lists all images stored in the GIS Data, Maps and Photos folder.
- GIS objects. This lists all GIS data objects stored in the GIS Data, Maps and Photos folder.

Setting Elevation for Collar Points

You can set the elevation for all collar points or for a subset of collar points by projecting them onto a surface. This overwrites elevation values in the z column of the collar table, using the data from the selected surface. If the surface does not intersect vertically with the selected points, you can choose how the z values for those unprojected points will be handled.

To set the elevation for collar points from a surface, right-click on the collar table in the project tree and select **Set Elevation**. The **Set Elevation from Surface** window will appear:

🖉 Set Elevation fro	m Surface		×
Set elevation for '	collar'		
Query filter:	🖓 collar: Stage	e 1 Drilling	~
Select surface:	i Topography		~
Unprojected point		d opto the ourf	
·	annot be projecter ation values to:		ace.
 Leave unchage 		0	~
? <u>c</u>	ancel	<u>о</u> к	

Select from the surfaces available in the project and set a query filter, if required.

Next, select how unprojected points should be handled. There are three options:

- Assign elevation values to sets the z values to a fixed elevation for all unprojected points.
- Leave elevation values empty clears the z values for all unprojected points.
- Leave unchanged makes no changes to the z values for unprojected points.

Click **OK** to set elevation values.

The collar table will be updated with an additional column, z_on_terrain:

✓ ♣	Projects		Scer	ie View	C	Central Proje	ects	Collar	×	\triangle	O Alex Rock
Fix Erro > Collar E > Query											
Ignored	trench	id	^ holeid	x	у	z	z_on_terrain	maxdepth	Completed		1
		1	M001	3999.231	7499.063	727.169	727.112658	250.0	1996-03-05		
		2	M002	4050.382	7500.755	726.926	726.778757	-250.0	1996-03-09		
		3	M003	4098.904	7500.572	727.68	727.619181	250.0	1996-03-14		
		4	M004	4149.058	7501.102	728.876	729.560285	275.0	1996-03-20		
		5	M004	4199.59	7499.877	729.739	730.533700	300.0	1996-03-27		
		6	M006	4250.21	7099.258	707.249	707.199124	480.0	1996-04-09		
		7	M007	4249.95	7149.795	703.073	702.342256	425.0	1996-04-23		
		8	M008	4250.86	7200.874	706.324	706.321854	409.0	1996-04-30		

The original z values are preserved in the z column. To switch back to the original z values, click on **Collar Elevation**, then select the original column:

✓ ♣ F	Projects		Scene	View	C	Central Proje	ects	🔁 collar	×	\bigtriangleup	Q Alex Rock	
Fix Erro		?										
Collar eleva	tion column	to use										
() z		-		_								
z_on	_terrain											
> Query	All 172 rows											
Ignored	trench	id ^	holeid	x	у	z	z_on_terrain	maxdepth	Completed			
Ignored	trench	id ^ 1	holeid M001	x 3999.231	y 7499.063	z 727.169	z_on_terrain 727.112658	maxdepth 250.0	Completed 1996-03-05			
Ignored												
		1	M001	3999.231	7499.063	727.169	727.112658	250.0	1996-03-05			
		1 2	M001 M002	3999.231 4050.382	7499.063 7500.755	727.169 726.926	727.112658 726.778757	250.0 -250.0	1996-03-05 1996-03-09			
		1 2 3	M001 M002 M003	3999.231 4050.382 4098.904	7499.063 7500.755 7500.572	727.169 726.926 727.68	727.112658 726.778757 727.619181	250.0 -250.0 250.0	1996-03-05 1996-03-09 1996-03-14			
		1 2 3 4	M001 M002 M003 M004	3999.231 4050.382 4098.904 4149.058	7499.063 7500.755 7500.572 7501.102	727.169 726.926 727.68 728.876	727.112658 726.778757 727.619181 729.560285	250.0 -250.0 250.0 275.0	1996-03-05 1996-03-09 1996-03-14 1996-03-20			
		1 2 3 4 5	M001 M002 M003 M004 M004	3999.231 4050.382 4098.904 4149.058 4199.59	7499.063 7500.755 7500.572 7501.102 7499.877	727.169 726.926 727.68 728.876 729.739	727.112658 726.778757 727.619181 729.560285 730.533700	250.0 -250.0 250.0 275.0 300.0	1996-03-05 1996-03-09 1996-03-14 1996-03-20 1996-03-27			

If you switch back to using the original z column, the $z_on_terrain$ column will remain in the collar table.

Geological Models

The model building process involves several key steps:

- Creating the project and setting up the modelling environment
- Importing borehole data and correcting errors
- Importing other required data
- Visualising the data in the scene and inspecting it to make sense of the model that will be built. It is at this stage that you might create new borehole data columns to select data that will be the basis of geological models.
- Creating a basic GM, then refining its boundary and defining a fault system
- Modelling the contact surfaces
- Setting the cutting relationships between the different contact surfaces and generating volumes

A fault system can also be defined that divides the geological model into subunits in which the internal structure can be defined independent of the other subunits in the model. This is described in <u>Faulted</u> <u>Models</u>.

The rest of this topic describes the process of creating a geological model. It is divided into:

- Creating a New Geological Model
- The Geological Model in the Project Tree
- Geological Model Display
- Copying a Geological Model
- Creating a Static Copy of a Geological Model
- Geological Model Volumes and Surfaces Export Options
- Extracting Model Volumes

A geological model can be created using only a basic set of parameters. The only parameter that cannot be changed once the model has been created is the base lithology.

Creating a New Geological Model

To create a new geological model, right-click on the **Geological Models** folder and select **New Geological Model**. The **New Geological Model** window will open, together with a set of controls in the scene that help in defining the model extents.

The Base Lithology

Select the borehole data column that will be used as the basis of a model from the **Base Lithology Column** list. If you do not wish to use lithology data as the basis for the model, select **<None>**. This may be the case if, for example, you want to build a model from points data or from an imported map. If you select **<None>**, you will need to manually define the lithologies that will be modelled.

If more than one column of lithology data is available for creating models, be sure to choose the correct one as it cannot be changed once the initial model has been created. If after creating and modifying the model, you find you need to modify the borehole data, resulting in a new lithology column, you can use that new column to create contact surfaces using **Other Contacts** options.

You can also filter the borehole data used to build the geological model using query filters. To do so, select the required query filter from the **Filter data** list. Once the model has been created, you can remove the filter or select a different filter.

Surface Resolution

The surface resolution setting Leapfrog Works automatically uses as the default is based on the data available in the project. Set the surface resolution for the model as a whole and choose whether or not the resolution will be adaptive. See <u>Surface Resolution in Leapfrog Works</u> for more information on the effects of these settings.

Later, while refining the model, you can change the resolution of each surface and enable or disable adaptive resolution. See Surface Resolution for a Geological Model.

Model Extents

A geological model is initially created with a basic rectangular set of extents aligned with the south/north and east/west axes. You can define the model's extents in three ways:

- Enter the coordinates.
- Select **Enclose Object** and choose from the list of objects in the project. If the model is based on borehole data, select the lithology segments from the **Enclose Object** list.
- Use the controls that appear in the scene. The orange handle adjusts the centre of the plane and the red handles adjust the size.


See Object Extents for more information.

Enter a **Name** for the model that describes the purpose of the model. This **Name** will be used in naming the objects that will be added to the model. Click **OK** to create the new model. The new geological model will be created and added to the **Geological Models** folder.

See Editing a Geological Model for information on how to change the basic settings for the model.

The Geological Model in the Project Tree

The objects under the geological model in the project tree represent different parts of the model:



• The **Boundary** object defines the limits of the geological model. When the model is first created, this is the rectangular model extents. If a topography has been defined, it is automatically used for as the

upper boundary. See <u>Modifying a Geological Model's Boundary</u> for more information about modifying the boundary.

- The Fault System object defines faults and their interactions in the model. See Faulted Models.
- The **Lithologies** object describes all the lithological units to be modelled and the colours that are used to display them on the screen. It is generated automatically from all the lithologies identified in borehole data selected when the model is created. If no column was selected, you will need to define the lithologies manually before you start modelling the lithology layers.
- The **Surface Chronology** object describes the contact surfaces in the model, organised in chronological order, from youngest to oldest. These surfaces and their chronology determine how the volume inside the model extents is divided into lithological units. When the model is first created, the **Surface Chronology** is empty, but it will eventually hold all contact surfaces and inputs to them.
- The Output Volumes folder contains all the volumes generated in building the geological model. When the model is first created, the Surface Chronology is empty and so there is only a single output volume in the Output Volumes folder. This volume fills the model's extents and is called "Unknown". Once contact surfaces have been generated and added to the Surface Chronology object, new volumes will be generated and added to the Output Volumes folder.

Geological Model Display

Right-click on the geological model in the project tree to view its display options:

- The **View Object** option adds the geological model to the shape list as a single object. You can also display the geological model in this way by dragging it from the project tree into the scene. Change the visibility of the model's volumes by clicking the **Edit Colours** button in the shape list.
- The **View Output Volumes** option adds the model to the scene as a series of output volumes. It is the equivalent of dragging the **Output Volumes** folder into the scene. Change the visibility of the model's volumes individually.
- The View Surface Chronology option displays the surfaces that are used to divided up the model.
- The **View Fault Block Boundaries** option is only available when a fault system has been defined and enabled for the model. Selecting **View Fault Block Boundaries** displays the fault blocks without displaying the lithology layers.

Copying a Geological Model

Creating a copy of a geological model is a useful way of experimenting with changes to a model.

To copy a geological model, right-click on it in the project tree and select **Copy**. Enter a name for the copy of the model and click **OK**. The copy will be added to the project tree.

Creating a Static Copy of a Geological Model

Creating a static copy preserves a snapshot of a geological model that does not change, even when changes are made to the data on which the original model was dependent. This is a useful way of storing historical models and comparing models. Static copies can be exported from Leapfrog Works, as described in Geological Model Volumes and Surfaces Export Options below.

To create a static copy of a geological model, right-click on it in the project tree and select **Static Copy**. Enter a name for the copy of the model and click **OK**. The copy will be added to the **Geological Models** folder.

You can also import static geological models from Central, as described in <u>Importing Central Data</u> <u>Objects</u>.

In the project tree, the static copy () is made up of a **Legend** object (), a boundary (), a fault system (), the output volumes () and all surfaces created in building the model. The surfaces can be used elsewhere in the project and exported for use in other projects.

To view the date a static copy was created, right-click on it in the project tree and select **Properties**. The date the copy was created is shown in the **General** tab.

Geological Model Volumes and Surfaces Export Options

There are three options for exporting a geological model's output volumes and surfaces. These are:

- Export an output volume or a surface as a mesh. Right-click on it in the project tree and click **Export**. You will be prompted for a file name and location. See <u>Exporting a Single Mesh</u>.
- Export an output volume as a thickness grid. Right-click on it in the project tree and click **Export Thickness Grid**. See <u>Thickness Grids</u>.
- Export multiple output volumes and surfaces. Right-click on the geological model in the project tree and select **Export**. See Exporting Multiple Meshes from Models.

When exporting output volumes, the **Merge output lithology volumes** setting in the geological model's **General** tab (see <u>Editing a Geological Model</u>) determines how the output volumes are handled when they are exported. If this setting is enabled, internal walls and surface seams will be removed from volumes of the same lithology.


Extracting Model Volumes

There are number of options for extracting meshes from geological model output volumes. These options are available by right-clicking on volumes in the **Output Volumes** folder and selecting **Extract Mesh**. There are five options:


- Mesh Parts
- Component Surfaces
- Younger Surfaces
- Older Surfaces
- Boundary Surfaces

The **Mesh Parts** option is the same as the option available on meshes elsewhere in the project. See Extracting Mesh Parts.

The **Younger Surfaces**, **Older Surfaces** and **Boundary Surfaces** options extract different parts of the selected volume, which are saved into the **Meshes** folder. Here, the boundary surfaces are shown in blue, the younger surfaces in yellow and the older surfaces in orange:



Component Surfaces extracts a separate surface for each volume the selected volume interacts with, including the boundary. The component surfaces are named after the boundary they are derived from and saved into a subfolder in the **Meshes** folder. For example, here meshes have been extracted for each contact with the Intermineral diorite volume:



Editing a Geological Model

Once a geological model has been created, you can change the model's resolution and other basic settings by double-clicking on the model in the project tree. The **Geological Model** window will open with the **General** tab selected. The other tabs in the **Geological Model** window represent the different parts of the geological model. It is generally more useful, however, to work with these parts of the model on an individual basis by either double-clicking on the object in the project tree or right-clicking and seeing what options are available.

The rest of this topic describes how to change the basic settings for a geological model. It is divided into:

- Changing the Query Filter
- Surface Generation Options
- Volume Generation Options

Changing the Query Filter

Although the **Base lithology column** cannot be changed once a geological model has been created, you can change the filters applied to the data. Any filters defined for the lithology table used to define the model can be applied to the **Base lithology column**:

Geological I	Model - M Camp	aign GM			>
General	Devendence	Fault Custom	Linkslasias	01	
General	Boundary	Fault System	Lithologies	Chronology	_
Base Lith	ology				
Base lit	thology column:	M_Geology - Sir	nple_RockType		
Filter d	ata:	<none></none>		ĸ	
Surface (Generation	<none></none>			
		🗸 🏢 collar			
Surface	e resolution:	🖓 M c	ampaign		
<u>S</u> nap to	o data:				
Maxim	um snap <u>d</u> istanc	e:	-•	50.0%	
Exa	ct clipping				
Volume G	Seneration				
Do no	ot merge output v	olumes		\sim	
?)		Cano	el	<u></u> ΟK	
_					

Individual surfaces in the geological model can inherit the query filter from the parent geological model or can use a different filter. To change what query filter is used for a surface, double-click on the points used to create the surface and change the **Query filter** setting in the **Lithology** tab:

Edit Intrusion
Lithology Compositing Point Generation Intrusion in column Simple. RockType' on table M_Geology Query filte: Vone Query filte: Query fi

You may first need to disable the Inherit from GM option to change the Query filter.

Surface Generation Options

The **Surface Generation** options apply to the model as whole, but can be overridden for individual surfaces.

General	Boundary	Fault System	Lithologies	Chronology
Base Lith	ology			
Base li	thology column	: M_Geologs-Sir	mple_RockType	
<u>F</u> ilter d	ata:	<none></none>		~
Surface (Generation			
Surfac	e resolution:	50.0 🗘	Adaptive	
<u>S</u> nap to	o data:	Off		~
Maxim	um snap <u>d</u> istan	ce:	-•	50.0%
- Eva	ct clipping			

See <u>Surface Resolution for a Geological Model</u> for information on changing the **Surface resolution** and **Adaptive** settings for individual surfaces.

When **Exact clipping** is enabled, model surfaces will be generated without "tags" that overhang the model boundary. This setting is enabled by default when you create geological model.

Surfaces created in building the geological model can be set to snap to the data used in the model. There are three options:

- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to surfaces as part of the model refinement process.
- Drilling only. Surfaces snap to borehole data within the Maximum snap distance but not to other data used to modify surfaces.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

If you need surfaces to honour borehole data but treat other data objects as interpretations, select **Drilling only**. If you want finer control over what objects are snapped to, you can do this on a surface-by-surface basis. See:

- Surfacing Options for Deposits and Erosions
- Surfacing Options for Intrusions
- Surfacing Options for Veins
- Changing Surfacing Options for an Offset Surface
- Surfacing Options for a Structural Surface

Volume Generation Options

The **Merge output volumes** setting determines whether or not output volumes of the same lithology are merged when the volumes are exported. If **Merge output volumes** is set to **Fast** or **Robust**, internal walls and surface seams will be removed from volumes of the same lithology. Either option is suitable when you are using output volumes as extents for other models.

The difference between Fast and Robust is the algorithm used:

- Fast removes back-to-back triangles before generating output volumes.
- **Robust** uses the volume cutter, which tracks where the triangles originated and is, therefore, a slow option for building output volumes.

If there are issues with surfaces exported to other modelling packages using the **Do not merge output volumes** setting, try the **Fast** setting. If there are still issues, try the **Robust** setting.

When projects created in earlier versions of Leapfrog Works are opened in Leapfrog Works 4.0, the **Volume Generation** setting for any existing geological models will not be changed.

Surface Resolution for a Geological Model

When you create a geological model (see <u>Creating a New Geological Model</u>), the surface resolution is set for the model as a whole. When surfaces and boundaries are created as part of the model-building process, their resolution is inherited from the geological model:

- For deposit and erosion contact surfaces, stratigraphic sequences and model boundaries, the resolution is the same as the geological model.
- For intrusion contact surfaces, the resolution is half that set for the geological model.
- For vein contact surfaces, the resolution is the same as the geological model, but the **Adaptive** option does not apply.

You can change the resolution and enable or disable the adaptive isosurfacer on a surface-by-surface basis. This is useful if you want to build a detailed model of some lithologies without increasing processing time for other volumes.

To change the resolution settings for a contact surface, double-click on the surface in the project tree, then click on the **Surfacing** tab:

Edit D2 - D1 cont	icts		
Lithologies	Surfacing Inputs	Trend	
Boundary filter:	Custom		~
Snap to data:	Inherit from GM (Of	f)	~
Maximum snap	distance:		20.00
ounded [650	lution: 40.0 🔾	Adaptive	
Name: D2 - D1 c	ontacts		

For a lateral extent or fault, simply double-click on the surface in the project tree to change its resolution settings.

Untick the **Inherit resolution from GM** box to change the resolution settings for a surface. This setting may be disabled, depending on the data used to create the boundary or surface.

The resolution of intrusion contact surfaces is also affected by the point generation parameters. See <u>Intrusion Point Generation Parameters</u> for more information.

Modifying a Geological Model's Boundary

Geological models are created with a basic set of rectangular extents that can then be refined using other data in the project. These extents usually correspond to the ground surface and known boundaries. Creating extents can also be used to restrict modelling to a particular area of interest; for example, modelling can be restricted to a known distance from boreholes by applying a distance function as a lateral extent. Extents do not need to be strictly vertical surfaces, and can be model volumes. It is also possible to define a base that serves as the geological model's base.

When a topography is defined for the project, it will be automatically applied as a geological model's upper boundary when the model is created.

The rest of this topic describes how to create and work with geological model extents. It is divided into:

- Creating Extents for a Geological Model
- Changing an Extent's Settings
- Adding Data to an Extent
- Editing an Extent With a Polyline
- Editing an Extent With Structural Data
- Removing an Extent From a Geological Model

Creating Extents for a Geological Model

To create an extent, expand the geological model in the project tree. Right-click on the **Boundary** object and select from the **New Lateral Extent** or **New Base** options. Follow the prompts to create the extent, which will then appear in the project tree under the model's **Boundary** object. For example, this geological model has two lateral extents, one from a polyline and the other from GIS data:



New extents are automatically applied to the boundary being modified. Leapfrog Works usually orients a new extent correctly, with red presenting the inside face of the extent and blue representing the outside face. If this is not the case, you can change the orientation by right-clicking on the extent in the project tree and selecting **Swap Inside**.

Extent From a Polyline

You can create an extent from a polyline that already exists in the project or you can draw a new one. If you want to use an imported polyline, import it into the **Polylines** folder before creating the new extent.

To create a new extent from a polyline, right-click on the model's **Boundary** object and select **New Lateral Extent > From Polyline** or **New Base > From Polyline**. In the window that appears, select whether you will create a new polyline or use an existing one:

oundary	×
From	
w Drawing O Existing Polyline	
Curved polyline	
Boundary	
Cancel	ок
	From w Drawing _ Existing Polyline <f curved="" polyline<br="">my Type frace @ Vertical Wall Boundary</f>

For lateral extents, you can create the extent as a **Vertical Wall** or **Surface**. If you create the lateral extent as a **Surface**, you will be able to modify it using additional data, as described below. A lateral extent created as a **Vertical Wall**, however, cannot be modified. A base is always created as a surface and so can be modified as described below.

Click **OK** to generate the new extent. If you have chosen to create a **New Drawing**, the drawing controls will appear in the scene and you can begin drawing, as described in <u>Drawing in the Scene</u>.

The new extent will appear in the project tree as part of the **Boundary** object.

If the surface generated does not fit the polyline adequately, you can increase the quality of the fit by adding more points to the polyline. See <u>Drawing in the Scene</u> for information on adding points to polylines.

Extents created from polylines can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an Extent</u>, <u>Editing an Extent With a Polyline</u> and <u>Editing an Extent With Structural Data</u> for more information.

Extent From GIS Vector Data

GIS data in the project can be used to create a lateral extent or a base for a geological model. Once the data you wish to use has been imported into the project, right-click on the model's **Boundary** object and select **New Lateral Extent > From GIS Vector Data** or **New Base > From GIS Vector Data**. In the window that appears, select the data object you wish to use:

Select Vector GIS To Add	×
GIS Vector	
✓ ☐ GIS Data, Maps and Photos	
Footwall Dyke	
🖾 Hangingwall Dyke	
SIS line	
Streams	
Lateral Extent Type	
Surface Surface	
(?) <u>C</u> ancel <u>Q</u> K	

For lateral extents, you can create the extent as a **Vertical Wall** or **Surface**. If you create the lateral extent as a **Surface**, you will be able to modify it using additional data, as described below. A lateral extent created as a **Vertical Wall**, however, cannot be modified. A base is always created as a surface and so can be modified as described below.

If you select the **Surface** option, you can use the GIS data object with its own elevation data or projected onto the topography:




Using the **On Topography** option makes sense for GIS data as it is, by nature, on the topography. The **On Topography** option also mitigates any issues that may occur if elevation information in the GIS data object conflicts with that in the project.

Click **OK** to create the new extent. The new extent will appear in the project tree as part of the **Boundary** object.

Extents created from GIS data can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an Extent</u>, <u>Editing</u> an Extent With a Polyline and Editing an Extent With Structural Data for more information.

Extent From Points

To create a new extent from points data, right-click on the **Boundary** object for the model you are working on and select **New Lateral Extent > From Points** or **New Base > From Points**. The **Select Points To Add** window will be displayed, showing points data available in the project:



Select the information you wish to use and click **OK**.

The new extent will appear in the project tree as part of the **Boundary** object.

Extents created from points can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an Extent</u>, <u>Editing an</u> <u>Extent With a Polyline and Editing an Extent With Structural Data for more information</u>.

Extent From Structural Data

Planar structural data can be used to create a lateral extent or a base for a geological model. You can create a new structural data table or use a table that already exists in the project. If you want to use categories of structural data in creating the extent, use an existing table and create filters for those categories before creating the lateral extent.

To start, right-click on the **Boundary** object for the model you are working on and select **New Lateral Extent > From Structural Data** or **New Base > From Structural Data**. The **New Structural Data** window will be displayed, showing structural data available in the project:

😫 New Str	uctural Data	×
Structural	Data from	
New D	rawing O Existing Structural Data	
g beig	ica_structural_data	2
Query Filt	er: None	
Name:	Boundary	
	<u>C</u> ancel QK	

Select the **New Drawing** option to draw the structural data points directly in the scene.

Select the **Existing Structural Data** option to use a table in the **Structural Modelling** folder. With this option, you will be able to select from the categories available in the data table, if query filters have been created for those categories:

🗸 New Structural Data 🛛 💙							
Structural Da	_						
	New Drawing Existing Structural Data Selgica_structural_data						
Query Filter:							
Name: belo	None						
	✓ ≤ belgica_structural_data						
Ca	P Block 1						
	Block 2						

Click **OK** to generate the new extent. If you have chosen to create a **New Drawing**, the drawing controls will appear in the scene and you can begin drawing, as described in <u>Creating New Planar</u> <u>Structural Data Tables</u>. To share the new structural data table, right-click on it and select **Share**. The table will be saved to the **Structural Modelling** folder.

The new extent will appear in the project tree as part of the **Boundary** object.

Extents created from structural data can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an</u> <u>Extent</u>, <u>Editing an Extent With a Polyline</u> and <u>Editing an Extent With Structural Data</u> for more information.

Extent From a Surface

To use a surface as an extent for a geological model, right-click on the model's **Boundary** object and select **New Lateral Extent > From Surface** or **New Base > From Surface**. The **Select Boundary** window will appear, showing all the meshes that can be used as an extent:

Select Boundary Mesh		;
Topographies		
Meshes		
> GM Surfaces		
> D Merge Meshes		
✓ ☐ Pit Shells		U
✓ ☐ Pit Designs		
🛞 Ultimate Pit		
🛞 Year 5 Pit design		
🛞 Year 10 Pit design		
> D Pit Walls		
(?)	Ormeri	01/
()	Cancel	<u>0</u> K

Select the required mesh and click **OK**. The extent will be added to the model's **Boundary** object.

You cannot modify an extent created from a mesh by adding data, editing with polylines or structural data or by applying a trend. However, the extent is linked to the mesh used to create it, and updating the mesh will update the extent.

Extent From Distance to Points

Leapfrog Works can calculate the distance to set of points and use the resulting distance buffer as a lateral extent for a geological model. To create a new lateral extent from a distance buffer, right-click on the **Boundary** object for the model you are working on and select **New Lateral Extent > From Distance To Points**. The **Smoothed Distance Buffer** window will appear:

🔏 Smoothed Distar	ice Buffer			×
Locations:		collar	🔛 collar	
Query filter:		None	None	
Distanc <u>e</u> : 200	0			
Anisotropy				
	Dip	Dip Azimuth	Pitch	
Directions:	0	, 0	, 90	
	Maximum	Intermed.	Minimum	
Ellipsoid Ratios:	1	, 1	, 1	
<u>V</u> iew Pla	ane S	Set From <u>P</u> lane	<u>S</u> et to	\sim
<u>N</u> ame: collar dis	stance buffer 200.0			
?		<u>C</u> ancel	<u>о</u> к	

Select the **Distance** and set an **Anisotropy**, if required.

The Ellipsoid Ratios determine the relative shape and strength of the ellipsoids in the scene, where:

- The **Maximum** value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The **Minimum** value is the relative strength in the direction orthogonal to the plane.

You can also use the **Set to** list to choose different options Leapfrog Works has generated based on the data used to build the model. **Isotropic** is the default option used when the model is created.

Click **OK** to create the new extent, which will appear in the project tree as part of the **Boundary** object.

To change the extent's settings, expand the model's **Boundary** object in the project tree and doubleclick on the extent. Adjust the **Distance** and **Anisotropy**, if required.

The resolution of extents is automatically inherited from the geological model. You can change the resolution for an extent if you want more or less detail than for the geological model as a whole. To do so, untick the box for **Inherit resolution from GM** and change the setting.

Extents created from a distance to points function can be modified by adding points data and GIS vector data. See Adding Data to an Extent.

Extent From a Distance Function

A distance function calculates the distance to a set of points and can be used to bound a geological model. You can use an existing distance function as a lateral extent or create a new one.

To use a distance function as a lateral extent, right-click on the **Boundary** object for the model you are working on and select **New Lateral Extent > From Distance Function**. If there are no distance functions in the project, you will be prompted to create a new one. See <u>Distance Functions</u> for information on defining and editing the distance function.

When there are already distance functions in the project, you will be prompted to choose between creating a new function or using an existing one:

🖉 New Lateral Extent		×	
Select Distance Functi			
Distance function: Sistance to drillhole data			
<u>B</u> uffer distance:	450.0	0	
○ Create <u>n</u> ew distanc	e function		
<u>C</u> ;	ancel <u>O</u> K		

To use an existing function, select it from the list and set a **Buffer distance**. Click **OK** to create the lateral extent.

When you create a new distance function, it will be part of the model's **Boundary** object and will not be available elsewhere in the project. To share it within the project, expand the lateral extent in the project tree and right-click on the distance function. Select **Share**. The distance function will be saved to the **Numeric Models** folder.

To change the extent's settings, expand the model's **Boundary** object in the project tree and doubleclick on the extent. The **Edit Distance Buffer** window will appear.

🖌 Edit Distance Buffer 🛛 🗙					
Distance buffer of Distance to fault					
Buffer distance: 100.0					
Inherit resolution from GM					
Surface resolution: 80.0 0					
Name: Distance to fault < 100.0					
<u>C</u> ancel <u>O</u> K					

The resolution of extents is automatically inherited from the geological model. You can change the resolution for an extent if you want more or less detail than for the geological model as a whole. To do so, untick the box for **Inherit resolution from GM** and change the setting.

Base From Lithology Contacts

To create a base from lithlogy contacts, right-click on the **Boundary** object and select either **New Base** > **From Base Lithology** or **New Base > From Other Contacts**.

The only difference in the two methods is that when creating a base from other contacts, you must first select the lithology column from those available in the project.

When defining the base, select the primary lithology and the contacts to use:

Contact in Column 'Simple_RockType' on '	Table 'M_Geology'
Query filter: None	Inherit from GM
Select primary lithology	
AvT	~
Use contacts above Use contacts	s <u>b</u> elow
Contacting/Avoided lithologies:	Ignored lithologies:
GnD (3)	
QzP (72)	
Treat unspecified intervals as	
Ignored Primary Contacting	
Reference Plane	
Vereference riane	
Dip: 0.0	
Dip azimuth: 0.0	
View Plane Set From Plane	
View Mane Set From Mane	
Name: AvT contacts	

For complex geologies, the up and down directions for the base may not be clear. If this is the case, untick the **Horizontal Plane** box. A reference plane will appear in the scene, with the up-facing surface

labelled A and the downward-facing surface labelled B. Controlling the position of the reference plane is similar to controlling the position of the moving plane:

- Use the handles in the scene window to move the plane.
- Set the **Dip** and **Dip Azimuth** values in the **New Contact Points** window. The reference plane will be updated in the scene.

When you disable the **Horizontal plane** option for the **Reference Surface**, the number of contacts is longer displayed in the lithologies lists, as the number of contact points is not updated when the reference surface used changes.

Once the reference plane is correctly oriented, click the **Set From Plane** button.

Click **OK** to create the base, which will appear under the **Boundary** object. The new base will automatically be added to the model.

Each geological model can have only one base defined, so if you wish to define a new base, you must first delete the existing base from the model. Do this by right-clicking on the **Base** object and selecting **Delete**. You can also choose not to use the base you have defined. See <u>Removing an Extent</u> From a Geological Model for more information.

Changing an Extent's Settings

For geological model extents created from polylines, GIS data, points and structural data, you can change the extent's settings by double-clicking on it in the project tree.

🞸 Edit belgica_structural_data	×
Surfacing Inputs Trend	
Snap to data: Off	× 5.00
Maximum snap distance: Surface resolution: 10.0	
Name: belgica_structural_data	

In the **Surfacing** tab, you can change surface resolution and contact honouring options, which are described below. In the **Trend** tab, you can apply a trend to the extent, which is described in <u>Applying a</u> <u>Trend</u>.

Surface Resolution

For geological models, the resolution of extents and whether or not the adaptive isosurfacer is used is automatically inherited from the geological model. You can change these settings for an extent if you want more or less detail than for the geological model as a whole. To do so, untick the box for **Inherit resolution from GM** and make the required changes.

Contact Honouring

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations. For extents, the **Snap to data** setting in the **Surfacing** tab determines whether or not the extent honours the data used to create it. Options are:

- Off. The extent does not snap to the data used to create it. This is the default setting.
- All data. The extent snaps to all data within the **Maximum snap distance**, which includes borehole data and any data added to the extent.
- Drilling only. The extent snaps to borehole data and data objects derived from borehole data within the **Maximum snap distance**, but not to other data used to modify the extent. For example, the extent will honour points data derived from borehole data, but not points data imported into the **Points** folder.
- Custom. The extent snaps to the data objects indicated in the **Inputs** tab that are within the **Maximum snap distance**.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

The snap setting for the geological model will be used if **Snap to data** is set to **Inherit from GM**.

Whatever the setting, you can see what objects are snapped to by clicking on the **Inputs** tab.

If you need the extent to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Applying a Trend

You can adjust an extent created from polylines, GIS data, points and structural data by applying a trend to it. To do this, add the extent to the scene. Next, double-click on the extent in the project tree and click the **Trend** tab.

Often the easiest way to apply a trend is to click on the **Draw plane line** button (27) and draw a plane line in the scene in the direction in which you wish to adjust the surface. You may need to rotate the scene to see the plane properly.

The **Ellipsoid Ratios** determine the relative shape and strength of the ellipsoids in the scene, where:

- The **Maximum** value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The **Minimum** value is the relative strength in the direction orthogonal to the plane.

Once you have adjusted the plane to represent the trend you wish to use, click the **Set From Plane** button to copy the moving plane settings.

The **Set to** list contains a number of different options Leapfrog Works has generated based on the data used in the project. **Isotropic** is the default option used when the extent was created. Settings made to

other surfaces in the project will also be listed, which makes it easy to apply the same settings to many surfaces.

Click **OK** to apply the changes.

See <u>Global Trends</u> for more information.

Adding Data to an Extent

Extents created from polylines, GIS data, points and structural data can be modified by adding points data objects, GIS vector data and structural data. Extents created from a distance to points function can be modified by adding points data and GIS vector data. To add data to an extent, right-click on the extent in the project tree and select the data type you wish to use from the **Add** menu.

- Points data. Select from the points data objects available in the project and click **OK**.
- GIS vector data. Select from the GIS vector data available in the project and click **OK**.
- Structural data. Select from the structural data tables available in the project. If the selected table has query filters defined, you can apply one of these filters by selecting the required query from the list. Click **OK** to add the selected data to the extent. An alternative to adding an existing structural data table to an extent is to edit the extent with structural data. This is described in Editing an Extent With Structural Data below.

You can also add a polyline that already exists in the project. To do this, right-click on the extent in the project tree and select **Add > Polyline**. You will be prompted to choose from the polylines in the **Polylines** folder.

Editing an Extent With a Polyline

You can edit an extent using a polyline, which is described in <u>Editing Surfaces With Polylines</u>. A polyline used to edit an extent will be added to the project tree as part of the extent. To edit the polyline, rightclick on it and select **Edit Polyline** or add it to the scene and click the **Edit** button (\mathcal{O}) in the shape list. If you wish to remove the polyline from the extent, right-click on it in the project tree and select **Delete** or **Remove**.

To add an existing polyline to a geological model extent, use the **Add > Polyline** option.

Editing an Extent With Structural Data

You can edit an extent using structural data, which is described in <u>Editing Surfaces With Structural Data</u>. A structural data table will be added to the project tree as part of the extent. To edit the table, right-click on it and select **Edit In Scene** or add it to the scene and click the **Edit** button (\mathcal{O}) in the shape list. If you wish to remove the table from the extent, right-click on it in the project tree and select **Delete** or **Remove**.


Removing an Extent From a Geological Model

If you have defined an extent and want to remove it from the model, there are two options. The first is to right-click on the extent in the project tree and click **Delete**. This deletes the extent from the model, but does not delete parent objects from the project unless they were created as part of the model, e.g. a polyline used as a lateral extent but not shared within the project. Use this option only if you are sure you do not want to use the extent.

The second method is useful if you are making changes to the extent and do not want to recompute the model with each change. Double-click on the model's **Boundary** object or double-click on the model and click on the **Boundary** tab. The **Boundaries** part of the window lists all objects used as extents for a geological model:

Model Exten	s			
	Mini	imum	Maxi	mum
X (East):	3700.0	÷	4900.0	
Y (North):	7050.0	Ŷ	7990.0	
Z (Elev):	180.0	¢	760.0	
			Enclos	e Object 🕓
Boundaries				
Use top Use bas				
Lateral Ext				
🔽 📦 E	ast boundary	-		
V 🔊 🗸	Vest boundary			

Untick the box for extents to temporarily disable them in the model. The model will be reprocessed, but you can then work on the extent without reprocessing the model. Disabled extents will be marked as inactive in the project tree:



Model Lithologies

To view the lithologies used for a geological model, you can:


- Double-click on the geological model in the project tree and then click on the **Lithologies** tab.
- Double-click on the **Lithologies** object for the geological model in the project tree.

All the lithologies defined for the geological model are displayed, together with the colours used to display them:

Geological I	Model - Maia G	eological Model			
General	Boundary	Fault System	Lithologies	Chronology	
Code			Colou	r 🚺	
Unknow	vn			1	
Casing					
D1					
D2				\sim	
D3					
D4				Ă	
D5				11	
Dike					
GnD					
\oplus	Rena	ame			
?		Cano	cel	<u>0</u> K	

Click a colour chip to change the colours used to display the lithologies.

The order of the lithologies in this window is the order used for the model's legend when the model is displayed in the scene. Click on a lithology in the list and use the arrow keys to reorder the list.



Use the Shift or Ctrl keys to select multiple lithologies. This is useful for changing multiple colour chips to a single colour or for moving multiple lithologies up and down in the list.

If the geological model was created from borehole data, the lithologies are automatically generated from that data. There is also an additional lithology, "Unknown", which is used to label lithologies that cannot be labelled using known lithologies. This is the case when a geological model is first created and no contact surfaces have been defined. The entire model volume has no identified lithologies and so is assigned as "Unknown".

An alternative to setting unidentified lithologies to "Unknown" is to select one of the defined lithologies as the "background lithology". To do this, double-click on the model's **Surface Chronology** and set **Background lithology** to one of the available lithologies. When you set the background lithology for a geological model and then enable the fault system, the background lithology will be copied to each fault block.

If there is no borehole data in the project or if the model is not based on borehole data, you will need to define the lithologies one-by-one. To do this, click on the **Add** button, enter a name for the lithology and choose a colour.

Faulted Models

This topic describes how to use the fault system to create and organise faults:

- The Fault System
- Fault Interactions
- Activating the Fault System
- Copying the Surface Chronology to an Empty Fault Block
- Faulted Model Display Options

Each geological model is created with a **Fault System** object that is used to construct faults. Once the faults are active in the geological model, the geological model will be divided into separate fault blocks, which will appear in the project tree as part of the model. Here, the geological model has been divided into five fault blocks:

🗸 🗀 Geological Models						
🗸 🍘 Faulted GM						
> 🧀 Boundary						
> 🍫 Fault System						
Lithologies						
> 🌍 Faulted GM unit 1						
> 🃦 Faulted GM unit 2						
> 🌍 Faulted GM unit 3						
> 🃦 Faulted GM unit 4						
> 🌍 Faulted GM unit 5						
> Output Volumes						

Each fault block has its own **Surface Chronology**, which can be modified without affecting other fault blocks in the geological model. There is no top-level **Surface Chronology** for the geological model once the **Fault System** has been activated. This means that lithology layers can be constructed for a faulted model in two ways:

- Define the **Surface Chronology** before enabling the **Fault System**. All surfaces defined for the unfaulted model will automatically be copied to each fault block. Some surfaces defined for the model as a whole will not occur in every fault block, which can be corrected by working with the surfaces in each fault block.
- Enable the **Fault System** before any surfaces are defined in the unfaulted model, then define the **Surface Chronology** for each fault block. An aid to working with a faulted model in this way is the ability to copy contact surfaces from one faulted block to another. See <u>Copying the Surface</u> <u>Chronology to an Empty Fault Block</u> below.

Which approach is best depends on the model being built. You may already know where the faults are and choose to define them and subdivide the geological model before defining any lithology layers. On the other hand, sometimes it is not apparent where the faults are until the layers have been built, in which case you can add the new fault, activate it in the model, then work with the surfaces in each fault block.

The Fault System


When a geological model is first created, the **Fault System** object is empty. To create faults, right-click on the **Fault System** object and select from the options available. Many of these options are similar to those for creating lateral extents. For more information, see:

- Extent From a Polyline
- Extent From GIS Vector Data
- Extent From Points
- Extent From Structural Data
- Extent From a Surface

Faults created from polylines and GIS vector data can be created as vertical walls or surfaces. Faults created as surfaces can be modified by adding further data, as described in <u>Editing Faults</u>.

Creating a fault from the base lithology or other contacts is similar to creating contact surfaces. See <u>Deposits and Erosions From the Base Lithology</u> and <u>Deposits and Erosions From Other Lithology</u> <u>Contacts</u> for more information.

Faults (*) will appear in the project tree as part of the **Fault System** object (*) and can be expanded to show how they were created. Here, Fault 1 was created from a GIS line draped on the topography (^(A)) and structural data (^(C)):



Once faults have been created, you can modify them as described in Editing Faults.

Fault Interactions

Once all the faults required have been created, you can start defining the interactions between the faults by double-clicking on the **Fault System** object. The **Geological Model** will be opened with the **Fault System** tab displayed:

😵 Geological Model - Faulted GM 🛛 🗙						
General	Boundary	Fault System	Lithologies			
Fa <u>u</u> lt s	ystem chronology	<i>I</i> :				
	Faults					
_	📌 Fault 1 (On 1	Fopography)	\sim			
_	📌 Fault 2 (On 1					
	📌 Fault 3 (On 1					
~	📌 Fault 4 (On 1	Гopography)				
Interac	tions of selected	fault:				
Intera	action Type Fau	lt Side				
\oplus	TÎIT					
?	<u>C</u> an	icel	<u>о</u> к			

To add an interaction, click on a fault, then click the **Add** button. Select the **Interaction Type** and set how the faults interact:

B	Geologica	l Model - Faulted	GM				×
r	General	Boundary	Fault System	Lithologies			1
	Fa <u>u</u> lt sy	stem chronology:					
	~	🔶 Fault 1 (On To	opography)			\wedge	
	~	✦ Fault 2 (On To	opography)				
		✦ Fault 3 (On To	opography)			\sim	
	~	🛧 Fault 4 (On To	opography)				
	Interact	ions of Fault 3 (Or	n Topography):				
	Intera	ction Type	Fault		Side		
	Termi	inates against \vee	Fault 1 (On To	pography) 🗸	North West	-X	
					North West	~	
					South East		
	\oplus	Ē					
	?			<u>C</u> ancel		<u>о</u> к	

Once you have defined each fault interaction, click **OK** to generate the fault system. Add the **Fault System** object to the scene to check that the faults interact correctly.

You can also edit fault interactions by double-clicking on individual faults. The **Edit Fault** window will open, which shows only the interactions for the selected fault:

B	Edit Fault						×
	Interactions	Surfacing	Inputs	Trend			
	Interactions	of Fault 3 (Or	1 Topography):				
	Interaction	Туре	Fault		Side		
	Terminate	s against \sim	Fault 1 (On T	opography) 🗸	North West	~	
	\oplus						
1	Name: Fault 3	(On Topograf	ohy)				
	?			<u>C</u> ancel		<u>о</u> к	

Faults are not active in the geological model until the box is ticked for each fault in the **Fault System** window, as described in <u>Editing Faults</u>. This means you can check the fault system without regenerating the geological model.

Activating the Fault System

Activating the fault system divides the geological model into fault blocks, which can result in considerable processing time for complex models. It is important, therefore, to define fault interactions before enabling the fault system, otherwise a large number of fault blocks could be generated that significantly increase processing time. See <u>Fault Interactions</u> above.

To activate the fault system in the geological model, double-click on the **Fault System** object once again and tick the box for each fault. The model will be divided into separate fault blocks that can be worked with in a similar manner to the geological model as a whole.

Copying the Surface Chronology to an Empty Fault Block

If you are working with a faulted model and have defined the **Surface Chronology** for one fault block, you can copy the **Surface Chronology** to the empty fault blocks. To do this, right-click on the **Surface Chronology** for which you have defined surfaces and select **Copy Chronology To**. In the


window that appears, select the fault blocks you want to copy contacts to and click **OK**. The surfaces will be copied and you can modify them without affecting the surfaces in the other fault blocks.

Faulted Model Display Options

Drag the model into the scene or right-click on it and select **View Object**; these options add the model to the shape list as a single object and you can change the visibility of each lithology by clicking the **Edit Colours** button. You can also add the model to the scene as a series of output volumes by right-clicking on the model and selecting **View Output Volumes**.

Another display option lets you view the individual fault blocks without displaying the lithology layers. Right-click on the model and select **View Fault Block Boundaries**.

To work with a specific fault block, click on it in the scene. The window that appears displays the name of the selected fault block:



You can also view the output volumes for each individual fault block by right-clicking on the fault block in the project tree and selecting **View Output Volumes**.

Editing Faults

Once a fault has been defined, you can refine it in several ways:

- Add other data. This option is available for faults created as surfaces, but not for those created as vertical walls. Right-click on the surface to see the options available, which will depend on how the surface was created.
- Edit the surface with a polyline. Right-click on the surface in the project tree and select either **Edit > With Polyline**. See Editing Surfaces With Polylines for more information.
- Edit the surface using structural data. Right-click on the surface and select **Edit > With Structural Data**. See Editing Surfaces With Structural Data for more information.

The rest of this topic describes other options for editing faults. It is divided into:

- Surfacing Options for Faults
- Changing Fault Inputs
- Applying a Trend to a Fault

Surfacing Options for Faults

To change surfacing options for a fault, double-click on the fault in the project tree, then click on the **Surfacing** tab.

See <u>Surface Resolution for a Geological Model</u> and <u>Honouring Surface Contacts</u> for information about the settings in the **Surfacing** tab.

The settings in the **Surfacing** tab will be disabled if the fault inputs have been replaced with a mesh.

Boundary Filtering

When data objects are added to a fault, there are two ways to handle the data that lies outside the fault boundary:

- Filter the data. The fault is only influenced by the data that falls inside the fault boundary.
- Leave the data unfiltered. The fault is influenced by the data both inside and outside the fault boundary.

The **Boundary filter** setting determines how data used to define the fault is filtered:

- Off. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- **Custom**. Only the data objects specified in the **Inputs** tab are filtered.

Snapping to Data

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab.

For faults, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. The fault surface does not snap to the data used to create it.
- All data. The fault surface snaps to all data within the **Maximum snap distance**, which includes borehole data and any data added to the fault.
- **Drilling only**. The fault surface snaps to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the fault. For example, the fault surface will honour points data derived from borehole data, but not points data imported into the **Points** folder.
- Custom. The fault surface snaps to the data objects indicated in the Inputs tab.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

If you need the fault surface to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Changing Fault Inputs

For faults, the **Inputs** tab shows all the data objects used to create the fault and whether the **Snap** and **Boundary filter** options are enabled for each object used to define the fault. If an input has any query filters defined, you can select one in this window.

8 E	dit Fault						×
	Interactions	Surfacing	Inputs	Trend			
	O Mesh:	Select Mesh					
	Other ot	bjects:					
	Snap	Boundary filter	Input		Query Filter		
		~	🙈 Fault 3 ((On Topography)			
		~	🛃 Fault_F	3	No query filter		
		~					
	⊕ 1						
Na	me: Fault	3 (On Topograph	ıy)				
(?	\bigcirc				<u>C</u> ancel	<u>0</u> K	

You can also replace the fault's inputs with a single mesh or add more data to the fault.

Replacing Fault Inputs With a Single Mesh

To replace the fault inputs with a single mesh, click on the **Mesh** option, then select from the meshes available in the project.

Mesh:	Select Mesh				Select Mes				
Other ol	bjects:				∼ ⊡ Mes	nes Fault2			
Snap	Boundary filter	Input	Query Filter		-	Fault 3			
	~	🖉 Fault 3 (On Topogr			> 🗋 Geo	logical Mo	odels		
	\checkmark	Cault_F3	No query filter						
							<u>C</u> ancel	<u>o</u> k	
+							<u>C</u> ancel	<u>o</u> k	
÷	1						Cancel	<u>o</u> k	
	III 3 (On Topograp	hy)					<u>C</u> ancel		

When you select a single mesh to define the fault, all other inputs listed in the **Inputs** tab will be removed from the fault. This can result in objects being deleted from the project. For example, if the fault has been edited using a polyline, the polyline will be deleted when the inputs are replaced with the mesh. If you wish to retain such inputs, be sure to share the object before changing the inputs. See <u>Sharing Objects</u> for more information.

The snap and boundary filtering controls in the **Surfacing** tab will be disabled as the settings from the geological model will be used. The settings in the **Trend** tab will also be disabled as it is not possible to set a trend for a fault defined from a mesh.

Adding Data to the Fault

To add more data to the fault, click on the **Select Objects** button, then select from the suitable objects available in the project.

Snap Settings for Individual Inputs

The **Snap** setting determines whether or not the faults surface honours a particular data object. Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations, as discussed in <u>Honouring Surface Contacts</u>. To change snap settings for a fault, click on the **Surfacing** tab and set **Snap to data** to **Custom**. You will then be able to change **Snap** settings in the **Inputs** tab.

Boundary Filtering Settings for Individual Inputs

When data objects are added to a fault, there are two ways to handle the data that lies outside the fault boundary:

- Filter the data. The fault is only influenced by the data that falls inside the fault boundary.
- Leave the data unfiltered. The fault is influenced by the data both inside and outside the fault boundary.

To change the **Boundary filter** settings for each object used to define a fault, click on the **Surfacing** tab and set **Boundary filter** to **Custom**. You will then be able to change **Boundary filter** settings in the **Inputs** tab.

Applying a Trend to a Fault

To apply a trend to a fault, either:

- Double-click on the fault in the project tree, then click on the **Trend** tab.
- Right-click on the fault in the project tree and select **Adjust Surface**. This opens the **Edit Fault** window with the **Trend** tab displayed.

See <u>Global Trends</u> for information on using the controls in this tab.

The settings in the **Trend** tab will be disabled if the fault inputs have been replaced with a mesh.

Contact Surfaces

Defining the internal structure of a geological model involves generating contact surfaces that correspond to the boundaries between lithological units, refining the contact surfaces, arranging them in chronological order and then using the surfaces and the chronological order to divide the geological model into units. The **Surface Chronology** object represents the collection of contact surfaces and defines how they interact to produce the volumes of the geological model. Factors that influence the interaction of contact surfaces with the volumes of the geological model are:

- The order of the contact surfaces in the **Surface Chronology**. See <u>Contact Surfaces in the Surface</u> <u>Chronology</u>.
- The type of contact surface. See <u>Contact Surfaces Types</u> for more information.
- The orientation of the older and younger sides of the surface. See Younging Direction.


The remainder of this topic describes how the different types of contact surface interact and will help you in deciding how to model different units. For specific information on creating the different types of contact surfaces, see:

- Deposits and Erosions
- Intrusions
- Veins
- Vein Systems
- Stratigraphic Sequences

Contact Surfaces in the Surface Chronology


When a geological model is first created, it is simply a volume that is assigned the background lithology. This background lithology is initially "Unknown", as although the model has lithologies defined, Leapfrog Works cannot determine what lithology to use for the background lithology.

The contact surfaces and their order in the **Surface Chronology** determine how they divide this larger "Unknown" volume into known lithological units. The scene below shows the **Surface Chronology** for four deposit contact surfaces and two intrusion contact surfaces, bounded by the geological model extents (pink). The two intrusion contacts are labelled as Unknown on the outside and the intrusion lithology on the inside:




The **Surface Chronology** is open, showing the contact surfaces in chronological order, with the youngest at the top of the list. This is the order in which contact surfaces will be used to cut the "Unknown" volume of a newly created model. The different types of contact surfaces cut older volumes in different ways, which are described below in <u>Contact Surfaces Types</u>.

For the model shown above, the first contact surface to cut the geological model volume is the oldest surface, D5 - D4 contacts. The volume is divided into D5 (red) below and D4 (green) above:




When the next contact surface (D4 - D3 contacts) is enabled in the model, the volume above the contact surface is labelled with the lithology assigned to the surface's younger side (blue):




Therefore, any volume in a geological model is labelled with the lithology assigned to the youngest side of the surface that last cut the volume.


With a simple deposit geological model, as long as each side of each contact surface is assigned a lithology, all volumes will be labelled with known lithologies. Intrusive contact surfaces, however, are often of unknown lithology on the outside, as they contact multiple lithologies. When the two intrusive surfaces in the model above are enabled but all deposit surfaces are disabled, the unknown lithology is replaced with each intrusive lithology on the inner sides of each contact surface, but outside each intrusive contact surface the lithology is not known:



If the outside of the older contact surface (green) is assigned a lithology (red), the volume outside each intrusion is known and, therefore, the surrounding volume can be labelled:



If, however, the outside of the younger intrusion is known but the outside of the older intrusion is unknown, it is not possible to determine the lithology of the surrounding volume as the lithology on the outer side of the surface making the first cut is not known:



Contact Surfaces Types

The different types of contact surfaces result in different shapes and cut older volumes in different ways. The contact surface types are:

- **Deposit**. Deposit contact surfaces tend to be sheet-like, with the primary lithology on the young side and the contacting/avoided lithologies on the older side. Deposits do not cut older volumes. A volume defined by a deposit contact surface will, therefore, appear conformably on top of older volumes.
- **Erosion**. Erosion contact surfaces are similar to deposits, but cut away other contact surfaces on the older side of the erosion contact surface.
- **Intrusion**. Intrusion contact surfaces are rounder in shape, with an interior lithology that represents the intrusion lithology. The intrusion removes existing lithologies and replaces them with the intrusive lithology on the younger side of the contact surface. Often, the older side of an intrusion contact surface is labelled "Unknown" as typically intrusions displace multiple older lithologies.
- Vein. Vein contact surfaces remove existing lithologies and replace them with the vein lithology within the boundaries defined by hanging wall and footwall surfaces and points and a reference surface.


These terms are indicative of the resulting shape and cutting behaviour of a surface rather than of the geological formations that can be modelled. In fact, it might make sense to model something like basement granite as a deposit rather than as an intrusion when it forms the lowest layer in the geological model. If there are no older layers for an intrusion-type contact surface to remove and it is apparent from the borehole data that the lithology simply fills the lowermost parts of the model, then it makes sense to model it as a deposit.

An important consideration in building contact surfaces is that they have an older side and a younger side. This is described in more detail in <u>Younging Direction</u> below, but it is sufficient to understand, at this


point, that younging direction is one factor in determining how the different types of contact surfaces cut older surfaces.

Deposit and Erosion Contact Surfaces


Deposits and **erosions** are both roughly flat surfaces. The difference between the two is that deposits appear conformably on top of underlying older volumes and do not occur in regions defined by older deposits, while erosions remove existing lithologies on the older side of the erosion. This difference is illustrated here, using a model made up of three deposits, A, B and C:




The contact surfaces that define the three output volumes are the B-C contacts surface (pink) toward the top of the model extents and the A-B contacts surface (gold) lower down:




An erosion contact surface (C-D contacts) added to the model cuts across the A-B and B-C contacts. The younger (purple) side of the C-D contact surface faces up:



Once the model is recalculated, the erosion (D) has cut away the deposits on the older side of the erosion:



However, if the C-D contact surface is changed to be a deposit surface, D only occurs on the younger side of the C-D contact surface and does not cut away the A, B and C volumes:




See <u>Deposits and Erosions</u> for information on techniques for creating deposits and erosions.

Intrusion Contact Surfaces


An **intrusion** is a type of contact surface that removes existing lithologies and replaces them with the intrusive lithology. Intrusions are rounder in shape than deposits and erosions, with an interior lithology that represents the intrusion lithology on the inside of the shape.

Adding an intrusion (E) surface added to the example model above as the youngest surface cuts away the other lithologies on the inside of the surface:




Note that the intrusion contacts multiple units. This is typical of intrusion contact surfaces as an intrusion will usually displace multiple older lithologies. Although the outside of the intrusion is not labelled with a lithology, the lithology of each volume the intrusion comes into contact with can be known from the lithologies assigned to the deposit contact surfaces.


However, when all contact surfaces are intrusions, the lithology of the surrounding volume cannot be known, which results in intrusion volumes surrounded by an Unknown volume:



In this instance, the contact surfaces each have a known side and an unknown side:



Adding the boreholes to the scene helps in understanding what lithology the outside of each intrusion should be:




In this case, opening the **Surface Chronology** and assigning AvT as the background lithology results in a model for which all volumes are labelled with a known lithology:

Geological Model - IntGM General Boundary Fault System Lithologies	Chronology		IntGM AvT GnD Q2P
Contact surface chronology: Contact surface Contact sur	~ ~		Uniown
Background lithology: AvT	~	• II ++ A =	M_Geology
? Cancel	<u>O</u> K		Silce mode: Unsliced Query filter: No Filter Filter trace lines

See Intrusions for information on techniques for creating intrusions.

Vein Contact Surfaces

Veins remove existing lithologies and replace them with the vein lithology within the boundaries defined by hangingwall and footwall surfaces and points and a reference surface. Here, a slice has been made horizontally through a model made up of three deposits:



Adding five dykes modelled as veins and enabling them in the model results in the veins cutting away each deposit at the point of contact:



Here the sliced deposits are displayed but the veins are hidden in order to show how they cut away the deposits:



See Veins for information on techniques for creating veins.

Younging Direction

An important factor in determining how surfaces interact is the younging direction of each surface. Each contact surface has a younger side and an older side. For deposit and erosion contact surfaces, Leapfrog Works will, by default, put the younger side up, since this is geologically reasonable in most situations. If, for example, you know that the geology is overturned, you can change the younging direction once the surface has been created.

For intrusion contact surfaces, the younger side of the surface is the inside, although this can be swapped if Leapfrog Works has assigned it incorrectly, as may be the case with flatter intrusion surfaces.

When contact surfaces are displayed in the scene, you can choose whether to display the surfaces using the lithology or the younging direction. When the younging direction is displayed, the younger side is typically green and the older side is brown:



When a contact surface is displayed using the younging direction, Leapfrog Works by default colours the younger side green and the older side brown.

Deposits and Erosions

This topic describes creating and editing deposits and erosions. The topic is divided into:

- Creating Deposits and Erosions
- Deposits/Erosions in the Project Tree
- Refining Deposits and Erosions
- Surfacing Options for Deposits and Erosions

For a general introduction to how deposits and erosions interact with other contact surfaces, see Deposit and Erosion Contact Surfaces in Contact Surfaces.

Creating Deposits and Erosions

Lithology data is often the most reliable data source to use when building geological surfaces, and it is best to derive contact surfaces from lithology data when it is available. If no lithology data is available, you can create deposits and erosions from other data in the project. You can also create offset surfaces from other surfaces in the project, which is useful for creating a series of surfaces. See <u>Offset Surfaces</u> for more information.

Deposits and Erosions From the Base Lithology

It is best to derive contact surfaces from lithology data, when it is available. There are two ways to create contact surfaces from lithology data:

• Using the base lithology column assigned when the model was created. This is the process described below.


• Using other lithology information available in the project. This is useful when you have created an additional lithology column as part of correcting and working with the borehole data. For example, if when building a geological model it becomes apparent that changes need to be made to the borehole data, you can import additional data or create a new column using the split lithology, group lithology or interval selection tools. See <u>Deposits and Erosions From Other Lithology Contacts</u> for more information.

Selecting the From Base Lithology option opens the New Contact Points window:

Contact in Column 'Lithology' on Table 'Geolo	θ β ,
Query filter: None	Inherit from GM
Select primary lithology	
Alluvium	~
Use contacts <u>above</u> Use contacts <u>be</u>	
Contacting/Avoided lithologies:	Ignored lithologies:
Coarse Sand (6)	Aquifer Miocene Alluvium (0)
	Basement Granite (0)
	Glacial Till (0)
	Gravel (0)
	Lower Gravel (0)
Treat unspecified intervals as	
Ignored Primary Contacting	
Reference Plane	
V Horizontal plane	
Dip: 0.0 0	
Dip azimuth: 0.0	
View Plane Set From Plane	
view mane Set monimale	

Select the lithology you wish to use to create the surface from the **Select primary lithology** list; this will be the older lithology (lower down) in the geological model. The **Contacting/Avoided lithologies** list shows the lithologies that contact the primary lithology and the number of contacts. This helps in selecting which contacts to use to create the contact surface.

The options in the **Lithology** tab are useful for creating a surface when one lithology is interbedded with another. For example, here we can see that the coarse sand is interbedded with alluvium:



The solution to this is to create two surfaces from the Alluvium contacts, one using the contacts above (younger contacts) and the other using the contacts below (older contacts):

🖉 New Contact Points	×	R New Contact Points	×
Lithology Compositing		Lithology Compositing	
Contact in Column 'Lithology' on Table 'Geology'		Contact in Column "Lithology' on Table 'Geology'	
Query filter: None	Inherit from GM	Query filter: None	Inherit from GM
Select primary lithology		Select primary lithology	
Alluvium	~	Alluvium	~
Use contacts above Use contacts below		Use contacts above . Use contacts below	
Contacting voided lithologies:	Ignored lithologies:	Contacting/Avoided Jithologies:	Ignored lithologies:
Coar: Sand (6)	Aquifer Miocene Alluvium (0)	Coarse Sand (6)	Aquifer Miocene Alluvium (0)
	Basement Granite (0)	Gravel (6)	Basement Granite (0)
	Glacial Till (0)		Glacial Till (0)
	Gravel (0)		Lower Gravel (0)
	Lower Gravel (0)		
Treat unspecified intervals as		Treat unspecified intervals as	
Ignored Primary Contacting		Ignored Primary Contacting	
Reference Plane		Reference Plane	
Horizontal plane		Horizontal plane	
Dip: 0.0 0		Dip: 0.0	
Dip azimuth: 0.0		Dip azimyth: 0.0	
View Plane Set From Plane		View Plane Set From Plane	
Name: Alluvium - Coarse Sand contacts		Name: Alluvium contacts	
0	Gancel QK	0	<u>Cancel</u> OK

Note that the gravel contacts should be excluded for the surface created from the **Use contacts below** option, as we can see from the borehole data that gravel appears lower down in the model than the surface we are creating. Do this by dragging the contacts that should be excluded to the **Ignored lithologies** list:

Contact in Columr	n 'Lithology' on Table 'Geolo	ea,
Query filter: No	ne	Inherit from GM
Select primary lith	nology	
Alluvium		~
 Use contacts Contacting/Avoi 	above 💿 Use contacts be ided lithologies:	low Ignored lithologies:
Coarse Sa	and (6)	Aquifer Miocene Alluvium (0)
Gravel (6)		Basement Granite (0)
		Glacial Till (0)
		Lower Gravel (0)
		Gravel (6)
Treat unspecified	intervals as	
Ignored 🔾 🛉	Primary O Contacting	
Reference Plane		
Horizontal pl	ane	
Dip:		
Dip azimyth:		
View Plane	e Set From Plane	
Name: Alluvium	contacts	

Unspecified intervals are intervals that have no data. By default, unspecified intervals are ignored when creating a contact surface, but you can also treat them as the primary lithology or as avoided lithologies.

For complex geologies, the up and down directions for the surface may not be clear. If this is the case, untick the **Horizontal Plane** box. A reference plane will appear in the scene, with the up-facing surface labelled A and the downward-facing surface labelled B:

💋 New Contact Points	X	1	0 16
Lithology Compositing			
Contact in Column 'Lithology' on Table 'Geology			
Query filter: None	V Inherit from GM		
Select primary lithology Alluvium	~	n 7	a 🚺
 Use contacts <u>above</u> Use contacts <u>belo</u> Contacting/Avoided lithologies: 	Ignored lithologies:		
Coarse Sand	Aquifer Miocene Alluvium	Biev (Z)	
_	Basement Granite		5500 307000 42307590- Haast (X)
	Glacial Till	0058695	-2306500 +2305500 +23075 =ast ()
	Gravel		+
	Lower Gravel	+2305500	
		9 + +	Plunge +20
Treat unspecified intervals as			Azimuth 030 V
Ignored Primary Contacting			
Reference Plane		() Pi	ane
Horizontal plane		Plane	Orientation
Dip: 0.0 ℃		Dip:	0.0
Dip azimuth: 0.0 0		Dip az	
View Plane Set From Plane			
Tew fiance Get Hom Fiance		Pitch:	90.0 🗘
Name: Coarse Sand - Alluvium contacts			
		Centre	Point
		X: 2	2306330.341724918
?	<u>Cancel</u> <u>O</u> K	Y: 5	6698327.896106152
L			

When you disable the **Horizontal plane** option for the **Reference Surface**, the number of contacts is longer displayed in the lithologies lists, as the number of contact points is not updated when the reference surface used changes.

Controlling the position of the reference plane is similar to controlling the position of the moving plane:

- Use the handles in the scene window to move the plane.
- Set the **Dip** and **Dip Azimuth** values in the **New Contact Points** window. The reference plane will be updated in the scene.

Once the reference plane is correctly oriented, click the **Set From Plane** button.

Setting a reference plane for contact points is different from applying a global trend to a surface. To apply a global trend to a surface, double-click on the surface in the project tree and click on the **Trend** tab. See <u>Global Trends</u>.

Data can be composited at the borehole level or on a surface-by-surface basis. To composite the data used to generate the contact surface, click on the **Compositing** tab. See <u>Category Composites</u> for more information.

Click **OK** to create the contact surface, which will appear in the project tree under the **Surface Chronology**. See <u>Refining Deposits and Erosions</u> below for more information on refining the contact surface.

Deposits and Erosions From Other Lithology Contacts

Creating deposit and erosion contact surfaces using the **From Other Contacts** option is useful when you have created an additional lithology column as part of correcting and working with the borehole data. For example, if when building a geological model it becomes apparent that changes need to be made to the borehole data, you can import additional data or create a new column using the split lithology, group lithology or interval selection tools. See <u>Splitting Lithologies</u>, <u>Grouping Lithologies</u> and <u>Interval Selection</u> for more information.

The process is similar to creating a surface from the base lithology column, but you must first select the lithology column you will use:

	😂 Select Column	
😰 New Depositional Contact 🛛 🕹 🔪		
	Objects Query Filter	
Select Data:	✓ ☐ Drillhole Data	
Select	V Drillholes	
Select Lithology	✓ IIII M_Geology	
Eirst lithology: Unknown \lor is Younger \lor	RockType	
Second lithology: Unknown v is Older	Simple_RockType	
	Meathering_Zone	
Name: Unknown - Unknown contacts	V 📓 Merged_Table_1	
	RockType	
Cancel OK		
	Cancel OK	

Select the **First Lithology** and **Second Lithology**, if known. Click **OK**. The **New Contact Points** window will appear. Assign the **Primary lithology**, **Contacting/Avoided lithologies** and the **Ignored lithologies**. These can only be selected from the model's base lithology.

The rest of the process is similar to defining a contact surface from the base lithology. See <u>Deposits and</u> Erosions From the Base Lithology above for more information.

Be sure to add the contact surface to the scene to view it and check that it is oriented correctly.

See <u>Refining Deposits and Erosions</u> below for more information on the different techniques that can be used for adjusting a contact surface.

Deposits and Erosions From Other Data

If suitable lithology data is not available, deposits and erosions can be created from other data in the project, such as GIS data, structural data, points, polylines and surfaces. The steps for creating deposits and erosions from other data are similar, regardless of the data used to create the surface:

- Right-click on the **Surface Chronology** and select one of the data types from the **New Deposit/Erosion** menu.
- Select the data object that will be used to define the surface. This must already be in the project, unless you are using a polyline, in which case you are given the option to create a new polyline.
- Select the **First lithology** and **Second lithology**. These are the lithologies that will be assigned to each side of the contact surface. The lithologies you can choose from are those defined for the geological model in the **Lithologies** object (see <u>Model Lithologies</u>).
- Set whether the **First lithology** is older or younger than the **Second lithology**. Leapfrog Works will, by default, put the younger side of a contact surface up, but this can be changed later.

Here, a points data object is being used to create a deposit:

	Select points	
	Objects Query Filter	
New Depositional Contact X	✓ ☐ Drillhole Data ✓ III Drillholes	
lect Data:	Au_Composited_Values Points Extracted vertices	
lect Lithology	C Intrusion points C Lithology contacts	
Second lithology:	1 D2 - D1 contacts No query filter	
me: D - C contacts	C_D_contacts No query filter	
	Grid_of_Points No query filter	
	points No query filter	
	<u>C</u> ancel <u>O</u> K	¢

For polylines, you first set the lithologies and the younging order, then click **OK** to move on to the next step:



You can draw the polyline in the scene directly by selecting the **New Drawing** option. You can also use any polyline in the project by selecting the **Existing Polyline** option. You can then select the required polyline from the list.

The new contact surface will appear in the project tree under the **Surface Chronology**. Add the contact surface to the scene to view it and check that it is oriented correctly.

Expand the surface in the project tree to see how it was made. Here, a number of surfaces have been created using different types of data:

🗸 🍘 GM	9
> 🥡 Boundary	
🍫 Fault System	
Lithologies	
🗸 🏹 Surface Chronology	
🗸 衝 Unknown - E cont	acts
Unknown - E	contacts
🗸 🛞 C - D contacts	
C_D_contacts	
∨ 🛞 B - C contacts	
B-C contacts	
🗸 🛞 A - B contacts	Ŭ
A-B contacts	
> 🗋 Output Volumes	

If creating a surface from a new polyline, the polyline will not be able to be used elsewhere in the project unless it has been shared. To share the polyline, expand the contact surface in the project tree, rightclick on the polyline and select **Share**. The polyline will then be available elsewhere in the project.

As further refinements are made to the surface, that information will also be added to the contact surface in the project tree.

Deposits/Erosions in the Project Tree

The name Leapfrog Works automatically assigns to a deposit or an erosion is the lithologies assigned to each side of the surface. In the project tree, expand the surface to see how it was made:



Double-click on the surface to edit it. Double-click on the contact points object (¹¹) to edit the lithology and change compositing parameters.

As further refinements are made to the surface, that information will also be added to the project tree. See <u>Refining Deposits and Erosions</u> below for more information.

Refining Deposits and Erosions

You can refine deposits and erosions in several ways:

- Add other data. Right-click on the surface to see the options available, which will depend on how the surface was created. See <u>Adding Data to Surfaces</u> for more information.
- Edit the surface with a polyline. Right-click on the surface in the project tree and select either **Edit > With Polyline**. See <u>Editing Surfaces With Polylines</u> for more information.
- Edit the surface using structural data. Right-click on the surface and select Edit > With Structural Data. This option is available for deposits and erosions created from lithology data and other data in the project, but not for offset surfaces. See Editing Surfaces With Structural Data for more information.

To edit the surface's settings, double-click on it in the project tree. In the **Lithologies** tab, change the lithologies assigned to each side of the surface, if required.

You can swap the younging direction if the direction was assigned incorrectly when the surface was created. The change will be reflected in the scene. Note that changing the younging direction does not change which lithology is older or younger.

The difference between deposit and erosion contact surfaces is how they cut older lithologies, as described in <u>Contact Surfaces</u>. For this reason, it is possible to change between the two types using the **Contact Type** setting.

For information on other techniques for refining deposits and erosions, see:

- Surfacing Options for Deposits and Erosions
- Offset Surfaces

Surfacing Options for Deposits and Erosions

Surfacing options for deposits and erosions can be changed by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab. There are additional settings related to boundary filtering and snapping to data in the **Inputs** tab.

Boundary Filtering

When data objects are added to a surface, there are two ways to handle the data that lies outside the surface's boundary:

- Filter the data. The surface is only influenced by the data that falls inside the surface's boundary.
- Leave the data unfiltered. The surface is influenced by the data both inside and outside the surface's boundary.

The **Boundary filter** setting determines how data used to define the surface is filtered:

- **Off**. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- Custom. Only the data objects specified in the Inputs tab are filtered.

Snapping to Data

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations. See <u>Honouring Surface Contacts</u>.

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab.

For individual contact surfaces, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to the surfaces.
- **Drilling only**. Surfaces snap to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surfaces.
- Custom. Surfaces snap to the data objects indicated in the Inputs tab for each surface.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

If you need a surface to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Setting the Surface Resolution

See <u>Surface Resolution for a Geological Model</u> for information about the surface resolution settings in the **Surfacing** tab.

Applying a Trend to a Deposit/Erosion

There are two ways to change the trend for a deposit or an erosion:

- Right-click on the surface in the project tree and select Adjust Surface.
- Double-click on the surface in the project tree and then click on the **Trend** tab.

See <u>Global Trends</u> for more information.

Intrusions

This topic describes creating and editing intrusions. The topic is divided into:

- <u>Creating Intrusions</u>
- Intrusions in the Project Tree
- Displaying Intrusion Points
- Refining Intrusions
- Surfacing Options for Intrusions
- Applying a Trend to an Intrusion
- Clipping Values for Intrusions
- Interpolation Settings

For a general introduction to how intrusions interact with other contact surfaces, see <u>Intrusion Contact</u> <u>Surfaces</u> in <u>Contact Surfaces</u>.

Creating Intrusions

Lithology data is often the most reliable data source to use when building geological surfaces, and it is best to derive contact surfaces from lithology data when it is available. If no lithology data is available, you can create intrusions from other data in the project.

One thing to keep in mind for all intrusion contact surfaces is that an intrusion removes all the existing material on the younger side of the contact surface. Therefore:

- An intrusion should always have the younger side of its surface labelled with the intruded material. This is called the "interior lithology".
- The older side will typically be labelled "Unknown" as an intrusion will usually displace multiple older lithologies. This is called the "exterior lithology".

Intrusions from Lithology Contacts

Lithology data is often the most reliable data source to use when building geological surfaces, and it is best to derive contact surfaces from lithology data when it is available. There are two ways to create intrusions from lithology data:

- Using the base lithology column assigned when the model was created.
- Using other lithology information available in the project. This is useful when you have created an additional lithology column as part of correcting and working with the borehole data. For example, if when building a geological model it becomes apparent that changes need to be made to the borehole data, you can import additional data or create a new column using the split lithology, group lithology or interval selection tools.

To create a new intrusion from lithology contacts, right-click on the **Surface Chronology** object and select either **New Intrusion > From Base Lithology** or **New Intrusion > From Other Contacts**. The only difference in the two methods is that when creating an intrusion from other contacts, you must first select the lithology column from those available in the project and specify the **First lithology** and the **Second lithology**.

Select the intrusive lithology as the interior lithology. Other lithologies will be displayed in the **Exterior lithologies** list. Drag any younger lithologies to the **lgnore** list.

B	New Intrusio	n					×
	Lithology	с	ompositing				_
	Intrusion i	n col	umn 'RockType' on table 'I	M_Geology'			
	Query fi	lter:	None			Inherit from GM	
	Select inte	erior	ithology				
	11					\sim	
	Exterior	lithol	ogies:	lg	nore (Younger lithologies)	:	
	D1						
	D2	2					
	D3	;					
	D4	Ļ					
	D5	5					
	12						
	Treaturs	necifi	ed intervals as				
			Interior C Exterior				
	Name:	1					
(?)				Cancel	ок	

Unspecified intervals are intervals that have no data. By default, unspecified intervals are ignored when creating an intrusion, but you can also treat them as the interior lithology or as exterior lithologies.

Sometimes intrusive boundaries are poorly defined, with fragments of country rock intermixed with the intrusive body. This can result in very small segments near the edges of the intrusion. Modelling the fine detail is not always necessary, and so compositing can be used to smooth these boundaries. Compositing parameters are set in the **Compositing** tab:

New Intrusio	n			
Lithology	Compositing			
Conver	t enclosed ignored segments			
Shor	ter than: 1.000			
✓ Simplif	y geology by filtering short seg	ments		
✓ Set f	rom surface resolution			
Filter int	erior segments shorter than:	10.000		
Filter ex	terior segments shorter than:	10.000		

The settings in this tab are described in <u>Category Composites</u>.

Click **OK** to create the intrusion, which will be added to the project tree as part of the **Surface Chronology** object.

Intrusions from Other Data

If suitable lithology data is not available, intrusions can be created from other data in the project, such as GIS data, structural data, points, polylines and surfaces. The steps for creating intrusions from other data are similar, regardless of the data used to create the surface:

- Right-click on the **Surface Chronology** and select one of the data types from the **New Intrusion** menu.
- Select the data object that will be used to define the surface. This must already be in the project, unless you are using a polyline, in which case you are given the option to create a new polyline.
- Select the **First lithology** and **Second lithology**. These are the lithologies that will be assigned to each side of the contact surface. The lithologies you can choose from are those defined for the geological model in the **Lithologies** object (see <u>Model Lithologies</u>).
- Set whether the **First lithology** is older or younger than the **Second lithology**. Leapfrog Works will, by default, put the younger side of a contact surface up, but this can be changed later.

Here, a points data object is being used to create an intrusion:

	Select points	
	Objects	Query Filter
	✓ 🗀 Drillhole Data	
New Intrusional Contact X	V Drillholes	
	Au_Composited_Value	9S
elect Data:	→ □ Points	
Select	> Extracted vertices	
elect Lithology	✓ ☐ Intrusion points	
Eirst lithology: III V is Younger V	11	No query filter
	12	No query filter
econd lithology: Unknown V is Older	Lithology contacts	
ne: [1]	D2 - D1 contacts	No query filter
	D2 contacts	No query filter
Cancel OK	C_D_contacts	No query filter
	Grid_of_Points	No query filter
	Marvin_topo_large	No query filter
	points	No query filter

For polylines, you first set the lithologies and the younging order, then click **OK** to move on to the next step:

26 New Intrusional Contact X	🖉 New Polyline 🛛 🗙
Select Lithology First lithology: III is Younger V Second lithology: Unknown V is Older	Polyline From New Drawing C Existing Polyline C contacts
Name: 11	Name: 11
(? Cancel OK	Qancel QK

You can draw the polyline in the scene directly by selecting the **New Drawing** option. You can also use any polyline in the project by selecting the **Existing Polyline** option. You can then select the required polyline from the list.

The new intrusion will appear in the project tree under the **Surface Chronology**. Add the contact surface to the scene to view it and check that it is oriented correctly.


Expand the surface in the project tree to see how it was made.

If creating a surface from a new polyline, the polyline will not be able to be used elsewhere in the project unless it has been shared. To share the polyline, expand the contact surface in the project tree, right-click on the polyline and select **Share**. The polyline will then be available elsewhere in the project.

As further refinements are made to the surface, that information will also be added to the contact surface in the project tree.

Intrusions in the Project Tree

The name Leapfrog Works automatically assigns to an intrusion is the name of the intrusive lithology. In the project tee, expand the intrusion to see how it was made:




Double-click on the intrusion to edit it. Double-click on the points object (!!!) to edit the intrusion lithology, change compositing parameters and change point generation options.


As further refinements are made to the surface, that information will also be added to the project tree. See <u>Refining Intrusions</u> below for more information.

Displaying Intrusion Points

When you view the intrusion points in the scene, you can display only the contact points or all the points used in creating the intrusion. To display all points, click on the points object (11) in the shape list and tick the box for **Show volume points**. Here, only the contact points are displayed:



When the volume points are displayed, points with negative values are those outside the surface, while points with positive values are those inside. **Show text** (\mathbb{A}) has been enabled in the shape list so that the values are displayed:



You can change the way intrusion points are generated by double-clicking on the points object (^{‡‡}) in the project tree. See Intrusion Point Generation Parameters.

Refining Intrusions

You can refine intrusions in several ways:

- Add other data. Right-click on the surface to see the options available, which will depend on how the surface was created. See <u>Adding Data to Surfaces</u> for more information.
- Edit the surface with a polyline. Right-click on the surface in the project tree and select either **Edit > With Polyline**. See Editing Surfaces With Polylines for more information.
- Edit the surface using structural data. Right-click on the surface and select **Edit > With Structural Data**. See <u>Editing Surfaces With Structural Data</u> for more information.

To edit an intrusion's settings, double-click on it in the project tree. In the **Lithologies** tab, change the lithologies assigned to each side of the surface, if required.

Surfacing Options for Intrusions

Surfacing options for an intrusion can be changed by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab. There are additional settings related to boundary filtering and snapping to data in the **Inputs** tab.

Boundary Filtering

When data objects are added to a surface, there are two ways to handle the data that lies outside the surface's boundary:

- Filter the data. The surface is only influenced by the data that falls inside the surface's boundary.
- Leave the data unfiltered. The surface is influenced by the data both inside and outside the surface's boundary.

The boundary of an intrusion can be the geological model boundary or a fault block boundary.

The **Boundary filter** setting determines how data used to define the surface is filtered:

- **Off**. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- Custom. Only the data objects specified in the Inputs tab are filtered.

Snapping to Data

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations, as discussed in <u>Honouring Surface Contacts</u>.

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab.

For individual contact surfaces, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to the surfaces.
- **Drilling only**. Surfaces snap to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surfaces.
- Custom. Surfaces snap to the data objects indicated in the Inputs tab for each surface.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

If you need a surface to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Surface Resolution

See <u>Surface Resolution for a Geological Model</u> for information about the surface resolution settings in the **Surfacing** tab.

Clicking **Additional options** adds **Value Clipping** and **Interpolant** tabs to the window and also allows the use of a structural trend in the **Trend** tab:

😹 Edit I2	×
Lithologies	Surfacing Inputs Trend
Boundary filter:	Custom ~
Snap to data:	Inherit from GM (Off)
Maximum snap	distance: 10.00
✓ Inherit resolu	ition from GM
Surface reso	olution: 20.00 🗘 🗌 Adaptive
Additional og	tions
Name: 12	
?	<u>C</u> ancel <u>O</u> K

These are described in <u>Applying a Trend to an Intrusion</u>, <u>Clipping Values for Intrusions</u> and <u>Interpolation</u> <u>Settings</u> below.

Applying a Trend to an Intrusion

There are two ways to change the trend for an intrusion:

- Right-click on the surface in the project tree and select Adjust Surface.
- Double-click on the surface in the project tree and then click on the **Trend** tab.

See <u>Global Trends</u> for more information.

You can also use a structural trend for an intrusion. To do this, click the **Additional options** button in the **Surfacing** tab, then click on the **Trend** tab.


Lithologies Surfacing Inputs Trend Value Clipping Interpolant Global Trgnd Dip Dip Azimuth Pitch Directions: 0 0 90 Maximum Intermed. Minimum Ellipsoid Ratios: 1 1 1 View Plane Set From Plane Set to						
Global Trgnd Dip Dip Azimuth Pitch Directions: 0 0 90 Maximum Intermed. Minimum Ellipsoid Ratios: 1 1 View Plane Set From Plane Set to Structural Trend						
Dip Dip Azimuth Pitch Directions: 0 0 90 Maximum Intermed. Minimum Ellipsoid Ratios: 1 1 View Plane Set From Plane Set to Structural Trend	Lithologies	Surfacing	Inputs	Trend	Value Clipping	Interpolant
Directions: 0 0 90 Maximum Intermed. Minimum Ellipsoid Ratios: 1 1 View Plane Set From Plane Set to Structural Trend	⊖ Global Tr <u>e</u> n	d				
Maximum Intermed. Minimum Ellipsoid Ratios: 1 1 1 View Plane Set From Plane Set to Structural Trend		Dip		Dip Azimu	th Pitch	
Ellipsoid Ratios: 1 1 View Plane Set From Plane Set to Structural Trend	Directions:	0		, 0	, 90	
View Plane Set From Plane Set to Structural Trend Image: Structural trend (blending) Image: Structural trend (blending)		Maxim	num	Intermed.	Minim	um
Structural Trend Structural trend (blending)	Ellipsoid Ra	atios: 1		, 1	, 1	
Se structural trend (blending)	Vie	w Plane	Set	From Plane	Se	t to
Structural trend (blending)	Structural T	rend				
Outside value: -1			ding)			~
	Outside value:	-1				^
						Y
ame: 12	ame: 12					
ame: 12	ame: 12					
ame: 12 ? <u>C</u> ancel <u>O</u> K	lame: 12			Ca	ncel	<u>0</u> K

Click on **Structural Trend**, then select the required trend from the list. See <u>Structural Trends</u> for more information.

Clipping Values for Intrusions

You can change settings for intrusions by double-clicking on the contact surface in the project tree. The **Value Clipping** tab is only available for intrusion contact surfaces.

In the Value Clipping tab, you can manipulate the data distribution by clipping the data:



Clipping caps values that are outside the range set by the **Lower bound** and **Upper bound** values. For example, if you change the **Upper bound** from 16.00 to 10.00, distance values above 10.00 will be regarded as 10.00.

The **Automatic clipping** setting has different effects based on whether a global trend or structural trend is set in the **Trend** tab:

- When a global trend is applied, Leapfrog Works automatically clips the values. That is, the
 Automatic clipping setting is Do clipping and Leapfrog Works sets the Lower bound and Upper
 bound from the data. To disable clipping, untick Automatic clipping, then untick Do clipping. To
 change the Lower bound and Upper bound, untick Automatic clipping, then change the values.
- When a structural trend is applied, Leapfrog Works automatically does not clip the values. To clip values, untick **Automatic clipping**, then tick **Do clipping**. Again, Leapfrog Works sets the **Lower bound** and **Upper bound** values from the data and you can change them, if required.

Interpolation Settings

You can change settings for an intrusion by double-clicking on the intrusion in the project tree and clicking on the **Interpolant** tab. For more information on the settings in this tab, see the <u>Interpolant</u> <u>Functions</u> topic.

Veins

This topic describes creating and editing veins. It is divided into:

- Creating Veins
- Veins in the Project Tree
- Displaying Veins
- Refining Veins
- Surfacing Options for Veins
- The Vein Reference Surface
- The Vein Boundary
- Editing Vein Segments

For a general introduction to how veins interact with other contact surfaces, see <u>Vein Contact Surfaces</u> in <u>Contact Surfaces</u>.

A vein is a type of contact surface that removes existing lithologies and replaces them with the vein lithology within the boundaries defined by hangingwall and footwall surfaces constructed from selected input data. A reference surface is defined that is the best fit for the hangingwall and footwall surfaces. The reference surface can be curved or planar.

Creating Veins

Options for creating veins are:

- From lithology data, using the base lithology used to define the geological model or other contacts available in the project. See <u>Veins From Lithology Contacts</u> below.
- From GIS vector data, point data and polylines. See <u>Veins From Other Data</u> below.
- Creating a vein system. This results in a single lithology that represents all the veins in a model. Veins and their interactions are defined within the vein system. See <u>Vein Systems</u>.

Veins From Lithology Contacts

To create a new vein from lithology contacts, right-click on the **Surface Chronology** object and select either **New Vein > From Base Lithology** or **New Vein > From Other Contacts**. The only difference in the two methods is that when creating a vein from other contacts, you must first select the lithology column from those available in the project and specify the **Vein lithology** and **Outside lithology**.

In the New Vein window, select the Vein lithology:

W New Vei			×
Vein in co	lumn 'litho' on tabl	le 'vein_walls_litholog	3 X ,
Query filte	er: None	🗸 🔽 Inherit from	m GM
Vein lithol	logy: 📕 B1		~
V Include	e points at the end	s of holes	
Name:	B1		
?	<u>C</u> ancel	<u>о</u> к	

When extracting the hanging wall and footwall points, Leapfrog Works automatically includes points at the ends of the boreholes. To exclude these points, untick the **Include points at the ends of holes**. Once the vein has been created, this setting can be changed by double-clicking on the vein segments object (**III**) in the project tree.

Click **OK** to create the vein, which will be added to the project tree as part of the **Surface Chronology** object.

Veins From Other Data

If suitable lithology data is not available, veins can be created from other data in the project, such as GIS data, points and polylines. The steps for creating veins from other data are similar, regardless of the data used to create the surface:

- Right-click on the **Surface Chronology** and select one of the data types from the **New Vein** menu.
- Select the data objects for the **Hangingwall** and **Footwall**. These objects must already be in the project.
- Select the **Vein lithology** and the **Outside lithology**. The lithologies you can choose from are those defined for the geological model in the **Lithologies** object (see Model Lithologies).

Here, points data is being used to create a vein:


B New Vein Conta	ıct	×	
Select points		Select footwall points	×
Hangingwall:	B1_Hangingwall		
Footwall:	Select	Objects Query Filter	
Select Lithology		V D Points	
Vein lithology:	Unknown	B1_Footwall No query filter	
Outside litholo	av: Unknown ~	B1_Hangingwall No query filter	
outside infiloio	y. Ondoni		
Name: Unkno	wn	Cancel	<u>0</u> K
?	<u>C</u> ancel <u>O</u> K		

Select points data objects for both the **Hangingwall** and **Footwall**, then click **OK** to create the new vein. The new contact surface will appear in the project tree under the **Surface Chronology**. Expand the vein in the project tree to see how it was made.

Veins in the Project Tree

Veins are stored in the project tree as part of the **Surface Chronology** object. Further modifications can be made to the vein by working on the objects that make up the vein. Expand the vein in the project tree to view these objects.

Here, the hanging wall and footwall surfaces and points are displayed in the scene for a vein defined from lithology data. The reference surface (yellow) and the vein segments (red and blue cylinders) used to create the vein are also shown:



This vein is made up of:

- Hangingwall and footwall surfaces (), which, when expanded, show the hangingwall and footwall data objects used to create the surfaces.
 - Export hanging wall and footwall surfaces as described in <u>Exporting Meshes</u> and <u>Exporting an</u> <u>Elevation Grid</u>.

 - Edit the hanging wall and footwall surfaces with polylines by right-clicking on them and selecting one of the **Edit** options.
 - Change contact honouring and boundary filtering options as described in <u>Surfacing Options for</u> <u>Veins</u> below.
- Vein segments and pinch out segments (!!!) extracted from borehole data.
 - These are only included when a vein is created from lithology contacts.
 - If Vein Pinch Out
- A reference surface (**) calculated as the best fit surface using the hanging wall and footwall surfaces.
 - The reference surface can be curved, planar or another surface in the project can be used.
 - You can add points, GIS vector data and polylines to a curved reference surface.
 - If a curved reference surface is made up of multiple objects, you can switch between the objects and change how they are filtered in order to see the effects on the vein.
- A boundary object (⁽¹⁾), which is empty when the vein is first created.
 - The Vein Boundary

It is not possible to add structural data or polylines with orientation information to the hangingwall, footwall and reference surfaces. If you edit these surfaces with a polyline, your options for editing the polyline will be limited.

Displaying Veins

You can change the way the different objects that make up the vein are displayed using options in the shape list:

۲	vein_walls_lithology		×	🎼 litho 🗸	Edit Colours	•	A	B1 Footwall		
0	B1: B1 Footwall		×	HW / S	Edit Colours		A	Slice mode:	From Scene	~
٢	B1: B1 Hangingwall		×	🔶 Flat colour	Edit Colours	•	Α 🗉	Query filter:	No Filter	~
٢	🔆 B1: B1 Reference Surface		×	HW / FW				Point radius:	4.000	0
O	// B1: B1 Footwall		×	À Lithol ∨			1			
٢	// B1: B1 Hangingwall		×	À Lithol 🗸		-	4 🔝		Format Display Text	
٢	81: B1	0	×	HW / 🗸	Edit Colours	•	Α 🗉			

Refining Veins

To edit a vein's settings, double-click on it in the project tree. In the **Lithologies** tab, change the lithologies assigned to each side of the surface, if required. For information on the settings in the **Surfacing** and **Inputs** tabs, see <u>Surfacing Options for Veins</u> below.

Surfacing Options for Veins

Surfacing options for veins can be changed by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab. There are additional settings related to boundary filtering and snapping to data in the **Inputs** tab.

Boundary Filtering

When data objects are added to a surface, there are two ways to handle the data that lies outside the surface's boundary:

- Filter the data. The surface is only influenced by the data that falls inside the surface's boundary.
- Leave the data unfiltered. The surface is influenced by the data both inside and outside the surface's boundary.

The boundary of a vein can be the geological model boundary or a fault block boundary.

The Boundary filter setting determines how data used to define the surface is filtered:

- Off. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- **Custom**. Only the data objects specified in the **Inputs** tab are filtered.

The **Filter segments by boundary** setting in the **Inputs** tab is enabled by default when the **Boundary filter** setting in the **Surfacing** tab is **All data** or **Drilling only**. When **Filter segments by boundary** is enabled, the vein surface will only be influenced by the segments that falls inside the vein boundary.

Snapping to Data

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations, as discussed in <u>Honouring Surface Contacts</u>.

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab.

For individual contact surfaces, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to the surfaces.
- **Drilling only**. Surfaces snap to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surfaces.
- Custom. Surfaces snap to the data objects indicated in the Inputs tab for each surface.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See Honouring Surface Contacts for more information on these settings.

If you need a surface to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Surface Resolution

Note that although you can change the **Surface resolution** for a vein, the **Adaptive** option is not available, even when the resolution for the geological model is set to be **Adaptive**.

Vein Thickness

Veins have two thickness settings that force the vein to maintain a minimum or maximum thickness. If footwall and hanging wall points are in pairs, it is not usually necessary to set the **Minimum thickness** or **Maximum thickness**.

- If the vein intersects itself, set the **Minimum thickness** to a value that is less than the minimum distance between any two contact points.
- If the vein widens out toward the edges of the geological model set the **Maximum thickness** to a value that limits the effects of long segments.

If the **Pinch out** option is enabled, you will not be able to set the **Minimum thickness**.

If you set the **Maximum thickness** and **Pinch out**, the **Pinch out** is applied before the **Maximum thickness**.


Note that if **Snap to data** is enabled, snapping occurs after the vein thickness has been calculated. If it appears that the vein surface is not honouring the thickness setting, check what data the surface is snapping to.


Vein Pinch Out

Vein walls can be set to pinch out where borehole data indicates they do not occur. This is achieved by creating 'outside' intervals on boreholes that do not have an interior vein segment. These intervals are then flipped with respect to interior vein intervals, which, in effect means the footwall and hangingwall orientation has the opposite sense to the nearest interior intervals. This forces the hangingwall and footwall surfaces to cross, thereby pinching out.

The **Pinch out** option is disabled when a vein is first created. To enable it, double-click on the vein in the project tree and click on the **Surfacing** tab. Tick the box for **Pinch out**. Click **OK** to process the changes. The vein will be updated and pinch out points (**!!**) will be added to the vein in the project tree.

For this vein, the surface occurs even where the vein lithology (green cylinders) does not occur and terminates at the boundary of the geological model:






When the vein is set to pinch out, it tapers out where the vein lithology does not occur:

You can change how much the vein pinches out by excluding some pinch out segments. To do this, right-click on the pinch out segments (iii) in the project tree and select **Edit in Scene**. The **Pinch Out Properties** window will appear in the scene. Click on a segment to view information about it and set it to be **Excluded**, if required. Note that the segments displayed in the scene below are the pinch out segments rather than the borehole segments shown in earlier scenes. The grey segments are excluded and the currently selected segment is highlighted in the scene:



Click the **Save** button (a) to view the effect of the excluded pinch out segments on the vein. Excluding the two segments results in the vein terminating at the boundary of the geological model:



The Vein Reference Surface

A vein includes a reference surface (i) that is the best fit for the objects that make up the hanging wall and footwall surfaces.

A vein can have a curved reference surface, a planar reference surface or it can use another mesh in the project. Double-click on the reference surface in the project tree; this opens the **Edit Vein Reference**

Surface window and you can see what option is being used for the surface. In this example, the B1 vein has been created from lithology data and so it has a curved reference surface and the midpoints for the vein lithology are used as **Input values**:

Active Bou	undary filter Input	l midpoints	
	190 D	i maponito	
Planar refere	nce surface		
Location:	917.89851299	, 1754.206279	, 61.201556787
	917.89851299 3.9537465998755		, 61.201556787
 Dip:		694	61.201556787
Location: Dip: Dip a <u>z</u> imuth:	3.9537465998755	694	61.201556787 Set to Defat

Each option is described below:

- <u>Curved Reference Surface</u>
- Planar Reference Surface
- <u>Custom Reference Surface</u>

Curved Reference Surface

The **Curved reference surface** option is the default for veins created from lithology data and the objects used to build the reference surface are shown in the **Input values** part of the **Edit Vein Reference Surface** window:

Active Bo	undary filter	
V		C B1 from points Reference Surface
~		C Polyline from points
v		Curved polyline
\checkmark	~	points
Planar refere	ence surface	3
	ence surface 918.1360	
Location:	918.1360	
Location: Dip:	918.1360 3.818779	6712 1752.3619375 68.208074064 4033469395
Planar refere Location: Dip: Dip a <u>z</u> imuth:	918.1360 3.818779	6712 1752.3619375 68.208074064 4033469395 616822704
Location: Dip:	918.1360 3.818779 247.4843	6712 1752.3619375 68.208074064 4033469395 616822704 Set to Defa

You can enable or disable the different data objects to see their effects on the vein by ticking and unticking the **Active** box, then clicking **OK** to reprocess the vein.

The **Boundary filter** setting for each object determines whether or not the data that lies outside the reference surface's boundary is filtered.

- Tick **Boundary filter** so that the surface is only influenced by the data that falls inside the reference surface's boundary.
- Untick **Boundary filter** if you want the surface to be influenced by the data both inside and outside the reference surface's boundary.

Boundary filtering for the midpoints used to create a curved reference is controlled by the setting for the vein itself. See <u>Boundary Filtering</u> in <u>Surfacing Options for Veins</u> for more information.

The **Curved reference surface** option is the default for veins created from lithology data, whereas the **Planar reference surface** option is the default for veins created from other types of data. In order for a vein created from data other than lithology data to use a curved reference surface, other data must be added to it. To add data, right-click on the reference surface in the project tree and select **Add** or **Edit**.

Using the **Add** option, you can add points data, GIS data or polylines to the surface. Using the **Edit** option, you can add a polyline to the reference surface, but its editing options are limited in that you can not add tangents or normals to the polyline.

Planar Reference Surface

Veins created from objects other than lithology data use a planar reference surface by default. To edit a planar reference surface, double-click on the reference surface in the project tree. This will open the **Edit Vein Reference Surface** window and display controls in the scene for adjusting the plane.

Look 🗸	∂ 8 B ■ ~ 🕞 Z Ø	1. The second se				0 🖌
😰 Edit Vein Refer	ence Surface	×				
<u>Curved refere</u>	ence surface					
Input values:						
Active Bou	undary filter Input					
Z	B2 midpoints					
		<	TT I			
			F. F.			
		200				
		PA -		HE	E C	
			+	E.F.	A REAL	
Planar refere	nce surface		+ 8	E.	HERE (2)	>
Location:		0	41			
Dip:	0.00000	<u> </u>	1	1200		00
Dip azimuth:	0.0	0		100	B Plunge	
		Set to Default			+0 0 Plunge + Azimu	
		Set to Default		0	500	750
 Custom refer 			10000000	(† pi		
Mesh: Se	lect mesh			🗗 Pla		
					Orientation	
?	Cancel	<u>о</u> к		Dip:	0.0	Û
				Dip az:	. 0.0	0

These handles work in the same manner as the moving plane controls, as described in <u>The Moving</u> <u>Plane</u>.


To use a planar reference surface for a vein created from lithology data, double-click on the reference surface to open the **Edit Vein Reference Surface** window, then select the **Planar reference surface** option. Adjust the plane in the scene, then click **OK** to reprocess the vein.

Custom Reference Surface

If you wish to use another surface in the project as a reference surface, double-click on the reference surface to open the **Edit Vein Reference Surface** window. Enable the **Custom reference surface** option, then select the mesh from those available in the project:


Edit Vein Refe	erence Surface	×
<u>Curved refe</u>	rence surface	
Input values:		
Active Bo	oundary filter Input	₩ Select mesh >
×	B2 midpoints	Meshes
		⊕ B1 FW
		B1 HW
		GM reference surface
		Geological Models
		🗸 🎲 GM
) <u>P</u> lanar refer	rence surface	Surface Chronology
Location:	930.89715006 , 1747.6420861 , 2.3954 , 0	► S1
<u>D</u> ip:	14.613227142700076	Cancel <u>O</u> K
Dip a <u>z</u> imuth:	138.99550700667598	
	Set to De	afault
Custom refe	erence surface	00 1400
Mesh: S	Select mesh	
?	<u>C</u> ancel <u>O</u> K	

This option is useful if you wish to use a mesh in the project as, for example, a common reference surface for all veins in a geological model. To do this, edit the reference surface for each vein so they all use the common surface for the **Custom reference surface** option:




The Vein Boundary

When a vein is first created, its boundary (\square) is empty:




Once a vein has been created, you can change its boundary by adding a polyline an adjusting the boundary plane.

To edit the boundary using a polyline, right-click on it in the project tree and select **Edit**. The current vein boundary will appear in the scene, together with drawing controls. Begin drawing the new boundary, as described in <u>Drawing in the Scene</u>, ensuring that the polyline drawn closes and does not intersect itself.



When you save the boundary, the vein will be updated to reflect the changes made. If you want to revert to the original boundary, right-click on the boundary object (¹) and select **Delete Polyline**.

The other option is to adjust the boundary plane. To do this, right-click on the boundary in the project tree and select **Adjust Plane**. The plane will be displayed in the scene, along with the **Adjust Boundary Plane** window. You can use the handles on the plane to adjust its position or you can enter the information in the **Adjust Boundary Plane** window.



Click **OK** to apply the changes to the vein.

To revert to the original boundary plane, right-click on the boundary object and select **Adjust Plane**. In the **Adjust Boundary Plane** window, click on the **Set to Default** button and click **OK**.

Editing Vein Segments


When a vein has been created from contact points, you can change the vein segment settings by double-clicking on the vein segments object (**III**) in the project tree. This opens the **Edit Vein** window:



When extracting the hanging wall and footwall points, Leapfrog Works automatically includes points at the ends of the boreholes. To exclude these points, untick the **Include points at the ends of holes** option in the **Edit Vein** window.

If you need to change the orientation of individual vein segments, e.g. for curved veins, you can do this by right-clicking on the vein segments object (\blacksquare) in the project tree and selecting **Edit In Scene**. If the vein segments object is already in the scene, you can edit it by clicking the **Edit** button (\checkmark) in the shape list.

The **Vein Segment Orientations** window will appear in the scene. Click on a vein segment to view information about that segment:



Points A and B are labelled in the scene and can be changed by unticking the box for each point and choosing whether to exclude the point or make it a hangingwall or footwall point. Once you have finished editing vein segments, click the **Save** button (🖹).


If you wish to return to the default settings, ensure the **Auto** box is ticked for each point.

Vein Systems


This topic describes creating a vein system for a geological model. The topic is divided into:

- Creating a Vein System
- Adding Veins to the Vein System
- Editing the Veins
- Changing Vein System Lithology Settings
- Setting Vein Interactions

An alternative to defining veins one-by-one is to create a vein system. The vein system represents a single lithology within the geological model. For example, for a model of a sedimentary system cross-cut by vertical intersecting dykes, we could model the veins one-by-one, in which case each "vein" in the model is represented by a separate lithology, as shown here:



Modelled as a vein system, however, the veins are grouped into a vein system object (\checkmark) that defines the lithology for the vein system as a whole:




Note that the individual veins are defined as part of the vein system.

The vein system defines how the veins interact, and veins can be added to it using the same techniques used to create individual veins.

Creating a Vein System

To create a vein system, right-click on the **Surface Chronology** and select **New Vein System**. In the window that appears, select the **Vein lithology**:




If the vein system contacts only one lithology, set the **Outside lithology**. Otherwise, leave **Outside lithology** set to Unknown.

Click **OK**. An empty vein system (\checkmark) will be added to the project tree under the **Surface Chronology**. Double-click on it to change the lithologies.

Adding Veins to the Vein System

Once the vein system has been created, you can create veins using the same techniques described in <u>Veins From Lithology Contacts</u> and <u>Veins From Other Data</u>.

To add veins to the vein system, right-click on the vein system and select one of the **New Vein** options:



Veins will appear in the project tree as part of the vein system object and can be expanded to show how they were created.

Editing the Veins

The techniques for editing vein system veins are the same as those for veins created one-by-one. See Refining Veins.

Changing Vein System Lithology Settings

You can change the lithology settings for a vein system by double-clicking on the vein system (下) in the project tree. In the **Lithology** tab, change the **Vein lithology** or the **Outside lithology**.

Setting Vein Interactions

Once all the veins required have been created, you can start defining the interactions between them by double-clicking on the vein system (, then clicking on the **Vein System** tab:

💋 Edit Vein System	×
Lithology Vein System	
Vein priority	
Veins	
In 1	
In 2	_
In 3	
□ In 4	
In 5	Ť
Interactions of	
Interaction Type Vein	Side
\oplus \oplus	
Name: Dyke Vein System	
Marrie. Dyne ven system	
(?) Cancel	<u>о</u> к

The veins appear in the list from highest priority to lowest. Organise the veins in chronological order before defining interactions.

The **Vein priority** determines which veins other veins can interact with. You cannot define an interaction for the highest priority vein in the list, and other veins in the list can interact only with those of higher priority.

Lithology	Vein System	
Vein priority		
Veins		
🗌 In 1		
🗌 In 2		
🗌 In 3		
In 4		
In 5		~
Interactions	of In 2	
_		Side
Interaction		
Terminate	In 1	Hanging wall
(+) (f)		
÷ (Э	
	Vein System	

Here, Vein B can only interact with Vein A, the higher priority vein:

The lowest priority vein, Vein D, can interact with all the other veins in the system:


🖌 Edit Vein System	۱					>
Lithology	Vein Sys	tem				
Vein priority						
Veins						
🗌 In 1						
🗌 In 2						
🗌 In 3					\wedge	
In 4						
In 5					\sim	
Interactions of	In 5					
Interaction Ty		Vein		Side		
Terminates a		In 1	Y	Hanging	wall 🗸	
	-	In 1	-67			
		In 2				
		In 3				
		In 4				
$\oplus \in$)					
Name: Dyke Ve	in Syste	m				
(?)		Cancel			ок	

To define an interaction, click on a vein, then click the **Add** button. Add an interaction for each vein and then set the **Side** on which they interact.

🖉 Edit Veir	n System					×
Litholo	gy Veir	n System				
Vein pr	iority					
	Veins					
	In 1					
	In 2				•	
	In 3				\sim	
	In 4					
	In 5				\sim	
	tions of In 5					
	action Type	Vein		Side		
Term	ninates agai	nst In 1	~	Hanging	10	
				Hanging		
				Foot wa		
(F)	\ominus					
<u>N</u> ame:	Dyke Vein S	ystem				
?		<u>C</u> an	cel		<u>0</u> K	

Once you have defined the required vein interactions, tick the box for each vein, then click **OK**. Once the **Vein System** object has been processed, add it to the scene to check that the veins interact correctly.

You can also edit vein interactions by double-clicking on the individual veins, which opens the vein's **Edit** window:



Veins and the vein system are not active in the geological model until the box is ticked for each vein in the **Edit Vein System** window and the vein system is enabled in the **Surface Chronology**. This means you can check the vein system without regenerating the geological model.

Stratigraphic Sequences

When you have a series of continuous layers in a geological model, you can model each layer separately, as part of a single stratigraphic sequence or using the offset surface tool. Modelling a stratigraphic sequence works best for sequences uniform in thickness with a consistent stacking order. If a layer varies in thickness, the contact surface may not match the contact points in some places. This will be a consideration when choosing whether to model layers as separate layers, as offset surfaces or as part of a stratigraphic sequence. For information on the offset surface tool, see Offset Surfaces.

Once you have created a stratigraphic sequence, you can refine it by adding and removing layers and by adjusting the surfaces produced.

This topic describes using the stratigraphic sequence tool and is divided into:

- Creating a Stratigraphic Sequence
- Editing the Stratigraphic Sequence
- Editing Individual Surfaces

Creating a Stratigraphic Sequence

To create a stratigraphic sequence, right-click on the **Surface Chronology** object and select **New Stratigraphy**. The **New Stratigraphic Sequence** window will appear:


New Stratigrap	hic Sequence	×		
Chronology	Surfacing			
Lithology Ab	ove: Unknown			
Stratigraphic	Lithologies:			
	~			
	\sim			
$\oplus \ominus$				
Lithology <u>B</u> e	low: Unknown			
Bottom Cont	act <u>T</u> ype: Deposit			
Surfaces avoid borehole segments				
Name: Stratigr	aphic Sequence			
?	<u>C</u> ancel <u>O</u> K			

Select the lithologies at the top and bottom of the stratigraphic sequence. To do this, select the **Lithology Above** and **Lithology Below** from the lithologies available in the geological model:

🖉 New Stratigraphic Sequence	2	×		
Chronology Surfacing		_		
Lithology Above: Stratigraphic Lithologie	Unknown Gravel Upper Shale Upper Shale Upper Banded Iron Formation Middle Shale Upper Carbonate Lower Banded Iron Formation Lower Shale Upper Basalt Lower Carbonate Middle Basalt Sandstone Lower Basalt Granite			
Name: Stratigraphic Sequence				
?	<u>C</u> ancel <u>O</u> K			

You can add lithologies to the Stratigraphic Lithologies list first, but if you set the Lithology

Above and Lithology Below first, those lithologies will be filtered out when you select the Stratigraphic Lithologies.



Next, click the **Add** button (🕀) to view available lithologies:

Select the lithologies that you want to use in the stratigraphic sequence, then click **OK** to add the layers to the **Stratigraphic Lithologies** list. Make sure they arranged in the correct order, using the arrows alongside the window to rearrange them, if necessary:

🚧 Edit Stratigraphic Sequence	×
Chronology Surfacing Trend	
Lithology Above: Gravel Stratigraphic Lithologies:	
Upper Shale Upper Banded Iron Formation	
Middle Shale	\sim
\oplus \ominus	

In the **New Stratigraphic Sequence** window, select whether the **Bottom Contact Type** is an erosion or a deposit.

When the **Surfaces avoid borehole segments** option is enabled, the surfaces in the stratigraphic sequence will not cut through intervals of lithologies that are selected for the stratigraphic sequence.

Next, click on the **Surfacing** tab to set the surfacing settings for each surface created for the sequence:

Boundary filter: All data Snap to data: Inherit from GM (Off)	
Snap to data: Inherit from GM (Off)	Ý
	~
Maximum snap distance:	25.00
✓ Inherit resolution from GM	
Surface resolution: 50.0 🗘 🗌 Adaptive	
Surface stiffness:	0.0

For the **Boundary filter** and **Snap to data** options, it is possible to override these settings for the individual contact surfaces that are part of the stratigraphic sequence. To do this, select **Custom**. Once the stratigraphic sequence has been created, expand it in the project tree and double-click on each surface to change its surfacing options, as described in <u>Contact Honouring and Boundary Filtering for Individual Surfaces</u> below.

Boundary Filtering

When data objects are added to a surface, there are two ways to handle the data that lies outside the surface's boundary:

- Filter the data. The surface is only influenced by the data that falls inside the surface's boundary.
- Leave the data unfiltered. The surface is influenced by the data both inside and outside the surface's boundary.

The **Boundary filter** setting determines how data used to define the surface is filtered:

- **Off**. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- Custom. Only the data objects specified in the Inputs tab are filtered.

All contact surfaces that make up a stratigraphic sequence will inherit the **Boundary filter** setting from the stratigraphy unless **Boundary filter** is set to **Custom**.

Snapping to Data

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab. For a stratigraphic sequence, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to the surfaces.
- **Drilling only**. Surfaces snap to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surfaces.
- Custom. Surfaces snap to the data objects indicated in the Inputs tab for each surface.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

All contact surfaces that make up a stratigraphic sequence will inherit the **Snap to data** setting from the stratigraphy unless **Snap to data** is set to **Custom**.


Surface Stiffness

The **Surface Stiffness** controls the smallest bend a surface will make, where a higher value will result in a smoother surface that bends less. The default value is 0, which is no stiffening.

Click **OK** to create the stratigraphy, which will be added to the project tree as part of the **Surface Chronology** object.

Editing the Stratigraphic Sequence

The objects that make up the stratigraphic sequence include the generated contact surfaces and any points that result in pinch-out errors:



Correcting Pinch-Out Errors

Add the pinch-out errors object (10) to the scene to view the points that are causing errors. To find out more about the errors, right-click on the sequence and select **List Errors**.

In the **Stratigraphic Errors** window, information is provided about the different errors that occur in the stratigraphic sequence, with pinch-out errors and other errors listed separately:

📽 Stratigrap	phic Errors	×
Pinch-out The follow	Errors ing lithologies are discontinuous and should be removed from the	stratigraphic sequence
Ignored	Invalid Contacts	Pinch-out Lithology
	'Lower Banded Iron Formation' touches 'Lower Shale' 20 times	Middle Basalt
	'Middle Basalt' touches 'Sandstone' 25 times	'Lower Shale', 'Uppi
	'Middle Basalt' touches 'Lower Carbonate' 23 times	'Lower Shale' and 'l
Other Erro	rs	
Ignored	Error Message	
	'Lower Banded Iron Formation' does not contact 'Middle Basalt'	
	'Middle Basalt' does not contact 'Lower Shale'	
	'Lower Carbonate' does not contact 'Lower Basalt'	
?	Cancel	<u>0</u> K

Use this information, together with the pinch-out error points, to either remove lithologies from the sequence or adjust surfaces using any of the tools available for individual surfaces, as described in <u>Editing</u> <u>Individual Surfaces</u> below.

Remove lithologies from the sequence by double-clicking on the sequence in the project tree, then reorganising the lithologies in the **Chronology** tab.

You can also ignore an error by ticking the **Ignored** box in the **Stratigraphic Errors** window.

Surfacing Options

To change a stratigraphic sequence's surfacing options, double-click on the sequence in the project tree and click on the **Surfacing** tab. See <u>Boundary Filtering</u> and <u>Snapping to Data</u> above for more information on the settings in this tab. Note that boundary filtering and snap settings can also be set for the individual surfaces that make up the stratigraphic sequence, which is described in <u>Contact Honouring</u> and Boundary Filtering for Individual Surfaces below.

Applying a Trend

To apply a global trend to a stratigraphic sequence either right-click on it in the project tree and select **Adjust Surface** or double-click on the stratigraphic sequence and then click on the **Trend** tab. You can then apply a trend to the surface as described in <u>Global Trends</u>.

Editing Individual Surfaces

Individual surfaces that make up a stratigraphic sequence can be modified by:

- Contact Honouring and Boundary Filtering for Individual Surfaces
- Adding Data to Individual Surfaces
- Editing Surface Contacts

Contact Honouring and Boundary Filtering for Individual Surfaces

There are general boundary filtering and snap settings for the stratigraphic sequence as a whole, but it is possible to override these settings for the individual surfaces that are part of the stratigraphic sequence.

To do this, first double-click on the stratigraphic sequence itself, then click on the **Surfacing** tab.

- To change boundary filtering for an individual surface, **Boundary filter** must be set to **Custom** for the stratigraphic sequence.
- To change the snap setting for an individual surface, **Snap to data** must be set to **Custom** for the stratigraphic sequence.

Next, double-click on an individual surface in the project tree. The window that appears shows all the data objects used to create the surface:

😰 Edit Stra	tigraphic Surface		
Inputs:			
Snap	Boundary filter	Input	
	~	Middle Shale - Upper Carbonate contacts	
	~	C Upper Carbonate - Middle Shale Contacts	
Name Upper Carbonate - Middle Shale Contacts			
?		<u>C</u> ancel <u>Q</u> K	

See Boundary Filtering and Snapping to Data for more information.

Adding Data to Individual Surfaces

You can also refine the individual surfaces in a stratigraphic sequence in several ways:

- Add other data. Right-click on the surface to see the options available, which will depend on how the surface was created. See <u>Adding Data to Surfaces</u> for more information.
- Edit the surface with a polyline. Right-click on the surface in the project tree and select either **Edit > With Polyline**. See Editing Surfaces With Polylines for more information.

It is not possible to add structural data or polylines with orientation information to individual surfaces in a stratigraphic sequence. If you edit a surface with a polyline, your options for editing the polyline will be limited.


Editing Surface Contacts

You can edit the contacts used to generate the surface by expanding the contact surface in the project tree and double-clicking on the points object (¹¹). See <u>Extracting Contact Points from Borehole Data</u> for more information on the settings in the **Edit Contacts** window.

Offset Surfaces

The offset surface tool is useful way of creating a series of deposit or erosion contact surfaces from a reference mesh. The surface can be offset from the reference mesh by points or by a fixed distance, and additional options for offsetting to points can be adjusted once the surface has been created.

Here a deposit contact surface (blue) has been created using the reference mesh (green) offset to points (red):



Important considerations when creating offset surfaces is the characteristics of the reference mesh, especially in relation to the geological model's boundary.

- It is best to use a reference mesh that extends beyond the model's boundary. If the reference mesh is too small, the offset surface may be distorted where the reference mesh does not occur.
- If the reference mesh changes significantly near the model's boundary, offset surfaces may show unexpected changes. Offset surfaces are projected in the direction the reference mesh is going, and if the reference mesh changes direction just inside the boundary, that change will be reflected in the offset surface. This is normal if there is data that takes the reference mesh in a different direction, but if this is not desirable for the offset surface, consider making the geological model's boundary smaller.

The rest of this topic describes creating and working with an offset surface. It is divided into:

- Creating an Offset Surface
- The Offset Surface in the Project Tree
- <u>Refining an Offset Surface</u>
- Changing Surfacing Options for an Offset Surface
- <u>Changing Offset Limits</u>
- Changing the Reference Mesh
- Editing the Reference Mesh

Creating an Offset Surface

To start creating an offset surface, right-click on the **Surface Chronology** and select **New Deposit/Erosion > From Offset Surface**. The **New Offset Surface** window will appear:

🖉 New Offset Surface	:	×			
Reference mesh					
Select reference	ce mesh				
Surface points					
\oplus \ominus					
 Constant offset 	 Constant offset 				
Distance: 0.0		0			
Direction: • Fo	Direction: • Forward · Backward				
Select lithology					
First lithology:	Unknown	is Younger 🗸			
Second lithology:	Unknown	is Older			
Name: Unknown	n - Unknown contacts				
?	Cancel	<u>о</u> к			

In the window that appears, you need to select a reference mesh, then either select **Surface points** to offset to or set a **Constant offset**.

Click **Select reference mesh** to view the meshes available in the project.

If you wish to offset from the reference mesh using a fixed distance, click **Constant offset** and set the **Distance**. For **Direction**, selecting **Forward** offsets the surface on the younger side of the reference mesh, and selecting **Backward** offsets on the older side.

If you wish to offset to points, click **Add**. You can offset to:

- Base lithology contacts or other lithology contacts in the project.
- Other data in the project. GIS data, points data and polylines can be used.

If you offset to points, you will be able to set additional options such as distance limits once the surface has been created. See Changing Offset Limits below for more information.

Select the **First Lithology** and **Second Lithology** from the lithologies defined for the model. If you have added base lithology contacts or other contacts to the surface, these will be set automatically from the data used.

Click OK to create the surface, which will appear in the project tree as part of the Surface Chronology.

The Offset Surface in the Project Tree

The name Leapfrog Works automatically assigns to an offset surface is the lithologies assigned to each side of the surface. In the project tree, expand the surface to see how it was made:



Double-click on the surface to edit it. Double-click on the contact points object (¹¹) to edit the lithology and change compositing parameters.

As further refinements are made to the surface, that information will also be added to the project tree. See <u>Refining an Offset Surface</u> below for more information.

Refining an Offset Surface

You can refine an offset surface by:

- Adding other data. Right-click on the surface to see the options available, which will depend on how the surface was created. See <u>Adding Data to Surfaces</u> for more information.
- Editing the surface with a polyline. Right-click on the surface in the project tree and select either **Edit**. See <u>Editing Surfaces With Polylines</u> for more information.

It is not possible to add structural data or polylines with orientation information to an offset surface. If you edit an offset surface with a polyline, your options for editing the polyline will be limited.

To edit the surface's settings, double-click on it in the project tree. In the **Lithologies** tab, change the lithologies assigned to each side of the surface, if required.

You can swap the younging direction if the direction was assigned incorrectly when the surface was created. The change will be reflected in the scene. Note that changing the younging direction does not change which lithology is older or younger.

An offset surface can be created as a deposit or as an erosion. The difference between deposit and erosion contact surfaces is how they cut older lithologies, as described in <u>Contact Surfaces</u>. For this reason, it is possible to change between the two types using the **Contact Type** setting.

An offset surface cannot be adjusted by applying a trend.

Changing Surfacing Options for an Offset Surface

Surfacing options for an offset surface can be changed by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab. There are additional settings related to boundary filtering and snapping to data in the **Inputs** tab.

Boundary Filtering

When data objects are added to a surface, there are two ways to handle the data that lies outside the surface's boundary:

- Filter the data. The surface is only influenced by the data that falls inside the surface's boundary.
- Leave the data unfiltered. The surface is influenced by the data both inside and outside the surface's boundary.

The **Boundary filter** setting determines how data used to define the surface is filtered:

- **Off**. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- Custom. Only the data objects specified in the Inputs tab are filtered.

Snapping to Data

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations, as discussed in <u>Honouring Surface Contacts</u>.

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab.

For individual contact surfaces, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to the surfaces.
- **Drilling only**. Surfaces snap to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surfaces.
- Custom. Surfaces snap to the data objects indicated in the Inputs tab for each surface.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

If you need a surface to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

There is also a snap setting that can be used when offset limits are used. This option is discussed in <u>Changing Offset Limits</u> below.

Surface Resolution

The surface resolution for an offset surface can be inherited from the geological model or it can be set specifically for the surface. To change the surface resolution for an offset surface, double-click on the

surface in the project tree and then click on the **Surfacing** tab. See <u>Surface Resolution for a Geological</u> <u>Model</u> for information about the surface resolution settings in the **Surfacing** tab.

Smoothing

The **Smoothing** parameter in the **Surfacing** tab can be used for all offset types other than **Constant**. If your reference surface is highly curved, you may see distortions in the offset surface. If this is the case, set **Smoothing** to a higher value.

Increasing the **Smoothing** parameter will generally result in faster processing when offsetting to large distances. If you are finding that processing time is excessively long for an offset surface, consider increasing **Smoothing**. In some situations, however, increasing **Smoothing** can exaggerate imperfections in the reference surface.

If you are offsetting by a small distance and processing is taking longer than expected, consider setting **Smoothing** to **None**.

Changing Offset Limits

There are four options for **Offset limits** in the **Surfacing** tab. Three relate to offsetting to points and the fourth to offsetting to a fixed distance from the reference mesh.

- The **None** option is the default setting used when a surface is created as an offset to points. No distance limits are used in creating the offset surface, and it simply follows the points used.
- The **Unidirectional limits** option allows you to set distance limits in one direction. Points outside the limits will be disregarded.
- The **Bidirectional limits** option allows you to set distance limits in both directions, and points outside these limits are disregarded. This setting is useful for modelling folded surfaces such as veins.
- The **Constant offset** option offsets the surface to a fixed distance from the reference mesh.

The **Forward** direction is the younger side of the reference mesh.

If the **Snap to data outside limits** setting is enabled, the surface will honour data, even if it is outside the distance limits. This option will be greyed out if **Snap to data** is off.

Changing to a Constant Offset

To use a constant offset rather than points, select the **Constant offset** option and set the **Distance** and **Direction** to offset the surface. Selecting **Forward** offsets the surface on the younger side of the reference mesh, whereas selecting **Backward** offsets on the older side.

If you created a surface as an offset to points and switch to using a constant offset, the points added to the surface when it was created will be disabled.

Changing to an Offset to Points

If you created an offset surface using a constant offset, you can change the surface to offset to points, but you must first add data to it. Do this by right-clicking on it in the project tree and selecting **Add**. Once you have added the data you wish to use, double-click on the surface and click on the **Surfacing** tab. Change the **Offset limits** option from **Constant offset** to one of the other three options.

Changing the Reference Mesh

To change the surface used as the reference mesh, click on the **Inputs** tab, then click on the reference mesh:

🖉 Edit UBif	- Unknown contac	xts X						
Litholog	ies Surfacing	Inputs						
Reference	Reference mesh:							
Surface	points:							
Snap	Boundary filter	Input						
	×	UBif contacts						

Select from the surfaces available in the project, keeping in mind the considerations discussed in Changing the Reference Mesh.

Editing the Reference Mesh

You can also edit the reference mesh as you would other surfaces. All dependent offset surfaces will be updated as you make changes to the reference mesh.

Changing the younging direction of the reference mesh affects how offset surfaces are generated.

- For a constant offset surface, the younging direction of the reference mesh determines the forward and backward direction of the offset surface and, therefore, determines the location of the offset surface. Changing the younging direction of the reference mesh results in dependent offset surfaces changing location; the updated offset surface will be the mirror image of the original relative to the reference mesh.
- For surfaces offset to points, the location is determined by the points themselves. If the reference
 mesh's younging direction is changed, the offset surface's younging direction will also be flipped.
 The offset surface will still honour the contact data and will still appear at the same location relative to
 the reference mesh.

Structural Surfaces

A structural surface uses contact data and non-contact structural data to create a surface. A structural surface can interact with other volumes in the model as a deposit, an erosion or an intrusion contact surface. The shape of the structural surface is suggested by the non-contact structural data used.

When creating a structural surface, there are two options for declustering the non-contact structural data:

- The input data is automatically declustered as part of creating the structural surface. There are no additional controls that determine how the data is declustered.
- Use a declustered structural data set as the non-contact input to the surface. This approach is recommended over the first approach as you can change how the data is declustered.

The rest of this topic describes how to create and work with a structural surface. It is divided into:

- Creating a Structural Surface
- The Structural Surface in the Project Tree

- Refining a Structural Surface
- Surfacing Options for a Structural Surface
- Non-Contact Structural Inputs Settings
- Applying a Trend to a Structural Surface
- Value Clipping

Creating a Structural Surface

To create a new structural surface, right-click on the **Surface Chronology** and select **New Structural Surface**. The **New Structural Surface** window will appear:

📽 New Structural Surface				×
Select non-contact struct	ural data:			
Structural Data	Query Filter		Use Polarity	
\oplus \ominus				
Select other input data:				
\oplus \bigcirc				
Select lithologies:				
	Unknown	~	is Younger 🗸 🗸	
	Unknown	√ is	Older	
Our to at Turney Descent				
Contact Type: Deposit	L			<u> </u>
Name: Unknown - Unk	nown contacts			
?	<u>C</u> ancel		<u>о</u> к	

Use the **Add** buttons to add non-contact structural data and on-surface contacts, then set the **First lithology** and **Second lithology**. Other settings are:

- **Query Filter**. Select from the query filters defined for the selected structural data object.
- Use Polarity. Untick the box to use tangents only.
- **Contact Type**. Structural surfaces can be deposit, erosion or intrusion contacts. The same algorithm is used for each setting; the only difference is in how the surface interacts with other surfaces.


The Structural Surface in the Project Tree

The name Leapfrog Works automatically assigns to a structural surface is the lithologies assigned to each side of the surface. In the project tree, expand the surface to see how it was made:



As further refinements are made to the surface, that information will also be added to the project tree. See <u>Refining a Structural Surface</u> below for more information.

To add more non-contact structural data to the surface, right-click on it in the project tree and select **Add > Structural Data**. In the window that appears, tick the box for **Non-contact Structural Data**:



Refining a Structural Surface

You can refine structural surfaces in several ways:

- Add other data. Right-click on the surface to see the options available, which will depend on how the surface was created. See <u>Adding Data to Surfaces</u> for more information.
- Edit the surface with a polyline. Right-click on the surface in the project tree and select either **Edit > With Polyline**. See Editing Surfaces With Polylines for more information.
- Edit the surface using structural data. Right-click on the surface and select **Edit > With Structural Data**. See Editing Surfaces With Structural Data for more information.

To edit the surface's settings, double-click on it in the project tree. In the **Lithologies** tab, change the lithologies assigned to each side of the surface, if required.

You can swap the younging direction if the direction was assigned incorrectly when the surface was created. The change will be reflected in the scene. Note that changing the younging direction does not change which lithology is older or younger.

The **Contact Type** setting determines how the structural surface interacts with other lithologies, as described in <u>Contact Surfaces</u>. A structural surface can be a deposit, erosion or intrusion contact surface.

For information on other techniques for refining structural surfaces, see <u>Surfacing Options for a</u> <u>Structural Surface</u> below.

Surfacing Options for a Structural Surface

Surfacing options for a structural surface are accessed by double-clicking on the surface in the project tree and clicking on the **Surfacing** tab. There are additional settings related to boundary filtering and snapping to data in the **Inputs** tab.

Setting the Surface Resolution

See <u>Surface Resolution for a Geological Model</u> for information about the surface resolution settings in the **Surfacing** tab.

Boundary Filtering

When data objects are added to a surface, there are two ways to handle the data that lies outside the surface's boundary:

- Filter the data. The surface is only influenced by the data that falls inside the surface's boundary.
- Leave the data unfiltered. The surface is influenced by the data both inside and outside the surface's boundary.

The boundary of a structural surface can be the geological model boundary or a fault block boundary.

The **Boundary filter** setting determines how data used to define the surface is filtered:

- **Off**. Data is not filtered.
- All data. All data is filtered.
- Drilling only. Only borehole data and data objects derived from borehole data are filtered.
- Custom. Only the data objects specified in the Inputs tab are filtered.

Snapping to Input Data

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations. See <u>Honouring Surface Contacts</u>.

There is a **Snap to data** setting for a geological model as a whole that is set in the **Geological Model > General** tab (see <u>Editing a Geological Model</u>). **Snap to data** can also be set on a surface-by-surface basis by double-clicking on the surface in the project tree and then clicking on the **Surfacing** tab.

For individual contact surfaces, the options are:

- Inherit from GM. The setting for the geological model as a whole is used. This is the default setting.
- Off. Surfaces do not snap to the data used to create them.
- All data. Surfaces snap to all data within the **Maximum snap distance**, which includes borehole data and any data added to the surfaces.
- **Drilling only**. Surfaces snap to borehole data and data objects derived from borehole data within the **Maximum snap distance** but not to other data used to modify the surfaces.
- Custom. Surfaces snap to the data objects indicated in the Inputs tab for each surface.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to**

data, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

If you need a surface to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Non-Contact Structural Inputs Settings

For the non-contact structural inputs, you can:

- Change the **Query Filter** setting. Select from the query filters defined for the selected structural data object.
- Change the **Use Polarity** setting. Untick the box to use tangents only.
- Change the **Boundary filter** setting, if the **Boundary filter** setting in the **Surfacing** tab is set to **Custom**.

Applying a Trend to a Structural Surface

There are two ways to change the trend for a structural surface:

- Right-click on the surface in the project tree and select Adjust Surface.
- Double-click on the surface in the project tree and then click on the **Trend** tab.

See Global Trends for more information.

Value Clipping

In the **Value Clipping** tab, you can manipulate the data distribution by clipping the data. Clipping caps values that are outside the range set by the **Lower bound** and **Upper bound** values. For example, if you change the **Upper bound** from 16.00 to 10.00, distance values above 10.00 will be regarded as 10.00.

When Automatic clipping and Do clipping are enabled, Leapfrog Works sets the Lower bound and Upper bound from the data. To change the Lower bound and Upper bound, untick Automatic clipping, tick Do clipping and then change the values.


The Surface Chronology

When you create a contact surface, it appears in the project tree under the **Surface Chronology** object, but it is not enabled and, therefore, does not affect the geological model volumes. This means you can work on the surface without having to reprocess the model whenever you make a change to the surface. In Leapfrog Works, you can easily define, enable and remove contact surfaces from a model, and you can experiment with modelling lithologies using different techniques in order to arrive at a geologically reasonable model.

To add a contact surface to the surface chronology, double-click on the **Surface Chronology** object. The **Surface Chronology** window will be displayed:

E	Geologic	al Model - RockTy	/pe GM			×
	General	Boundary	Fault System	Lithologies	Chronology]
	Conta	ct <u>s</u> urface chrono	logy:			
		Contact surface				
	~	12				
	~	11				
		🛞 D2 - D1 cont	tacts		~	
	~	🛞 D3 - D2 cont	tacts			
		💓 D4 - D3 cont	tacts		\sim	
	~	💓 D5 - D4 cont	tacts			
	Bac <u>k</u> ç	ground lithology:	Unknown		\sim	
	?		Cano	cel	<u>о</u> к	

In the project tree, the surfaces are also arranged in chronological order:



The **Surface Chronology** determines the overall chronological order of the contact surfaces in the model. If you build your models from the bottom up, you will find that often the contact surfaces are in the correct chronological order when you first open the **Surface Chronology** window. However, you can easily rearrange the chronology using the arrows alongside the table of contact surfaces. Tick the boxes for surfaces you wish to include in the model. When you click **OK**, the included surfaces will be used to subdivide the geological model into lithological volumes. The volumes will appear in the **Output Volumes** folder.

Output volumes are named according to the lithologies assigned to each side of the contact surfaces that bound each volume. If the lithology assigned to an output volume cannot be determined, it will be assigned the **Background lithology**.

If you are working with a faulted model and have defined the **Surface Chronology** for one fault block, you can copy the **Surface Chronology** to the empty fault blocks. See <u>Copying the Surface</u> Chronology to an Empty Fault Block.

Refined Models

When you have built a geological model and want to model further within one of the volumes, you can do this by creating a refined geological model. This changes the way the original (parent) geological model is organised in the project tree and makes it possible to create a sub-model within one or more of the lithological volumes.

Before starting to refine lithological volumes, it is a good idea to make a copy of the original geological model.

To start refining a lithological volume, first create the refined geological model. To do this, right-click on the **Geological Models** folder and select **New Refined Model**:

✓ ☐ Geological Models	
> 🍘 GM	í New Geological Model
> 🍘 GM 2	Wew Refined Model
> 🍘 GM copy	import Geological Model from <u>C</u> entral
> 🍘 GM copy 2	New Subfolder
> 🍘 IntGM	


In the window that appears, select the geological model to refine and then select from its lithologies.

~					
🧉 New R	efined Mode			×	
Model to	o refine:	1	M Campaign GM	~	
Litholog	y to refine:		QzP	~	
General					
Base	ithology colu	ımn:	RockType	~	
<u>F</u> ilter	data:		🖓 collar: M campaign	~	
Surfac	ce resolution	:	50.0	🗘 🗌 Adaptive	
Name:	Refined M	Camp	aign GM		
?			<u>C</u> ancel	<u>0</u> K	

Next, set the **Base lithology column**, **Filter data** and **Surface resolution**. You cannot change the **Base lithology column** once the refined geological model has been established, but you will be able to change the resolution and data filter settings.

Click **OK** to create the refined lithology.

A new refined model () will be created in the project tree and the parent geological model will be moved into it. Here, a model called "M Campaign GM" has been used to created a new refined model, with the QzP volume selected as the refined lithology ():



The sub-model () is created inside the refined geological model and has its own **Boundary**, **Lithologies**, **Surface Chronology** and **Output Volumes** objects.


You can work with the sub-model in the same manner you would a normal geological model. The exceptions are:

- The sub-model's boundary cannot be refined directly. However, changes to the parent geological model will be updated in the sub-model's boundary.
- The sub-model cannot have its own fault system. If the parent geological model is faulted, the submodel will have its own fault blocks in which you can work.

See Editing the Sub-Model below for more information.


You can still work with the parent geological model in the usual manner. Any changes to the parent geological model that change the extents of the sub-model will be reflected in the sub-model's boundary.

You can create additional sub-models by right-clicking on the refined model (⁴) and selecting **Refine** Lithology:



A sub-model can be viewed and evaluated in the same manner as normal geological models. However, sub-models cannot be used as layer guides for flow models.

Deleting the refined geological model deletes all models it contains. To return to the original project tree organisation for a geological model, delete the sub-models:



Once there are no more sub-models, the refined model object is also deleted, leaving the parent geological model.

The refined model has its own **Lithologies** table, which contains all the lithologies from the parent model and any sub-model lithologies. You cannot add lithologies to this table, but you can change the colours used to display them in the scene, as described in <u>Model Lithologies</u>. To add more lithologies to a refined model, add them to the lithology table in either the sub-model or the parent geological model.

The refined model also has its own **Output Volumes** folder that combines information from the parent geological model and the sub-model. If no surfaces have been created in the sub-model, adding the refined model to the scene will simply display the volumes from the parent geological model. If surfaces have been created in the sub-model, then the volumes of the sub-model will be displayed alongside the volumes from the parent geological model.

Editing the Sub-Model

Work with the sub-model in the same manner described in:

- Editing a Geological Model
- <u>Contact Surfaces</u>
- The Surface Chronology

The sub-model can have resolution settings that are different from those of the parent model. See <u>Surface Resolution in Leapfrog Works</u> and <u>Surface Resolution for a Geological Model</u>.

To change the sub-model's resolution settings, double-click on it () in the project tree. The **Geological Model** window appears:

		Chronology	_
Base Lith			
		M_Geology - RockType	
<u>F</u> ilter da	ata:	🖓 collar: M campaign	~
Surface G	eneration		
Surface	eresolution:	50.0 🗘 🗌 Adaptive	
Snap to	data:	Off	~
Maximu	um snap <u>d</u> istanc	e:	50.0%

This window has only three tabs:

- There is no **Boundary** tab because the sub-model's boundary can only be modified by modifying the parent geological model.
- There is no Fault System tab because a sub-model cannot have its own fault system.

Numeric Models

The FastRBF algorithm employs interpolation functions to estimate values from known data. From these estimated values, geological surfaces are constructed as part of the model-building process.

With the Numeric Models folder, you can create numeric models and change their parameters.

- An RBF interpolant describes a physical quantity that varies continuously in space. An RBF interpolant can be used to model, for example, RQD data, with isosurfaces values set to represent both high-quality and low-quality rock. See <u>RBF Interpolants</u>.
- A multi-domained RBF interpolant is an RBF interpolant that has a number of individual subinterpolants that are bounded by the fault blocks or output volumes of a selected geological model. Changes to all sub-interpolants can be made by editing the parent interpolant, while sub-interpolants can be edited to account for local influences on the values used, the trend and interpolation parameters. See <u>Multi-Domained RBF Interpolants</u>.
- A distance function calculates the distance to a set of points, which is useful for restricting processing to a specific region. To do this, create a distance function, select the objects to use, then add at least one buffer. You can then use one of the distance function's isosurfaces as a lateral extent for another model. See <u>Distance Functions</u>.

Values that can be interpolated include downhole numeric data, composited borehole data and points data. See <u>Interpolant Functions</u> for a general introduction to interpolation.

The rest of this topic describes:

- Copying a Numeric Model
- Creating a Static Copy of a Numeric Model
- Exporting Numeric Model Volumes and Surfaces
- Exporting Numeric Model Midpoints

Importing a Variogram Model

Leapfrog Works can import spheroidal variogram models exported from Snowden Supervisor. The settings that can be imported are:

- The anisotropy settings in the **Trend** tab
- The Nugget, Total Sill, Base Range and Alpha settings in the Interpolant tab

To import a variogram model, first create an interpolant. Next, right-click on the interpolant and select **Import Variogram Parameters**. In the window that appears, navigate to the folder that contains the XML file and select it. Click **Open**. The interpolant will be updated with the parameters in the XML file.

The imported variogram model overwrites the parameters in the interpolant, which cannot be undone. If you wish to save the original settings, make a copy of the interpolant before importing the new parameters.

Once the interpolant has been updated, you can edit it further by double-clicking on the interpolant in the project tree.

Copying a Numeric Model

Creating a copy of a numeric model is a useful way of experimenting with changes to a model.

To copy a numeric model, right-click on it in the project tree and select **Copy**. Enter a name for the copy of the model and click **OK**. The copy will be added to the project tree.

Creating a Static Copy of a Numeric Model

Creating a static copy preserves a snapshot of a numeric model that does not change, even when changes are made to the data on which the original model was dependent. This is a useful way of storing historical models and comparing models. Static copies can be exported from Leapfrog Works, as described in Exporting Numeric Model Volumes and Surfaces below.

To create a static copy of a numeric model, right-click on it in the project tree and select **Static Copy**. Enter a name for the copy of the numeric model and click **OK**. The copy will be added to the **Numeric Models** folder.

The objects that make up a static copy of a numeric model depend on the type of model:

- For an RBF interpolant, a static copy is made up of a **Legend** object, a **Boundary** object, and all isosurfaces and output volumes created in building the model.
- For a multi-domained RBF interpolant, a static copy is made up of a **Legend** object, a **Boundary** object, and the output volumes created in building the model. There are also static copies of the sub-interpolants, which are the same as static copies of RBF interpolants.
- For an indicator RBF interpolant, a static copy is made up of a **Legend** object, a **Boundary** object, the model's isosurface and the output volumes.

To view the date a static copy was created, right-click on it in the project tree and select **Properties**. The date the copy was created is in the **General** tab.

Exporting Numeric Model Volumes and Surfaces

There are three options for exporting a numeric model's output volumes and surfaces. These are:

- Export an output volume or a surface as a mesh. Right-click on it in the project tree and click **Export**. You will be prompted for a file name and location. See <u>Exporting a Single Mesh</u>.
- Export an output volume as a thickness grid. Right-click on it in the project tree and click **Export Thickness Grid**. See <u>Thickness Grids</u>.
- Export multiple output volumes and surfaces. Right-click on the interpolant in the project tree and select **Export**. See Exporting Multiple Meshes from Models.

Exporting Numeric Model Midpoints

To export interval midpoints from a numeric model, right-click on the model's values object (¹/₂) and select **Export**. Interval midpoints can be exported in the following formats:

- CSV text file (*.csv)
- DXF file (*.dxf)
- Snowden Supervisor CSV file (*.csv)

- Isatis 3D points file (*.asc)
- Drawing Files (2013/LT2013) (*.dwg)

The values exported are the midpoints of each segment, the X-Y-Z values and the hole ID. The Snowden Supervisor and Isatis 3D points formats also include the interval length, when the model has been created from borehole data.

In each case, you will be prompted for a filename and location.

You can extract interval midpoints from borehole data and then export them from the **Points** folder. See <u>Extracting Interval Midpoints from Borehole Data</u> for more information.

RBF Interpolants

If the data is both regularly and adequately sampled, different RBF interpolants will produce similar results. In practice, however, it is rarely the case that data is so abundant and input is required to ensure an interpolant produces geologically reasonable results. For this reason, only a basic set of parameters are required when an RBF interpolant is first created. Once the interpolant has been created, you can refine it to factor in real-world observations and account for limitations in the data.

The rest of this topic describes how to create and modify RBF interpolants. It is divided into:

- Creating an RBF Interpolant
- The RBF Interpolant in the Project Tree
- Interpolant Display
- <u>RBF Interpolant Statistics</u>
- Modifying an RBF Interpolant's Boundary With Lateral Extents
- Changing the Settings for an RBF Interpolant

Creating an RBF Interpolant

To create an RBF interpolant, right-click on the **Numeric Models** folder and select **New RBF Interpolant**. The **New RBF Interpolant** window will be displayed:

🧉 New RBF Interpolant								×
Values To Interpolate		RQD		Interpolant Boun	dary			
Query Filter		ΝQD	~	-	Minim		Maximur	
Surface Filter				X (East):	115893	8.1 🗘	1165562.1	0
Interpolant Bounda	ary			Y (North):	488640	5.9 🗘	4895573.9	0
○ O <u>t</u> her		Select surf	ace	Z (Elev):	-166.0	÷	1466.0	$\hat{}$
Compositing						Enc	close Object	\sim
Composite in:	No cor	npositing	~	 Existing mode 	el boundai	y or vol	ume	
Compositing length:		10.00				8	Select Surfac	е
If residual end length les	s than:	0.00		General				
then	discard			Surface resolution	tion: 30	0.0	0 🗌 🗌 🗋 🗍	tive
Minimum coverage:		50%		Volumes enclo	ise: In	tervals		\sim
Additional weighting col	umn:	<none></none>						
Name: RQD								
?				Cano	cel		<u>0</u> K	

This window is divided into four parts that determine the values used to create the interpolant, the interpolant boundary, any compositing options and general interpolant properties.

If you are unsure of some settings, most can be changed later. However, the **Numeric values** object selected when the interpolant is created cannot be changed.

Values Used

In the **Values To Interpolate** part of the **New RBF Interpolant** window, you can select the values that will be used and choose whether or not to filter the data and use a subset of those values in the interpolant.

You can build an interpolant from either:

- Numeric data contained in imported borehole data.
- Points data imported into the **Points** folder.

All suitable data in the project is available from the Numeric values list.

Applying a Query Filter

If you have defined a query filter and wish to use it to create the interpolant, select the filter from the **Query filter** list. Once the interpolant has been created, you can remove the filter or select a different filter.

Applying a Surface Filter

All available data can be used to generate the interpolant or the data can be filtered so that only the data that is within the interpolant boundary or another boundary in the project influences the interpolant. The **Surface Filter** option is enabled by default, but if you wish to use all data in the project, untick the box for **Surface Filter**. Otherwise, you can select the **Interpolant Boundary** or another boundary in the project.

You can use both the **Query Filter** option and the **Surface Filter** option together.

The Interpolant Boundary

There are several ways to set the **Interpolant Boundary**:

- Enter values to set a **Custom** boundary.
- Use the controls in the scene to set the **Custom** boundary dimensions.
- Select another object in the project from the **Enclose Object** list, which could be the numeric values object being interpolated. The extents for that object will be used as the basis for the **Custom** boundary dimensions.
- Select another object in the project to use as the **Interpolant Boundary**. Click the **Existing model boundary or volume** option and select the required object from the list.

Once the interpolant has been created, you can further modify its boundary. See <u>Modifying an RBF</u> Interpolant's Boundary With Lateral Extents and <u>Adjusting the Interpolant Boundary</u> below.

Compositing Options

When numeric values from borehole data are used to create an interpolant, there are two approaches to compositing that data:

- Composite the borehole data, then use the composited values to create an interpolant. If you select composited values to create an interpolant, compositing options will be disabled.
- Use borehole data that hasn't been composited to create an interpolant, then apply compositing settings to the interpolated values. If you are interpolating values that have not been composited and do not have specific **Compositing** values in mind, you may wish to leave this option blank as it can be changed once the model has been created.

If you are interpolating points, compositing options will be disabled.

See <u>Numeric Composites</u> for more information on the effects of the **Compositing length**, **For end lengths less than**, **Minimum coverage** and **Additional weighting column** settings.

General Interpolant Properties

Set the **Surface resolution** for the interpolant and whether or not the resolution is adaptive. See <u>Surface Resolution in Leapfrog Works</u> for more information on the effects of these settings. The resolution can be changed once the interpolant has been created, so setting a value in the **New RBF Interpolant** window is not vital. A lower value will produce more detail, but calculations will take longer.

The Volumes enclose option determines whether the interpolant volumes enclose **Higher Values**, **Lower Values** or **Intervals**. Again, this option can be changed once the interpolant has been created.

Enter a Name for the new interpolant and click OK.


Once you have created an RBF interpolant, you can adjust its properties by double-clicking on it. You can also double-click on the individual objects that make up the interpolant.

See also:

- Copying a Numeric Model
- Creating a Static Copy of a Numeric Model
- Exporting Numeric Model Volumes and Surfaces

The RBF Interpolant in the Project Tree

The new interpolant will be created and added to the **Numeric Models** folder. The new interpolant contains objects that represent different parts of the interpolant:



- The **Boundary** object defines the limits of the interpolant. See <u>Adjusting the Interpolant Boundary</u>.
- The **Trend** object describes the trend applied in the interpolant. See <u>Changing the Trend for an RBF</u> <u>Interpolant</u>.
- The points data values object contains all the data used in generating the interpolant. See <u>Adjusting</u> <u>the Values Used</u>.
- The Isosurfaces folder contains all the meshes generated in building the interpolant.
- The **Output Volumes** folder contains all the volumes generated in building the interpolant.

Other objects may appear in the project tree under the interpolant as you make changes to it.

Interpolant Display

Display the interpolant by:

- Dragging the interpolant into the scene or right-clicking on the interpolant and selecting **View Output Volumes**. Both actions display the interpolant's output volumes.
- Right-clicking on the interpolant and selecting View Isosurfaces.

RBF Interpolant Statistics

You can view the approximated mean for each output volume by right-clicking on the interpolant and selecting **Properties**. Click on the **Statistics** tab:

General	Processing	Sta	tistics	History		
			Approx	x. Mean		
Interval	Interval Volu	me	Value		Units	
< 47.0	9672379.82	955	47		454601851.98	9
47.0-65.0	336448068.3	76	56		18841091850.	6
65.0-85.0	251085825.	524	75		18831436914.	3
> 85.0	3393725.88	628	85		288466700.33	4
			Approx	x. Total:	38,415,597,317	7
multiplied by For example, specified in m	a density to pro if the original da	duce v ata we values	weights. ere in gra	ms/tonne	then the values w and distances ha ultiplied by the sp	ive been

You can copy the information displayed in the **Statistics** tab to the clipboard for use in other applications.

Modifying an RBF Interpolant's Boundary With Lateral Extents

RBF interpolants are created with a basic set of rectangular extents that can then be refined using other data in the project. These extents usually correspond to the ground surface and known boundaries. Creating extents can also be used to restrict modelling to a particular area of interest; for example, modelling can be restricted to a known distance from boreholes by applying a distance function as a lateral extent. Extents do not need to be strictly vertical surfaces and can be model volumes.

Creating Lateral Extents

To create an extent, expand the RBF interpolant in the project tree. Right-click on the **Boundary** object and select from the **New Lateral Extent** options. Follow the prompts to create the extent, which will then appear in the project tree under the interpolant's **Boundary** object.

New extents are automatically applied to the boundary being modified. Leapfrog Works usually orients a new extent correctly, with red presenting the inside face of the extent and blue representing the outside

face. If this is not the case, you can change the orientation by right-clicking on the extent in the project tree and selecting **Swap Inside**.

Extent From a Polyline

You can create an extent from a polyline that already exists in the project or you can draw a new one. If you want to use an imported polyline, import it into the **Polylines** folder before creating the new extent.

To create a new extent from a polyline, right-click on the interpolant's **Boundary** object and select **New Lateral Extent > From Polyline**. In the window that appears, select whether you will create a new polyline or use an existing one:

😹 New B	oundary	×
Polyline	From	
Ne	w <u>D</u> rawing O <u>E</u> xisting Polyline	
	Curved polyline	
Bounda O <u>S</u> u	ry Type Iface	
<u>N</u> ame:	Boundary	
?	<u>C</u> ancel <u>Q</u> K	

You can create the extent as a **Vertical Wall** or **Surface**. If you create the lateral extent as a **Surface**, you will be able to modify it using additional data, as described below. A lateral extent created as a **Vertical Wall**, however, cannot be modified.

Click **OK** to generate the new extent. If you have chosen to create a **New Drawing**, the drawing controls will appear in the scene and you can begin drawing, as described in <u>Drawing in the Scene</u>.

The new extent will appear in the project tree as part of the **Boundary** object.


If the surface generated does not fit the polyline adequately, you can increase the quality of the fit by adding more points to the polyline. See <u>Drawing in the Scene</u> for information on adding points to polylines.

Extents created from polylines can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an Extent</u>, <u>Editing</u> an Extent With a Polyline and Editing an Extent With Structural Data for more information.

Extent From GIS Vector Data

GIS data in the project can be used to create a lateral extent for an RBF interpolant. Once the data you wish to use has been imported into the project, right-click on the interpolant's **Boundary** object and select **New Lateral Extent > From GIS Vector Data**.

In the window that appears, select the data object you wish to use:



You can create the extent as a **Vertical Wall** or **Surface**. If you create the lateral extent as a **Surface**, you will be able to modify it using additional data, as described below. A lateral extent created as a **Vertical Wall**, however, cannot be modified.

If you select the **Surface** option, you can use the GIS data object with its own elevation data or projected onto the topography:

🖌 Select Vector GIS To Add
GIS Vector
✓ C Topographies
✓ ☐ Draped GIS Objects
🙈 Footwall Dyke (On Topography)
🙈 Hangingwall Dyke (On Topography)
🙈 Topography contours (On Topography)
🙈 GIS line (On Topography)
🙈 Streams (On Topography)
✓ ☐ GIS Data, Maps and Photos
😹 Footwall Dyke
😹 Hangingwall Dyke
als line
and the streams and the streams are streams and the streams are streams and the stream are stream and the stream are stre
Lateral Extent Type
● <u>S</u> urface ○ <u>V</u> ertical Wall
Cancel OK

Using the **On Topography** option makes sense for GIS data as it is, by nature, on the topography. The **On Topography** option also mitigates any issues that may occur if elevation information in the GIS data object conflicts with that in the project.

Click **OK** to create the new extent. The new extent will appear in the project tree as part of the **Boundary** object.

Extents created from GIS data can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an Extent</u>, <u>Editing</u> an Extent With a Polyline and <u>Editing an Extent With Structural Data</u> for more information.

Extent From Points

To create a new extent from points data, right-click on the interpolant's **Boundary** object and select **New Lateral Extent > From Points**. The **Select Points To Add** window will be displayed, showing points data available in the project:

💋 Select Points On Boundary	×
Objects	Query Filter
V D Points	
Cover contacts	No query filter
soil_grid	No query filter
👪 Wolfpass_Lidar_Topo	No query filter
? <u>C</u> ancel	<u>о</u> к

Select the information you wish to use and click **OK**.

The new extent will appear in the project tree as part of the **Boundary** object.

Extents created from points can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an Extent</u>, <u>Editing an</u> <u>Extent With a Polyline</u> and <u>Editing an Extent With Structural Data</u> for more information.

Extent From Structural Data

Planar structural data can be used to create a lateral extent for an RBF interpolant. You can create a new structural data table or use a table that already exists in the project. If you want to use categories of structural data in creating the extent, use an existing table and create filters for those categories before creating the lateral extent.

To start, right-click on the interpolant's **Boundary** object and select **New Lateral Extent > From Structural Data**. The **New Structural Data** window will be displayed, showing structural data available in the project:

🖉 New Structu	ıral Data	×
Structural Dat		
_	ing O Existing Structural Data _structural_data	
Query Filter:	None	
Name: Bou	ndary	
<u>C</u> a	ncel <u>O</u> K	

Select the **New Drawing** option to draw the structural data points directly in the scene.

Select the **Existing Structural Data** option to use a table in the **Structural Modelling** folder. With this option, you will be able to select from the categories available in the data table, if query filters have been created for those categories:

🖉 New Structu	ıral Data	×
Structural Dat	ta from ing ● <u>E</u> xisting Structural Data	
belgica	_structural_data	
Query Filter:	None	1
Name: belo	None Selegica_structural_data	
<u>C</u> a	Block 1 Block 2	

Click **OK** to generate the new extent. If you have chosen to create a **New Drawing**, the drawing controls will appear in the scene and you can begin drawing, as described in <u>Creating New Planar</u> <u>Structural Data Tables</u>. To share the new structural data table, right-click on it and select **Share**. The table will be saved to the **Structural Modelling** folder.

The new extent will appear in the project tree as part of the **Boundary** object.

Extents created from structural data can be modified by adding points data, GIS vector data and structural data. You can also add polylines and structural data to the extent. See <u>Adding Data to an</u> <u>Extent</u>, <u>Editing an Extent With a Polyline</u> and <u>Editing an Extent With Structural Data</u> for more information.

Extent From a Surface

To use a surface as lateral extent for an RBF interpolant, right-click on the interpolant's **Boundary** object and select **New Lateral Extent > From Surface**. The **Select Boundary** window will appear, showing all the meshes that can be used as an extent:

Select Boundary Mesh		×
✓ ☐ Topographies		
💣 Topography		
V D Meshes		
> 🗋 GM Surfaces		
> D Merge Meshes		
✓ □ Pit Shells		
✓ 🗋 Pit Designs		
🛞 Ultimate Pit		
🛞 Year 5 Pit design		
🛞 Year 10 Pit design		
> Dit Walls		
?	<u>C</u> ancel	<u>о</u> к

Select the required mesh and click **OK**. The extent will be added to the interpolant's **Boundary** object.

You cannot modify an extent created from a mesh by adding data, editing with polylines or structural data or by applying a trend. However, the extent is linked to the mesh used to create it, and updating the mesh will update the extent.

Extent From Distance to Points

Leapfrog Works can calculate the distance to set of points and use the resulting distance buffer as a lateral extent for an RBF interpolant. To create a new lateral extent from a distance buffer, right-click on the interpolant's **Boundary** object and select **New Lateral Extent > From Distance To Points**. The **Smoothed Distance Buffer** window will appear:

🖉 Smoothed Distan	ce Buffer			×
Locations:		collar		~
Query filter:		None		~
Distanc <u>e</u> : 200	0			
Anisotropy				
	Dip	Dip Azimuth	Pitch	
Directions:	0	, 0	, 90	
	Maximum	Intermed.	Minimum	
Ellipsoid Ratios:	1	, 1	, 1	
<u>V</u> iew Pla	ine	Set From Plane	<u>S</u> et to	\sim
Name: collar dis	tance buffer 20	0.0		
?		<u>C</u> ancel	<u>о</u> к	

Select the **Distance** and set an **Anisotropy**, if required.

The Ellipsoid Ratios determine the relative shape and strength of the ellipsoids in the scene, where:

- The **Maximum** value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The **Minimum** value is the relative strength in the direction orthogonal to the plane.

You can also use the **Set to** list to choose different options Leapfrog Works has generated based on the data used to build the interpolant. **Isotropic** is the default option used when the interpolant is created.

Click **OK** to create the new extent, which will appear in the project tree as part of the **Boundary** object.

To change the extent's settings, expand the interpolant's **Boundary** object in the project tree and double-click on the extent. Adjust the **Distance** and **Anisotropy**, if required.

Extents created from a distance to points function can be modified by adding points data and GIS vector data. See Adding Data to an Extent.

Extent From a Distance Function

A distance function calculates the distance to a set of points and can be used to bound an RBF interpolant. You can use an existing distance function as a lateral extent or create a new one.

To use a distance function as a lateral extent, right-click on the interpolant's **Boundary** and select **New Lateral Extent > From Distance Function**. If there are no distance functions in the project, you will be prompted to create a new one. See <u>Distance Functions</u> for information on defining and editing the distance function. When there are already distance functions in the project, you will be prompted to choose between creating a new function or using an existing one:

📽 New Lateral Extent		×
Select Distance Functi Use existing distan 		
Distance function:	🕟 Distance to drillhole data	\sim
<u>B</u> uffer distance:	450.0	0
O Create <u>n</u> ew distance	e function	
<u>C</u>	ancel <u>O</u> K	

To use an existing function, select it from the list and set a **Buffer distance**. Click **OK** to create the lateral extent.

When you create a new distance function, it will be part of the interpolant's **Boundary** object and will not be available elsewhere in the project. To share it within the project, expand the lateral extent in the project tree and right-click on the distance function. Select **Share**. The distance function will be saved to the **Numeric Models** folder.

To change the extent's settings, expand the interpolant's **Boundary** object in the project tree and double-click on the extent. Adjust the **Distance** and **Anisotropy**, if required.

Changing a Lateral Extent's Settings

For lateral extents created from polylines, GIS data, points and structural data, you can change the extent's settings by double-clicking on it in the project tree.

😵 Edit b	elgica_structural_data	×
Surfa	ncing Inputs Trend	
Sna	ip to data: Off ~~	
Max	ximum snap distance: 5.00	
sur	face resolution: 10.0 0 Adaptive	
<u>N</u> ame:	belgica_structural_data	
?	<u>C</u> ancel <u>Q</u> K	

In the **Surfacing** tab, you can change surface resolution and contact honouring options, which are described below. In the **Trend** tab, you can apply a trend to the extent, which is described in <u>Applying a</u> <u>Trend</u>.

Surface Resolution

For RBF interpolants, the resolution of lateral extents is inherited from the settings in the interpolant's **Outputs** tab, but the adaptive isosurfacer is automatically disabled. Enter a different **Surface resolution** value, if required, and tick **Adaptive** to enable the adaptive isosurfacer.

Contact Honouring

Often, surfaces should honour borehole data and treat data objects such as polylines and GIS data as interpretations. For extents, the **Snap to data** setting in the **Surfacing** tab determines whether or not the extent honours the data used to create it. Options are:

- Off. The extent does not snap to the data used to create it. This is the default setting.
- All data. The extent snaps to all data within the **Maximum snap distance**, which includes borehole data and any data added to the extent.
- **Drilling only**. The extent snaps to borehole data and data objects derived from borehole data within the **Maximum snap distance**, but not to other data used to modify the extent. For example, the extent will honour points data derived from borehole data, but not points data imported into the **Points** folder.
- Custom. The extent snaps to the data objects indicated in the **Inputs** tab that are within the **Maximum snap distance**.

Take care in enabling snapping and in selecting what data the surface will snap to, as the more data you include, e.g. by setting a large **Maximum snap distance** or selecting **All data** for **Snap to data**, the greater the possibility that errors in the data or assumptions inherent in interpretations (e.g. polylines) will cause distortions in the meshes. If you do enable snapping, it is best to snap only to drilling data. See <u>Honouring Surface Contacts</u> for more information on these settings.

Whatever the setting, you can see what objects are snapped to by clicking on the **Inputs** tab.

If you need the extent to honour borehole data but treat other data objects as interpretations, select **Drilling only**. To honour some data objects while treating others as interpretations, select **Custom**, then click on the **Inputs** tab to enable snapping for individual objects.

Applying a Trend

You can adjust an extent created from polylines, GIS data, points and structural data by applying a trend to it. To do this, add the extent to the scene. Next, double-click on the extent in the project tree and click the **Trend** tab.

Often the easiest way to apply a trend is to click on the **Draw plane line** button (27) and draw a plane line in the scene in the direction in which you wish to adjust the surface. You may need to rotate the scene to see the plane properly.

The Ellipsoid Ratios determine the relative shape and strength of the ellipsoids in the scene, where:

- The **Maximum** value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The Minimum value is the relative strength in the direction orthogonal to the plane.

Once you have adjusted the plane to represent the trend you wish to use, click the **Set From Plane** button to copy the moving plane settings.

The **Set to** list contains a number of different options Leapfrog Works has generated based on the data used in the project. **Isotropic** is the default option used when the extent was created. Settings made to other surfaces in the project will also be listed, which makes it easy to apply the same settings to many surfaces.

Click **OK** to apply the changes.

See <u>Global Trends</u> in the <u>Trends and Anisotropy</u> topic for more information.

Adding Data to an Extent

Extents created from polylines, GIS data, points and structural data can be modified by adding points data objects, GIS vector data and structural data. Extents created from a distance to points function can be modified by adding points data and GIS vector data. To add data to an extent, right-click on the extent in the project tree and select the data type you wish to use from the **Add** menu.

- Points data. Select from the points data objects available in the project and click **OK**.
- GIS vector data. Select from the GIS vector data available in the project and click **OK**.
- Structural data. Select from the structural data tables available in the project. If the selected table has query filters defined, you can apply one of these filters by ticking **Use query filter** and then selecting the required filter from the list. Click **OK** to add the selected data to the extent. An alternative to adding an existing structural data table to an extent is to edit the extent with structural data. This is described in Editing an Extent With Structural Data below.

You can also add a polyline that already exists in the project. To do this, right-click on the extent in the project tree and select **Add > Polyline**. You will be prompted to choose from the polylines in the **Polylines** folder.

Editing an Extent With a Polyline

You can edit an extent using a polyline, which is described in <u>Editing Surfaces With Polylines</u>. A polyline used to edit an extent will be added to the project tree as part of the extent. To edit the polyline, rightclick on it and select **Edit Polyline** or add it to the scene and click the **Edit** button (?) in the shape list. If you wish to remove the polyline from the extent, right-click on it in the project tree and select **Delete** or **Remove**.

To add an existing polyline to a lateral extent, use the **Add > Polyline** option.

Editing an Extent With Structural Data

You can edit an extent using structural data, which is described in <u>Editing Surfaces With Structural Data</u>. A structural data table will be added to the project tree as part of the extent. To edit the table, right-click on it and select **Edit In Scene** or add it to the scene and click the **Edit** button (\mathcal{O}) in the shape list. If you wish to remove the table from the extent, right-click on it in the project tree and select **Delete** or **Remove**.

Removing an Extent from an Interpolant

If you have defined an extent and want to remove it from the interpolant, there are two options. The first is to right-click on the extent in the project tree and click **Delete**. This deletes the extent from the interpolant, but does not delete parent objects from the project unless they were created as part of the interpolant, e.g. a polyline used as a lateral extent but not shared within the project. Use this option only if you are sure you do not want to use the extent.

The second method is useful if you are making changes to the extent and do not want to recompute the interpolant with each change. Double-click on the interpolant's **Boundary** object or double-click on the interpolant and click on the **Boundary** tab. The **Boundaries** part of the window lists all objects used as extents for the interpolant. Untick the box for extents to temporarily disable them in the interpolant. The

interpolant will be reprocessed, but you can then work on the extent without reprocessing the interpolant. Disabled extents will be marked as inactive in the project tree.

Changing the Settings for an RBF Interpolant


To change the settings for an RBF interpolant, you can either double-click on the interpolant in the **Numeric Models** folder or right-click and select **Open**. When creating an RBF interpolant, only a basic set of parameters is used. The **Edit RBF Interpolant** window provides finer controls over these basic parameters so you can refine the interpolant to factor in real-world observations and account for limitations in the data.

For a multi-domained RBF interpolant, these parameters can be changed for the parent interpolant, and the trend, clipping, transformation and interpolation settings can be changed for the sub-interpolants.

Adjusting the Values Used

The **Values** tab in the **Edit Interpolant** window shows the values used in creating the interpolant and provides options for filtering the data. Although you cannot change the values used to create an interpolant, you can filter the values using the **Query filter** and **Surface filter** options.

You can adjust the values using a contour polyline or by adding points. Both options are available by expanding the interpolant in the project tree, then right-clicking on the values object:



These options are described below in Adding a Contour Polyline and Adding Points.

To apply a query filter, tick the **Guery filter** box in the **Values** tab and select the available queries from the list.

To change the object used as the **Surface filter**, select the required object from the list. Note that the list contains an object that defines the interpolant's own boundary, which can be adjusted in the **Boundary** tab.

Adding a Contour Polyline

Adding a contour polyline is a useful tool for manually adjusting a surface to make it more geologically reasonable. To start adding a contour polyline, draw a slice where you wish to adjust the surface and decide what value you will assign to the contour line. Next, right-click on the values object and select

New Contour Polyline. The next step is to choose whether you will draw a new polyline or use one already in the project:

🗳 New Contour	×
AU_gpt values Contour Polyline New Drawing	
○ Existing Polyline <	
Value On Contour: 0.65	
Name: AU_gpt values 0.65	
? <u>Cancel</u> <u>QK</u>	

Only GIS lines, polylines imported into Leapfrog Works or polylines created using the straight line drawing tool can be used to create contour lines.

Enter the value to be used for the contour and a name for it. Click **OK**. If you have chosen the **New Drawing** option, the new object will be created in the project tree and drawing tools will appear in the scene. Start drawing in the scene as described in <u>Drawing in the Scene</u>. When you have finished drawing, click the **Save** button (a). The new contour will automatically be added to the interpolant and will appear in the project tree as part of the interpolant's values object. To change the value assigned to a contour polyline, double-click on the interpolant in the project tree. In the **Values** tab, contour polylines and their assigned values are shown in the **User contour values** table:

ø	Edit RBF In	terpolant						×
[Values	Compositing	Boundary	Value Transform	Trend	Interpolant	Outputs	
	Numeric	Values: RQD on	Lake_Aura_RQ	D				
		ilter: None					~	
			Boundary				_	
		ntour values	lus.					
	Object ROD v	values 69.0 69						
	_						_	
	_							
1	Name: RQ	D						
(?				<u>C</u> ance	el	<u>0</u> K	

To change the value on a contour, click in the **Value** column and edit the entry.

To edit the polyline, right-click on it in the project tree and select **Edit Polyline** or add it to the scene and click the **Edit** button (\mathcal{O}) in the shape list. If you wish to remove a contour polyline from the interpolant, right-click on it in the project tree and select **Delete** or **Remove**.

Adding Points

To add points to an RBF interpolant, right-click on the values object in the project tree and select **Add Values**. Leapfrog Works will display a list of all suitable points objects in the project. Select an object and click **OK**.

A hyperlink to the points object will be added to the values object in the project tree. To remove the points object, right-click on the points object and select **Remove**.

Compositing Parameters for an RBF Interpolant

When an RBF interpolant has been created from data that has not been composited, compositing parameters can be changed by double-clicking on the interpolant in the project tree, then clicking on the **Compositing** tab.

🧉 Edit RBF In	terpolant						>
Values	Compositing	Boundary	Value Tr	ransform	Trend	Interpolant	: Outputs
Compos	ite in:			Entire bo	rehole		~
_	iting length:			10.00			0
lf <u>r</u> esidu	al end length less	than:		0.00			0
then				discard			~
Minimur	n coverage:			50%			Û
Addition	al <u>w</u> eighting colur	nn:		<none></none>			~
Name: RQ	D						
Name: RQ	U						
?					<u>C</u> ance		<u>о</u> к

The **Compositing** tab will only appear for interpolants created from borehole data that has not been composited.

You can composite in the entire borehole or only where the data falls inside the interpolant boundary. See <u>Numeric Composites</u> for more information on the effects of the **Compositing length**, **For end lengths less than** and **Minimum coverage** settings.

Adjusting the Interpolant Boundary

See <u>Modifying an RBF Interpolant's Boundary With Lateral Extents</u> above for information on creating and working with lateral extents.

To change an RBF interpolant's boundary, double-click on the interpolant in the project tree, then click on the **Boundary** tab:

Values Co	ompositing	Boundary	Value Transform	Trend	Interpolant	Outputs
Interpolant E	ctents					
		Minimum			Maximum	
X (East):	1164200.0		\$	1165700.0		÷
Y (North):	4889500.0		Ĵ	4892100.0		÷
Z (Elev):	26.0		Ŷ	180.0		0
					Enclose	object v
Boundaries						,
🗸 Use Тор	ography					
Devedenter	-					
Boun <u>d</u> aries						
Boun <u>d</u> aries						
<no 0<="" p=""></no>						
<no 0<="" p=""></no>						

Controls to adjust the boundary will also appear in the scene.


Tick the **Use Topography** box to use the topography as a boundary. The topography is normally not used as a boundary for interpolants and so this option is disabled when an interpolant is first created.

The **Boundaries** list shows objects that have been used to modify the boundary. You can disable any of these lateral extents by unticking the box.

Lateral extents can be used to restrict modelling to a particular area of interest; for example, modelling can be restricted to a known distance from boreholes by applying a distance function as a lateral extent.

Clipping and Transforming Values for an RBF Interpolant

To clip data and apply a transformation to an RBF interpolant, double-click on the interpolant in the project tree, then click on the **Value Transform** tab:



The options for **Transform Type** are **None** and **Log**. **Log** uses a natural logarithm to compress the data values to a smaller range. This may be useful if the data range spans orders of magnitude. The function used is:

ln(x+s)+c

where s is the **Pre-log shift** and c is a constant. In order to avoid issues with taking the logarithm of zero or a negative number, **Pre-log shift** is a constant added to make the minimum value positive. The value of the pre-log shift will automatically be chosen to add to the minimum value in the data set to raise it to 0.001. This constant is then added to all the data samples. You can modify the value of the **Pre-log shift**, as increasing this value further away from zero can be used to reduce the effect of the natural logarithm transformation on the resultant isosurfaces.

Note that a further constant, c, is added to the natural logarithm of the data with the pre-log shift added to it. If there are any negative numbers that result from taking the natural log of the data, the absolute value of the most negative number is taken and added to all the transformed data results. This will raise the value of all the data so the minimum data value is zero. The value of c is chosen automatically and cannot be modified.

'alues	Compositing	Boundary	Value T	ransform	Trend	Interpolant	Outputs
Clippin	-			Transform			
	o pr <u>e</u> -transform clip			Tr <u>a</u> nsfo	rm Type:	None	\sim
LO	wer bound:	0.01000					
<u>U</u> p	per bound:	43.60000					
Opti	ons 🗸						
l 🔓 🧕	opy Graph Image		Histogra	am of Valu	le		
F	ercentage	-					
	<u>ercentage</u>						
	in Width 1.0						
		-					
	/in/max whiskers						
	nner fence whisker						
0	uter fence whisker	S					
10	-						
0							_
							-
	0 5	10 15	20	25	30	35 40	<u> </u>
	-			/alue		10	
L							
ne: All	apt						
ne: AU	_gpt						

Click on the Options button to change the histogram's display, including the Bin Width.

If you tick the **Do pre-transform clipping** option, you can set the **Lower bound** and the **Upper bound** to cap values that are too low or too high. For example, if you set the **Upper bound** from 14.00 to 10.00, grade values above 10.00 will be regarded as 10.00.

Changing the Trend for an RBF Interpolant

You can apply a global trend or a structural trend to an RBF interpolant. To do this, add the interpolant to the scene, then double-click on the interpolant in the project tree. Click on the **Trend** tab in the **Edit RBF Interpolant** window.


See:

- Using a Global Trend
- Using a Structural Trend

Using a Global Trend

The easiest way to change the trend applied to an interpolant is using a global trend set from the moving plane.

Click **View Plane** to add the moving plane to the scene, then click on the plane to view its controls. You may need to hide part of the interpolant to click on the moving plane:



You can also use the **Set to** list to choose different options Leapfrog Works has generated based on the data used to build the interpolant. **Isotropic** is the default option used when the interpolant is created.

The Ellipsoid Ratios determine the relative shape and strength of the ellipsoids in the scene, where:

- The Maximum value is the relative strength in the direction of the green line on the moving plane.
- The **Intermed.** value is the relative strength in the direction perpendicular to the green line on the moving plane.
- The **Minimum** value is the relative strength in the direction orthogonal to the plane.

Click **OK** to regenerate the interpolant and view changes.


Using a Structural Trend

You can also set the trend for an RBF interpolant from a structural trend. First, you must create or import the required mesh and create a structural trend. See <u>Structural Trends</u> in the <u>Trends and Anisotropy</u> topic for more information.

Once the structural trend has been created, add it to the interpolant by double-clicking on the interpolant in the project tree, then clicking on the **Trend** tab. Select the **Structural Trend** option, then select the required trend from the list:

Values	Boundary	Value Transform	Trend	Interpolant	Outputs	
O Glob		Dip	Dip Azi	muth	Pitch	
<u>D</u> irec	ctions:	7.5463342567	, 34.11	3103329	, 72.278411448	
		Maximum	Interme	ed.	Minimum	
Ellip	soid R <u>a</u> tios:	3	, 3		. 1	
	<u>V</u> iew F	lane	Set From <u>F</u>	Plane	<u>S</u> et to	
Struct	tural Trend					
% Ce	entral Shear					\sim
Outside	value: 0					^
Outsi <u>d</u> e	value: 0					Ŷ
Outsi <u>d</u> e	value: 0					÷
Outsi <u>d</u> e	value: 0					¢
Outsi <u>d</u> e	value: 0					¢
Outsi <u>d</u> e	value: 0					÷
Outsi <u>d</u> e	value: 0					0
Outsi <u>d</u> e	value: 0					0
						0
	value: 0					\$

Click **OK**. The trend will be added to the interpolant and will appear as part of the interpolant, as shown:



When you apply a structural trend, you cannot use the **Linear** interpolant. See <u>Interpolant Functions</u> for more information.

Once a structural trend has been defined for the interpolant, you can edit it by clicking on the trend hyperlink in the project tree, then opening the structural trend applied to the interpolant. The **Structural Trend** window will appear. See <u>Structural Trends</u> in the <u>Trends and Anisotropy</u> topic for more information on the settings in this screen.

The structural trend information included as part of the interpolant is a link to the original structural trend. When you change the structural trend that is part of the interpolant, the changes are also made for the original structural trend.

When a structural trend that is **Strongest along meshes** or **Blending** is used, the interpolant will regress to the global mean trend away from the meshes. The global trend that will be used is set in the **Global Trend** tab for the structural trend.

Adjusting Interpolation Parameters

To adjust interpolation parameters for an RBF interpolant, double-click on the interpolant in the project tree, then click on the **Interpolant** tab:

Edit RBF Interpo	lant						
Values Bo	undary	Value Transform	Tre	nd Inter	polant	Outputs	
Variance:	1.96						
In <u>t</u> erpolant:	Linear		~				
	1.0			Munant	0		^
Total <u>S</u> ill:			0	N <u>ugg</u> et:	U		\sim
Base <u>R</u> ange:	2000.0		÷				
<u>D</u> rift:	Constant	t	\sim	Accuracy:	0.020		0
1.25 - 1.00 - 0.75 - 0.25 - 0.00 -							- - - -
c	1	500 1000		1500 tance	2000) 2500	
Name: Au_gpt							
?					<u>C</u> ance	I	<u>0</u> K

Two models are available, the spheroidal interpolant and the linear interpolant. See the <u>Interpolant</u> <u>Functions</u> topic for more information on the settings in this tab.

Output Settings for an RBF Interpolant

You can change the parameters used to generate RBF interpolant outputs by double-clicking on the interpolant, then clicking on the **Outputs** tab.

💋 Edit RBF Interpolant	t			×
Values Bound	dary Value Transform Tr	end Inte	rpolant Outputs	
Evaluation limits				
<mark>⊻</mark> Minim <u>u</u> m:	0.0			
Ma <u>x</u> imum:	43.6			
Isosurfaces		Volumes		
<u>D</u> efault resoluti	ion: 240.0 🗘 🗆 <u>A</u> daptive	Enclose:	Intervals	~
✓ Exact clippin	ng			
Iso Value S	urface Resolution		< 0.3	
0.3 2	240 (default)		0.3 - 0.55	
	240 (default)		0.55 - 1.03	
1.03 2	240 (default)		> 1.03	
\oplus \bigcirc				
Name: Au_gpt				
		_		
?			<u>C</u> ancel	<u>о</u> к

The **Evaluation limits** apply when interpolants are evaluated against other objects in the project. When the limits are enabled, all values outside the limits will be set to the **Minimum** and **Maximum**.

When **Exact clipping** is enabled, the interpolant isosurface will be generated without "tags" that overhang the interpolant boundary. This setting is enabled by default when you create an interpolant.

To add a new isosurface, click the **Add** button and enter the required value. To delete an isosurface, click on it in the list, then click the **Remove** button. You can also change the colours used to display the isosurfaces by clicking on the colour chips.

If you find that grade shells are overlapping, the resolution may be too coarse. Set **Default resolution** to a lower value or enable adaptive resolution in the **Outputs** tab. See <u>Surface Resolution</u> in Leapfrog Works.

Multi-Domained RBF Interpolants

This topic describes creating and editing multi-domained RBF interpolants:

- <u>Creating a Multi-Domained RBF Interpolant</u>
- <u>Compositing and Filtering the Values Used</u>
- Selecting Domains

- Clipping and Transforming Values
- Setting the Trend
- Interpolation Parameters
- Output Options
- The Multi-Domained RBF Interpolant in the Project Tree
- Interpolant and Sub-Interpolant Display
- Sub-Interpolant Statistics

A multi-domained RBF interpolant is an RBF interpolant that has a number of individual sub-interpolants bounded by the domains of a geological model.

- Changes to all sub-interpolants can be made by editing the parent interpolant.
- Sub-interpolants can be edited to account for local influences on the values used, the trend and interpolation parameters.


A multi-domained RBF interpolant is a single object that can be evaluated as a single column on points and block models.

Creating a Multi-Domained RBF Interpolant

Creating a multi-domained RBF interpolant is a two-step process:

- Selecting the values to be used and the domains in which sub-interpolants will be created.
- Setting the multi-domained RBF interpolant's properties.

To start creating a multi-domained RBF interpolant, right-click on the **Numeric Models** folder and select **New Multi Domained RBF Interpolant**. The **New Multi-domained RBF Interpolant** window will be displayed:



In this window, select the basic parameters for the multi-domained RBF interpolant. You will be able to set additional properties once you click **OK**.

- Select the **Values To Interpolate** from the suitable data available in the project. You will be able to change how data is filtered at the next step, but you will not be able to change the values used.
- Select the domains used to generate sub-interpolants. These options cannot be changed once the multi-domained RBF interpolant has been created, although you will be able to select which volumes are used to generate sub-interpolants.
 - Select from the geological models available in the project.
 - If the selected **Model** has no faults defined, the **Volume Type** will be set to output volumes.
 - If the selected **Model** is a faulted model, the **Volume Type** can be output volumes, faulted output volumes or fault blocks.

Click **OK** to move on to the next step. The **Edit RBF Interpolant** window will appear:

Numeric Values: CU_pct on WP_assay Query Filter: None		
Composite in:	No compositing	\sim
Compositing length:	10.00	
If residual end length less than:	0.00	
then	discard	
Minimum coverage:	50%	
Additional weighting column:	<none></none>	

Compositing and Filtering the Values Used

In the Values tab, you can apply any query filters that have been defined for the data used.

When numeric values from borehole data are used to create an interpolant, there are two approaches to compositing that data:

- Composite the borehole data, then use the composited values to create an interpolant. If you select composited values to create an interpolant, compositing options will be disabled.
- Use borehole data that hasn't been composited to create an interpolant, then apply compositing settings to the interpolated values. If you are interpolating values that have not been composited and

do not have specific **Compositing** values in mind, you may wish to leave this option blank as it can be changed once the model has been created.

If you are interpolating points, compositing options will be disabled.

See <u>Numeric Composites</u> for more information on the effects of the **Compositing length**, **For end lengths less than**, **Minimum coverage** and **Additional weighting column** settings.

Selecting Domains

In the **Domains** tab, you can select the volumes in which sub-interpolants will be generated. You cannot, however, change the geological model or the types of volumes used.

Clipping and Transforming Values

In the **Value Transform** tab, clip data and apply a transformation, if required. See <u>Clipping and</u> Transforming Values for an RBF Interpolant for more information about the settings in this tab.

You will be able to change the **Value Transform** settings for individual sub-interpolants once the parent interpolant has been created.

Setting the Trend

In the **Trend** tab, you can apply a global or structural trend to the interpolant. See <u>Changing the Trend</u> for an RBF Interpolant for more information about these options.

You will be able to change the **Trend** settings for the interpolant and individual sub-interpolants once the parent interpolant has been created.

Interpolation Parameters

In the **Interpolant** tab, you can change interpolation parameters. See <u>Adjusting Interpolation</u> <u>Parameters</u> for more information about these options.

You will be able to change the **Interpolant** settings or import variogram parameters for the interpolant and individual sub-interpolants once the parent interpolant has been created.

Output Options

In the **Outputs** tab, you can change the parameters used to generate interpolant outputs.

The **Evaluation limits** apply when interpolants are evaluated against other objects in the project. When the limits are enabled, all values outside the limits will be set to the **Minimum** and **Maximum**.

Set the **Default resolution** for the interpolant and whether or not the resolution is adaptive. See <u>Surface Resolution in Leapfrog Works</u> for more information on the effects of these settings. The resolution can be changed once the interpolant has been created, so setting a value when creating the parent interpolant is not vital. A lower value will produce more detail, but calculations will take longer.

When **Exact clipping** is enabled, the interpolant isosurface will be generated without "tags" that overhang the interpolant boundary. This setting is enabled by default when you create an interpolant.

To add a new isosurface, click the **Add** button and enter the required value. To delete an isosurface, click on it in the list, then click the **Remove** button. You can also change the colours used to display the isosurfaces by clicking on the colour chips.

The **Volumes enclose** option determines whether the interpolant volumes enclose **Higher Values**, **Lower Values** or **Intervals**. This option can be changed once the interpolant has been created.

Enter a Name for the new interpolant and click OK.

Once you have created a multi-domained RBF interpolant, you can adjust its properties as described in <u>Changing the Settings for an RBF Interpolant</u>. You can also change trend, clipping, transformation and interpolation settings for a sub-interpolant. To do this, double-click on a sub-interpolant. For the settings you wish to change, untick the **Inherit parameters from parent** box:


B	Edit RBF Interpolant					×
L	Value Transform	Trend	Interpolant			
	_					
	🔽 Inherit parame	eters from	parent			
	Clipping	I'		Transform		
	Do pr <u>e</u> -trar			Tr <u>a</u> nsform Type:	None	~
	Lower bour	id:	0.02			
	Upper boun	d:	7.130000 🔅			
	Options 🗸					
	30 - 5		Histog	ram of Value		
	Erequency (percent)				6	
Ν	lame: CU_pct in G	M v2 fault	block 1: Baseme	nt		
(?)			Cancel		<u>0</u> K

See also:

- Importing a Variogram Model
- Copying a Numeric Model
- Creating a Static Copy of a Numeric Model
- Exporting Numeric Model Volumes and Surfaces

The Multi-Domained RBF Interpolant in the Project Tree

The new multi-domained RBF interpolant will be created and added to the **Numeric Models** folder. It contains objects that represent different parts of the interpolant:



- There is a link to the geological model from which domains are selected for the sub-interpolants.
- The **Trend** object describes the trend applied in the interpolant. See <u>Changing the Trend for an RBF</u> <u>Interpolant</u> for more information.
- The points data values object contains all the data used in generating the interpolant. See <u>Adjusting</u> <u>the Values Used</u> for more information.
- The **Sub-interpolants** folder contains the sub-interpolants, which can be edited to change the trend, clipping, transformation and interpolation settings. Each sub-interpolant has its own boundary, trend, isosurfaces and output volumes.
- The **Output Volumes** folder contains all the volumes generated in building the interpolant.

Other objects may appear in the project tree under the interpolant as you make changes to it.


Interpolant and Sub-Interpolant Display

Display the interpolant by:

- Dragging the interpolant into the scene or right-clicking on the interpolant and selecting **View Output Volumes**. Both actions display the parent interpolant's output volumes.
- Right-clicking on the interpolant and selecting **View Isosurfaces**. This displays the isosurfaces of each sub-interpolant.

Sub-Interpolant Statistics

You can view the approximated mean for each output volume of a sub-interpolant by right-clicking on the sub-interpolant and selecting **Properties**. Click on the **Statistics** tab:



You can copy the information displayed in the **Statistics** tab to the clipboard for use in other applications.

Distance Functions

A distance function calculates the distance to a set of points. This topic describes how to create and modify distance functions. It is divided into:

- Creating a Distance Function
- The New Distance Function in the Project Tree

Creating a Distance Function

To create a distance function, right-click on the **Numeric Models** folder and select **New Distance Function**. The **New Distance Function** window will be displayed:


le New Distance Func	tion		×			
<u>General</u> <u>B</u> oun	dary <u>T</u> rend	Buffers				
Calculate the dis	tance to these obje	ects:				
Objects		Query Filter	Select Objects			×
			Available objects:		Selected objects:	
			✓ 🗀 Topographies	•	V 🗋 Meshes	
			a Topography		🔗 sphere	
			Draped GIS Objects			
			🔬 fault (On Topog 🙈 GIS line (On Top	>		
			West boundary			
			GIS Data, Maps and Ph	<		
			S fault			
			GIS line			
			S West boundary			
			Select All Select None			
Select Object	5				Cancel	<u>о</u> к
Treat closed surf	aces as: Volume	es 🗸				1 N
Name:						<u> </u>
(?)		Cancel	<u>ο</u> κ			1
\odot		Jancer				

Click **Select objects** to choose from the objects available in the project. For boreholes, points, GIS points and imported GIS lines, you can apply any filter that has been defined for that object.

If any of the objects selected are closed surfaces, you can choose whether these surfaces are treated as **Volumes** or as **Surfaces**.

- When treated as **Volumes**, buffers will be generated only on the outside of the mesh. If the mesh is inverted, buffers will appear on its inner surface.
- When treated as **Surfaces**, buffers will be generated on both sides of the mesh.

For example, here a distance function has been created using a sphere and one isosurface set to 2. The inner surface of the sphere is red, indicating that it is the inside of the mesh. The sphere is treated as a volume and there is a single isosurface (yellow) outside of the sphere:



When the orientation of the sphere is reversed, indicated by the blue inside of the sphere, the isosurface (yellow) is generated on the inner surface of the sphere:

🐔 Edit Distance Function X	
General Boundary Irend Buffers	North (Y) +7135
Calculate the distance to these objects:	+/133
Objects Query Filter	
	+7
Select Objects Treat closed surfaces as: Surfaces	0+71
Name: Distance to sphere (Surfaces)	east (X)
(?) Cancel OK	Looking down
	0 5 10 15

However, when the sphere is treated as a surface rather than as a volume, isosurfaces are generated on both sides of the sphere:

🖉 Edit Distance Function X	North (Y)
General Boundary Trend Buffers	+7135
Calculate the distance to these objects:	
Objects Query Filter Meshes 	
Select Objects Treat closed surfaces as: Surfaces Name: Distance to sphere (Surfaces)	+71 +71150 Clev (2)
Image: Cancel OK	<u>0 5 10 15</u>

If you are unsure of some settings, most can be changed later. For a basic distance function click **Select Objects** to select from the suitable objects available in the project, then click on the **Buffers** tab to define at least one buffer so that the distance function can be visualised in the scene.

See:

- Setting the Boundary
- Setting a Trend
- Adding Buffers
- The New Distance Function in the Project Tree

Setting the Boundary

In the **Boundary** tab, you can set whether the function boundary is clipped or unclipped. **No distance buffer clipping** is the default setting, but if you choose to clip the buffers, you can choose between:

- Sharing another object's extents
- Defining a set of extents that is independent of other objects in the project.

When you select the **Shared with** option, the distance function will be updated when the extents object it shares is updated.

Setting a Trend

In the **Trend** tab, you can set a trend using the moving plane or by entering the required values. You can also use the **Set to** list to choose different options used in the project. **Isotropic** is the default option used when the function is created.

The **Ellipsoid Ratios** determine the relative shape and strength of the ellipsoids in the scene, where:

- The **Maximum** value is the relative strength in the direction of the green line on the moving plane.
- The Intermed. value is the relative strength in the direction perpendicular to the green line on the

moving plane.

• The Minimum value is the relative strength in the direction orthogonal to the plane.

Adding Buffers

To add buffers, click on the **Buffers** tab, then click the **Add** button:

B	Edit Distanc	e Function				×
	General	Boundary	Trend	Buffers		_
	Isosurfac	es				
	Distar	ice Surface	Resolution			
	2	0.4 (def	ault)			
	4	0.4 (def	ault)			
	\oplus	Θ			Default resolution:	
	Volumes					
	Volume			< 2		
	Conc			< 4		
	 Inter 	vals				
	?				<u>C</u> ancel <u>O</u> K	


Enter the required value. To delete a buffer, click on it in the list, then click the **Remove** button. You can also change the colours used to display the buffers by clicking on the colour chips.

There are two options for **Volume Type** that affect how the buffers are calculated when more than one buffer is used. Selecting **Concentric** produces higher distance buffers that include the lower distance buffers, whereas selecting **Intervals** produces discrete, non-intersecting buffers.

The **Default resolution** setting is used for all new buffers and for existing buffers that use the default resolution.

The New Distance Function in the Project Tree

Click **OK** to create the distance function, which will be added to the **Numeric Models** folder. The new distance function contains objects representing different parts of the function, which can be expanded to show the inputs to each part of the function:



- The **Trend** object that describes the trend applied.
- Hyperlinks to objects used for the distance function.
- An **Isosurfaces** folder that contains all the meshes generated in building the distance function.
- An **Output Volumes** folder that contains all the distance buffer meshes.

Other objects may appear in the project tree under the function as you make changes to it.

Display the function by dragging it into the scene or by right-clicking on it and selecting **View Buffers**.

Once you have created a distance function, you can adjust its properties by double-clicking on it. You can also double-click on the individual objects that make up the function.

Combined Models

This topic describes creating and working with combined models. It is divided into:

- Creating a Combined Model
- The Combined Model in the Project Tree
- Editing a Combined Model
- Creating a Static Copy of a Combined Model
- <u>Combined Model Export</u>

A combined model uses information from up to four geological models, interpolants and distance functions in order to visualise relationships between different types of data in the project. For example, you could combine a geological model with an interpolant to see what lithologies higher grades are occurring in.

Creating a Combined Model

To create a combined model, right-click on the **Combined Models** folder in the project tree and select **New Combined Model**. In the window that appears, select the models you wish to combine, then click **OK**:

Select Models To Combine	×
✓ ☐ Geological Models	
SimpleRockType	
V 🗋 Numeric Models	
🔽 💽 Au	
Name: Au in QzP	
<u>С</u> апсеі <u>О</u> К	

Once you have created a combined model, you cannot edit it to add new models or remove existing ones.

The next step is to select the output volumes to use in the combined model and arrange them in order of priority. For this combined model, the QzP volume from the selected geological model will be subdivided using information from the Au interpolant:


🖉 Select	Volumes To Combine	×
× =	impleRockType	
	🔽 b QzP	
	🗌 🌰 GnD	
	🗌 🗁 AVT	•
~ 🗹	🖲 Au	\sim
	✓	\sim
	✓	
	0.44 – 0.92	
	✓	
	sing models with fewer selected volume he processing time.	s first can
<u>N</u> ame:	Au in QzP	
?	Cancel	<u>о</u> к

If you are using a distance buffer with concentric buffers, you will be able to select only one volume.

Click OK to generate the model, which will appear in the project tree in the Combined Models folder.


The Combined Model in the Project Tree

In the project tree, the combined model includes hyperlinks to the models used to create the combined model:



Changes made in the original models will be reflected in the combined model.

Add the model to the scene to view the results:



To change the colours used to display the model, double-click on the **Legend** object (E). In the window that appears, click on the colour chip for each category and change it as described in <u>Single Colour</u> <u>Display</u>.

To set multiple categories to a single colour, use the Shift and Ctrl keys to select the colour chips you wish to change, then click on one of the colour chips. The colour changes you make will be made to all selected categories.

Editing a Combined Model

To change how the volumes from the source models are combined, double-click on the combined model in the project tree. Once you have created a combined model, you cannot add new models to it, nor can you remove a selected model.

Creating a Static Copy of a Combined Model

Creating a static copy preserves a snapshot of a combined model that does not change, even when changes are made to the data on which the original model was dependent. This is a useful way of storing historical models and comparing models. Static copies can be exported from Leapfrog Works, as described in Combined Model Export below.

To create a static copy of a combined model, right-click on it in the project tree and select **Static Copy**. Enter a name for the copy of the model and click **OK**. The copy will be added to the **Combined Models** folder.

The static copy (^(C)) is made up of a **Legend** object (^[]]) and the output volumes (^(C)). To view the date a static copy was created, right-click on it in the project tree and select **Properties**. The date the copy was created is in the **General** tab.

Combined Model Export

There are two options for exporting a combined model's output volumes. These are:

- Export an output volume as a mesh. Right-click on it in the project tree and click **Export**. You will be prompted for a file name and location. See <u>Exporting a Single Mesh</u>.
- Export multiple output volumes. Right-click on the combined model in the project tree and select **Export**. See Exporting Multiple Meshes from Models.

Contaminant Models

The Contaminants extension adds the **Contaminant Models** folder to the project tree. The **Contaminant Models** folder contains two folders:

- With the **Estimation** folder, you can define a boundary and values to be used for a contaminant estimation. Once a contaminant estimation is defined, you can then define variograms, sample geometries and estimators inside it.
- With the **Block Models** folder, you can import block models in CSV format and create block models. You can then evaluate estimators on the block model and carry out reporting and validation tasks.

The contaminant modelling workflow is as follows:

- Data analysis. First, gain a thorough understanding of your data. Leapfrog Works has general tools that help you understand your data, which are described in <u>Analysing Data</u>. These tools help you become familiar with your data, identify possible errors and identify or confirm different mineralisation populations. Make sure that the data is clean, with special and invalid values in the assay data properly handled. See <u>Handling Special Values</u> for more details.
- Set up a contaminant estimation. A contaminant estimation defines the boundary and values that will be used in contaminant modelling. See <u>Contaminant Estimations</u>.
- Variography. A theoretical variogram model is proposed and tested using experimental variography. Kriging, nearest neighbour, inverse distance weighting or RBF estimators are defined. See <u>Experimental Variography and Variogram Models</u>.
- Define standard estimators. These will use the variogram models defined during variography and may also make use of a variable orientation. See <u>Standard Estimators</u> and <u>Variable Orientations</u>.
- Visualise estimators on block models. See <u>Visualising Estimators</u> and <u>Block Models</u>.
- Validate the models and report the results. Tools for validating and reporting results include block model interrogation, swath plots and reports. See <u>Validation and Reporting</u>.

Contaminant Estimations

The features described in this topic are only available if you have the Contaminants extension.

A contaminant estimation describes the boundary and values to be used for an estimation. Once a contaminant estimation is defined, you can then define variograms and estimators inside it.

This topic describes how to create and work with a contaminant estimation. It is divided into:

- Creating a Contaminant Estimation
- The Contaminant Estimation in the Project Tree
- Viewing Statistics
- Copying a Contaminant Estimation

Creating a Contaminant Estimation

To create a contaminant estimation, right-click on the **Estimation** folder and select **New Contaminant Estimation**. The **New Contaminant Estimation** window will be displayed:

Wew Contaminant Estin	nation	
Domain Definition		Value Distribution Boundary Analysis
Do <u>m</u> ain: Select do	omain	
Hard boundary Soft boundary	<u>R</u> ange: 0	Column 2 Copy Clipping distance: 50 Bin spacing: 10
Values		
Numeric <u>v</u> alues:	c_DCE_12	Insufficient data to plot graph
Query filter: Nor	ne	
Transform		
Tr <u>a</u> nsform Type:	Log	
Pre-log shift: -0.0490		
Compositing		
Com <u>p</u> osite in:	No compositing	×
Compositing length:	10.00	
If <u>r</u> esidual end length l	ess than: 0.00	
then	discard	
Minimum coverage:	50%	
Additional <u>w</u> eighting c	column: <none></none>	
Name: c_DCE_12		
? <u>C</u> anc	el <u>O</u> K	

This window is divided into three parts:

- The domain definition
- The values used in the estimation and how they are composited
- The value distribution and boundary validation chart

Tools in the window allow you to validate the domain and select whether the boundary should be a hard or soft boundary.

Defining the Domain


Click on the **Select domain** button to select from the suitable objects available in the project:

New Contaminant Est	imation		×
Domain Definition	domain 📐	Value Distribution Boundary Analysis	
 <u>Hard boundary</u> <u>Soft boundary</u> 	Range:	Image: Copy Clipping distance: 50 ○ Bin spacing: 10 ○	
Values Numeric <u>v</u> alues:	c_DCE_12	🗱 Select Domain X	
Query filter: N	lone	✓ Ø Domain Model Ø Boundary	
Tr <u>a</u> nsform Type: Pre-lo <u>g</u> shift:	Log ~		
Compositing Composite in:	No compositing	Beurock Geology Model Boundary	
Compositing <u>l</u> ength:	10.00	○ Output Volumes	
lf <u>r</u> esidual end length <u>t</u> hen	less than: 0.00 discard	Cancel QK	
M <u>i</u> nimum coverage: Additional <u>w</u> eighting	50% column: <none></none>		
Name: c_DCE_12			
? <u>C</u> an	icel <u>O</u> K		


Any closed mesh can be selected to be used as the domain, including boundary objects and model volumes.

The selected domain can be used with a **Hard boundary** or **Soft boundary**. It is essential to the integrity of an estimate to select the type of boundary according to the real nature of the geology. This is discussed in more detail in <u>Boundary Validation</u> below.

A **Hard boundary** uses only data within the domain's boundary. This can be seen when you add an estimation to the scene; the values used do not extend beyond the boundary:



A **Soft boundary** will also make use of data beyond the domain boundary, up to the distance specified in the **Range** field. Here, the range is set to 10 and we can see that values outside the boundary are used:



The **Soft Boundary** option provides the ability to create estimation objects strictly within the selected boundary, but to inform those estimation objects using relevant data immediately adjacent to but beyond the boundary.

- A fully soft boundary can be achieved by setting the **Range** to its maximum value.
- A semi-soft boundary can be achieved by constraining the **Range** to a lower value.

When a soft boundary is used, the values are taken within the specified range, measured perpendicular to the domain rather than along a borehole. This prevents errors arising from boreholes at acute angles to the domain boundary.

Selecting Values


In the **Values** part of the **New Contaminant Estimation** window, select the values that will be used. If you have defined a query filter, you can use it to filter the values for the contaminant estimation by selecting it from the **Query Filter** list. Once the contaminant estimation has been created, you can remove the filter or select a different filter.

You can build a contaminant estimation from either:

- Numeric data contained in imported borehole data, including composited data
- Points data imported into the **Points** folder

All suitable data in the project is available from the **Numeric values** list.

It is usually necessary to **Transform** the contaminant values data using a natural logarithm function. By default the **Transform Type** is **Log** but **None** can be chosen when no transformation of the data is required. A **Pre-log shift** value automatically offsets all the data values by the same amount to bring the minimum data value to zero, but the value can be changed to an alternative offset value that also provides positive input values to the log function. The **Value Distribution** tab shows a histogram of the transformed data values.



As well as applying a pre-log shift before the log transform, a constant calculated shift is applied after the transform to bring the resulting transformed data set minimum data value to zero. The complete function used is as follows:

transformed_value = ln(input_value + **Pre-log shift**) + post-log_shift

where input_value is each value in the selected values set, and the constant post-log_shift is calculated as:

post-log_shift = 0.0 - In (min_value + Pre-log shift)

where min_value is the lowest value in the selected value set.

Setting Compositing Options

When numeric values from borehole data are used to create the contaminant estimation, you can composite the data to simplify the geology for the purposes of estimation. If you do not have specific **Compositing** values in mind, you may wish to leave this option blank as it can be changed once the model has been created.

If the numeric values selected have already been composited, the **Compositing** settings will not be available in the **New Composited Estimation** window. Borehole data can be composited directly by right-clicking on the **Composites** folder (under the **Boreholes** object) and selecting **New Numeric Composite**. See Numeric Composites.

There are three compositing options:

- No compositing
- Entire borehole
- Within boundary


The compositing settings available depend on whether the boundary type is a hard or soft boundary. For soft boundaries, compositing is limited to the **Entire borehole** option, whereas for hard boundaries, compositing can also be limited to the data within the contaminant estimation's boundary.

See <u>Numeric Composites</u> for more information on the **Compositing length**, **For end lengths less than**, **Minimum coverage** and **Additional weighting column** settings.

When selecting compositing options, you may see a message: **Warning: missing numeric data**. This is not an error, but alerts you that some intervals are missing data.

Boundary Validation

Once you have selected the domain and the values you wish to use and set compositing options, the boundary analysis tools in the **New Contaminant Estimation** window help you to determine the best type of boundary to use:



If compositing is enabled for the contaminant estimation, the boundary validation information displayed is that for the uncomposited data.

A histogram of the sample count for each bin is included, so you can ignore things like an anomalous spike in mean value associated with a very small sample count. Adjust the size of the horizontal axis bins using the **Bin spacing** setting.

The pale blue bars show the sample count for each bin, and the red dotted line segment plot shows the mean value for the bin. The position of the **Hard boundary** is marked with a solid black vertical line. When a **Soft boundary** is selected, a vertical dotted blue line appears to show what values will be included, based on the **Range** setting. You can click on the soft boundary line and drag it to adjust the range.

When the mean value line segment plot shows a sharp change at the boundary, a hard boundary may be appropriate. Click on points in the line segment plot to see statistics relating to the selected point.

To zoom the x-axis of the chart:

- Use the scroll wheel on your mouse to zoom in or out.
- Reset the zoom level by clicking the **Reset view** button (^[C]).

The number to the left of the **Bin spacing** is the **Clipping distance**. This constrains the calculation of the graph to the specified distance from the domain, to improve application responsiveness. You can choose to set the distance to be right at the limit of the x-axis for maximum performance, or increase the distance to plot additional points to be visible when zooming out.

You can export the graph for use in external reports and other documents. Select the export button (之) to see two options:

- The **Export graph image** option saves a PDF, SVG or PNG file of the chart.
- The **Export data** option saves a CSV file containing the data so it can be reproduced and reformatted in a spreadsheet application.

Alternatively, you can choose the **Copy** option to save a copy of the graph image to the Windows clipboard for pasting into another application.

Note that when the **Export data** option is used, it is the last three columns (**Starting bin distance from** domain, **Mean** value and **Sample count**) that are required to reproduce the chart. The first two columns, **Distance from** domain to value column and the values column contain all the data points required to create a new chart with different bin spacing.

	Distance from		Starting bin distance																
1	LMS1 to Zn_pc Z	n_pc	from LMS1	Mean Zn_pc	Sample count							D	1	dest and					
2	-26.60208643	11.846	-27	10.692	2							Bound	lary Vali	dation					
3	-26.50009643	9.538	-26	8.538666667	3	16	5												
4	-25.77657143	8.077	-25	11.58966667	6														
5	-25.73047396	9.385	-24	13.59827778	18														
6	-25.19200428	8.154	-23	14.60206897	29	14													
7	-24.87891487	11.077	-22	13.27626531	49		· •	1											
8	-24.72571148	10.077	-21	13.0596375	80			N											
9	-24.14909668	10.692	-20	12.77135849	106			- N -											
10	-24.09388004	14.615	-19	12.3969	150	12		- ` \$4	Anna										
11	-24.08312213	12.923	-18	12.0748973	185		11			~									
12	-24.02666296	10.154	-17	11.78816832	202		•												
13	-23.97867739	7.615	-16	11.89542241	232	10	• I I												
14	-23.94375023	13.846	-15	11.76189712	243		11			1									
15	-23.63950258	20.231	-14	12.08922222	279					1									
16	-23.63216124	12.846	-13	11.79301672	299														
17	-23.62161931	6.115	-12	11.92378134	343	8	8												
18	-23.59424354	9.308	-11	11.77064829	381														*
19	-23.57383618	12.846	-10	11.70611026	390														Λ
20	-23.56615203	7.269	-9	11.63102457	407	6	5				-								-
21	-23.47524868	18	-8	11.84738508	496			-										. N/	
22	-23.3978312	17.385	-7	11.26283023	483												م مو	VV	
23	-23.2803701	16.385	-6	11.35214823	452	4									• • •	A	1		
24	-23.16875527	19.308	-5	11.2518433	485							8		*	x/*	• V •			
25	-23.1568989	11.154	-4	10.82670339	472							1			¥ ¥	-			
26	-23.14686193	7.538	-3	10.59642081	442			_				┣┓/ ┥		. 1	•				
27	-23.08114	13.077	-2	10.00583512	467	2	2					1 m		124				uh L	
28	-23.05791848	22.154	-1	9.188286713	572						A A	المعر	- V V	¥ •	1111				H
29	-23.04313507	13.769	0	1.43694683	489						M								
30	-23.02214905	15.923	1	1.329197719	263		, L												
31	-22.97459322	14.538	2	0.897594697	264		-27 -24	-21 -18 -	15 -12 -9	-6 -3	0 3 6	5 9 12	15 18	21 24 2	7 30 33	36 39	42 45 48	51 54	57
32	-22.96508297	13.154	3	0.696840206	194							Sample	count -	Mean Zn	nc				
33	-22.94424235	15	4	0.977808917	157							sample	Course	- mean zn_	p.c.				


The Contaminant Estimation in the Project Tree

Once you have entered a name for the contaminant estimation, click **OK**. The contaminant estimation will be added to the project tree in the **Contaminant Models > Estimation** folder. You can edit its settings by double-clicking on it.

A contaminant estimation is made up of the following objects:


- The **Domain** defines the limits of the estimation object. To select another domain, double click on the contaminant estimation and click the **Domain** button to select a new mesh.
- The points data values object contains all the data used in generating the estimation object. These comprise midpoints for all the value intervals. You can easily change the values used by selecting a different **Numeric values** column or by applying an optional query filter.
- The **Spatial Models** folder contains variogram models. Create a variogram model by right-clicking on the **Spatial Models** folder and selecting **New Variogram Model**. See <u>Experimental</u> <u>Variography and Variogram Models</u> for more information.
- The Variable Orientation folder is used for creating objects that make it possible to re-orient the search and variogram according to local characteristics. See <u>Variable Orientations</u> for more information.
- The **Sample Geometry** folder contains data density functions that can be used when declustering data. See <u>Standard Estimators</u> for more information.
- The **Estimators** folder contains estimators that can be evaluated onto block models. Estimators are similar to Leapfrog RBF interpolants, with the exception that estimators select and refer to an independently constructed variogram model. See <u>Standard Estimators</u> for more information.

You can view a contaminant estimation by dragging it into the scene; this adds the **Domain** and **Values** objects to the scene.



Viewing Statistics

You can view statistics for the values used in the contaminant estimation by right-clicking on the numeric data object and selecting **Statistics**:



What happens when **Statistics** is selected depends on whether or not the data values were composited.

- If the values were composited, a popup window will offer the choice between:
 - Univariate Graphs
 - Compositing Comparison
 - Compositing Interval Lengths
- If the values were not composited, a dockable tab window opens displaying the **Univariate** histogram of the point values.

For more details on these statistics options, see <u>Analysing Data</u>.

Copying a Contaminant Estimation

Reusing the same variograms, spatial models and estimators can be achieved by copying an estimation and then changing its boundary and values. Organising estimations in this way allows you to define a set of spatial functions and estimators that can then be reused with different values. For example, if you have multiple domains to estimate, you can define one, copy it, then change that copy's domain to one of the additional domains. Or you could experiment with different hypotheses: once you have defined a set of spatial functions and estimators, you can make a copy of the estimation and change that copy's values and boundary. Because the variograms and sills are normalised to the data variance when copying a estimation, you can change the values selection to a different data column and the sills and variance will be rescaled to the new data column's variance.

The Ellipsoid Widget

The features described in this topic are only available if you have the Contaminants extension.

Features in the Contaminants extension make use of an ellipsoid widget in the scene. This widget is used in a variety of situations:


- To visualise anisotropy proportions and orientation
- To visualise the variogram model in the scene, including rotation and ranges
- To depict search neighbourhoods

To aid in the visualisation of the ellipsoid, the major, semi-major and minor axes are also drawn as red, green and blue lines respectively. Additionally, translucent planes can be seen within the ellipsoid if the opacity of the ellipsoid is reduced. This assists in visualising the orientation and shape of the ellipsoid.


These planes show the major-semi-major plane and the semi-major-minor plane.

Display and Editing Modes

An ellipsoid may appear in the scene in a display mode or an editing mode. In display mode, the ellipsoid has no visible handles, and in editing mode the widget has drag handles on the outer edges of the ellipsoid to change its shape and orientation. For instance, you can drag the variogram model into the scene from the project tree, and it will appear in the scene in display mode.




You can also open the variogram model and switch back to the scene or undock the variogram tab and move it away to see the scene, and because the variogram model is open for editing, the ellipsoid widget appears in the scene with drag handles.



Changing Movement Handles


Ellipsoid widgets can be repositioned, perhaps so the ellipsoid is not obstructing the view of part of the model. To reposition the widget, select the widget in the shape list then click the widget in the scene. If the ellipsoid does not have arrows in the centre, click the ellipsoid and the movement arrows will appear. You can click the ellipsoid again to turn them off.




In the properties panel for the selected widget, settings control the **Centre Point** of the ellipsoid. The **X**, **Y** and **Z** position can be specified directly.

There are two modes for the widget movement handles. In the properties panel for the selected widget, **Align movement handles to** has the options **Axes** and **Camera**.


If the option is set to **Align movement handles to Axes** the drag handles in the centre of the widget will be red, green and blue and point along the directions of the project axis lines.




You can click on one of the red, green or blue movement handles and drag it in the scene, and the ellipsoid will move forward or back in the direction of the selected project axis.




Don't confuse the red, green and blue centre point arrows with the red, green and blue axis adjustment arrows that may appear on the edge of the widget.



If the option is set to **Align movement handles to Camera** the drag handles in the centre of the widget will be orange and point up/down/left/right across the scene view.




You can click anywhere on the orange handles and drag it in the scene, and the ellipsoid will move across the viewing plane



Changing Look Direction


When an ellipsoid widget is selected in the shape list, the **Look** button in the properties panel provides options for quickly changing the camera viewpoint.



Changing Controls in Edit Mode


The ellipsoid widget only has handles when it is in editing mode. If there are no drag handes on the edges of the ellipsoid widget, it is in display mode and cannot be directly modified.

If your ellipsoid widget is in edit mode, you will see drag handles on the edges of the widget. There are two modes for these controls. Click on the widget to toggle between control modes. Each mode offers different handles for directly manipulating the ellipsoid widget. When the arrows on the edge of the widget are yellow, blue and red, the handles adjust the ellipsoid trend.



Drag a yellow arrow handle to adjust the **Dip**, blue to adjust the **Dip Azimuth** and red to adjust the **Pitch**.

When the arrows on the edge of the widget are red, green and blue, the handles adjust the ellipsoid ranges.



Drag a red arrow handle to adjust the **Maximum** axis range, green to adjust the **Semi-major** range and blue to adjust the **Minimum** range.

If you click on the widget and the outer arrows do not change, you probably have a variogram model with a second structure defined. Once the second structure is defined, the structure that is controlled by the arrows would be ambiguous, which is why the range arrows are disabled for multiple structure variograms.

As you modify the ellipsoid by manipulating the drag handles, the respective settings values are updated.

Experimental Variography and Variogram Models

The features described in this topic are only available if you have the Contaminants extension.

After data analysis and domaining comes the key part of the contaminant estimation workflow: variography. A theoretical variogram model is proposed and tested using experimental variography. Kriging, nearest neighbour, inverse distance weighting or RBF estimators are defined and potentially combined.

Variography is the analysis of spatial variability of values within a region. Understanding how sample values relate to each other in space is a vital step in informing estimates in a contaminant model. A variogram is used to quantify this spatial variability between samples.

In estimation, the variogram is used for:

- Selecting appropriate sample weighting in Kriging and RBF estimators to produce the best possible estimate at a given location
- Calculating the estimators' associated quality and diagnostic statistics

In Leapfrog Works contaminant estimations, variograms are created and modified using the **Spatial Models** folder. To create a new variogram model, right-click on the **Spatial Models** folder and select **New Variogram Model**. A new variogram model is not auto-fitted and should not be assumed to be the initial hypothesis for the workflow. While some reasonable defaults have been selected for the variogram model, the geologist's personal hypothesis should be the starting point for the estimation workflow.

You can define as many variograms as you wish; when you define an estimator that uses a variogram model, you can select from those available in the contaminant estimation's **Spatial Models** folder:


🔏 New Kriging - Kr	, Total_Conc in Ur	nconsolidated	Sediments		×
Value Clipping	Interpolant	Ellipsoid	Search	Outputs	
Kriging Option	ıs				
<u>K</u> riging ty	pe: Ordinar	y			~
Mean <u>v</u> alu	e: 0.00000)			÷
Discretisa	tion: <u>X</u> : 1	<u>੍ਹੇ ⊻</u> : 1	: :	1 $$ (poir	nt kriging)
Search elli	psoid: Maj = 180)14.3; Semi-n	naj = 18014.	3; Minor = 925.	.6
Variogram Mo	del 🔗 Total_C	onc in Uncon	solidated Se	diment 🗸	View
		onc in Uncon	solidated Se	diments: Single	Structure
1.2 -	N 🔗 Total_C	onc in Uncon	solidated Se	diments: Two S	tructure
	I Minor	S	emi-maj	I	
E ^{1.0}	Ci -				

Working with variograms is an iterative process. The rest of this topic provides an overview of the **Variogram Model** window and describes how to use the different tools available for working with variograms. This topic is divided into:

- The Variogram Model Window
- Variogram Model Controls
- Experimental Controls

See The Ellipsoid Widget for information that is useful in working in the Variogram Model window.

The Variogram Model Window



The **Variogram Model** window is divided into three parts:

The variogram model controls (1) are for adjusting the variogram model type, trend and orientation. See <u>Variogram Model Controls</u> below. The graphs (2) plot the selected variogram. Finally, the experimental controls (3) are for verifying the theoretical variogram model. See <u>Experimental Controls</u> below.

When you edit a variogram model in the **Variogram Model** window, an ellipsoid widget is automatically added to the scene. The ellipsoid widget helps you to visualise the variogram in 3D, which is useful in setting variogram rotation and ranges and in defining search neighbourhoods.

If the **Variogram Model** window is docked as a tab, you can tear the window off. As a separate window, you can move and resize the window so you can see the ellipsoid change in the 3D scene while you make adjustments to the model settings. The detached window can be docked again by dragging the tab back alongside the other tabs, as described in <u>Organising Your Workspace</u>.

There are two ways to save the graph for use in another application:

- Click the **Export** button (□) and select **Export graph image** from the options to export the graph as a PDF, PNG or SVG file.
- Click the **Copy graph** button (^(b)) to copy the graph to the clipboard. You can then paste it into another application.


Additionally, you can save variogram parameter data by selecting a theoretical variogram from the list, clicking the **Export** button ($rac{1}$) and selecting **Export data** from the options. Note that **Export data** is not available for the experimental variogram or the **Radial Plot**.

Pi						• % 9 -00			ng ~		↓ ~ ♦ ~		Ideas	
CI	ipboard 🗳	Font	r <u>s</u> ∣ A	lignment	F <u>s</u> N	umber 😼		Styles		Cells	Ed	ting	Ideas	
E3	7 * :	×	f _x											,
4			С		E	F	G	н	1	J	к	L	1	M
	01 -> 000 Major Axis	Variograp	ny for c_DO	E_12 (log)	values									
	Number Of Points	21												
3	Variance	6.66014												
4														
5														
6	Dip	1												
7	Dip Azimuth	0												
8	Pitch	90												
9														
10	[Variogram Parame													
	Structure		Normalise		Alpha	Major	Semi-Maj	Minor						
12	Nugget	0	0											
	Structure 1	6.66	1	Spherical	-	1500	920	310						
14	Total Sill:	6.66	1											
15														
16	[Experimental Para	meters]												
	Lag	306												
	Lag tolerance	153												
19	Number of lags	10												
20		in plane	off plane											
21	Angle tolerance	22.5	22.5											
22	Bandwidth	306	306											
23														
	[Data Capping]													
	Lower bound	-												
	Upper bound	-												
27	Capped Variance	6.66014												
28														
29	Experimental Data													
	Spher	ical1500-92		(+)				: •					_	Þ

There are two buttons for refreshing the graphs when changes are made:

- When **Auto Refresh** is enabled, recalculations will be carried out each time you change a variogram value. This can produce a brief lag.
- When auto refresh is disabled, you can click the **Refresh** button (\bigcirc) whenever you want the graphs to be updated. This is the best option to use when working with a large dataset.

If auto refresh is disabled and values have been changed without the graphs being updated, the chart will turn grey and a reminder will be displayed over it:



Variogram Model Controls

The **Variogram Model** controls adjust the variogram model type, trend and orientation; the graph will update to reflect changes you make to model parameters. The ellipsoid in the scene will also reflect the changes you make to the **Variogram Model**.

Multi-structured variogram models are supported, with provision for nugget plus two additional structures.

The **Nugget** represents a local anomaly in values, one that is substantially different from what would be predicted at that point based on the surrounding data. Increasing the value of **Nugget** effectively places more emphasis on the average values of surrounding samples and less on the actual data point and can be used to reduce noise caused by inaccurately measured samples.

Each additional structure has settings for the component **Sill** and the normalised sill, labelled **Norm. sill**, model **Type**, **Alpha** (if the model type is spheroidal), and the **Major**, **Semi-Major** and **Minor** ellipsoid ranges.

The **Sill** defines the upper limit of the model, the distance where there ceases to be any correlation between values. The **Sill** can be set for the **Nugget**, **Structure 1** and **Structure 2**.

Piecewise models rise to the **Sill** at the **Range** and stay there for increasing distances beyond the **Range**. Distances beyond the **Range** in the domain are uncorrelated.

Asymptotic models approach the sill asymptotically near the range and continue to approach it for increasing distances beyond the range. For asymptotic models, the **Range** parameter used in the model has no equivalent physical meaning, as it does for piecewise models. Common practice is to instead use a scaling of the **Range** parameter so that the value entered in this screen somewhat mimics the sill/range

behaviour of a piecewise model. Typically, this scaling parameter is chosen so that the 'practical range' or 'effective range' entered corresponds to a point on the asymptotic function that is a defined percentage of the total sill. There is no universally accepted way of defining what this scaling parameter should be. The practical range used in Leapfrog Works is noted below for each variogram model **Type**.

A linear model has no sill in the traditional sense, but, along with the ellipsoid ranges, the sill sets the slope of the model. The two parameters **Sill** and **Range** are used instead of a single gradient parameter to permit switching between interpolant functions without also manipulating these settings.

The **Norm. sill** represents the same information as the **Sill**, but proportionally scaled to a range between 0 and 1, where 1 represents the data **Variance**. As you select the radio buttons for **Sill** and **Norm. sill**, the Y-axis scale on the displayed chart will change to correspond to your selection.

The **Total sill** is the sum of the component sills for both the data sills and the normalised sills.

The **Lock sill** icon indicates if the sill is unlocked () or locked (). Click the icon to change the lock state. If unlocked, changing a sill value will adjust the **Total sill** by the same amount. If locked, adjusting any sill value will not change the **Total sill** at all, but other sill values will change to keep the **Total sill** fixed.

The **Variance** is calculated automatically from the data and shows the magnitude of the variance for the dataset.

Linear, Spherical and Spheroidal Model Options

Leapfrog Works provides a variety of 'authorised' variogram model types to ensure the spatial character of continuity can be modelled. 'Authorised' variogram models are guaranteed to have the mathematical property of 'positive definiteness' for the associated covariance function, meaning the model is guaranteed to produce a valid result when used in Kriging. The model **Type** provides the options **Linear**, **Spherical**, **Spheroidal**, **Gaussian**, **Exponential**, **Cubic** and **Generalised Cauchy**.

Variogram models can be bounded or unbounded. Linear is the only unbounded type provided by Leapfrog Works, where the value of the variogram increases as a linear function of distance. Linear models cannot be combined with the bounded models.


All other model types provided in Leapfrog Works are bounded models that rise to a sill. These can be separated into two further types:

- Piecewise models that rise to a sill at a range, then are constant beyond that range
- Asymptotic models that approach but never reach a sill

Spherical and Cubic models are piecewise; Spheroidal, Gaussian, Exponential and Generalised Cauchy are asymptotic.

The functions vary in how quickly they rise toward the sill both initially and at (and beyond) the range.

Which function you select will depend on the variable you are modelling, as well as the performance required. For instance, **Generalised Cauchy** is provided as it is faster than the **Gaussian** function when applied to an RBF estimator, but provides reasonably similar results.




Variogram model types **Cubic**, **Gaussian** and **Generalised Cauchy** are included specifically for modelling variables with high continuity and local correlation such as dispersed groundwater contaminants. Screening effects and negative Kriging weights can be more pronounced when using these models with continuous behaviour, so use the block model interrogation tool to check the Kriging plan is optimal and the Kriging weights are appropriate.

Each of the variogram model **Types** are described below. For each, a formula is presented for the model. They all use the following terms:

- $\gamma(h)$ is the value of the variogram at distance h
- C_0 is the sill
- *h* is the distance on the x axis
- a is the range parameter


For each model type, the effect of the interpolation function is depicted by evaluation onto a grid of points, using as input just four samples, A = 7, B = 14, C = 2 and D = 8. A thin slice is taken through the grid of points to provide a sort of 2D visualisation of the operation of the function. One of the points has been selected in each view to display the value being estimated for a specific location.



Type = Linear

 $\gamma(h) = C_0(h/a)$


Linear is a general-purpose multi-scale option suited to sparsely and/or irregularly sampled data. It is typically used for modelling of categorical variables.



Type = Spherical

$$\gamma(h) = \begin{cases} C_0 \left[\frac{3}{2} \frac{h}{a} - \frac{1}{2} \left(\frac{h}{a} \right)^3 \right] & \text{for } h \le a \\ C_0 & \text{for } h > a \end{cases}$$

Spherical is suitable for modelling most variables where there is a finite range beyond which the influence of the data should fall to zero. Because the spherical model is piecewise, beyond the range the variogram value is the constant sill.




Type = Cubic

$$\gamma(h) = \begin{cases} C_0 \left[7 \left(\frac{h}{a} \right)^2 - \frac{35}{4} \left(\frac{h}{a} \right)^3 - \frac{7}{2} \left(\frac{h}{a} \right)^5 - \frac{3}{4} \left(\frac{h}{a} \right)^7 \right] & \text{for } h \le a \\ C_0 & \text{for } h > a \end{cases}$$

Cubic, like **Spherical**, is a piecewise model that has a finite range beyond which the influence of the data should fall to zero, and the variogram value is the constant sill. It has been included specifically for modelling variables with high continuity and local correlation such as dispersed groundwater contaminants. Screening effects and negative Kriging weights can be more pronounced when using the

cubic model type with continuous behaviour, so use the block model interrogation tool to check the Kriging plan is optimal and the Kriging weights are appropriate.




Type = Exponential

The **Exponential** variogram model type is used in modelling precious metals such as gold. It has a steeper slope toward the origin than other model types.

$$\gamma(h) = C_0 \left[1 - exp\left(-\frac{h}{a} \right) \right]$$

The Exponential model is asymptotic and approaches but never quite reaches the Sill.

An exponential model with a range parameter of *a* reaches a value of ~95% of the sill at a distance of 3 x *a*. The **Range** value is scaled by a factor of 1/3 in the formulation. This has the effect of ensuring that the exponential variogram reaches ~95% of the sill at the 'practical range'. Beyond the practical range, a point has a small but non-zero correlation.




Type = Gaussian

$$\gamma(h) = C_0 \left[1 - exp\left(-\frac{h^2}{a^2} \right) \right]$$

The Gaussian model is asymptotic and approaches but never quite reaches the Sill.

Gaussian has been included specifically for modelling variables with high continuity and local correlation such as dispersed groundwater contaminants. Screening effects and negative Kriging weights can be more pronounced when using these models with continuous behaviour, so use the block model interrogation tool to check the Kriging plan is optimal and the Kriging weights are appropriate.

A **Gaussian** model with a range parameter of *a* reaches a value of ~95% of the sill at a distance of $\sqrt{3} \times a$. The **Range** value is scaled by a factor of $1/\sqrt{3}$ in the formulation. This has the effect of ensuring that the Gaussian variogram reaches ~95% of the sill at the 'practical range'. Beyond the practical range, a point has a small but non-zero correlation.



Type = Generalised Cauchy

The **Generalised Cauchy** model is asymptotic and approaches but never quite reaches the **Sill**. The **Generalised Cauchy** covariance can be expressed as:

$$C(h) = \left(1 + \frac{h^2}{a^2}\right)^{-\alpha}$$
 $(a > 0, \alpha > 0)$

By considering only particular values for the exponent α this expression can be simplified to derive a standardised **Generalised Cauchy** covariance function of order *m*, where $m = 2\alpha$

$$M_m(h) = \left(1 + (h/a)^2\right)^{-m/2}$$

This can in turn be expressed as a variogram function for the **Generalised Cauchy** variogram of order *m*:

$$\gamma_m(h) = c_0 \left[1 - \left(1 + (h/a)^2 \right)^{-m/2} \right]$$

Select the order *m* by selecting from the **Alpha** options of 3, 5, 7 or 9, which are the only values allowed in Leapfrog Works. For a given range parameter *a*, the variograms of order *m* reach the same proportion of total sill at quite difference distances. In order to equate the shape of the variogram to the entered **Range** parameter, scaling parameters are applied.


For a **Generalised Cauchy** variogram of order 9, the value of γ at the specified range parameter is 95.58% of the total sill. Because the convention is arbitrary, Leapfrog Works considers that a variogram

of order 9 does not require a re-scaling of the range parameter. Leapfrog Works then uses this sill proportion of 95.58% to calculate scaling factors for variograms of order 3, 5 and 7. In practice, a lookup table is used with ideal values rounded to 10 decimal places:

Order (<i>m</i>)	Range scaling factor
3	0.3779644730
5	0.6347188807
7	0.8339047224
9	1.0000000000

This has the effect of ensuring that the **Generalised Cauchy** variogram reaches 95.58% of the sill at the 'practical range'. Beyond the practical range, a point has a small but non-zero correlation. For further details on the derivation see <u>The Spheroidal Family of Variograms Explained</u> on the Seequent blog.

This chart shows the relative differences for different values of **Alpha**, which is the order (m) of the function, in comparison to a spherical curve:



Type = Spheroidal

The **Spheroidal** model is asymptotic and approaches but never quite reaches the **Sill**. However, the first part of the function is linear.

Spheroidal is suitable for modelling most variables where there is a finite range beyond which the influence of the data should fall to zero. The spheroidal variogram was developed by Seequent primarily for use in RBF interpolants. Seequent wanted an effectively compact spatial function that has linear behaviour near the origin and an asymptotic approach to the sill. This was developed by taking a commonly used family of radial functions and linearizing them near the origin. This results in a variogram

that combines the **Linear** model with the **Generalised Cauchy** variogram model. The transition point between these two is the inflection point on the **Generalised Cauchy** model.

$$\gamma_m(h) = \begin{cases} \left[\lambda_m \kappa_m h/a\right], & h \le x_m^* \kappa_m^{-1} a \\ C_o \left[1 - c_m^{-1} \left(1 + \left(\kappa_m h/a\right)^2\right)^{-m/2}\right], & h \ge x_m^* \kappa_m^{-1} a \end{cases}$$

where

$$x_m^* = 1/\sqrt{m+1}$$
$$\lambda_m = \frac{m}{2\sqrt{m+1}}$$
$$c_m = 2\left(\frac{m+2}{m+1}\right)^{-m/2^{-1}}$$


Select the order *m* by selecting from the **Alpha** options of 3, 5, 7 or 9, which are the only values allowed in Leapfrog Works. For a given range parameter *a*, the variograms of order *m* reach the same proportion of total sill at quite difference distances. In order to equate the shape of the variogram to the entered **Range** parameter, scaling parameters are applied.

For a **Spheroidal** variogram of order 9, the value of γ at the specified range parameter is 96% of the total sill with no nugget. Because the convention is arbitrary, Leapfrog Works considers that a variogram of order 9 does not require a re-scaling of the range parameter. Leapfrog Works then uses this sill proportion of 96% to calculate scaling factors for variograms of order 3, 5 and 7. In practice, a lookup table is used with ideal values rounded to 10 decimal places:

Order (<i>m</i>)	Range scaling factor
3	0.3731574337
5	0.6319995630
7	0.8327312240
9	1.000000000

This has the effect of ensuring that the **Spheroidal** variogram reaches 96% of the sill at the 'practical range' with no nugget. Beyond the practical range, a point has a small but non-zero correlation. For further details on the derivation see <u>The Spheroidal Family of Variograms Explained</u> on the Seequent blog.

This chart shows the relative differences for different values of **Alpha**, which is the order (m) of the function, in comparison to a spherical curve:



Alpha is only available when the model **Type** is **Spheroidal** or **Generalised Cauchy**. The **Alpha** constant determines how steeply the interpolant rises towards the **Sill**. A low **Alpha** value will produce a variogram that rises more steeply than a high **Alpha** value. A high **Alpha** value gives points at intermediate distances more weighting, compared to lower **Alpha** values. For **Spheroidal**, an **Alpha** of 9 provides the curve that is closest in shape to a spherical variogram. In ideal situations, it would probably be the first choice; however, high **Alpha** values require more computation and processing time, as more complex approximation calculations are required. A smaller value for **Alpha** will result in shorter times to evaluate the variogram.

RBF estimators will only work when the **Structure 2** model **Type** is set to **None**.

When **Structure 2** is defined, the model ranges cannot be adjusted by manipulation of drag handles on the ellipsoid. Because it would not be clear which structure was being manipulated, the drag handles to change the range settings do not appear.

Normalised Y Axis

A key use of copying a variogram is to apply it to another correlated contaminant. This would typically be accomplished, having determined the appropriate variogram using the values for one contaminant, by copying the domained estimation and changing the **Numeric values** field to a different contaminant. However, the absolute values for the nugget and sills for each structure would be completely inappropriate for the new contaminant; while we desire the shape to be the same, the values for different compounds will inevitably be different. To make this work correctly, the variogram is normalised or standardised, rescaling the range of Y-axis values to be tween 0 and 1, where 1 is equivalent

to the data **Variance**. This makes the variogram information portable between domained estimations. This is performed automatically, requiring no intervention on your part.

You can freely switch between the **Sill** and **Norm. sill** options. The selection only changes the Y-axis scale on the displayed chart.

You do not need to select the **Normalised** option before copying the domained estimation and using it as the basis for a different mineral resource. The normalised scale will always be used when applying the variogram model to the new data set.

As you adjust the **Nugget** or the **Structure 1** or **Structure 2** sill values, the **Total sill** will change both for the absolute **Sill** values and the **Norm. sill** values. The **Norm. sill** total may end up being something other than 1.0. This is expected, as the value reference for the normalised scale uses the data **Variance** for 1.0, not the total sill.

Note that the data **Variance** is recorded in the Y axis label so the chart scale is always meaningful, including when the chart is exported.

Direction

The trend **Direction** fields set the orientation of the variogram ellipsoid. Adjust the ellipsoid axes orientation using the **Dip**, **Dip Azimuth** and **Pitch** fields.

The **Set From Plane** button sets the trend orientation of the model ellipsoid based upon the current settings of the moving plane.


The **View Ellipsoid** button adds a 3D ellipsoid widget visualisation to the scene, in case it has been deleted from the scene since the variogram model window was opened for editing.

Experimental Controls

A variogram model can be verified through the use of the experimental variography tools that use sample data. Use these to find the directions of maximum, intermediate and minimum continuity.

The variogram displayed in the chart is selected from the variograms listed in the panel in the top left corner of the window.


The top entry in the variograms list is the theoretical variogram model rather than an experimental variogram:




All other variograms in the list and the other controls on the left-hand side of the screen relate to **Experimental Variograms**.

Besides the theoretical **Variogram Model**, a set of experimental **Axis Aligned Variograms** are available, including a **Radial Plot** variogram and a variogram for each axis of the variogram ellipsoid.

Click on one of these experimental variograms to select it and display its parameters. The displayed graph will change to match this selection. For example, here the graph and settings for the combined **Axis Aligned Variograms** are displayed:





Selecting the Semi-major Axis variogram changes the chart and settings displayed:

Adjust the model variogram parameters to see the effect different parameters have when applied to the actual data.

Experimental Variogram Parameters

The experimental variogram controls along the left side of the window define the search space, define the orientation for custom variograms and change how the variograms are displayed.

Capping

Data **Capping** fields limit the values of the **Lower bound** and **Upper bound** for the data as specified. This is not a filter that discards these points, but values below or above the caps are treated as if the value was the lower or upper bound.

Capping		
Lower bound:	0.031	ĉ
Upper bound:	28.308	Ĵ
Variance:	21.3085	

These **Capping** controls only affect the data values considered for the purposes of experimental variography, and they do not cap the values of the data points used in estimation. If you wish to also cap values used in estimation, set the **Lower bound** and **Upper bound** limits in the **Value Clipping** tab in the applicable estimator. To eliminate an anomalous data point or discard certain data values,

you should modify the domain definition options using a **Query Filter**.

Defining the Search Space

The search space for experimental variography is not shown in the scene. It is not an ellipsoid, and should not be confused with either the variogram model ellipsoid or the estimator's search ellipsoid.

The first set of parameters controls the search space.


- Lag distance controls the size of the lag bins. The first bin will be one quarter of the size of the Lag distance. Experimental variograms generally measure lags as distances along a direction vector, though downhole variograms measure lags as distances along the boreholes.
- Lag tolerance allows for the reality that data pairs are rarely the same distance apart. The data is scanned and pairs are assembled after applying a Lag tolerance to the Lag distance. If the Lag tolerance Auto box is ticked, Leapfrog Works defaults to using a Lag tolerance of half the Lag distance. Controlling the Lag tolerance explicitly allows you to test the sensitivity of the variogram. Typically, a larger value will be used for sparse datasets and a smaller value for dense datasets.

Some software treats a **Lag tolerance** of 0 as a special value that does not mean 'no lag tolerance' but instead is interpreted as meaning half the **Lag distance**. In Leapfrog Works, it is possible to set **Lag tolerance** to 0, but this means literally what the number implies: there is no **Lag tolerance** and the only data pairs that are displayed are those that occur exactly at the **Lag distance** spacing.


- Number of lags constrains the number of lag bins in the search space.
- The **In Plane** and **Off Plane Angle tolerance** and **Bandwidth** settings define the search shape, and the effects of these settings are discussed in more detail below.

General				
Lag <u>d</u> istance:	7			$\hat{\cdot}$
Lag t <u>o</u> lerance:	3.5		✓ <u>A</u> uto	
Number of lag <u>s</u> :	10			$\hat{}$
	In Plane		✓ Off Plane	
Angle tolerance:	22.5	Ŷ	22.5	$\hat{}$
<mark>⊠ <u>B</u>andwidth:</mark>	7	¢	7	$\hat{}$

The search shape usually approximates a right rectangular pyramid on a rectangular parallelepiped. The pyramid and parallelepiped will be square if the **In Plane Angle tolerance** and **Bandwidth** are used without defining **Off Plane** values. Using the **Off Plane Angle tolerance** and **Bandwidth** fields will make the shape rectangular. The plane being referred to is the major-intermediate axis plane of the variogram ellipsoid, the same plane used for the radial plot. The **Angle tolerance** is the angle either side of a direction vector from the data point origin. Once the sides of the pyramid defined by the angle tolerance extend out to the limits specified by the **Bandwidth**, the search neighbourhood is constrained to the bandwidth dimensions.




The search shape becomes a more complex "carpenter's pencil" shape when a wide **In Plane** angle and a narrow **Bandwidth** are defined along with a narrow **Off Plane** angle and a wide **Bandwidth**, or vice versa. This rendering should assist in visualising the shape; the major axis is shown in red, the semi-major axis is shown in green, and the orthogonal minor axis in a transparent blue:



Note that although not shown here, the outer ends of the search shapes are not flat, but rounded, being defined by the surface of a sphere with a radius of the maximum distance defined by the number of lags and their size.

Off Plane Angle tolerance and **Bandwidth** settings cannot be set for the minor axis variogram. Because the angle tolerance and bandwidth are described relative to the major-intermediate plane and because the minor axis is orthogonal to this plane, only one angle can be described. This results in a square pyramid search shape.



The In Plane Bandwidth also cannot be set for the Minor Axis.


Note that although not shown here, the outer ends of the pyramids are rounded, defined by the surface of a sphere with a radius of the maximum distance defined by the number of lags and their size.

Radial Plot Parameters

Radial Plot has parameters specifically for the radial plots in Axis Aligned Variograms.

Increasing the **Radial divisions** slices the space into a larger number of sectors, with each block in the radial plot covering a smaller arc of the compass. As a result, each block has a smaller volume; this also means that the amount of data in each block is reduced. Because the bandwidth angle above and below the major-intermediate plane matches the angle used to slice the plot into its sectors, increasing the **Radial divisions** also reduces the number of data points used above and below the plane. Using a smaller number of **Radial divisions** will be faster. If you increase the number of divisions, you may want to turn off **Auto Refresh Graphs** first and click **Refresh graphs** afterwards. Experiment with the number of divisions and choose the lowest number of **Radial divisions** that helps you gain the best understanding of continuity; this will maximise the data that falls in each division.

Mean Value will display radial plot bins coloured to indicate the mean value for each bin. **Contour** will display a plot showing lines of equal value. **Fill** shades the chart between the contour lines.



Changing Axis Limits

The Axis Limits settings control the chart scaling.


X axis limits and Y axis limits control the ranges for the X-axis and Y-axis and can effectively be used to zoom the chart. You can directly control these by manipulating the axes with your mouse. Click and drag an axis to increase or decrease the maximum limit of the axis. Right-click and drag an axis to reposition the axis so the minimum value on the axis is not zero. Double-click the axis to reset the axis minimum and maximum range to the default values. **Fit Graph** will auto-fit the graph to the available data.

Axis Limits				
X-axis:	0	Û	3589	¢
Y-axis:	0	¢	2.416	¢
		Fit Gr	aph	

Changing Variogram Display


The **Display** settings change how the variogram is displayed:

- Show model variogram plots the variogram on the chart.
- Show pair count annotates the chart with the count of data point pairs.
- Tick the **Scale points to pair size** checkbox and the chart will display the plotted points with dots that scale to the size of the pair count. Choose **Actual** so the dots represent the pair size proportionally and **Inverse** to see larger dots for lower pair counts.
- Tick **Moving avg** for a rolling mean variogram value, drawn on the variogram plots in orange. Next to it, select a value for the window size relative to the **Lag distance**. The window size will be the given number times the lag distance. This window, centred on x, will be used to plot y, the average of all the variogram values falling inside the window. The lag multiplier field has a useful tooltip reminder; hover your mouse pointer over the field to see the tooltip.




Axis Aligned Variograms


The **Axis Aligned Variograms** are useful for determining the direction of maximum, intermediate and minimum continuity. When you select the **Axis Aligned Variograms** option, all four variograms are displayed in the chart:




The radial plot and each of the axes variograms can be viewed in greater detail by clicking on them in the variogram tree:



In the axes variogram plots, you can click-and-drag the plus-shaped dragger handle to adjust the range and the sill. A triangular dragger handle adjusts the nugget. A solid line shows the model variogram, and dotted horizontal lines show the **Total Sill** and, if **Sill** is chosen instead of **Norm. sill**, the variance.



In the radial plot, you can click-and-drag the axes arrows to adjust the pitch setting, between the values 0 and 180 degrees. Each bin in the mean value radial plot shows the mean semi-variogram value for pairs of points binned by direction and distance. When the contour plot is selected, lines follow the points of equal value.



The experimental variogram controls can be different for each axis direction.

Standard Estimators

The features described in this topic are only available if you have the Contaminants extension.

This topic describes creating and working with the different types of estimators the Contaminant extension supports:

- Inverse Distance Estimators
- Nearest Neighbour Estimators
- Kriging Estimators
- RBF Estimators

Estimators can be copied, which makes it easy to experiment with different parameters. Simply rightclick on the estimator in the project tree and select **Copy**.

Inverse Distance Estimators

The basic inverse distance estimator makes an estimate by an average of nearby samples weighted by their distance to the estimation point. The further a data point is from the estimate location, the less it will be relevant to the estimate and a lower weight is used when calculating the weighted mean.

To create an inverse distance estimator, right-click on the **Estimators** folder and select **New Inverse Distance Estimator**. The **New Inverse Distance** window will appear:

New Inverse Dista	nce - ID, Total_C	onc in Uncon	solidated Sed	iments	
Value Clipping	Interpolant	Ellipsoid	Search	Outputs	
Inverse Distanc	e Options				
Exponent:	2.0				0
Ellipsoid rang	es: Max = 1801	4.3; Int = 123	845.0; Min = 6	5000.0	
	Invers	e Distance	Weighting		
1.0	1	e Diotanee	I Unt	Max	
0.8 -	М	lin	-Tinc -		
2° 0.6 -			1 .1	I	
ighti			1		
₿ 0.4 - 1			1	1	
0.2			-		
0.0			<u>.</u>	<u> </u>	
0	2500 5000 7	7500 10000 1 Distance	12500 15000 B	17500 20000	
Name: ID, Total	Conc in Uncons	olidated Sedi	ments		_
?		<u>(</u>	ancel	<u>0</u>	К

Leapfrog Works extends the basic inverse distance function with the option for anisotropic distance. In the **Interpolant** tab:

- **Exponent** adjusts the strength of the weighting as distance increases. A higher exponent will result in a weaker weight for the same distance.
- Ellipsoid Ranges identify the Max, Int and Min ranges set in the Ellipsoid tab.
- A chart depicts the resultant weights that will be applied by distance.

In the **Ellipsoid** tab:

- The **Ellipsoid Definition** sets the anisotropic distance and direction, scaling distances in three orthogonal directions proportionally to the range for each of the directions of the ellipsoid axes. This effectively makes the points in the direction of greater anisotropy appear closer and increases their weighting. Adjust the **Ellipsoid Ranges** and **Directions** to describe the anisotropic trend.
- Click View Ellipsoid to see an ellipsoid widget in the scene that helps to visualise the anisotropic trend.

Value Clipping	Interpolant	Ellipsoi	d Search	Outputs	
Ellipsoid Definition	ı				
Ellipsoid range	s		Directions		
Ma <u>x</u> imum	18014.30	÷	Dip	0.00	<u></u>
Intermed.	12345.00	$\hat{}$	Dip Azimuth	0.00	Û
<u>M</u> inimum	6000.00	$\hat{\mathbf{v}}$	Pitch	90.00	¢
View Ellips	oid	Set From	<u>P</u> lane	<u>S</u> et to	~

In the **Search** tab The **Minimum Samples** and **Maximum Samples** parameters determine the number of samples required or used within the search neighbourhood.

lew Inverse Dista	nce - ID, Total_C	onc in Uncons	olidated Sed	iments	
Value Clipping	Interpolant	Ellipsoid	Search	Outputs	
Search Definit	tion				
Minimum sa	imples: 4) Max	imum samp	les: 255	Û

In the **Value Clipping** tab, you can enable value clipping by ticking the **Clip input values** box. This caps values outside of the range set by the **Lower bound** and **Upper bound** to the bounding values.

In the **Outputs** tab, you can specify attributes that will be calculated when the estimator is evaluated on a block model. **Value** and **Status** attributes will always be calculated, but you can choose additional attributes that are useful to you when validating the output and reporting. These attributes are:

- The number of samples (NS) is the number of samples in the search space neighbourhood.
- The distance to the closest sample (**MinD**) is a cartesian (isotropic) distance rather than the ellipsoid distance.
- The average distance to sample (**AvgD**) is the average distance using cartesian (isotropic) distances rather than ellipsoid distances.
- The number of duplicates deleted (**ND**) indicates how many duplicate sample values were detected and deleted by the estimator.
- When the estimator must select from equidistant points to include or exclude in the search space because it found more samples than the **Maximum Samples** threshold, the number of equidistant points detected (**EquiD**) is recorded. You can use this output as a trigger for further investigation.

Nearest Neighbour Estimators

Nearest neighbour produces an estimate for each point by using the nearest value as a proxy for the location being estimated. There is a higher probability that the estimate for a location will be the same as the closest measured data point, than it will be for some more distance measured data point.

To create a nearest neighbour estimator, right-click on the **Estimators** folder and select **New Nearest Neighbour Estimator**. The **New Nearest Neighbour** window will appear:

Value Clipping	Ellipsoid	Outp	uts		
Ellipsoid Definitio	n				
Ellipsoid rang	es		Directions		
Ma <u>x</u> imum	18014	.30 🗘	Dip	0.00	÷.
Intermed.	18014	.30 🗘	Dip Azimuth	0.00	Û
<u>M</u> inimum	925.60	0	Pitch	90.00	÷

Nearest Neighbour uses an astral search algorithm to determine what point is considered the nearest. Leapfrog Works includes support for anisotropy when determining what is considered the 'nearest' value. Adjust the **Ellipsoid Ranges** and **Directions** to describe the anisotropic trend.

Click **View Ellipsoid** to see an ellipsoid widget in the scene that helps to visualise the anisotropic trend.

In the **Value Clipping** tab, you can enable value clipping by ticking the **Clip input values** box. This caps values outside of the range set by the **Lower bound** and **Upper bound** to the bounding values.

In the **Outputs** tab, you can specify attributes that will be calculated when the estimator is evaluated on a block model. **Value** and **Status** attributes will always be calculated, but you can choose additional attributes that are useful to you when validating the output and reporting. These attributes are:

- The number of samples (**NS**) is the number of samples in the search space neighbourhood.
- The distance to the closest sample (**MinD**) is a cartesian (isotropic) distance rather than the ellipsoid distance.
- The average distance to sample (**AvgD**) is the average distance using cartesian (isotropic) distances rather than ellipsoid distances.

Kriging Estimators

Kriging is a well-accepted method of interpolating estimates for unknown points between measured data. Instead of the simplistic inverse distance and nearest neighbour estimates, covariances and a Gaussian process are used to produce the prediction.

To create a Kriging estimator, right-click on the **Estimators** folder and select **New Kriging Estimator**. The **New Kriging** window will appear:

Wew Kriging - Kr, Total_Conc in Unconsolidated Sediments	×
Value Clipping Interpolant Ellipsoid Search Outputs	
Kriging Options	
Kriging type: Ordinary ~	
Mean <u>v</u> alue: 0.00000	
Discretisation: X: 1 0 Y: 1 0 Z: 1 0 (point kriging)
Search ellipsoid: Maj = 18014.3; Semi-maj = 18014.3; Minor = 925.6	
Variogram Model 🖉 Total_Conc in Unconsolidated Sediment 🗸 View	
Normalised Variogram for Single Structure	
Name: Kr, Total_Conc in Unconsolidated Sediments	
? <u>Cancel QK</u>	

In the Interpolant tab:

- Both Ordinary and Simple Kriging are supported.
- For Simple Kriging, specify a Mean value for the local mean to use in the Kriging function.
- **Discretisation** sets the number of discretisation points in the X, Y and Z directions for block Kriging. Block Kriging provides a means of estimating the best value for a block instead of only at the centre of the block. Each block is broken down (discretised) into a number of sub-units without actually sub-blocking the blocks. A geologist will consider a variety of factors including spatial continuity when deciding on the discretisation to use. Set the X, Y and Z parameters to 1 for point Kriging. To use additional discretisations, copy the estimator and change the **Discretisation** parameters.
- Search Ellipsoid identifies the Max, Int and Min ranges set in the Ellipsoid tab.
- Select from the Variogram Model list of models defined in the Spatial Models folder.
- The **View** button will show an ellipsoid widget in the scene to assist in visualising the variogram model ranges and direction.
- A chart depicts colour-coded semi-variograms for the variogram model.

If you select a Kriging estimator to be evaluated onto points, it will always use Point Kriging (Block Kriging with a discretisation of 1x1x1), overriding any discretisation settings specified for the Kriging estimator.

In the **Ellipsoid** tab:

- The Ellipsoid Definition sets the Ellipsoid Ranges and Direction.
- Click the **View Ellipsoid** definition to show an ellipsoid widget in the scene to assist in visualising the search ellipsoid. Note that this is not the same as the variogram model ellipsoid, unless the **Set to** option is used to select the variogram model to copy the details.

lue Clipping	Interpolant	Ellipsoid	Search	Outputs	
llipsoid Definitio	n				
Ellipsoid range	es		Directions		
Ma <u>x</u> imum	18014.30	÷	Dip	0.00	$\hat{\mathbf{x}}$
Intermed.	18014.30	÷	Dip Azimuth	0.00	Ŷ
<u>M</u> inimum	925.60	÷	Pitch	90.00	Ŷ
View Ellip		Set From		<u>S</u> et to	~

In the **Search** tab the **Minimum Samples** and **Maximum Samples** parameters determine the number of samples required or used within the search neighbourhood.

Value Clipping	Interpolant	Ellipsoid	Search	Outputs	
Search Definit	tion				
Minimum sa	mples: 4	0 N	laximum sar	mples: 255	÷

In the **Value Clipping** tab, you can enable value clipping by ticking the **Clip input values** box. This caps values outside of the range set by the **Lower bound** and **Upper bound** to the bounding values.

Kriging Attributes


In the **Outputs** tab, you can specify attributes that will be calculated when the estimator is evaluated on a block model. **Value** and **Status** attributes will always be calculated, but you can choose additional attributes that are useful to you when validating the output and reporting. These attributes are organised into two categories, **Sample properties** and **Estimation results**.

Sample properties are output attributes that relate to data sample statistics:

- The number of samples (**NS**) is the number of samples in the search space neighbourhood.
- The distance to the closest sample (**MinD**) is a cartesian (isotropic) distance rather than the ellipsoid distance.
- The average distance to sample (**AvgD**) is the average distance using cartesian (isotropic) distances rather than ellipsoid distances.
- The number of duplicates deleted (**ND**) indicates how many duplicate sample values were detected and deleted by the estimator.

Estimation results are additional information produced by the estimation:

- Value will always be included as it is the actual estimate result.
- Status will always be included as it classifies the estimation result as a **Normal** result, or non-normal **Blank**, **Without-value**, **Outside** or **Error** result.
- The Kriging mean (**KM**) is the local mean used for the estimate based around the selected sample data. For simple Kriging, this is the specified global mean. For ordinary Kriging, it is the unknown locally constant mean that is assumed when forming the Kriging equations. This value is only dependent on the covariance function and the sample locations and values for the chosen neighbourhood. It does not depend on the evaluation volume and therefore will be the same for block Kriging and point Kriging. It can give some indication of suitability of the assumptions when doing ordinary Kriging.
- The Kriging variance (**KV**) is important in assessing the quality of an estimate. It grows when the covariance between the samples and the point to estimate decreases. This means that when the samples are further away from the evaluation point, the quality of the estimation decreases. For simple Kriging, the value is capped by the value of the covariance between the target volume and itself. For ordinary Kriging, higher values indicate a poor value.
- The Kriging efficiency (**KE**) is calculated based on the block variance and Kriging variance (**KV**). It should be 1 when the Kriging variance is at is minimum and 0 when the Kriging variance equals the block variance.
- The slope of regression (**SoR**) is the slope of a linear regression of the actual value, knowing the estimated value. For simple Kriging it is 1 and for ordinary Kriging a value of 1 is desired as it indicates that the resulting estimate is conditionally unbiased. Conditional bias is to be avoided as it increases the chance that blocks will be misclassified when considering a cutoff value.
- The sum of weights (**Sum**) is the sum of the Kriging weights. For ordinary Kriging, the sum is constrained to being equal to 1.
- The sum of negative weights (**SumN**) can be used to assess the quality of an estimation. Negative weights are to be avoided or at least minimised. If there are negative weights, it is possible that the estimated value may be outside the range of the sample values. If the sum of negative weights is significantly large (when compared to the total sum), then it could result in a poorly estimated value, depending on the sample values.



When selecting the block model evaluation to display in the 3D scene, you can select either the Kriging values, or from these additional selected attributes.

0	Block Model	\times	🏫 Kr 🗸	Total_Conc	\sim	-•				۲	Block Mod	del					
			🔶 Flat co	lour													~
			EVALUA	TIONS													~
			i Domain	Model			Status										6
			Ceology 🔞	Model			Status										· · ·
			i Water T	able			Status										
			🚈 Kr, Total	LConc in Unconso	idated	Sediments	s Status	NS	MinD	AvgD	KM, KV	SoR	KE	Sum	SumN	ND	
			CALCUI	ATIONS							63						

RBF Estimators

The RBF estimator brings the Radial Basis Function used elsewhere in Leapfrog into estimation. Like Kriging, RBF does not use an overly-simplified method for estimating unknown points, but produces a function that models the known data and can provide an estimate for any unknown point. Where Kriging is limited to a local search neighbourhood, RBF utilises a global neighbourhood. An RBF estimator is good for grade control where there is a large amount of data.

To create an RBF estimator, right-click on the **Estimators** folder and select **New RBF Estimator**. The **New RBF** window will appear:

	Interpolant	Outputs			
) <u>V</u> ariogram m	odel: 🔗 Tota	al_Conc in Unconsol	lidated Sedim	ents: Single Struct	ture 🗸 View
⊖ St <u>r</u> uctural tre	nd:				~
Ou <u>t</u> side value:	0		Variance:	13.6	
Mod <u>e</u> l:	Spheroidal		Alp <u>h</u> a:	3	
Nugget:	0.0		Total <u>s</u> ill:	2000.0	
Range:	9007.0				
1.50 - 1.25 - 1.26 - 1.00 - 1.00 - 1.00 - 1.00 - 1.00 -	Minor 1 1 1	Semi-n			
		1000	1500 stance	2000	
L25 - 1.25 - 1.00 - 1.00 - 0.75 - 0.00 - 0.25 - 0.00 - 0 0 0 0 0 0 0 0 0 0 0 0 0		1000 Dis	1500 stance		
L25 - 1.25 - 1.00 - 1.00 - 0.05 - 0.25 - 0.00 -	rs Specified	1000 Dis	1500	0.08	
L25 - 1.25 - 1.00 - 1.00 - 0.75 - 0.00 - 0.25 - 0.00 - 0 0 0 0 0 0 0 0 0 0 0 0 0		1000 Dis	1500 stance		

Like other estimators, a spatial model defined outside the estimator as a separate **Variogram Model** can be selected. The **View** button will show an ellipsoid widget in the scene to assist in visualising the variogram model ranges and direction.

Alternatively, in a feature unique to RBF estimators, a **Structural trend** can be used, if one is available in the project. Set the **Outside value** at the long-range mean value of the data.

Otherwise, the RBF estimator behaves very similarly to the RBF interpolant in Leapfrog.

Drift is used to specify what the estimates should trend toward as distance increases away from data. The RBF estimator has different **Drift** options from the non-estimation RBF interpolants. The RBF estimator function offers the **Drift** options **Specified** and **Automatic**. When selecting **Specified**, provide a **Mean Value** for the trend away from data. **Automatic** is equivalent to the **Constant** option offered by non-estimation RBF interpolants, and **Linear** is not supported. **Specified** drift with a **Mean Value** of 0 is equivalent to **None**.

In the **Value Clipping** tab, you can enable value clipping by ticking the **Clip input values** box. This caps values outside of the range set by the **Lower bound** and **Upper bound** to the bounding values.

In the **Outputs** tab, the **Minimum** and **MaximumEvaluation Limits** constrain the values. Values outside the limits are set to either the minimum or maximum limit, as appropriate. To enable a limit, tick the checkbox and set a limit value.

In the **Outputs** tab, you can also define isosurfaces for an RBF estimator:


- The **Default resolution** will be used for all isosurfaces, unless you change the **Surface Resolution** setting for an individual isosurface. See <u>Surface Resolution in Leapfrog Works</u> for more information on the **Adaptive** setting. The resolution can be changed once the estimator has been created, so setting a value in the **New RBF** window is not vital. A lower value will produce more detail, but calculations will take longer.
- The Volumes enclose option determines whether the volumes enclose Higher Values, Lower Values or Intervals. Again, this option can be changed once the estimator has been created.
- Click the **Restore Defaults** button to add a set of isosurfaces based on the estimator's input data.
- Use the Add to add a new isosurface, then set its Iso Value.
- Click on a surface and then on the **Remove** button to delete any surface you do not wish to generate.

8	New RBF - RBF,	Total_Conc in Unco	onsolidated Sedim	ients			×
	Value Clipping	Interpolant	Outputs				
	Evaluation lim	nits					
	✓ Minim <u>u</u> m	n: 0.0	÷				
	Ma <u>x</u> imur	n: 12.3728616	95074636 🔅				
	Isosurfaces			Volumes			
	<u>D</u> efault reso	lution: 270.00	0 Adaptive	Enclose:	Intervals	\sim	
	Exac <u>t</u> clip	oping					
	Iso Value	Surface Resoluti	on		< 2.0		
	2.0	270 (default)			2.0 - 11.0		
	11.0	270 (default)			11.0 - 50.0		
	50.0	270 (default)			> 50.0		
	\oplus \bigcirc	R	estore <u>D</u> efaults]			
N	lame: RBF, To	tal_Conc in Uncor	nsolidated Sedime	ents			
	3				Cancel	04	
(<i>•</i>				<u>C</u> ancel	<u>0</u> K	

Variable Orientations

The features described in this topic are only available if you have the Contaminants extension.

The principal direction of contamination can change across a domain, such as when the domain features an undulating, gently-folded structure. Using a single fixed orientation for the sample search and the variogram can result in poor sample selection and weighting locally. Using a variable orientation makes it possible to re-orient the search and variogram according to local characteristics, which results in improved local value estimates. For example, here a variable orientation has been created using a mesh; disks indicate the local search space orientation and are coloured with the dip direction.



Variable orientations can have multiple inputs, including veins, the contact surfaces in a stratigraphic sequence and any mesh in the project.

A variable orientation can be applied to Kriging and inverse distance estimators. You can make as many variable orientations as you wish for each domained estimation, which allows you to experiment with a wide variety of scenarios.

Variable orientations cannot be used with RBF estimators. To achieve a similar capability for RBF estimators, use a structural trend.

The rest of this topic describes how to create and work with variable orientations. It is divided into:

- Visualisation Options for Variable Orientations
- Creating Variable Orientations
- The Variable Orientation in the Project Tree
- Applying a Variable Orientation
- Exporting Rotations


Visualisation Options for Variable Orientations

Variable orientations can be viewed as disks or lines. The grid used for visualisation can be any block model or sub-blocked model in the project or a custom grid can be specified as part of setting up the variable orientation.

Here a variable orientation is visualised on a custom grid, with disks coloured using the **Dip direction** values at each point on the grid. Enabling text display (A) shows the values in the scene. The disks are a representation of the local orientation of the maximum-intermediate plane calculated at the chosen centroids. They represent both the search ellipsoid and the variogram, by indicating their principal plane. The line on each disk indicates the position and direction of the major axis.

Search ellipsoids are described using axes of maximum, intermediate and minimum continuity.

Variogram ellipsoids are described using major, semi-major and minor axes. Because both the local search ellipsoid and local variogram orientation are indicated by variable orientation disk and line objects in the scene, we will avoid potential confusion by using the terms maximum, intermediate and minimum in this topic, unless specifically discussing variograms.




Click on a disk to view further information about it.

There is also the **Show as lines** option (\mathscr{P}), which hides the disks to reduce visual clutter while still showing the fundamental orientation information in the form of the maximum axis direction for each search space local to each centroid:



You can also change the **Anisotropy** used to display the variable orientation. Options are **Isotropic** and any variogram models and search spaces defined in the estimation:



When anisotropy is displayed, the ratio of the maximum-intermediate axis of the chosen object is indicated as a ratio. The actual range is not shown.

Creating Variable Orientations

Variable orientations are created on a per-contaminant estimation basis. You can copy variable orientations and make adjustments to them, but you cannot copy them to another contaminant estimation.

To create a variable orientation, right-click on the domained estimation's **Variable Orientation** folder and select **New Variable Orientation**. **Inputs** and the **Global Plunge** are set in the **General** tab, and how the variable orientation will be displayed is set up in the **Visualisation** tab.


	ion			
Inputs:				
$(+)$ \sim $(-)$				
\odot \bigcirc				
Global Plunge:				
0	🔗 Total	_Conc_Unconso	lid ∨	View
Global Plunge: <u>V</u> ariogram model	⊘ Total Azimuth:	_Conc_Unconso		
Global Plunge:			lid ∨ Set From	

Selecting the Inputs

Inputs to a variable orientation can include veins, a stratigraphic sequence and any mesh in the project. When a mesh is used, it should be an open mesh that draws out the shape of the undulations of the structure, rather than a closed mesh such as the domain. The facing direction of the surface is relevant; it is used to determine the direction of the surface normal vectors. Each vertex of the mesh is used to generate the orientation, so the resolution of the mesh should be sufficient to capture subtle changes in trend without adversely increasing processing time.


Using closed meshes such as the mesh of the domain used in the estimation is not advised. Doing so may result in boundary effects and inconsistent vector orientations, and the vector may become undefined in the middle of a mesh if components interpolate to zero.

At each vertex of the input mesh, a normal unit vector is calculated from the average orientation of the faces that meet at that vertex. This normal vector is then resolved into three orthogonal component vectors, Δ_x , Δ_y and Δ_z . Take a close look at this slice of an undulating part of a hangingwall mesh shaded according to the face dip:




In the above image, the component vectors have been added as explanatory annotations; these are not part of the scene.


Three radial basis functions are then created, one for each of the three orthogonal component vectors. These RBFs use a biharmonic splice basis function of degree zero and 'reduce' fit type. Accuracy is set at 1%. These parameters are fixed and cannot be customised or controlled.



Now that RBFs have been created and we have a continuous function throughout the space of interest, the component vectors for any point in space can be determined, not just at the vertices in the mesh. From the component vectors, the normal vectors can be constructed at any point in space, again, not just at the vertices in the mesh.



When a normal is reconstructed at any given point in the model, this defines the minimum axis, and, implicitly, the orientation of the principal plane that the maximum and intermediate axes lie on orthogonal to the minimum axis.



Note that although radial basis functions are used in this process to create functions that allow for the determination of normals at any point in space, a variable orientation is not available for use with RBF estimators; it is limited to Kriging and inverse distance estimators. To achieve a similar capability for RBF estimators, use a structural trend.

An important consideration in achieving a reasonable result is inputs that have consistently oriented normals on the mesh used at the start of this process.

- When multiple meshes are used, you need to ensure that the meshes are consistently oriented.
- Veins and stratigraphic sequences are made up of multiple surfaces, and the normals for these surfaces are combined into a single cloud of normal vectors.
 - When a vein is used as an input, the hangingwall and footwall surfaces are used. To make normal directions consistent, the hangingwall normals are flipped to point in the same direction as the footwall normals. Common vertices in the footwall and hangingwall, where the vein pinches out,

produce duplicate locations with slightly different normals. The two normals at these locations are averaged to give a single normal vector for that location.

• When a stratigraphic sequence is used, each point of each contact surface produces a normal vector.

Closed surfaces have a consistent inside and outside direction. Normals on a closed surface will therefore point either inwards or outwards, resulting in the normals on the opposite side of the mesh pointing in the opposing direction. Interpolating these conflicting normals will lead to sudden unpredictable changes in orientation.

Setting the Global Plunge


Next, the **Global Plunge** is used to determine the direction of the principal axis on the principal plane. The **Global Plunge** is a vector defined by either the major axis of the global variogram or globally defined search, or it is set from the view. This vector is used to determine where the direction of the principal axis should lie within the direction of the locally re-oriented principal plane. This is achieved by finding the direction on the local plane that is closest in orientation to the global vector. In practise this amounts to projecting the shadow of the global plunge vector, in the direction of the local normal vector, onto the re-oriented local plane.

You have two choices for the Global Plunge:


- Use one of the variogram models defined for the contaminant estimation. Select one from the dropdown list.
- Set a **Custom Direction**. Click and drag in the scene to align the view to the direction of the perceived maximum continuity, then click **Set From Viewer**. Capture the current scene to bookmark the direction you have set, as the **Custom Direction** cannot be visualised in the scene.

The projected **Global Plunge** is represented by the black pitch line on each of the variable orientation disks. Visually validate the disk's pitch lines to confirm that the **Global Plunge** has been applied in the manner you expect.

The **Global Plunge** is projected onto the principal plane to define the direction of the principal axis. Imagine a flashlight shining down the normal vector towards the principal plane and shining through a variogram model ellipsoid. The shadow cast by the major axis defines the principal direction.



The intermediate axis will lie on the principal plane at 90° to the principal direction axis. Together the normal vector, the principal direction and the intermediate axis orthogonal to them define the orientation for the minimum, maximum and intermediate axes for use at each point required for estimation, reorienting the search and variogram for that specific location in space. These directions are determined for each required location.



When visualised as lines, only the principal direction is shown, pointing away from the reference point. When visualised as disks, a circular disk is added to indicate the principal plane.


If the **Custom Direction** is left at the default settings of **Azimuth** = 0 and **Plunge** = 0, this will be the vector that is projected onto the principal plane. The resulting reorientation of the search space and variogram will likely be inappropriate, particularly for steeply oriented veins. Leapfrog Works relies upon the expertise of an informed expert to specify a reasonable and valid direction instead of defaulting to a best-guess that may appear meaningful at a cursory glance but may be just as invalid as the more obvious zero values chosen as defaults.

Setting Visualisation Options

In the **Visualisation** tab, you can choose between visualising the variable orientation on an existing block model or on a custom grid.

Using a block model or sub-blocked model for visualisation does not evaluate the variable orientation on the selected model. All block models and sub-blocked models in the project can be selected.


Here a variable orientation created from a mesh is visualised on a Custom Grid:



See <u>Visualisation Options for Variable Orientations</u> for more information on displaying the variable orientation.

The Variable Orientation in the Project Tree

Enter a name for the variable orientation and click **OK** to create it. It will be added to the project tree in the **Variable Orientation** folder. Expand it to see its parts:



The variable orientation includes links to the variogram model, if used, and to the inputs.

Drag the variable orientation into the scene to check it, and double-click on the variable orientation in the tree to edit it.

You can make multiple copies of a variable orientation, but you cannot copy them to another contaminant estimation.

Applying a Variable Orientation

Leapfrog Works supports variable orientations in Kriging and inverse distance estimators. Double-click on the estimator, then click on its **Ellipsoid** tab. Tick the box for **Variable Orientation** and select from those available for the contaminant estimation:

Value Clipping	Interpolant	Ellipsoid	Search	Outputs
Ellipsoid Definit	•			
-				
Ellipsoid ran	-		Directions	
Ma <u>x</u> imum	10000.00	÷	Dip	2.00
Intermed.	10000.00	$\hat{}$	Dip Azimuth	266.30
Minimum	1020.00	÷	Pitch	88.00
S Varia	entation ble Orientation ble Orientation ble Orientation o	n BN		~
S Varia	ble Orientation ble Orientation			~

When a variable orientation is applied to an estimator, the local search can be visualised using the block model interrogation tool.

Here one block in a block model is shown with the search area indicated by the ellipsoid widget. The orientation of the ellipsoid reflects the direction set by variable orientation for this block:


	× .							
🌧 Block Model				-				
Block index	64, 28, 11 (xyz)					/	The second se	
Block centroid	-7856220.0000, 5082200.0000, 20.0000							
Domain Model	Un snsolidated Sediments			2		4	\geq	
Geology Model	Till						\geq	
Water Table	Saturated					1		
Kr, Total_Conc in Unconsolidated Sediments	Without-value			-				
Variable Orientation	241.956				the second s			
Rot1Z	241.956							
Rot2X	25.0769							
Rot3Z	112.371							
Sinterrogate Estim	nator							
Add Comments								
Ø 🖉 Variable	Orientation	×	2 Dip directio	~	Dip direction	~	•	ØA
 Block Mo 			-			~		
BIOCK MO	luel	×	🚖 Kr, Total	~	Total_Conc	~		
🔘 🛛 🌖 Kr, Total_	Conc iediments: Search	×	À Flat colour	~				
Selected	block - Block Model	×	췆 Flat colour	~				

See Block Estimate Interrogation for more information on the interrogation tool.


Exporting Rotations

When a variable orientation is evaluated onto a block model or sub-blocked model, the **Dip Direction** and **Dip** in the variable orientation are represented in the rotation using the ZXZ convention. **Rot1Z** is

the value of the rotation about the z axis. This turns y into y' and x into x', which is equivalent to the **Dip Direction** in the variable orientation:



Rot2X is the value of the rotation about the x' axis and is equivalent to Dip:



When a variable orientation is evaluated onto a block model, you can click on a block to view the rotation information:

🌒 Block Model	
Block index	64,31,3 (xyz)
Block centroid	-7856220.0000, 5082440.0000, 180.0000
Domain Model	Unconsolidated Sediments
Geology Model	Outwash and local ice-contact deposit
Water Table	Vadose
Kr, Total_Conc in Unconsolidated Sediments	Without-value
Variable Orientation	302.134
Rot1Z	302.134
Rot2X	4.2808
Rot3Z	54.3351
😽 Interrogate Estim	nator
↓ Add <u>C</u> omments	

If required, you can export the rotations for use in other packages. When exporting the block model, be sure to select the variable orientation evaluation:

Export - Block Model	×
Select Items	uid he sussed of
Which evaluations, calculations, and filters sho	uia be exportea?
Available items:	Selected items:
😭 Domain Model	Variable Orientation
Call Geology Model	Variable Orientation Rot1Z
Kr, Total_Conc in Unconsolidated Se	& Rot2X
	😪 Rot3Z
	>
	<
Select <u>A</u> ll <u>S</u> elect None	
? <u>Cancel</u>	Back Next

Block Models

The features described in this topic are only available if you have the Contaminants extension.

This topic describes importing block models in Isatis and CSV formats, creating block models in Leapfrog Works, viewing block model statistics and exporting block models. It is divided into:

- Importing a Block Model
- Creating a Block Model
- Displaying a Block Model
- <u>Viewing Block Model Statistics</u>
- Exporting Block Models

Importing a Block Model

Leapfrog Works imports block models in the following formats:

- CSV + Text Header (*.csv, *.csv.txt)
- CSV with Embedded Header (*.csv)

Note that neither CSV format requires a header; once you start the import process, Leapfrog Works will use the data in the file to locate the minimum and maximum centroids. You can view this information and change how the data is mapped before the file is saved into the project.

Block models imported in CSV format must be regular, rotated only about the Z axis. You will also need to map the data in the file to the block model format Leapfrog Works expects.

To import a block model in CSV format, right-click on the **Block Models** folder and select **Import Block Model**. Select the file you wish to import and click **Open**. An import window will be displayed in which you can map the columns in the file to those Leapfrog Works expects. Once you have mapped the required columns, click **Next** to define the grid. In the next window, Leapfrog Works uses the data in the file to check the grid definition and confirm that the centroids match. The **Values to enter** list gives you different options for mapping the data in the file, and you can preview the file data and use it to choose the best option.

45 Import - Block Model - Grid							
Import Block Model: Select Columns > Define Grid Yalues to enter: Actimut Block size Size in blocks Minimum corner Block size Size in blocks Minimum corner Block size Block s	[Minim	Triple click w Block Model ing box of centroids i num: 10591.8746	n the file: 100617.6985 216.82	del.csv.txt ×	on the le	ft.
Block size Block size Block size Block size Maximum corner Maximum centroid		Maxin	num: 10851.8746	100917.6985 586.8 X Centre ~		✓ Z Cen	ntre
	<	1 2 3 4 5 6 7 8 9	ld 2845 2876 2907 3930 3961 3992 4023 4024	X 10811.8746 10811.8746 10811.8746 10811.8746 10811.8746 10811.8746 10811.8746 10811.8746	Y 100807.6985 100817.6985 100827.6985 100807.6985 100817.6985 100827.6985 100837.6985	Z 216.8 216.8 226.8 226.8 226.8 226.8 226.8 226.8 226.8	8203 8203 8203 8203 8203 8203 8203
None of the centroids in the file match the grid you've defined. Name: Imported Block Model		10 11 12 13	4054 4055 4117 4148	10811.8746 10821.8746 10821.8746 10821.8746	100847.6985 100847.6985 100867.6985 100877.6985	226.8 226.8 226.8 226.8	8203 8203
Cancel Previous Einish		-14	5015	10011 0746	100007 6005	9 4 6 0	0000

The easiest way to define the blocks is to use the **Block size, Minimum centroid, Maximum centroid** option. In defining the grid, you can select information in the file and drag it to the corresponding values on the left-hand side:

port Block Model: Select	Columns > Define Grid					View F	ile You can se Triple click	ect text below, the will select a whole	en dra e line.	ag it to the control	s on t	the left.
(alues to enter: 🔡 Bloc	k size 🔒 Minimum o	entroid 📑 M	aximum centroid	~		CSV da	ta Block Mode	l.csv 🗙 Bloc	k Moo	iel.csv.txt 🗙		
Azimuth:	0.00 🗘 degrees					Boundi	ng box of centroids	in the file:				
Block size:	100.00 0	00.00	100.00	0		Minim Maxin	um: 10591.8746 1um: 10851.8746	100617.6985 2 100917.6985 5				
Minimum centroid:	444750.00 0 49	92850.00	2340.00									
Maximum centroid:	446650.00 0 49		591.8746 100617.	6985 216.820	73							
Size in blocks:	20 × 20 × 10 = 4,000							X Centre	~	Y Centre		Z Centre
						1	Id	Х		Y		Z
						2	2845	10811.8746		100807.6985		216.8203
					<	3	2876	10811.8746		100817.6985		216.8203
						4	2907	10811.8746		100827.6985		216.8203
						5	3930	10811.8746		100807.6985		226.8203
						6	3961	10811.8746		100817.6985		226.8203
						7	3992	10811.8746		100827.6985		226.8203
						8	4023	10811.8746		100837.6985		226.8203
						9	4024	10821.8746		100837.6985		226.8203
						10	4054	10811.8746		100847.6985		226.8203
	as in the file match the grid y	rou ve denned.				11	4055	10821.8746		100847.6985		226.8203
None of the centroi						12	4117	10821.8746		100867.6985		226.8203
•	Aodel											
•	Nodel					13	4148	10821.8746		100877.6985		226.8203

You can also enter the grid definition values manually.

Once the grid has been defined, Leapfrog Works will display a message indicating that the data in the file matches the grid definition:

nport - wp_block_model	Grid								— D
ort Block Model: Selec	t Columns > Define Grid					View File	You can select to Triple click will s	ext below, then drag it to th elect a whole line.	e controls on the left.
alues to enter: 🔡 Blo	ick size 🔛 Size in	blocks 🔛	Minimum corner	~		CSV data	wp_block_model.	csv × wp_block_mod	el.csv.txt ×
Azimuth:	330.43 🗘 degre	es				Bounding b	ox of centroids in th	e file:	
Block size:	10.00 0	20.00	15.00	0			443984.45130147.	226 492336.5199670386 59 495278.1520789807	
Size in blocks:	160 0	125	94	0		maximani	440071.20000774		2305.4520000000
Minimum corner:	445208.884 0	492325.355	1952.932	0					
Total blocks:	1,880,000						ld ~	X Centre ~	Y Centre
						1	ld	x	Y
						2	0	445208.2979018642	492336.51996703
					<	3	1	445216.9954362408	492341.4548323
						4	2	445225.6929706174	492346.38969768
						5	3	445234.390504994	492351.3245630
						6	4	445243.0880393706	492356 2594283
						7	5	445251.7855737472	
						7 8	5	445251.7855737472 445260.4831081239	492361.1942936
									492361.1942936 492366.1291589
						8	6	445260.4831081239	492361.1942936 492366.1291589 492371.0640243
(i) All the centroids in	the file match the grid y	pu've defined.				8	6 7	445260.4831081239 445269.1806425005	492361.19429363 492366.1291589 492371.06402433 492375.99888963
•		ou've defined.				8 9 10	6 7 8	445260.4831081239 445269.1806425005 445277.8781768771	492361.19429365 492366.12915898 492371.06402430 492375.99888965 492380.93375498
•		ou've defined.				8 9 10 11	6 7 8 9	445260.4831081239 445269.1806425005 445277.8781768771 445286.5757112537	492361.19429365 492366.12915896 492371.06402433 492375.99888963 492380.93375495 492385.86862026 492390.80348560

Click Finish. The block model will be imported and will appear in the Block Models folder.

Creating a Block Model

To create a new block model, right-click on the **Block Models** folder and select **New Block Model**. The **New Block Model** window will appear, together with a set of controls that will help you set the size, location and orientation of the model in the scene:

Kew Block Model Grid Evaluations				>		North (Y)	t		~	
Blocks: Bloc <u>k</u> size:	X 100 \$	Y 100 \$	Z 100	Ĵ		+495800				
Extents						+494000				
Base point:	442897.6746819798 🗘	491185.2473481679 🗘	3700.00	¢	-					▶
Boundary size:	4700.00 🗘	4700.00 🗘	1700.00	¢		+495000				
Azimuth:	0.00 [^] degrees		Enclose Obje	ect 🗸						
Size in blocks:	47 × 47 × 17 = 37,553					492000 5	+445900	- Lo	ooking down	East (X)
Name: Block Model						0	1250	2500	3750	5000
?		Cance	91	<u>о</u> к	No Selec	etion				

The block model is defined from its **Base point**, and the reference centroid is the **Base point** plus one half the **Block size**. Block models cannot have partial blocks, and when changes are made to the **Block size** parameter, the model's extents will be enlarged to match the **Block size**.

If you know the values you wish to use for the model's **Extents**, enter them in **New Block Model** window. You can also:

- Use the controls in the scene to set the extents.
 - The orange handle sets the **Base point**.
 - The red handles adjusts the size of the boundary.
 - The blue handle adjusts the **Azimuth**.
- Use another object's extents. Select the object from the **Enclose Object** list.


It is a good idea to use larger values for the **Block size** as processing time for large models can be considerable. Once you have created a block model, you can change its properties to provide more detail.

You can also evaluate the block model against geological models, interpolants and distance functions in the project. To do this, click on the **Evaluations** tab. All objects available in the project will be displayed. Move the models you wish to use into the **Selected** list.

Enter a **Name** for the block model and click **OK**. The model will appear under the **Block Models** folder. You can make changes to it by double-clicking on it.

Displaying a Block Model

When a block model is displayed in the scene, there is an **Index Filter** option for displaying the grid:



The Index Filter can be set to Subset or Sliced.

- Subset shows the union of the selected X, Y and Z ranges.
- Sliced shows the intersection of the selected X, Y and Z ranges.

The range sliders have two modes: coarse control and fine control. Here an index filter is used for a set of values that ranges from 1 to 160; it is displayed in dark blue, to show the full range of values in coarse control mode:




You can restrict the data displayed by dragging on the handles. Here the range of values is restricted to 1 to 50:



You can click and drag on the selected range to change the values displayed:

52 - 101	
	\bigcirc

To switch to fine control, double-click anywhere along the range slider. Here the range of 52-101 has been expanded along the whole slider, giving you more control over the position of the range end points:




The slider is displayed in light blue in fine control mode.

Now you can use the handles to further restrict the range displayed:




Right-click on the slider to return to coarse control and the full range of values. Here, right-clicking reverts to coarse control, with the range restricted to the original range of 52-101:



Viewing Block Model Statistics

To view statistics on a block model, right-click on the model in the project tree and select **Statistics**. The following options are available:



See the <u>Analysing Data</u> topic for more information on each option:

- Table of Statistics
- Scatter Plots

- Q-Q Plots
- Box Plots

Right-clicking a block model evaluation or a numeric calculation and selecting **Statistics** opens a univariate graph for the selection. See <u>Univariate Graphs</u> in the <u>Analysing Data</u> topic for more information.

Table of Statistics

You can view statistics for all evaluations and calculations made on a block model broken down into categories and organised by numeric evaluations and calculations. To view statistics, right-click on a block model in the project tree, select **Statistics** then select the **Table of Statistics** option.

You can view statistics for as many numeric and category columns as you wish. When you have at least one **Category column** selected, you can organise the information displayed in two ways: **Group by Category** or **Group by Numeric**. Here, statistics are displayed organised by the category data columns:

Statistic	Statistics: Block Model ×								
	⊗ ጵ 🔇								
Query filter:	Processable Ore 🗸	Nam	ne v	Block Count	Volume	Mass	Mean	Std. dev.	Coeff. var.
Statistics weighting:	Un-weighted ~	\sim	Indicated	712	712,000.0	1,780,000.0			
			🔚 Declustering	712	712,000.0	1,780,000.0	50.044	8.265	0.165
Density:	Constant v 2.5 🗘		🎽 ID, Zn_pc in GM: LMS1	708	708,000.0	1,770,000.0	10.647	2.717	0.255
 Group by category Group by numeric ite 	em		🕌 NN, Zn_pc in GM: LMS1	708	708,000.0	1,770,000.0	10.704	4.326	0.404
Categories:			🚈 OK Kr, Zn_pc in GM: LMS1: 4x4x4	708	708,000.0	1,770,000.0	10.586	2.614	0.247
Level 1: 🚺 Class	s V Indicated, Isured, Waste		👰 RBF, Zn_pc in GM: LMS1	712	712,000.0	1,780,000.0	9.550	3.092	0.324
		\sim	Inferred	434	434,000.0	1,085,000.0			
			🔚 Declustering	434	434,000.0	1,085,000.0	26.235	8.220	0.313
			🎽 ID, Zn_pc in GM: LMS1	403	403,000.0	1,007,500.0	10.295	2.870	0.279
			🕌 NN, Zn_pc in GM: LMS1	406	406,000.0	1,015,000.0	10.393	4.274	0.411
\oplus \ominus			🚈 OK Kr, Zn_pc in GM: LMS1: 4x4x4	406	406,000.0	1,015,000.0	10.184	2.716	0.267
Hide empty categori	es		👰 RBF, Zn_pc in GM: LMS1	434	434,000.0	1,085,000.0	8.067	3.008	0.373
Hide inactive rows		\sim	Measured	607	607,000.0	1,517,500.0			
Numeric items:			🔚 Declustering	607	607,000.0	1,517,500.0	106.188	37.464	0.353
Declustering			🎽 ID, Zn_pc in GM: LMS1	607	607,000.0	1,517,500.0	12.051	2.667	0.221
☑ <u>➢</u> ID, Zn_pc in G	•		🕌 NN, Zn_pc in GM: LMS1	607	607,000.0	1,517,500.0	12.331	4.231	0.343
NN, Zn_pc in 🛛			🚖 OK Kr, Zn_pc in GM: LMS1: 4x4x4	607	607,000.0	1,517,500.0	12.007	2.588	0.216
🗌 🏫 OK Kr, Zn_pc i			n GM: LMS1 👰 RBF, Zn_pc in GM: LMS1	607	607,000.0	1,517,500.0	11.672	3.114	0.267
	in GM: LMS1: 1x1x1: NS								
	in GM: LMS1: 1x1x1: MinD								
	in GM: LMS1: 1x1x1: AvgD								
	in GM: LMS1: 1x1x1: KM								
	in GM: LMS1: 1x1x1: KV								
Select <u>All</u>	Select None								

The **Query filter** option uses a related filter to constrain the data set to a selected subset.

Statistics can be unweighted, weighted by volume or weighted by tonnage. Select the option you require from the **Statistics weighting** list.

You can also set the **Density** to be a **Constant** value that you specify, or you can use the one of the columns in the table.

The **Categories** list provides category classification options. When selected, the set of statistics measures for each evaluation or numeric calculation will be shown for each category.

You can hide empty categories (those with a count of zero) and inactive rows using the options below the **Categories** list:

Group by	cat <u>eg</u> ory n <u>u</u> meric item	
Level 1:	Class 🗸	Indicated, Isured, Waste/
\oplus (Э	
✓ <u>H</u> ide empt ☐ Hide inact	· · · 🧹	-

Group by category and **Group by numeric column** provide options for the table organisation. You can also change what columns are displayed in the table by clicking the **Edit columns** button (III). This opens a window in which you can select the columns that are displayed in the table:

🖻 🧤 I 🔣 💥 🔦 I 🕐		
Query filter:	Name ~ Block Count	t Volume Mass Mean
Statistics weighting: Un-weighted	V Indicated 712	712,000.0 1,780,000.0
	🖉 Edit Columns 🛛 🕹 🗙	712,000.0 1,780,000.0 50.044
		708,000.0 1,770,000.0 10.647
 Group by category Group by numeric item 	Slock Count	708,000.0 1,770,000.0 10.704
Categories:	O Volume	708,000.0 1,770,000.0 10.586
Level 1: Class V Indicated, Isured, Waste/	Mass	712,000.0 1,780,000.0 9.550
	STATISTICS	434,000.0 1,085,000.0
	Mean	434,000.0 1,085,000.0 26.235
	Standard deviation	403,000.0 1,007,500.0 10.295
	 Coefficient of variation 	406,000.0 1,015,000.0 10.393
(+) $(-)$		406,000.0 1,015,000.0 10.184
✓ Hide empty categories	Ciose	434,000.0 1,085,000.0 8.067
Hide inactive rows		607,000.0 1,517,500.0

Click rows to select them, and select multiple rows by holding down the Shift or Ctrl key while clicking rows. You can then copy rows by clicking the **Copy** button (^(b)), which allows you to copy the selected row(s) or all rows in the table.

The arrow buttons quickly expand (\checkmark) or collapse (\land) rows.

Exporting Block Models

Block models created in Leapfrog Works can be exported in the following formats:

- CSV + Text Header (*.csv, *.csv.txt)
- CSV with Embedded Header (*.csv)
- CSV as points (*.csv)

To export a block model, right-click on the block model in the project tree and select **Export**. You will be prompted to select the file format.

Enter a name and location for the file and click **Save**. Next, you will be able to choose custom settings for the selected format.

The selections you make when you export a block model will be saved. This streamlines the process of subsequent exports of the model.

When you choose to export a block model in CSV format, you must first choose the type of CSV export. Options are:

- With an embedded header file. The block model definition is included at the top of the CSV file.
- With a separate text header. The block model definition is written as a separate text file.
- As points. The CSV file does not include the block sizes and model description.

Click **Next**. The steps that follow are:

- Selecting From Evaluated Items
- Setting Row Filtering Options
- Setting Numeric Precision
- Setting Status Code Text Sequences
- Selecting the Character Set

Selecting From Evaluated Items

Choose which objects will be included in the exported file. The **Available items** list includes all evaluations made onto the model. The order of columns in the exported file will match the order shown in the project tree.

Click Next.

Setting Row Filtering Options

You can use a **Query filter** to filter rows out of the data exported.

This is different from exporting filters as columns, as selected in the previous step.

The second option in this window is useful when all block results are consistently the same non-Normal status. Select from **Error**, **Without value**, **Blank** or **Outside**; all rows that consistently show the selected statuses will not be included in the exported file.

Click Next.

Setting Numeric Precision

There are three encoding options for Numeric Precision:

- The **Double, floating point** option provides precision of 15 to 17 significant decimal places.
- The Single, floating point option provides precision of 6 to 9 significant decimal places.
- The **Custom** option lets you set a specific number of decimal places.

To change either the **Centroid and size precision** and **Column data precision** options, untick the box for **Use default precision** and select the required option.

Click Next.

Setting Status Code Text Sequences

When a block model is exported, non-Normal status codes can be represented in the exported file using custom text sequences.

The **Status Code** sequences are used for category status codes and filter status codes exported as columns. For filter status codes, Boolean value results will show FALSE and TRUE for Normal values or the defined **Status Codes** for non-Normal values.

Numeric Status Codes can be represented using custom text sequences. This is optional; if no separate codes are defined for numeric items, the defined **Status Codes** will be used.

Click Next.

Selecting the Character Set

The selection you make will depend on the target for your exported file. You can choose a character set and see what changes will be made.

Click **Next** to view a summary of the selected options, then click **Export** to save the file.

Visualising Estimators

The features described in this topic are only available if you have the Contaminants extension.

Estimators can be visualised by evaluating them on block models. To evaluate an estimator on a block model, right-click on the block model in the project tree and select **Evaluations**. See <u>Block Models</u> on how to work with the different types of block models available in Leapfrog Works.

Calculations and filters further enhance the visualisation options, adding computational analysis and processing of data capabilities to create new types of data to visualise. To create calculations and filters, right-click on a block model in the project tree and select **Calculations and Filters**. See <u>Defining</u> <u>Calculations and Filters</u> for information on creating filters and building calculations.

When you select **Evaluations**, the block model's main window will be opened with the **Evaluations** tab displayed:

🖉 Block Model - Block Model	x
Grid Evaluations	
Available evaluations:	Selected evaluations:
 Geological Models Contaminant Models Estimation Total_Conc in Unconsolid Variable Orientation Total_Conc_Unconsolidated Variable Orientation Estimators 	 Contaminant Models Estimation Total_Conc in Unconsolidate Variable Orientation Variable Orientation Estimators Kr, Total_Conc in Unc
Name: Block Model	
(?)	<u>C</u> ancel <u>O</u> K

You can add all of, for example, a contaminant estimations estimators to the **Selected evaluations** list by double-clicking on the contaminant estimation itself.

Click **OK** to process the evaluations, which will be added to the block model in the project tree:

✓ □ Contaminant Models
> 🗀 Estimation
V 🗋 Block Models
🗸 🏟 Block Model
EVALUATIONS
> 📬 Domain Model
> 👔 Geology Model
> 🍘 Water Table
> 🚈 Kr, Total_Conc in Unconsolidated Sediments
> 名 Variable Orientation
GRAPHS AND TABLES
🎲 Swath
📩 Report

Display an evaluation by dragging it into the scene or by right-clicking on it in the project tree and selecting **View Object**.

Each evaluation will appear in the list of block model evaluations:

\times	🚖 Kr, Total_Conc \vee 📙 Total_Conc 🛛 🗸	.		\triangleright	88			۲	Block	Model			
	췆 Flat colour												
	EVALUATIONS												
	n Model	Status											
	Ceology Model	Status											
	n 🗃 Water Table	Status											et 🄇
	啥 Kr, Total_Conc in Unconsolidated Sediments _N	Status	NS	MinD	AvgD	KM	KV	SoR	KE	Sum	SumN	ND	
	🛃 Variable Orientation	े Status	Rot1Z	Rot2X	Rot3Z								
	×	Flat colour EVALUATIONS Colour Geology Model Colour Table Colour Table Colour Table Colour Table Colour Colour In Unconsolidated Sediments Colour Co	Flat colour EVALUATIONS Call Domain Model Status Call Geology Model Status Call Water Table Status Mater Table Status Status	Flat colour EVALUATIONS Common Model Status Common Model Status Common Model Status Water Table Status Status Status Status Status Status	Flat colour EVALUATIONS Concern C	Flat colour EVALUATIONS Geology Model Status Geology Model Status Water Table Status Kr, Total_Conc in Unconsolidated Sediments Status	Flat colour EVALUATIONS @ Domain Model Status @ Geology Model Status @ Water Table Status @ Kr, Total_Conc in Unconsolidated Sediments Status Status NS MinD AvgD KM	Flat colour EVALUATIONS Call Domain Model Status Status Status NS MinD AvgD KM KV	Flat colour EVALUATIONS Constant Status Constant Status Constant Status Constant Status Constant Status Status Status Status	Flat colour EVALUATIONS Concerned Status Concerned Status Concerned Status Concerned Status Concerned Status Status Status Status Status Status		Flat colour EVALUATIONS Concerned Status Concerned Status Concerned Status Concerned Status Concerned Status Status Status Status Status Status Status	Flat colour EVALUATIONS EVALUATIONS @ Domain Model @ Domain Model @ Geology Model @ Water Table @ Kr, Total_Conc in Unconsolidated Sediments Status Mater Table Status Mater Table Status

🚖 Kr, Total_Conc ... 🗸 📙 Total_Conc 🗸 💶 🚺 O Block Model 🗐 💮 Block Model À Flat colour EVALUATIONS Carl Domain Model Status @ Geology Model Status et 🔘 📬 Water Table Status network in the second state and the second state in the second state in the second state in the second state in the second state is the second state in the second state is the second state in the second state is the second sta 5 Variable Orientation Status Rot1Z Rot2X Rot3Z

Any Attributes generated along with the estimator can also be displayed evaluated on the blocks:

Validation and Reporting


Leapfrog Works provides tools to validate the contaminant estimation models and report the results. Block estimation interrogation is used to inspect the contaminant estimate results. Swath plots and reports add additional insights and provide the basis for visual assets for inclusion in reporting documents.

The rest of this topic describes these tools. See:

- Block Estimate Interrogation
- Swath Plots
- Reports

Block Estimate Interrogation

It is good practise to check the estimates produced for blocks, inspecting the data used to create the estimate. The block estimate interrogator exposes the data used to produce an estimate. Right-click on a block model in the project tree and select **Interrogate Estimator**.



The **Block Model Interrogation** window will open as a dockable tab, showing the input data used in producing the estimates and other results. Additionally, in the scene view, the block details window will display inside the scene, containing properties for the currently selected block. These are primarily result properties.


Use the filter selector (∇) to see all the **Found** data points in the block estimate interrogator table, or only the data points **Included** in the estimate, or only the data points that are **Clamped**. The **Clamped** option will only be present if **Outlier Restrictions** are being used by the estimator.

You can change the **Estimator** to select between the inverse distance and Kriging estimators evaluated on the block model. Other estimators are not supported by the block model interrogation feature.


Click the **Open Estimator** button to inspect the estimator used in the estimate. This will open in a new window.

View Ellipsoid will display the search ellipsoid in the scene. The axial planes of the ellipsoid are shaded, which helps to visualise the 3-dimensional shape of the ellipsoid as well as it's orientation.

Click a block in the scene or set the **Block Index Definition X**, **Y** and **Z** coordinates to select a specific block.



Enable **Filter block model** to see only the selected block in the scene, which will reduce the visual noise of all the other blocks. This will help you see the associated data points and the search ellipsoid in relation to the selected block:



In the block estimate table, you will see all the input data columns for each data point. Data points can been hidden or made visible in the scene using the visibility button (⁽²⁾).

		😨 LFW Chlorinated Landfill Plume - Leapfrog Works			
	X	Kriging - Block Model Inte ×			
💭 Block Model					
Block index	32, 20, 4 (XYZ)	Filter: Found 🗸 🖻 👔			
Block centroid	-7858780.0000, 5081560.0000, 160.0000		•	Drillhole ID	
Domain Model	Unconsolidated Sediments		-	FE-1DL36B	
Geology Model	Till		۲	FE-1DL39A	
Vater Table	Vadose		\odot	FE-1DL38Z	
Kr, Total_Conc in Unconsolidated	0.0708104		0	FE-1DL38	
Sediments			0	FE-1DL38A	
NS	6	Set Tiler block model	0	FE-1DL43	
MinD	453.758		•	PE-TDE43	
AvgD	722.183				
KM	0.128935				
KV	16025.2	Kr, Total_Conc in Unconsolidated			
SoR	0.20512	Settiments			
KE	-0.180067	Block index 32,20,4			
Sum	1	Biock centroid -7855780.000,			
SumN	-0.0287797	BIOCK CENTROID 5081560.0000, 160.0000			
ND	0	Kr, Total_Conc in 0.0708104			
ariable Orientation	184.846	Unconsolidated Sediments			
Rot1Z	184.846	Security Sec			
Rot2X	5.08533	NS 0 MinD 453.758			
Rot3Z	171.515	MID 453.758			

Block information is shown in the bottom left corner of the **Block Model Interrogation** window, so it is not necessary to refer back to the scene and select the block information for the appropriate block.

In the Weights column	, negative values :	are highlighted in re	ed to make them easier to see.

	ndfill Plume - Leapfrog Works								-	
Kriging -	Block Model Inte $ imes$									
ilter: Found ~	₽ 🔓 🔅								_	
Estimator		0	Drillhole ID	x	Y	z	Total_Conc (log) values	Weights	Included	Distance
💼 Kr, Total_Conc	in Unconsolidated Sediments	0	FE-1DL36B	-7858369.05	5081648.73	-10.72	10.3	0.2596	Yes	434.75
Open Estimator	View Ellipsoid	0	FE-1GB22	-7858367.43	5081356.62	-107.20	11.01	-0.0144	Yes	504.48
lock Index Definition		0	FE-1GB22	-7858367.43	5081356.62	-122.70	3.932	0.0300	Yes	511.05
X	<u>Υ</u> <u>Ζ</u>	0	FE-1DL39A	-7859385.67	5081746.22	16.00	7.245	0.0572	Yes	639.20
32 🗘 2	0 0 C	0	FE-1DL38Z	-7859329.95	5081079.73	0.81	7.314	0.1726	Yes	736.85
Filter block model		0	FE-1DL38	-7859399.28	5081121.32	117.00	0	0.1527	Yes	759.10
			FE-1DL40A	-7859245.30	5082162.29	-27.00	7.901	-0.0334	Yes	771 61
		0	FE-1DL41	-7859209.65	5082196.16	-9.80	6.553	0.1298	Yes	775.47
🚵 Kr, Total_Conc ir		-								
Sediments	Tonconsolidated	٢	FE-1DL38A	-7859400.67	5081098.55	28.00	11.38	-0.0140	Yes	776.75
Block index	32, 20, 7	٢	FE-1DL40	-7859260.95	5082173.29	9.98	6.399	0.0950	Yes	784.56
Block centroid	-7858780.0000, 5081560.0000, 100.0000	٢	FE-1DL45	-7859554.48	5081313.26	7.96	6.399	-0.0372	Yes	818.03
Kr, Total_Conc in Unconsolidated Sediments	0.164144	٢	FE-1DL43	-7858262.42	5080797.91	-13.95	0	0.2021	Yes	928.26
NS	12									
MinD	434.753									
AvgD	703.343									
KM	0.0982766									
KV	8850.1									
SoR	0.427031									
KE	-0.039773	-								
Sum	1									
SumN	-0.0990226	Found	: 12 Duplic	ates: 0 Cla	mped: 0	Avg Va	lue: 6.536			
ND	0	Includ	ed: 12 Eauidi	stant: 0 Av	Distance: 703	3 Pts wit	h Neg. W: 4			

The block estimate interrogator table data can be exported for use in other programs such as Microsoft Excel. Click the **Export** button to save a CSV file, which will include the table data and the search statistics (found, clamped, included, equidistant, duplicates, etc) and the block information (index, centroid, Kriging attributes, etc). Click the **Copy** button to put a copy of the table data on the operating system clipboard, and you can then paste it into another program.

Swath Plots

Swath plots are an important validation tool for providing comparisons between sample points (composited or uncomposited) and estimated values to identify any bias towards under-estimation or over-estimation or any smoothing in the results. The effect of different estimation methods and parameters can also be compared.

The swath plot is a one-dimensional graph in a specific direction of interest. A swath is a sectional slice through the block model with a specified thickness. The swath plot shows the average values for the blocks in the swath, along with the averaged sample values in the swath.


Contaminant Models Scale Stimation Block Models Block Model	
	Open Evaluations Calculations and Filters Statistics Interrogate Estimator New Seport View Object Copy Prioritise In Freeze Rename F2 In Delete Del
 > (@ Geology Model SURFACE EVALUATIONS > @ Water Table - Water Level Surface > @ Topography 	

To create a swath plot, right-click on a block model and select **New Swath Plot**:


A new **Swath** window will open:


Swath ×	
Name: Swath	$\mathbb{B}^{\times} \to \mathbb{C}$
∽ Swath / Values setup	
Swath in X Swath in Y Swath in Z Swath size: 1 1 - 70	(i) Nothing is selected
Selected items:	
	-

Click the add button (①) to add data sets to the plot. You can select individual items from the list of **Available Numeric Items** or you can select a parent object to select all the child items within it. Click the right arrow button to move the selected items into the **Selected Numeric Items** list:




The graph plots the averaged sampled values against the averaged block values for a series of swaths slicing through the block model in a selected direction. The **Swath size** can be altered for finer or more coarse slices. The **Scene** view overlays a bounding cuboid that shows the **Swath size** and direction:





Changing the swath direction to **Swath in Y** is reflected in the scene:


The **Index filter** can be used to graph a reduced set of the swaths. Either the minimum or maximum threshold for the **Index filter** can be dragged to change the width of the filter, and the selected portion can be changed by sliding the inner bar. The swath indicator widget in the **Scene** is updated to show what the **Swath plot** is depicting:




Selected data sets in the chart can be hidden or revealed by clicking the line segment visibility button (^{III}) next to the data set. The histogram visibility button (^{III}) will reveal or hide a histogram showing the volume of blocks used in the swath calculation. The block volume may not be identical for all estimators.



The colour for the line segment plots and histograms can be changed for each data set by clicking the colour chip, and selecting a new colour from the colour picker:



Selecting an evaluation will show an **Associated Values** panel. This provides options to set the visibility and colour preference for the evaluation's raw data values and declustered values for the evaluation's input data.



Changes you make to swath plots are preserved. Multiple swath plots can be created to show different points for analysis and reference.

You can export the graph for use in external reports and other documents. There are three options:

- The **Export** button saves a PDF, SVG or PNG file of the graph.
- The **Copy** button opens a menu to offer the options of copying a image of the graph to the Windows clipboard, or copying the graph data as CSV data to the Windows clipboard, where they can be pasted into another application. It also allows you to select the resolution of a copied image: a low resolution **Screen Image**, a **Medium Quality, 300 dpi** image, or a **High Quality, 600 dpi** image. Choose your preferred resolution before selecting **Copy Graph Image**.

Reports

The contaminant report is a pivot table for reporting on contaminants, with the freedom to customise the table to the unique needs of the project requirements. A contaminant report can display multiple categories and multiple numeric columns.

To create or view a contaminant report, right-click on a block model in the project tree and select **Report**. In the window that appears, click the **Select Columns** button to choose from the **Category columns** and **Value columns** evaluated onto the block model. If you wish to set a **Cut-off** value, select from any numeric column evaluated on the block model and set the cut-off value. The column selected for the **Cut-off** does not need to be a column included in the resource report. You can also apply a **Filter** to the report.

Select between **Block size in metres** and **Block size in feet** to ensure units are correctly converted. Select **Constant** value from the list of **Density** options and specify a numeric constant, or select a density data measurement from the numeric columns listed. Specify the appropriate **Density unit** to match the **Density** selection. You can also choose to **Show material content** columns, **Show empty rows**, **Show volume column** and **Show density column**.

Repo	art ×									
Name Report		D								
	Select Columns	Titl <u>e</u> : Report								
Blocks Block size is in	n metres O Block size is in feet	Cut-off: <none></none>	√ 0.00							
Density:	Density ~	Eilter: 🖓 No I	Negative Kriging 🗸 🗸							
Density <u>u</u> nit:	g/cm³ ~	Click on the column	s below to edit them, or click and	drag to reorder.						
Options							Av	erage Value	Mat	erial Content
Show material content		Classification	Depletion Model	Volume	Density	Mass	RBF, Zn_pc in LMS1	Kr Generous, Zn_pc in LMS1	RBF, Zn_pc in LMS1	Kr Generous, Zn_pc in LMS1
Show empty ro Show volume					g/cm²	t		%		
Show density column		Measured	In Design	117,000.00	2.50	292,500.00	15.96	15.01	46,671.72	43,916.07
		Wedsuled	Mined	33,000.00	2.50	82,500.00	16.24	15.25	13,400.83	12,582.21
Column Properties Nothing selected		Indicated	In Design	853,000.00	2.50	2,132,500.00	12.22	12.12	260,551.02	258,552.71
Nothing selected		mulcated	Mined	129,000.00	2.50	322,500.00	12.27	12.13	39,582.66	39,111.28
		Measured & Ind	In Design	970,000.00	2.50	2,425,000.00	12.67	12.47	307,222.74	302,468.77
		measureu a mu	Mined	162,000.00	2.50	405,000.00	13.08	12.76	52,983.49	51,693.49
		Waste	In Design	28,000.00	2.50	70,000.00	3.26	4.90	2,281.01	3,432.76
		waste	Mined	8,000.00	2.50	20,000.00	12.89	12.02	2,577.97	2,403.25
		Total	In Design	998,000.00	2.50	2,495,000.00	12.40	12.26	309,503.75	305,901.53
		IVIA	Mined	170,000.00	2.50	425,000.00	13.07	12.73	55,561.46	54,096.74

If you have an estimator that produces **outside**, **blank**, **without_value** or **error** statuses for blocks, these will result in **#Invalid** entries in the resource report table. To address this:

- Create a filter (or modify your existing filter) to discard blocks with an invalid status, and select this filter in the **Filter** field above the resource report table, or
- Create a calculation that sets invalid values to an appropriate acceptable value, and select this column instead.

Click on a column to customise how the information is displayed. You can change the column title by editing the **Heading** field.

Enabling **Show total** will add a category row called **Total** with a summation for the categories. Any row that is a summation of categories will appear in bold in the table. It is possible to get a sub-total of some of the categories by grouping them, and these will also be shown in bold. To group categories, select multiple items in the **Visible categories** list by holding down the Ctrl key as you click the mouse. Click the **Group** button to add the new category.

	Select Columns	THE	Report								
locks		Titl <u>e</u> :									
	n metres OBlock size is in feet	Cut-off:	<none></none>	✓ 0.00							
Density:	Density ~	Eilter:	🖓 No Nega	tive Kriging \sim							
Density unit:	g/cm² ~	Click on th	e columns bel	ow to edit them, or click and	drag to reorder.						
ptions								Av	erage Value	Mate	erial Content
Show <u>m</u> ateria		Clas	sification	Depletion Model	Volume	Density	Mass	RBF, Zn_pc in LMS1	Kr Generous, Zn_pc in LMS1	RBF, Zn_pc in LMS1	Kr Generous, Zn_pc in LN
Show empty g						g/cm²			%		
Show density		Measure		In Design	117,000.00	2.50	292,500.00	15.96	15.01	46,671.72	43,916
		Measure	ia	Mined	33,000.00	2.50	82,500.00	16.24	15.25	13,400.83	12,583
olumn Properties		Indicate	d	In Design	853,000.00	2.50	2,132,500.00	12.22	12.12	260,551.02	258,553
Classification		indicate	u	Mined	129,000.00	2.50	322,500.00	12.27	12.13	39,582.66	39,111
<u>H</u> eading:	Classification	Measure	d 9 Ind	In Design	970,000.00	2.50	2,425,000.00	12.67	12.47	307,222.74	302,468
Sho <u>w</u> total Visible <u>c</u> ategorie		wiedsure	uαmu	Mined	162,000.00	2.50	405,000.00	13.08	12.76	52,983.49	51,693
		Waste		In Design	28,000.00	2.50	70,000.00	3.26	4.90	2,281.01	3,432
Measur		Wuble		Mined	8,000.00	2.50	20,000.00	12.89	12.02	2,577.97	2,403
🔽 📕 Indicat		Total		In Design	998,000.00	2.50	2,495,000.00	12.40	12.26	309,503.75	305,901
Measured &	lind	Total		Mined	170,000.00	2.50	425,000.00	13.07	12.73	55,561.46	54,096
Measured		Difference	may occur in	totals due to rounding.							
Inferred	J	Differences	s may occur m	totals due to rounding.							
 Waste 											

Note that some of the **Visible categories** can be unticked to hide them; these hidden categories can still be included in a grouped category:

\checkmark	Measured		
\checkmark	Indicated		
\checkmark	Measured & Ind Indicated Measured		
	Inferred		
	Waste		
	M&1&1 Indicated Inferred Measured		
		Group	C

Select a category and click the up or down buttons to reorder them in the list. Delete a grouped category by selecting it and clicking the **Delete** button ($\widehat{\blacksquare}$).

Visible <u>c</u> ategories:	
Measured	
🗹 📕 Indicated	
Measured & Ind Indicated Measured	
🗆 📒 Inferred	
🗆 🔜 Waste	
M&I&I Indicated Inferred Measured	
	Group

If there are multiple category columns, these can be reordered to select one as the primary

categorisation, with the others shown as sub-categories. Click anywhere in a category column and drag it to a new location. While you hold down the mouse button, a vertical bar will appear where the column will be inserted:

	belect Columns	Titl <u>e</u> : Report					
locks		Cut- <u>o</u> ff:	✓ 0.0	0 0			
Block size is	in metres 🛛 Bloc <u>k</u> size is in feet	Filter: V No Neg	ative Kriging 🗸 🗸				
Density:	🎨 Density 🗸 🗸 🗸						
Density <u>u</u> nit:	g/cm³ v	Click on the columns b	elow to edit them, or clic	k and drag to re	order.		
ptions	is contact	Depletion Model	Classification	Volume m ³	Mass	Av RBF, Zn_pc in LMS1 %	erage Value Kr Generous, Zn_pc in LMS %
Show empt			Measured	117,000.00	292,500.00	15.96	15.0
✓ Show empty ✓ Show volum	-		Indicated	853,000.00	2,132,500.00	12.22	12.
Show densi		In Design	Measured & Ind	970,000.00	2,425,000.00	12.67	12.
_ show densi	ty column		M&I&I	1,546,000.00	3,865,000.00	10.70	10.
lumn Properti	PC		Total	1,546,000.00	3,865,000.00	10.70	10.
🔊 Classificatio		=	Measured	33,000.00	82,500.00	16.24	15.
Heading:	Classification	-	Indicated	129,000.00	322,500.00	12.27	12
	Classification	Mined	Measured & Ind	162,000.00	405,000.00	13.08	12.
∠ Sho <u>w</u> total			M&I&I	235,000.00	587,500.00	11.52	11.
/isible <u>c</u> ategori	es:		Total	235,000.00	587,500.00	11.52	11.
🗸 📃 Measu	red		Measured	150,000.00	375,000.00	16.02	15.
🗸 📕 Indicat			Indicated	982,000.00	2,455,000.00	12.23	12.
Measured	& Ind	Total	Measured & Ind	1,132,000.00	2,830,000.00	12.73	12.
Measured			M&I&I	1,781,000.00	4,452,500.00	10.81	11.
🗆 🔜 Inferred	ł		Total	1,781,000.00	4,452,500.00	10.81	11.
Waste M&I&I Indicated Inferred Measured	The Group	Differences may occur	in totals due to rounding	ļ.			


When **Average Value** columns are selected, it is possible to change:

- The Heading
- The Data unit
- The **Display unit** to use in the table, which may be the **Same as data** or some other unit to convert to
- The number of **Decimal places** to display in the table

Data unit has the options Unknown, Grams per tonne, Parts per million, Parts per billion, Percent, Troy ounces per short ton, Dollars per tonne, Dollars per short ton, Milligrams per kilogram, Micrograms per kilogram, Milligrams per gram and Micrograms per gram. The Data unit may be automatically set based on indicators in the selected column name, but must be checked for correctness. Make sure that the column data matches the **Data unit** selected. Note that "dollars" is used as a general term to refer to whichever currency you are using.

When **Dollars per tonne** or **Dollars per short ton** are selected as the **Data unit**, the **Display unit** option is not selectable, and must be **Same as data**.

Material Content columns can have the **Heading** changed, as well as the column's **Unit** and **Decimal** places.



The **Report** tab has **Export** and **Copy** options for making use of the resource report in external documents.

- Select Export to save the table as a Microsoft Excel spreadsheet, a CSV file, or an HTML file. Formatting is preserved in the spreadsheet and HTML file so the table will be arranged identically to the report in Leapfrog Works. CSV files do not contain formatted data. If you select CSV, you will also be asked if you would like to use the Rounded numbers used in the table, or Full precision numbers. You can also select between ASCII characters only and Allow all characters, with UTF-8 encoding, as required by the software you are exporting to.
- If you select **Copy**, then **Copy Table**, the table is copied to the operating system clipboard, and you can paste it into another application such as Microsoft Excel or Microsoft Word. Formatting is

preserved so the table will be arranged identically to the report in Leapfrog Works and only the column and row sizes need to be adjusted to your preferences.

Reports you create appear in the **Graphs and Tables** section under the relevant block model. To delete a report, right-click the report and select **Delete** from the context menu.

Flow Models

Geological models created in Leapfrog Works can be used as the basis for MODFLOW and FEFLOW models. You can create flow models directly in Leapfrog Works and assign hydrological/material properties based on the lithologies in the geological model. Flow models can be exported for use in other applications, and you can import existing flow models and use them as the basis for the construction of new models. Flow models can be displayed in the scene, and time-dependent data can also be visualised.

Working with MODFLOW and FEFLOW models is available with the Hydrogeology extension. Contact Customer Support as described in <u>Getting Support</u> for more information about the Hydrogeology extension.

If the **Flow Models** folder appears in the project tree as **Restricted**, you will be able to display models in the scene and change how they are displayed, but you will not be able to make changes to the models themselves.

All tools for building flow models are accessed by right-clicking on the **Flow Models** folder and the objects in it. Imported objects and objects created while building a flow model are also stored in the **Flow Models** folder, and more complex functions can be carried out by right-clicking on individual objects.

MODFLOW Models

These features are only available as part of the Hydrogeology extension. See <u>Flow Models</u> for more information.

Once you have created a geological model, you can use it as the basis for a MODFLOW model. You can also import existing MODFLOW models and assign lithologies from a geological model.

Steps for creating a MODFLOW model that can be exported and run outside Leapfrog Works are:

- 1. Create a geological model.
- 2. Create the MODFLOW model using the geological model to set the grid spacing and layers.
- **3.** Evaluate the new model against a geological model, if it wasn't when it was created.
- 4. Edit the hydrological properties.
- 5. Export the MODFLOW model to MODFLOW or Groundwater Vistas.

Once the model has been processed outside of Leapfrog Works, the model can be imported into Leapfrog Works and visualised in the scene.

Creating MODFLOW models in Leapfrog Works has the advantage that the resolution can be easily changed and the properties of the grid can be made to honour boundaries defined in geological models. See Creating a MODFLOW Model.

See MODFLOW Model Display for information on options for displaying models in the scene.

Models created in Leapfrog Works can be evaluated against a geological model when they are created. Models imported into Leapfrog Works or that were not evaluated when they were created can be evaluated as described in <u>MODFLOW Evaluations</u>. Once a model has been defined and evaluated against a geological model, hydrological properties can be assigned and the grid can be exported. See <u>MODFLOW Hydrological Properties</u> and <u>MODFLOW Model</u> <u>Export</u>.

Creating a MODFLOW Model

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

To create a new MODFLOW model, you must first have at least one geological model defined in the project. Once this has been defined, add the geological model to the scene. Right-click on the **Flow Models** folder and select **MODFLOW > New Structured Model**. The **New MODFLOW Model** window will be displayed, together with controls in the scene that will help you to set the grid extents:

😵 New MODFLOW Model 🛛 🗡																				
Gridding from: 🚺 SimpleGM 💌			th (`	1)						1	r		1							
☑ <u>E</u> valuate Gridded Model		1 2"+5	995	500			7		1.1										_	4
Gr <u>i</u> d <u>L</u> ayers		3				7														
Grid Spacing		4		000																
Default Cell Size: 200.00000000		5																		
Row Spacings Column Spacings		6																		
Minimum <u>T</u> hickness: 20.00		8	985	500																-
<u>P</u> reserve Existing Grid Lines		9																		
Grid Position		10	980	000																
Base Point: 2304608.6163 , 5697183.3454		11				0														
<u>W</u> idth: 3600.0	:	12+5	975	00		0550												0800		East (X)
L <u>e</u> ngth: 2600.0			-		4	+23			1							÷		+23		East
Grid Angle: 0.0		₽	ź) 3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	
Name: MODFLOW Simulation																				
₩ Lelp	2 1	imple.	•	Edit	Colo	urs			-		A		Ī				leGN le: F		Scene	•

The new MODFLOW grid will be based on the geological model in the **Gridding from** setting. If you wish to use a geological model other than the one selected when the window is opened, select it from the list. The grid dimensions will be updated in the scene.


If the **Evaluate Gridded Model** box is ticked, the selected geological model will be evaluated on the new grid and set as the evaluation for export. If you do not wish to evaluate the geological model on the grid, untick the box. You will still be able to use the layers in the geological model to control the grid layers.

The **Preserve Existing Grid Lines** option is used when setting a non-uniform grid in the scene window. If you are going to define a non-uniform grid in this way, create the model with the **Default Cell Size** set to the smallest cell size you wish to use, then edit it as described in <u>Editing a MODFLOW</u> <u>Model</u>.

The grid should be slightly smaller than the selected geological model. Any MODFLOW cells that exist outside the geological model will be marked as inactive when the grid is exported to MODFLOW .

Horizontal Grid Spacing

By default, the horizontal grid for the model is uniform, with the size of each cell set by the **Default Cell Size** value. You can change the horizontal grid by editing row and column spacings. When you click on **Row Spacings** or **Column Spacings**, the **Edit Spacings** window will be displayed:




Changes made in the **Edit Spacings** window will be reflected in the scene.

There are four ways to change the spacings:

- Click on a value to edit it.
- Divide a row or column. Click on a row or column, then on the **Divide Row** or **Divide Column** button. Two new rows or columns will appear in the list.
- Merge rows or columns. Hold down the Shift key while clicking on each item, then click on the **Merge Rows** or **Merge Columns** button. The selected items will be combined.
- Set uniform spacing on selected rows or columns. You will be prompted to enter the number of cells you wish to create from the selected rows or columns.

Click OK.


For example, here, the rows and columns away from the model boundary have been divided to provide more detail. The different spacings are reflected in the scene:



Use close spacing for steep gradients and increase or decrease spacing gradually.

Vertical Grid Layering

The vertical grid layers are based on the geological model selected in the **New MODFLOW Model** window. Click on the **Layers** tab to view the layers:




Initially, there are two layers equally spaced between the topography and the geological model. Change the layers by clicking on **Select Layer Guides** button. The **Layer Guides** window will appear, showing the layers available in the selected geological model:

New MODFLOW Model	× North ((Y)	· · · · · · · · · · · · · · · · · · ·
Evaluate Gridded Model	1 2 3 4 + 56 9 9		×
Gr <u>i</u> d Layers	😵 Layer Guides		×
Select Layer Guides	A <u>v</u> ailable layers:	Selected layers:	
Layer Guide Topography <bottom 'simplegm'="" extents="" of=""></bottom>	Gravels - Alluvium contacts Aquifer Miocene Alluvium Basement Granite contacts		13 14 15 16 17 18
ame: MODFLOW Simulation	G Select <u>A</u> ll Select None	≹ ⊆ancel €20	Slice mode: From Scene

If the grid is required to follow a geological model lithology contact surface, move the layer into the **Selected** list and it will be honoured in the gridding process.

Click **OK** to return to the **New MODFLOW Model** window, in which the selected layers will be displayed:



Click **OK** to create the new MODFLOW grid, which will appear in the **Flow Models** folder. You can edit the model by expanding it in the project tree and double-clicking on the grid object (.). See <u>Editing a</u> <u>MODFLOW Model</u>.

For further information on working with the new model, see:


- MODFLOW Model Display
- MODFLOW Evaluations
- MODFLOW Hydrological Properties
- Head Values and MT3D Concentrations
- Generating a Head Value Mesh
- MODFLOW Model Export

Editing a MODFLOW Model

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

Once you have created a MODFLOW model, you can edit it by expanding the model in the project tree and double-clicking on the grid object (). The **Edit MODFLOW Grid** window will appear. You can edit the grid spacings as described in <u>Creating a MODFLOW Model</u>, using the information in the scene window as a guide.

Another way to edit the grid is to use the controls in the scene to apply different cell size settings in different parts of the grid. For example, you may want to define a grid that has smaller cells in the centre than at the outer edges:



To set cell sizes in this way, it is best to start with a MODFLOW model where the **Default Cell Size** is set to the smallest cell size you will use in the model.

For this example, we will start with a new grid with a **Default Cell Size** of 50. We will set the adjacent cell size to 100 and the cell size at the outer boundary to 200.

First, we need to reduce the area that uses the cell size of 50 by using the red handles in the scene:

😰 Edit MODFLOW Grid	× //
Gridding from: SimpleGM	
Grid Layers	North (Y)
Grid Spacing	
New Cell <u>Size:</u> 50.00000000	
Row Spacings Column Spacings	
Minimum Ihickness: 8.00	
✓ Preserve Existing Grid Lines	11111111111111111111111111111111111111
Grid Position	
<u>Base Point:</u> 2305508.6163 , 5697683.3454	
<u>W</u> idth: 2100.0	
L <u>e</u> ngth: [1400.0	23456789.012885678901238567890123856789012
Grid <u>A</u> ngle: 0.0	Elev (z)
Eancel Cancel	
👁 🗇 SimpleGM Extents 🛛 💥 🚷 Flat col 🗸	G SimpleGM Extents

The blue box in the scene is the geological model extents for the model used to define the MODFLOW model and represents the unedited boundary of the MODFLOW model.

Next, enter the cell size to use for the area adjacent to the 50.0 cells in the **New Cell Size** field. Then, drag the red handles to enlarge the grid. The centre part of the grid is still set to 50, while the new area is set to 100:

Gr <u>i</u> d <u>L</u> ayers			North (Y)														
Grid Spacing										1	•						5	
New Cell Size: 100		\$		1 2 3														
Row Spacing	s Colu <u>m</u> n Spacing.			\$														
Minimum <u>T</u> hicknes	s: 8.00	\$		8 11														
✓ Preserve Existing	g Grid Lines																	
Grid Position				Į														T
Base Point: 230510	8.6163 , 5697383.3454																	
<u>W</u> idth: 2800.0		•																
L <u>e</u> ngth: 2000.0		\$																
Grid Angle: 0.0		1	Elev (Z	172	3 4 5	5789 L 1	01234	5678	391041	22	8789	012	3458	7890	1/2/3/4	56 74	849	

If the **Preserve Existing Grid Lines** option is enabled, grid lines for cells already defined will not be moved to account for new cells.

Enter the next cell size in the **New Cell Size** field and then use the handles to enlarge the grid again:

😰 Edit MODFLOW Grid	×	(II
Gridding from: SimpleGM	_	North (Y)
Gr <u>i</u> d Layers		
Grid Spacing		2
New Cell Size: 200	\$	
Row Spacings Colu <u>m</u> n Spacings		
Minimum Thickness: 8.00	•	
☑ Preserve Existing Grid Lines		
Grid Position		
Base Point: 2304508.6163 , 5696983.3454		
<u>W</u> idth: 3800.0	•	
L <u>e</u> ngth: 2800.0	*	64 35 26
Grid <u>A</u> ngle: 0.0	•	
₩ Lelp	к	1 2 3 4 5 6 7 89.0129405038001228 0038001238350396442845676905152 53 54
👁 🗇 SimpleGM Extents 🛛 💥 🔒 Flat col 🗸 🗖		SimpleGM Extents

Click **OK** to update the grid.

For further information on working with the new model, see:

- MODFLOW Model Display
- MODFLOW Evaluations
- MODFLOW Hydrological Properties
- Head Values and MT3D Concentrations
- Generating a Head Value Mesh
- MODFLOW Model Export

Importing a MODFLOW Model

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

Leapfrog Works imports .nam files and .mfi and .mfn variations of .nam files.

To import a MODFLOW model, right-click on the **Flow Models** folder and select **MODFLOW > Import Model**. Leapfrog Works will ask you to specify the file location, and then will display the data in the file in the **Import MODFLOW Model** window:

😵 Import MOI	DFLOW Model	×
Grid Position		
Base <u>P</u> oint:	-1.4791461582 , -1.9961617048	
Grid <u>A</u> ngle:	0.0	+
<u>N</u> ame: Twist	edModel	
	Cancel Cancel	

If the world origin is available, the **Grid Position** will be displayed but cannot be edited.

Click **OK** to import the grid. The new MODFLOW model will appear in the project tree in the **Flow Models** folder. See <u>MODFLOW Model Display</u> for information on displaying the model. If the world origin was not available when the model was imported, you can change the **Grid Position**. To do this, expand the imported model in the project tree and double-click on its grid object (
 To associate lithologies with the grid, see <u>MODFLOW Evaluations</u>.

MODFLOW Evaluations

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

When a MODFLOW model is exported, the evaluated geological model is used to assign lithologies to the cells in the grid. If the grid has not been evaluated against a geological model, you must do so before you can edit the hydrological properties and before you can export the grid.

To evaluate a MODFLOW model, expand the model in the project tree, then right-click on the grid object () and select **Evaluations**. Although you can evaluate an interpolant or distance function, they cannot be exported with the grid and are simply used for displaying the grid in Leapfrog Works.

A window will appear listing all objects in the project that can be used for an evaluation. Once you have selected one or more objects, click **OK**. You will then be able to select the evaluations from the view list, as described in <u>Evaluations</u>.

Assigning an Evaluation for Export

For MODFLOW models created in Leapfrog Works, the evaluation used when creating the model will automatically be assigned as the evaluation for export. A hydrological properties table (IIII) will appear in the project tree as part of the model.

If the model was imported into Leapfrog Works or created without being evaluated against a geological model, you will need to manually set the evaluation for export. To do this:

- Evaluate the grid against one or more geological models, as described above.
- Right-click on the model (or in the project tree and select **Set Evaluation for Export**. The **Select Evaluation** window will appear showing all geological models evaluated on the grid. Select the required evaluation and click **OK**.

A hydrological properties table will be added to the model in the project tree. Edit hydrological properties by double-clicking on the table. See MODFLOW Hydrological Properties.

Combined Evaluations

You can combine geological models and set the priority used for evaluation. This is useful when you have geological models available that describe different parts of the area of interest or if you have a refined geological model for part of the model. To combine geological models for evaluation, select the required models in the **Select Models To Evaluate** window, then click on the **Combined Evaluation** button.

vailable:	5 <u>e</u> le	ected:
Numeri Au	Sombined Evaluation	×
💿 Au ir	Select evaluations to combine:	
	GM	
	G GegionalGM G G SimpleGM	
		1 Higher
		priority
		Lower
Select <u>A</u> ll		
Combined Ev		

In this example, there are three geological models selected:

The GM and GM from contacts models describe similar areas, but GM has more detail. The GM larger model describes a larger area but with less detail. Tick the models to combine them and set their priority. Click **OK** to create the combined evaluation, then click **OK** in the **Select Models To Evaluate** window. The combined evaluation will be available from the view list and can be selected as the evaluation for export.

To delete a combined evaluation, click on the **Delete Combined** button in the **Select Models To Evaluate** window.

MODFLOW Hydrological Properties

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

When a MODFLOW model is evaluated against a geological model, a hydrological properties table (IIII) is added to the model in the project tree. You can edit hydrological properties by double-clicking on the table. You can also open the table by right-clicking on the model in the project tree and selecting **Edit Hydrological Properties**.

If the model has been imported into Leapfrog Works and has not yet been evaluated against a geological model, you will be prompted to do so. Expand the model in the project tree, right-click on the grid object and select **Evaluations**. See MODFLOW Evaluations for more information.

Hydrological properties are assigned to model blocks based on the position of the block's centroid relative to the geological model used to evaluate the grid. The position of the centroid is calculated and Leapfrog Works then determines which lithology the centroid falls inside. The K values for the assigned lithology are assigned to the entire block; there is no averaging.

If more than one object has been evaluated on the grid, you can set hydrological properties separately for each evaluation. Select the required evaluation from the **Evaluation** list:

😵 Edit MODFLOW Parameters - MODFLOW Sir	nulation							×
Evaluation: 📑 Combined Evaluation								•
Geological 🛅 Combined Evaluation								
GM larger GM								
GM larger GM from contacts 5								
GM larger GM larger								
GM larger CoarseSand	5	0	0	0	0	0	0	
GM larger Lower Gravel	8	0	0	0	0	0	0	
GM from contacts Alluvium	10	0	0	0	0	0	0	
GM from contacts Aquifer Miocene Alluvium	11	0	0	0	0	0	0	
GM from contacts Basement Granite	12	0	0	0	0	0	0	
GM from contacts Gravel	13	0	0	0	0	0	0	-
			Set	Kx value for lit	hology 'Alluvium2'			
			۲	Value:	0.0			
Sort Zone Numbers			C	Interpolant:	O Contaminant			v
 Lithologies in light blue are unused and wi 	ll not be	exported.					🚽 All Liţi	nologies
1 Help						8	Cancel	<u>9о</u> к

However, the only hydrological properties information that will be exported is that set for the evaluation to be exported.

Setting Hydrological Properties

In the **Edit MODFLOW Parameters** window, you can enter the values for hydrological properties manually or you can use the values from an interpolant.

To enter values manually, click on a cell, then enter the value in the **Value** field:

Lithology	Zone	Кх	Ку	Kz	Ss	Sy	Initial Head	
Alluvium	2	0	0	0	0	0	0	
Aquifer Miocene Alluvium	3	0	0	0	0	0	0	
Basement Granite	4	0	0	0	0	0	0	
Coarse Sand	5	0		0	0	0	0	
Glacial Till	6	0	0	0	0	0	0	
ower Gravel	8	0	0	0	0	0	0	
Unknown	1	0	0		0	0	0	
Gravel	7	0	0	0	0	0	0	
Sort Zone Numbers					et 'Kx' value for lit ● <u>V</u> alue: ○ <u>I</u> nterpolant:	hology 'Alluvium 0.0 O Contaminan	:	ll Lithologie

Press the Enter key to move down the columns.

To use the values from an interpolant, click the **Interpolant** button, then select an interpolant from the list. The interpolant that will be used for the selected value will be displayed in the field:


Lithology	Zone	Kx	Ку	Kz	Ss	Sy	Initial Head	
Alluvium	2	Kx values	0	0	0	0	0	
Aquifer Miocene Alluvium	3	0	0	0	0	0	0	
Basement Granite	4	0		0	0	0	0	
Coarse Sand	5	0	0	0	0	0	0	
Slacial Till	6	0	0	0	0	0	0	
ower Gravel	8	0	0	0	0	0	0	
Jnknown	1	0	0		0	0	0	
iravel	7	0	0	0	0	0	0	
Sort Zone Numbers	e are unu:	sed and will not be	e exported.		et Kx Value for lith <u>V</u> alue: <u>I</u> nterpolant:	ology 'Alluvium' 0.0 Sx values		Lithologie

To use the interpolant for all the values in the selected column, click the **All Lithologies** button. The window will be updated to show that the interpolant values will be used for that column:

Lithology	Zone	Kx	Ку	Kz	Ss	Sy	Initial Head	
Alluvium	2	Kx values	0	0	0	0	0	
Aquifer Miocene Alluvium	3	 Kx values 	0	0	0	0	0	
Basement Granite	4	O Kx values	0	0	0	0	0	
Coarse Sand	5	 Kx values 	0	0	0	0	0	
Glacial Till	6	 Kx values 	0	0	0	0	0	
Lower Gravel	8	 Kx values 	0	0	0	0	0	
Unknown	1	 Kx values 	0	0	0	0	0	
Gravel	7	O Kx values	0	0	0	0	0	
		•	•		Set Kx value for lit	hology 'Alluvium'		
					○ <u>V</u> alue:			
Sort Zone Numbers					• Interpolant:	Kx values		
								All Lithologie

Zone Numbers

When the model is exported, the zone numbers are used to indicate the assignment of lithologies to blocks and are written to the MODFLOW zoned layer properties flow (*.lpf) file. In the **Edit MODFLOW Parameters** window, you can change the zone number for a lithology by clicking in a cell and entering a different zone number. If you reorder the zones in this way, zone number conflicts will be highlighted in red:



Zone numbers must be unique and you will not be able to close the window and save data if there are conflicts.

If you click on the **Sort Zone Numbers** button, the zone numbers will be ordered from top to bottom.

Zone numbers should not be sorted once a model has been exported as the new numbers will not be reflected in the exported model.

Click **OK** to update the grid.

MODFLOW Model Display


If you do not have the Hydrogeology extension, MODFLOW models will appear in the project tree as **Restricted**. You can change how MODFLOW models are displayed, but you will not be able to make changes to the models themselves.

In the project tree, MODFLOW models are made up of a grid object (), a **Simulation Outputs** folder and a hydrological properties table () object. If there is no hydrological properties table, an evaluation has not yet been set for export. See MODFLOW Evaluations for more information.

For MODFLOW models created in and imported into Leapfrog Works, dragging the model itself into the scene will display the grid () object. The different parts of the model can also be displayed.

Grid Display Options


Dragging a MODFLOW model into the scene displays its grid object. Here, an imported model has been evaluated against a geological model and added to the scene:



The viewing options available are the flat colour option, the evaluated geological model and zone data imported with the model. Other inputs imported with a model will also be available from this list, and once the model has been evaluated against a geological model or interpolant, you can also display the model using the grid's hydrological properties.

Grids are displayed as cells. When a geological model evaluation or lithological zone information is displayed, you can also display a legend for the grid.

When **Show edges** (\triangleright) is enabled, the edges of the cells will be displayed.




The **Show inactive blocks** (H) option displays inactive cells in grey:

To display a single layer, tick the **One layer** box in the shape properties panel, then select the layer to display.

Head values and MT3D concentrations can also be imported and displayed. See <u>Head Values and MT3D</u> <u>Concentrations</u>.

Viewing Block Information

When a MODFLOW model is displayed in the scene, you can view information about the individual cells in the model by clicking on a block. The window that appears shows information about the selected block, including its centroid and the lithology assigned to the block from the evaluated geological model. Information from all geological models and interpolants the grid has been evaluated against will be displayed:



Head Values and MT3D Concentrations

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

Leapfrog Works imports the following output file formats:


- Head values files in *.hds, *.hhd and *.hed formats
- MT3D concentrations files in *.ucn format

To import head values or MT3D concentration files for a MODFLOW model, right-click on the **Simulation Outputs** folder and select the required option. Navigate to select the file, then click **Open**.

The information will be added to the MODFLOW grid, and you can then select the head values and MT3D concentrations in the shape list when you display the grid in the scene. If the output is timedependent, a timestep slider will be available from the shape properties panel. Click and drag the slider or click along the timeline to view the different timesteps available:



Imported head values and MT3D concentrations are stored in the project tree in the **Simulation Outputs** folder:



To delete head values or MT3D concentrations, right-click on the object in the project tree and select **Delete**.

Once head values have been imported, you can generate a head value mesh. See <u>Generating a Head</u> Value Mesh.

Generating a Head Value Mesh

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

Once head values have been imported for a MODFLOW model, you can generate a head value mesh. To do this, expand the **Simulation Outputs** folder. Right-click on the head values object and select **Generate Head Value Mesh**. The **Generate Head Value Mesh** window will appear, showing the layers in the model and the timesteps available. Select the layer of the model you wish to generate a head value mesh for, then choose the heads. Click **OK** to create the mesh, which will be saved to the **Meshes** folder.

MODFLOW Model Export

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

Leapfrog Works has three options for exporting MODFLOW grids:

- Export the grid as a MODFLOW file.
- Export for Groundwater Vistas. Use this option the first time you export a grid for use in Groundwater Vistas.
- Export a Groundwater Vistas update. Use this option to generate a set of files that can be imported into Groundwater Vistas as an update.

The Groundwater Vistas options include a zoned layer properties flow (*.lpf) file that includes information about the zones in the grid.

As a MODFLOW File

To export a grid as a MODFLOW file for use in a package other than Groundwater Vistas, right-click on the grid in the project tree and select **Export to MODFLOW**. You will be prompted to choose a **File name** and location. Select the options required, then click **Save**.

For Groundwater Vistas

To export a grid for use in Groundwater Vistas for the first time, right-click on the grid in the project tree and select **Export to MODFLOW for GWV**. You will be prompted to choose a **File name** and location. Select the options required, then click **Save**.

If you have previously exported the grid to Groundwater Vistas and have made changes to the grid, use the **Export to GWV Updates** option.

As a Groundwater Vistas Update

If you have exported a grid to Groundwater Vistas but then make changes to the Leapfrog Works model, you can export the changes to the model. The set of files containing the changes can then be imported to Groundwater Vistas.

To export a Groundwater Vistas update, right-click on the grid in the project tree and select **Export GWV Updates**. The **Update Groundwater Vistas** window will appear listing the files that will be exported. Enter a **Base file name** to differentiate the original files from the updates. Click **Export**. The files will be saved in the specified directory.

FEFLOW Models

These features are only available as part of the Hydrogeology extension. See <u>Flow Models</u> for more information.

In Leapfrog Works, creating a 3D FEFLOW model requires:

- A geological model that will be used to assign lithologies to the FEFLOW model's blocks.
- A 2D grid that defines the block size, boundaries and surface features.

Steps for creating a 3D FEFLOW model that can be exported and run outside Leapfrog Works are:

- **1.** Create a geological model.
- 2. Create and refine a 2D model in Leapfrog Works or import a FEFLOW model.
- **3.** Create the 3D model from the 2D model or another 3D model in the project.

- **4.** Evaluate the new 3D model against a geological model.
- 5. Edit the material types.
- 6. Export the 3D FEFLOW model.

Once the model has been processed outside of Leapfrog Works, a results file can be saved that can be imported into Leapfrog Works and visualised in the scene.

A 2D grid can be created in or imported into Leapfrog Works. A 3D grid can also be used, in which case the layer information is not used in creating the 3D grid. Creating the 2D grid in Leapfrog Works provides the most flexibility, as the block sizes can easily be changed, the boundaries modified and features added to provide finer resolution where there is more data available.

For information about creating 2D and 3D grids, see <u>Creating a 2D FEFLOW Model</u> and <u>Creating a 3D</u> <u>FEFLOW Model</u>.

You can also import FEFLOW problem files and result files, visualise them in Leapfrog Works and use them as the basis for new models. See <u>Importing a FEFLOW Grid</u>.

See <u>FEFLOW Model Display</u> for information on options for displaying FEFLOW models in the scene.

3D grids created in Leapfrog Works can be evaluated against a geological model when they are created. Grids imported into Leapfrog Works or that were not evaluated when they were created can be evaluated as described in <u>FEFLOW Evaluations</u>.

Once a model has been defined and evaluated against a geological model, material types can be assigned and the grid can be exported. See <u>FEFLOW Material Types</u> and <u>FEFLOW Model Export</u>.


FEFLOW Model Display

If you do not have the Hydrogeology extension, FEFLOW models will appear in the project tree as **Restricted**. You can change how FEFLOW models are displayed, but you will not be able to make changes to the models themselves.

In the project tree, 3D FEFLOW models are made up of a grid object representing the finite elements, a nodes object and a material types table (IIII) object. If there is no material types table, an evaluation has not yet been set for export. See <u>FEFLOW Evaluations</u> for more information.

A 2D FEFLOW grid is made up of a grid object and a nodes object. Here, three types of FEFLOW models are shown expanded in the project tree:

- Feflow 3D Simulation is a 3D model created in Leapfrog Works.
- Feflow 2D Simulation is a 2D model created in Leapfrog Works.
- Feflow Results is an imported 3D model (DAC file).




From the information in the project tree, we can see that:

- The 3D simulation created in Leapfrog Works (m) uses the GM geological model to define the layers.
- The 2D simulation created in Leapfrog Works (a) uses the GM geological model as a boundary and has had collar points added as a feature.
- The imported results model () includes a number of simulation outputs.

For each type of FEFLOW model, dragging the model itself into the scene will display the grid (
object. The different parts of the model can also be displayed.

Displaying a 3D Model

Dragging a 3D simulation into the scene displays its grid object, which represents the finite elements. Here, a 3D model created in Leapfrog Works (a) has been added to the scene:




For 3D models imported into Leapfrog Works, you can display the model using other information available for the grid, such as conductivity data. This is available from the view list.

Grids for 3D models are displayed as blocks. You can also display a legend for the grid when a geological model evaluation is displayed.

When **Show edges** (\triangleright) is enabled, the edges of the blocks will be displayed.

To display a single layer, tick the **One layer** box in the shape properties panel, then select the layer to display.


You can display the nodes by adding the nodes (>) object to the scene. When a model with results is displayed, the simulation outputs can be displayed when the nodes are viewed in the scene. Here, the nodes for an imported results file have been added to the scene. The heads are displayed for a single layer:



When the results are time-dependent, a timestep slider will be available from the shape properties panel. Click and drag the slider or click along the timeline to view the different timesteps available.

Displaying a 2D Model

As with 3D models, dragging a 2D model into the scene displays its grid object. Here, a 2D model created in Leapfrog Works (()) has been added to the scene and viewed from above:




Also in the scene is a collar points object that shows collar points that have been added to the grid as a feature.

2D grids can be viewed as points or as blocks. As with imported 3D grids, an imported 2D grid can also be displayed using other information available for the grid.

Other viewing options are available for 2D grids created in Leapfrog Works. These are useful in refining a 2D grid and are described in <u>Creating a 2D FEFLOW Model</u>.

Viewing Block Information

When a FEFLOW model is displayed in the scene, you can view information about the individual blocks in the model by clicking on a block. The window that appears shows information about the selected block, including its centroid and the lithology assigned to the block from all evaluated geological models and interpolants:



Information from all geological models and interpolants the grid has been evaluated against will be displayed:

Importing a FEFLOW Grid

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

You can import 2D and 3D FEFLOW grids and use them as the basis for new models. Leapfrog Works imports two types of FEFLOW files:

- FEFLOW problem files (*.fem) in ASCII format. Importing these files results in a new 2D or 3D model with a grid and nodes.
- FEFLOW results files (*.dac). Importing these files results in a new 3D model with a grid, nodes and simulation outputs.

To import a FEFLOW grid or results file, right-click on the **Flow Models** folder and select one of the **FEFLOW > Import** options. Leapfrog Works will ask you to specify the file location. Click **Open** to import the file.

The new FEFLOW grid will appear in the project tree under the **Flow Models** folder. To use the imported grid or results file as the basis for a new FEFLOW model, see <u>Creating a 3D FEFLOW Model</u>.

To associate lithologies with a 3D grid, see <u>FEFLOW Material Types</u>.

See <u>FEFLOW Model Display</u> for information about displaying the FEFLOW grid in the scene window.

Creating a 2D FEFLOW Model

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

A 2D FEFLOW model defines the block size, boundaries and surface features for a 3D FEFLOW model. Although existing 2D grids can be imported into Leapfrog Works and used for creating 3D models, creating the 2D grid in Leapfrog Works provides the most flexibility, as the block sizes can easily be changed, the boundaries modified and features added to provide finer resolution where there is more data available.

It is not necessary to create a geological model before creating a 2D grid. However, you will not be able to create a 3D grid until a geological model has been created. Therefore, it is a good idea to create the geological model first, and its dimensions can be used in defining the boundary of the 2D grid.

To create a 2D grid, right-click on the **Flow Models** folder and select **FEFLOW > New 2D Model**. The **New 2D FEFLOW Grid** window will appear:

😫 New 2D FEF	LOW Grid		×
Boundary • From rect	angle		
	Minimum	Maximum	
X (East):	2283509.1948667	2314213.3300540!	•
<u>Y</u> (North):	5693596.9643332	5711371.7800939!	•
		Enclose Object 💌	
○ Fro <u>m</u> and	ther object		
☑ <u>S</u> implify b	ooundary <u>T</u> oleran	ce: 140	•
Element size:	3500		-
Feature vertex :	snapping <u>d</u> istance: 3	5.00 🗘 🗹 A	uto
Name: Feflow	/ 2D Simulation		
Help	🤾 Can	icel	

All settings can be changed once the grid has been created. It is, therefore, reasonable to accept the default settings and create the grid, then add it to the scene and begin refining it. Click **OK** to create the initial grid.

In the project tree, a 2D FEFLOW grid is made up of a grid object and a nodes object, as described in <u>FEFLOW Model Display</u>. Here, a newly-created grid with a rectangular boundary appears in the project tree:

🔻 ቒ Feflow 2D Simulation	
🔻 🗇 grid	
🔜 Boundary	-
🗇 nodes	

Expand the grid in the project tree and double-click on the grid object (*) to open the **Edit 2D FEFLOW Grid** window. The **Features** tab will be displayed. When a grid is first created, this window will be empty, but once features have been added, you can enable them in this tab. Click on the **Boundary** tab to modify the boundary:

Economy Te	atures	
• From rect	angle	
	Minimum	Maximum
X (East):	2283509.1948667383	2314213.3300540503
Y (North):	5693596.964333217	5711371.780093997
O Fro <u>m</u> ano	ther object	Enclose Object 🔻
✓ Simplify b	oundary <u>T</u> olerand	ce: 140
	\$500	Total elements:


Click the **Apply** button to view the effect of changes made without closing this window.


Boundary Options

When setting the **Boundary**, you can set a rectangular boundary defined by the **From rectangle** settings. You can use the extents of any other object in the project by selecting from the **Enclose Object** list, but the grid boundary will always be a rectangle.

To define a non-rectangular boundary, use the **From another object** options and select from the list of objects available in the project. This is useful if, for example, you wish to define a grid using the boundary of a geological model.

The **Simplify boundary** option reduces the number of points along the boundary. Reducing the **Tolerance** value increases the number of points along the boundary. The two settings together let you define a basic boundary with elements that are roughly uniform in size, set by the value of **Element size**. Here, a grid has been created from a geological model with the **Simplify boundary** option enabled:





Disabling the **Simplify boundary** option results in more detail around the edges of the grid:

Element Size

The **Element size** setting determines the basic size of the triangles that make up the grid, although the size will vary according to features applied to the grid and the **Feature vertex snapping distance**. The size will also vary if the **Simplify boundary** option is unticked, in which case the **Element size** setting is the maximum size of the triangles.

The **Feature vertex snapping distance** is automatically set to 1 percent of the **Element size**. To use a smaller snapping distance, untick the **Auto** box and set the value required.

The effects of the **Feature vertex snapping distance** do not become apparent until features have been added to the grid.

Adding Features to the Grid

To add features to the grid, right-click on the grid in the project tree and select **New Feature**. The **New FEFLOW Feature** window will appear:

😰 New FEFLOW Feature 🛛 🗙 🗙
Collar
Feature Type: Point Line Polygon
☑ Simplify Feature Iolerance: 4.00
Name: collar
🔀 Cancel 🥠 🖉 QK

You can add **Point**, **Line** and **Polygon** features, and the **Feature Object** list will display all suitable objects available in the project. Ticking the **Simplify Feature** option will reduce the number of points used.

Click **OK** to add the feature, which will appear in the project tree under the FEFLOW grid object:



You can edit the feature by double-clicking on it or by right-clicking and selecting **Open**. However, the feature has not yet been applied to the grid. To enable the feature, double-click on the grid to open the

Edit 2D FEFLOW Grid window. Tick the box to enable the feature, then adjust the number of **Refinement Steps**:


Feature Refinement Steps collar 10	
	1
ment size: 400.0 🗘 Total e	lements: 1

More Refinement Steps will produce more detail near the feature.

Click **Apply** or **OK** to view the effect the feature and its settings have on the grid.

If you want to modify a feature without having to reprocess the grid, untick it in the **Features** tab. If you want to delete a feature, right-click on it in the project tree and select **Delete**.

The images below show a grid displayed with collar points (in red) to demonstrate the effects of no features and collars applied with different refinement steps:



To view all features added to a grid, right-click on the grid and select **View Snapped Features**. A **Snapped Features** object will appear in the shape list that represents all objects used to add features to the grid:

▼ Projects 🗊 Scene View	Alex Rock ▼
😤 Edit 2D FEFLOW Grid X	🖻 👌
Boundary Eeatures	
Feature Refinement Steps	
✓ collar 10	
✓ East boundary 10	
Element sige: 800.0 + Total elements: 67496 Feature vertex snapping gistance: 8.000 + Auto	
Help X Cancel √ Apply ← OK	Snapped Features
	Slice mode: From Scene

Here, four snapped objects appear in the scene: the three features listed in the **Features** tab and the grid's boundary.

See <u>Creating a 3D FEFLOW Model</u> for information on using the 2D grid as the basis for a 3D model.

Creating a 3D FEFLOW Model

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

To create a new 3D FEFLOW model, you must first create or import a 2D FEFLOW grid as described in Creating a 2D FEFLOW Model and Importing a FEFLOW Grid.


Once you have created or imported a 2D FEFLOW grid, right-click on the **Flow Models** folder and select **FEFLOW > New 3D Model**. The **Extrude 3D FEFLOW Grid** window will appear:

😰 Extrude 3D FEFLOW Grid	×
EEFLOW Grid: 2D grid: grid Gridding from: SimpleGM Sizelate Gridded Model	v
Select Layer Guides	
Layer Guide	Num Layers
Topography <bottom 'simplegm'="" extents="" of=""></bottom>	2
Minimum <u>I</u> hickness: 20.00 Name: 3D grid	•
Help X Cancel	<u>ер</u> к

The dimensions and resolution of the grid are set by the 2D or 3D grid selected from the **FEFLOW Grid** list. See <u>Creating a 2D FEFLOW Model</u> for information on creating and refining a 2D grid that can be used as the basis for a 3D grid.

The **Gridding from** setting determines the geological model used for layer guides. Ticking the **Evaluate Gridded Model** box will evaluate the new 3D model against the selected geological model and set it as the evaluation for export. See <u>FEFLOW Evaluations</u> for more information. If you do not wish to evaluate the geological model on the grid, untick the box. You will still be able to use the layers in the geological model to control the grid layers.

The FEFLOW grid is initially made up of two layers equally spaced between the topography and the geological model, with the minimum thickness of each layer determined by the **Minimum Thickness** setting. You can add layers to the grid by clicking on the **Select Layer Guides** button and then selecting from the layers available in the geological model:



If the grid is required to follow a geological model lithology contact surface, move the layer into the **Selected** list and it will be honoured in the gridding process.

Click OK to return to the Extrude 3D FEFLOW Grid window. The selected layers will be displayed:

😵 Extrude 3D FEFLOW Grid		×
EFLOW Grid: The Second		•
Gridding from: SimpleGM		•
✓ Evaluate Gridded Model		
Select Layer Guides		
Layer Guide	Num Laye	-
Topography		
	2	
Gravels - Alluvium contacts		
Aquifer Miocene Alluvium - Gravels contacts	1	Ξ
Basement Granite contacts	1	
Contacts	1	
<bottom 'simplegm'="" extents="" of=""></bottom>		-
Minimum <u>T</u> hickness: 20.00		•
Mame: 3D grid		
Help & Cancel	<u> 🖉 о</u> к	

Click **OK** to generate the new FEFLOW grid, which will appear in the project tree under the **Flow Models** folder.

Once the model has been created, you can edit it by expanding the model in the project tree and doubleclicking on its grid object. The layer guides selected, the number defined and the **Minimum Thickness** can be modified, but the FEFLOW grid on which the model is based and the geological model used for gridding cannot be changed.

The boundaries of the selected geological model must be larger than the FEFLOW grid used as the basis for the new model. If this is not the case, you can change the geological model's extents so that they enclose the FEFLOW grid.

For further information on working with the new grid, see:

- FEFLOW Model Display
- FEFLOW Evaluations
- FEFLOW Material Types
- FEFLOW Model Export

FEFLOW Evaluations

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

When a 3D FEFLOW model is exported, the evaluated geological model is used to assign lithologies to the blocks in the grid. If the grid has not been evaluated against a geological model, you must do so before you can edit the material types and before you can export the grid.

To evaluate a FEFLOW grid, expand the model in the project tree. Right-click on the grid object () and select **Evaluations**. Although you can evaluate an interpolant or distance function, they cannot be exported with the grid and are simply used for displaying the grid in Leapfrog Works.

A window will appear listing all objects in the project that can be used for an evaluation. Once you have selected one or more objects, click **OK**. You will then be able to select the evaluations from the view list, as described in <u>Evaluations</u>.

Assigning an Evaluation for Export

For 3D grids created in Leapfrog Works, the evaluation used when creating the grid will automatically be assigned as the evaluation for export. A material types table (IIII) will appear in the project tree as part of the 3D grid.

If the grid was imported into Leapfrog Works or created without being evaluated against a geological model, you will need to manually set the evaluation for export. To do this:

- Evaluate the grid against one or more geological models, as described above.
- Right-click on the model (a) or a) in the project tree and select **Set Evaluation for Export**. The **Select Evaluation** window will appear showing all geological models evaluated on the grid. Select the required evaluation and click **OK**.

A material types table will be added to the FEFLOW grid in the project tree. Edit material types by double-clicking on the table. See <u>FEFLOW Material Types</u>.

Combined Evaluations

You can combine geological models and set the priority used for evaluation. This is useful when you have geological models available that describe different parts of the area of interest or if you have a refined geological model for part of the model. To combine geological models for evaluation, select the required models in the **Select Models To Evaluate** window, then click on the **Combined Evaluation** button.

In this example, there are three geological models selected:

The GM and GM from contacts models describe similar areas, but GM has more detail. The GM larger model describes a larger area but with less detail. Tick the models to combine them and set their priority. Click **OK** to create the combined evaluation, then click **OK** in the **Select Models To Evaluate** window. The combined evaluation will be available from the view list and can be selected as the evaluation for export.

To delete a combined evaluation, click on the **Delete Combined** button in the **Select Models To Evaluate** window.

FEFLOW Material Types

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

When a FEFLOW model is first evaluated against a geological model, a material types table (IIII) is added to the FEFLOW grid in the project tree. You can edit material types by double-clicking on the table. You can also open the table by right-clicking on the grid and selecting **Edit Material Types**.

If the grid has been imported into Leapfrog Works and has not yet been evaluated against a geological model, you will be prompted to do so. Expand the model in the project tree, right-click on the grid object and select **Evaluate Geological Model**. See <u>FEFLOW Evaluations</u> for more information.

If more than one object has been evaluated on the grid, you can set material types separately for each evaluation. Select the required evaluation from the **Evaluation** list:

aniperior 2.5 0.025 4e-6 0.2 asternet franke 0.7 0.7 0.007 1.2e-5 0.3 oarse Sand 1.4 1.4 0.014 2.8e-5 0.1 lacial Till 0.06 0.066 8e-6 0.1 over Gravel 1.47 1.47 0.047 6.7e-5 0.3 over Gravel 1.5 1.5 0.01 6.8e-5 0.3 over Gravel 1.5 1.5 0.047 6.7e-5 0.3 over Gravel 1.5 2.6 0 0 Set Kx value for lithology 'Alluvium' 2.6 0 0	Lithologies in light l	blue are unused an	d will not be exported.				All Li <u>t</u> hologies
intology GM Regional GM Jurvier SimpleGM quifer Moccene Alluvium 2.5 2.5 0.025 4e-6 0.2 assernent Granite 0.7 0.7 0.007 1.4 1.4 0.066 0.0006 8e-6 0.1 caial Till 0.06 0.047 6.7e-5 0.3 ower Gravel 1.5 1.5 0.015 6.8e-5 0.3 Set Kx value for lithology 'Alluvium'				O Interpolant:	O Contamina	nt	
intology GM Regional GM Regional GM quifer Miocene Alluvium 2.5 2.5 0.025 4e-6 0.2 asement Granite 0.7 0.7 0.007 1.2e-5 0.3 osares Sand 1.4 1.4 0.014 2.8e-5 0.1 lacial Till 0.06 0.006 8e-6 0.1 ravel 1.47 1.47 0.447 6.7e-5 0.3 over Gravel 1.5 0.015 6.8e-5 0.3				• <u>V</u> alue:	2.6		
Ideal Interview I				Set Kx value for lit	hology 'Alluvium	(
Image: Constraint of the second sec	Inknown	0	0	0	•	0	
ithology Regional GM Regional GM quifer Miocene Alluvium 2.5 2.5 0.025 4e-6 0.2 assement Granite 0.7 0.7 0.007 1.2e-5 0.3 coarse Sand 1.4 1.4 0.014 2.8e-5 0.1 lacial Till 0.06 0.066 8e-6 0.1	ower Gravel	1.5	1.5	0.015	6.8e-5	0.3	
Ibroim GM Inspired SimpleGM guiler Miocene Alluvium 2.5 0.025 4e-6 0.2 sement Granite 0.7 0.7 0.007 1.2e-5 0.3 oarse Sand 1.4 1.4 0.014 2.8e-5 0.1	iravel	1.47	1.47	0.047	6.7e-5	0.3	
Image: Constraint of the second sec	ilacial Till	0.06	0.06	0.0006	8e-6	0.1	
ithology GM Company Co	oarse Sand	1.4	1.4	0.014	2.8e-5	0.1	
ithology GR Constraints of the second	asement Granite	0.7	0.7	0.007	1.2e-5	0.3	
ithology GM Regional GM			2.5	0.025	4e-6	0.2	
ithology 🔲 GM N							
	Regiona	I GM					
Combined Evaluation							
	Combin	ed Evaluation					

However, the only material types information that will be exported is that set for the evaluation to be exported.

In the **Edit Material Types** window, you can enter the values for material types manually or you can use the values from an interpolant.

Lithology	Kx [m/d]	Ky [m/d]	Kz [m/d]	Drain/ fillable porosity ("specific yield") [volume/volume]	Specific storage due to compressiblity effects [1/m]	
Alluvium	2.6	2.6	0.026	4e-6	0.2	
Aquifer Miocene Alluvium	2.5	2.5	0.025	4e-6	0.2	
Basement Granite	0.7	0.7	0.007	1.2e-5	0.3	
Coarse Sand	1.4		0.014	2.8e-5	0.1	
Glacial Till	0.06	0.06	0.0006	8e-6	0.1	
Gravel	1.47	1.47	0.047	6.7e-5	0.3	
Lower Gravel	1.5	1.5	0.015	6.8e-5	0.3	
lakaawa	0	0	Set Kx value	o for lithology 'Alluvium'	٥	
			• <u>V</u> alue	2.6		
			⊖ <u>I</u> nterp	olant: 💿 Contaminant		

To enter values manually, click on a cell, then enter the value in the **Value** field:

Press the Enter key to move down the columns.

To use the values from an interpolant, click the **Interpolant** button, then select an interpolant from the list. The interpolant that will be used for the selected value will be displayed in the field:

Lithology	Kx [m/d]	Ky [m/d]	Kz [m/d]	Drain/ fillable porosity ("specific yield") [volume/volume]	Specific storage due to compressiblity effects [1/m]
Alluvium	🕘 Kx values 🍗	2.6	0.026	4e-6	0.2
Aquifer Miocene Alluvium	2.5	2.5	0.025	4e-6	0.2
Basement Granite	0.7	07	0.007	1.2e-5	0.3
Coarse Sand	1.4	1.4	0.014	2.8e-5	0.1
Slacial Till	0.06	0.06	0.0006	8e-6	0.1
Gravel	1.47	1.47	0.047	6.7e-5	0.3
ower Gravel	1.5	1.5	0.015	6.8e-5	0.3
Halmour		0	Set Kk value for li <u>V</u> alue:	n thology 'Alluvium' 2.6	0
Lithologies in light blue		11+ b	Interpolant:	🗿 Kx values	All Litholog

To use the interpolant for all the values in the selected column, click the **All Lithologies** button. The window will be updated to show that the interpolant values will be used for that column:

Lithology	Kx [m/d]	Ky [m/d]	Kz [m/d]	Drain/ fillable porosity ("specific yield") [volume/volume]	Specific storage due to compressiblity effects [1/m]	
Alluvium	Kx values	2.6	0.026	4e-6	0.2	
Aquifer Miocene Alluvium	-	2.5	0.025	4e-6	0.2	
	Kx values	0.7	0.007	1.2e-5	0.3	
Coarse Sand	Kx values	1.4	0.014	2.8e-5	0.1	
Glacial Till	Kx values	0.06	0.0006	8e-6	0.1	
Sravel	Kx values	1.47	0.047	6.7e-5	0.3	
ower Gravel	Kx values	1.5	0.015	6.8e-5	0.3	
Inknown	A Kruzhuer	0	0	0	0	
			Set Kx value for lit	thology 'Alluvium'		
			O <u>V</u> alue:	2.6		
			Interpolant:	Kx values		
			 <u>V</u>alue: <u>I</u>nterpolant: 			

Click **OK** to update the grid.

FEFLOW Model Export

This feature is only available with the Hydrogeology extension. See <u>Flow Models</u> for more information.

To export a 3D FEFLOW model as an ASCII format FEFLOW file (*.fem), right-click on the grid in the project tree and select **Export To FEFLOW**. You will be prompted to choose a **File name** and location. Select the options required, then click **Save**.

2D FEFLOW grids cannot be exported.

Presentation

Leapfrog Works has a number of tools for displaying and presenting data for use in reports and presentations.

- Create and export cross sections, fence sections and serial sections. See <u>Sections</u>.
- Create and export contours. See Contour Lines.
- Render and save images for use outside of Leapfrog Works. See Rendered Images.
- Save scenes that demonstrate different aspects of the model and the model-building process. These scenes can then be saved as a movie or as a scene file that can be opened in Leapfrog Viewer. See <u>Saved Scenes</u>.


See <u>Visualising Data</u> for information about the tools available in Leapfrog Works for changing how data is displayed.

Uploading to View

View is a web-based model sharing platform. You can upload Leapfrog Works data to View, visualise the data and organise it into slides. You can also share views with collaborators, all in your web browser, with data saved securely to the cloud. All your collaborators need is a My Seequent ID; a Leapfrog Works entitlement is not required.


There are two workflows for uploading data from Leapfrog Works to View, uploading the data currently displayed in the 3D scene and uploading saved scenes. Both techniques are described below, but first it is important to understand how View handles data objects uploaded from Leapfrog Works.

In this Leapfrog Works scene, we have a number of data objects, including a topography, drilling data, a geological model and its contact surfaces, plus grade shells from a numeric model. Data is sliced.




In View, all elements from the Leapfrog Works scene are displayed in the initial view, which is unsliced. View's slice tool is similar to the slicer in Leapfrog Works, and you can also rotate, pan and zoom the view and measure elements.


With the **Elements** list, you can select which objects to display and how they are displayed:




Once you have set up a view, save it as a slide. In this way, you can organise your data to tell a story and invite feedback from collaborators.



If you have permission to edit the view, you can add feedback and annotations and can create new slides:



To learn more about using View, visit <u>view.seequent.com</u>, where you can explore the View gallery and see what's possible:



The rest of this topic describes:

- Signing in to View
- Uploading to View
- Troubleshooting Connectivity Issues

Signing in to View

Signing in to My Seequent via the **Seequent ID** menu also signs you in to View.

To enable uploading to View, click on the **Leapfrog Works** menu and then on **Settings > User Interface**. Tick the box for **Show View upload**. The **View** button (**W**) will be displayed in the **Scene View** toolbar.

Uploading to View


There are two options for uploading to View:

- Uploading the current 3D view
- Uploading saved scenes

When selecting the data you will upload to View, think about the slides you wish to make in View.

Uploading the 3D View

The first option for uploading to View is to upload some or all of the objects in the 3D scene. To do this, click the **View** button (**V6**) in the toolbar:




A list of the objects currently in the scene is displayed, along with information about the upload size for each object. Objects that are visible in the scene will automatically be selected, whereas any hidden objects will appear in the list but will not be selected.

If an object in the scene does not appear in the list, it is because the upload of that type of object to View is not supported at this time.


The maximum number of objects and the maximum amount of data that can be uploaded are displayed in the window, so if your scene contains large objects or too many objects, you can select which ones you wish to upload. When uploading category data columns to View, there is a limit to how many unique codes can be uploaded. If your category data is displaying more than 250 unique codes, consider simplifying your data before uploading to View.

Once you have chosen which objects you want to upload and entered information about the view, click the **Upload** button.



Upload progress is shown in the notifications menu:

When the upload is complete, a link to View will be displayed in the notification list:



Notifications persist for the duration of your Leapfrog Works session; all notifications are cleared when you exit Leapfrog Works.

Uploading Saved Scenes

To upload one of the scenes in the **Saved Scenes and Movies** folder, right-click on the scene and select **Upload to View**. The process is the same as described in <u>Uploading the 3D View</u> above.

Troubleshooting Connectivity Issues

Seequent Start checks to see if your network will support the connection of Seequent web-based services to your desktop applications. If you are having trouble with your connection to View, see Checking Connectivity With Seequent Start.

Sections

There are four types of sections in Leapfrog Works:

- A typical cross section is a vertical plane with an image or geologic cross section applied to it. In Leapfrog Works, this type of cross section can be created directly in the scene, from the slicer or from an imported image.
- A fence section deviates. In Leapfrog Works, a fence section can be created from a polyline drawn in the scene or from any line object in the project.
- A serial section is a series of typical cross sections taken at an offset from a single base section.
- An alignment serial section uses an imported alignment to create a series of sections along the alignment.

Evaluating on Sections

Different objects in the project can be evaluated on sections, as described in $\underline{Evaluations}$. Such objects include:

- Geological models
- Numeric models
- Distance functions
- Surfaces
- Design lines
- GIS lines
- Polylines
- Combined models

When evaluating objects on sections, you can limit the evaluation to the section extents. To do this, enable the **Clip evaluations to section extents** option when selecting what objects you are evaluating.

Flow models can be evaluated on cross sections but not on serial sections and fence sections.

Objects evaluated on sections can be included when the section is exported.

Exporting Sections

Sections can be exported in the following formats:

- DXF Files (11/12 [AC1009]) (*.dxf)
- Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

Exporting a section as a DXF file (*.dxf) exports a series of DXF lines created from the intersection of the evaluation volumes and the section plane. The lines generated from each volume are saved as separate layers in the file.

For serial sections, the section will be exported in a single file with a collection of DXF lines based on intersections between the selected evaluation and the section planes.

To export a section in one of these formats, right-click on the section in the project tree and select **Export**. In the window that appears, select the evaluations you wish to export with the section:

meral 2D	Analysis		
elect Obj	ects		
Objects		Name	
\checkmark			
· ·	tions		
Select <u>#</u> xport Op <u>F</u> ormat: Folder:		· ·	

The **2D** Analysis tab contains two options, Flatten to **2D** and Simplify.

When you enable the **Flatten to 2D** option, the section will be flattened into the X-Y plane, making Z uniform across the section. You can change the origin, if required. The **Flatten to 2D** export option is available for:

- Regular cross sections
- Cross sections created from images
- Child sections of serial and alignment sections

The **Simplify** option is useful when the file is being exported for use in finite element slope stability packages. Enabling **Simplify** evens out the node spacing for model and line evaluations by setting a minimum allowable distance between nodes. Increasing the **Minimum spacing** setting reduces the number of nodes included but can result in loss of detail.

Enter a filename and location, then click **Save**.

Exporting Section Layouts

Another way to export a section is to create a section layout and then export it as a PDF file (*.pdf), Scalable Vector Graphics file (*.svg), PNG image (*.png) or GeoTIFF (*.tiff, *.tif). This option is more flexible than exporting the section as a DXF file as you have more control over the section layout. You can customise the page layout and include multiple evaluations and annotations. For typical cross sections and serial sections, you can also display boreholes and planned boreholes. See the <u>Section</u> Layouts topic for information in using the section editor.

Once you have finished adjusting the section layout, you can export it in one of the following formats:

- PDF Files (*.pdf)
- Scalable Vector Graphics Files (*.svg)

- PNG Image Files (*.png)
- GeoTIFF Files (*.tiff, *.tif)

Click the **Save and Export** button () at the top of the window. You will be prompted for a filename and location.

For serial sections and alignment serial sections, you can batch export multiple section layouts. All selected sections can be exported as a single PDF or individually in PDF file (*.pdf), Scalable Vector Graphics file (*.svg), PNG image (*.png) or GeoTIFF (*.tiff, *.tif) formats. When section layouts are exported individually, all outputs can be combined into a zip archive. To do this, right-click on the **Cross Sections and Contours** folder and select **Batch Export Layouts**.

In the window that appears, selection the layouts you wish to export, then select a format. If you select a format other than Single PDF, you can combine all outputs into a zip archive. Select where you wish to save the outputs, then click **Export**. Progress will be displayed at the top of **the Batch Export Section Layouts** window:

	Rendering Layout 6 of 17	Cancel
Select Objects		
Objects		Filenames

Creating Cross Sections

To create a cross section in the scene, add a model to the scene. Next, right-click on the **Cross Sections and Contours** folder and select **New Cross Section**. The **New Cross Section** window will appear, together with a section plane and controls in the scene that let you adjust the position of the section plane:

🔗 New Ci	ross Section			×
Location:	1185915.5319 , 4	909368.7777	, 112.49560547	
<u>W</u> idth:		<u>р</u> ір:	90	Ŷ
<u>H</u> eight:		Dip a <u>z</u> :	180	•
	Swap <u>F</u> ront		🌋 🚺 🔪 🛛	8
<u>N</u> ame:	4909368.778 North			
He E	elp		<u>Cancel</u>	

If the slicer is already in the scene when you select **New Cross Section**, the position of the slicer will be used to define the initial orientation of the section. This is an effective way of creating a section from the slicer: add the model to the scene, draw a slice and then create a cross section.

The front (F) and back (B) of the section plane is indicated in the scene. To swap the front and back, click the **Swap Front** button.

Use the handles in the scene to position the section plane. The handles work in the same manner as the moving plane controls, as described in <u>The Moving Plane</u>.

Two buttons in the **New Cross Section** window let you create a cross section that is aligned north-to-south (*) or east-to-west (*):

Location:	1185915.5319	, 4909	9368.7777	, 112.49560	547
<u>W</u> idth:	9890	\$	<u>D</u> ip:	90	Ŷ
<u>H</u> eight:	825	\$	Dip a <u>z</u> :	180	•
	Swap Erc	ont			
Name:	4909368.778 Nor	th			

The other two buttons are active when the slicer is in the scene. Clicking the **Set section to slicer** button (\mathscr{P}) creates a cross section from the position of the slicer in the scene. When the **Lock section to slicer** button (\mathscr{P}) is enabled, moving the position of the slicer will update the position of the cross section in the **New Cross Section** window.

Once the section plane is positioned as required, click **OK** to create the new cross section, which will appear in the **Cross Sections and Contours** folder. Display it by clearing the scene, then adding the cross section to the scene.

Many objects in a project can be evaluated on cross sections, as described in <u>Evaluations</u>. Such objects include:

- Geological models
- Interpolants
- Distance functions
- Surfaces
- Design lines
- GIS lines
- Polylines

Objects evaluated on a cross section or fence section can be included when the section is exported.

Importing Cross Sections

See Importing a Map or Image for more information on importing images into Leapfrog Works.

Leapfrog Works supports the following file formats for creating cross sections:

- PNG files (*.png)
- JPEG files (*.jpg, *.jpeg)
- TIFF and GeoTIFF files (*.tiff, *.tif)
- Windows Bitmap files (*.bmp)
- Graphics Interchange Format files (*.gif)

As with other images imported into Leapfrog Works, you can import a single cross section image or multiple images.

To import a single cross section image, right-click on the **Cross Sections and Contours** folder and select **New Cross Section From Image**. Navigate to the folder that contains the image, select the file and click **Open**.

- If the image contains georeference data, it will be imported into the **Cross Sections and Contours** folder.
- If the image does not contain georeference data, the **New Cross Section From Image** window will be opened so you can add the georeference data. See <u>Manually Georeferencing Images</u>. Once you have georeferenced the image, click **Import**. The image will be imported into the **Cross Sections** and **Contours** folder.

There are two ways to import multiple cross section images:

- Right-click on the Cross Sections and Contours folder and select New Cross Section From Image. Navigate to the folder that contains the files you wish to import. Select the images and click Open. The images will be imported and added to the Cross Sections and Contours folder.
- In the File Explorer, select all the files you wish to import. Drag and drop them into the **Cross Sections and Contours** folder in Leapfrog Works.

All images will be imported and added to the **Cross Sections and Contours** folder. If an image does not contain georeference data, you will need to open the image and add the information manually, as described in <u>Manually Georeferencing Images</u>.

Once you have created a cross section, you can edit it or use it to evaluate geological models, interpolants, distance functions and surfaces. See <u>Evaluations</u>.

Fence Sections

You can draw a polyline or use any existing line object in the project to create a cross section that deviates. To do this, right-click on the **Cross Sections and Contours** folder and select **New Fence Section**. The **New Fence Section** window will be displayed:

😰 New Fer	nce Section	×
Fence Line	From <u>Polyline</u> <u>Existing</u> Line	
🗏 G	IS line	
Section Ele	evation	
<u>T</u> op:	524.991	
<u>B</u> ottom:	-300	
<u>N</u> ame		
Fence Se	ection	
Hel	p 🔀 Cancel 🥥 QK	•

You can draw the polyline in the scene directly by selecting the **New Polyline** option. You can also use any polyline in the project by selecting the **Existing Polyline** option.

Only GIS lines, polylines imported into Leapfrog Works or polylines created using the straight line drawing tool can be used to create fence sections.

Click **OK** to create the fence section. If you chose to create a **New Polyline**, the drawing controls will appear in the scene and you can begin drawing, as described in <u>Drawing in the Scene</u>.

The fence section will appear under the **Cross Sections and Contours** folder and you can edit it by double-clicking on it. You can also use it to evaluate different objects in the project, as described in <u>Evaluations</u>. Such objects include:

- Geological models
- Interpolants
- Distance functions
- Surfaces
- Design lines
- GIS lines
- Polylines

If you create a section layout for a fence section, you can include multiple evaluations and annotations on the section layout. See <u>Section Layouts</u>.

Serial Sections

This topic describes the process of creating a serial section, which is a series of cross sections taken at an offset from a single base section. The topic is divided into:

- Setting the Base Section
- Setting the Offset Sections
- The Serial Section in the Project Tree
- Displaying a Serial Section
- Exporting a Serial Section

To create a serial section, add a model to the scene. Next, right-click on the **Cross Sections and Contours** folder and select **New Serial Section**. The **New Serial Section** window will appear and planes representing the base section and the offset sections will be added to the scene:

🙎 New Seria	l Section	×		
Base Section	ı			
Location:	1185915.5 , 49093	68.8 , 62.495605	8000 (X)	
<u>W</u> idth:	9890	<u>D</u> ip: 90		0000
<u>H</u> eight:	925	Dip a <u>z</u> : 180	A CONTRACTOR OF THE REAL	4000 0000
	Swap <u>F</u> ront			"ATTACK B
Offset Section	ons			8
Spacing:	336.541		3	
Extents	Distance	Sections		
Front:	3365.414	10	-	
<u>B</u> ack:	3365.414	10		Plunge +19 Azimuth 133
	<u>E</u> nclose Object ∨	21 total	······································	Mudstone
				Slice mode: From Scene
<u>N</u> ame:	4909368.8 North Serial Sec	tion	🖌 📣 📖	✓ Fill Slicer
Help		<mark>∭</mark> Cancel 🥠 🖉 OK		=

If the slicer is already in the scene when you select **New Serial Section**, the position of the slicer will be used to define the initial orientation of the base section.

Setting the Base Section

The handles in the scene control the position of the base section and work in the same manner as the moving plane controls (see <u>The Moving Plane</u>).

The front (F) and back (B) of the base section plane are indicated in the scene. To swap the front and back, click the **Swap Front** button.

Two buttons in the **New Serial Section** window let you create a base section that is aligned north-tosouth (O) or east-to-west (O). The other two buttons are active when the slicer is in the scene. Clicking the **Set section to slicer** button (\swarrow) creates a cross section from the position of the slicer in the scene. When the **Lock section to slicer** button (\bigotimes) is enabled, moving the position of the slicer will update the position of the cross section in the **New Serial Section** window.

Setting the Offset Sections

The number of offset sections is determined by the value of the **Spacing** setting and the **Front** and **Back Extents**:


Location:	1185915.5 , 4909	368.8 , 62.495605
<u>W</u> idth:	9890	<u>D</u> ip: 90
Height:	925	Dip a <u>z</u> : 180
	🔊 Swap <u>F</u> ront	
)ffset Sectio	ons	
Spacing:	336.541	
Extents	Distance	Sections
Front:	3365.414	10
<u>B</u> ack:	3365.414	10
	Enclose Object V	21 total

You can change the number of offset sections by:

- Changing the **Spacing** setting. The number of offset sections will be recalculated and updated in the scene.
- Changing the **Front** or **Back** settings. For example, increasing the **Front** setting adds an offset section on the front of the base section, increasing the extents by the value of **Spacing**.
- Changing the object used to define the extents. Select an object from the **Enclose Object** list. The base section will be moved to the centre of the selected object.

The Serial Section in the Project Tree

Click **OK** to create the section. In the project tree, the serial section includes the individual cross sections:




Many objects in a project can be evaluated on serial sections, as described in <u>Evaluations</u>. Such objects include:

- Geological models
- Interpolants
- Distance functions
- Surfaces
- Design lines
- GIS lines
- Polylines

Displaying a Serial Section

When you display a serial section in the scene, you can add the slicer to the scene and use it to move easily between the sections in the stack. To do this, click on the slicer in the shape list, then select the base section from the **Set to** list:



Next, set the **Step size** to the **Spacing** setting used to create the section. You can then use the < and > keys to view each individual cross section.

Exporting a Serial Section

The options for exporting serial sections differ for the section itself and the offset sections:

- A serial section cannot be used to create a section layout. When exported as a DXF file, the serial section will be exported in a single file with a collection of DXF lines based on intersections between the selected evaluation and the section planes.
- The offset sections that make up a serial section can be exported in DXF format or as a section layout. See <u>Exporting Sections</u> and <u>Section Layouts</u> for more information.

Alignment Serial Sections

An alignment serial section can be created using an alignment imported into the **Designs** folder, a polyline or a GIS line. When creating an alignment serial section from a polyline, you can use an existing polyline or draw a new one.

This topic describes the process of creating and working with an alignment serial section. It is divided into:

- Creating an Alignment Serial Section
- Displaying an Alignment Serial Section
- Exporting an Alignment Serial Section

Creating an Alignment Serial Section

To create an alignment serial section, right-click on the **Cross Sections and Contours** folder and select **New Alignment Serial Section**. The **New Alignment Serial Section** window will appear. Select whether you will use an existing line or create a new one.

Using an Existing Line

If you select an existing line, planes representing the base section and the offset sections will be added to the scene:

 New Alignment Serial Section X Alignment Serial Section From 	
○ New Polyline ● Existing Line	
Tunnel: Alignment	
Base Section	
Width: 50 C Swap Start	+4891200
Height: 50	500 +44891000 +44891000
Left of Line: 0	44 88 448
Above Line:	00 1485008000 1485008000 1485008000 1485008000 1485008000 1485008000 1485008000 1485008000 1485008000 148500800
	87 00990687 00 Elev (Z)
Alignment Chainage	e e e e e e e e e e e e e e e e e e e
Start Chainage: 1500	26 2
Offset Sections	+++489C 4890200 mm 4890200 mm 1644600 +1164600
Entire Line Line Section	
Ch <u>a</u> inage Spacing: 250	110
Line Section Start: 1500	Ш
Line Section En <u>d</u> : 3580	colour V Alignment
Name Alignment	Slice mode: From Scene

Once you have created an alignment serial section, you can change all settings except the line used.

The **Base Section** parameters determine the size of the sections and the **Offset Section** parameters determine how the sections are distributed along the selected line.

- Swap the start and end points of the selected line by clicking the Swap Start button.
- Generate sections along only part of the line by selecting **Line Section**, then changing the **Start Chainage** and **End Chainage**.

You can set a **Start Chainage** value that will be assigned to the first point of the line being used for the alignment.

All changes you make in the **New Alignment Serial Section** window will be displayed in the scene. Click **OK** to create the section.

Using a New Polyline

If you have chosen to create a **New Polyline**, set the **Base Section** and the **Offset Section** parameters, then click **OK**. Drawing controls will appear in the scene and you can begin drawing, as described in <u>Drawing in the Scene</u>.

Once you have finished drawing the polyline, click the **Save** button (a). The offset sections will be generated and will appear in the project tree. Double-click on the section in the project tree to edit its settings.

The Alignment Serial Section in the Project Tree

In the project tree, the alignment serial section includes the individual offset sections and the line used to create it:

▼ Cross Sections and Contours
★ Alignment
SECTIONS
第 1500.0
第 2000.0
第 2250.0
第 2250.0
第 2250.0
第 2500.0
第 2500.0
第 3500.0

Many objects in a project can be evaluated on serial sections, as described in <u>Evaluations</u>. Such objects include:

- Geological models
- Interpolants
- Distance functions
- Surfaces
- Design lines
- GIS lines
- Polylines

Displaying an Alignment Serial Section

Add the top-level section to the scene to view all the offset sections. You can also view individual offset sections.

If a master section layout has been created for an alignment serial section, dragging the master section layout into the scene displays all sections that use that layout.

Exporting an Alignment Serial Section

Alignment serial sections can be exported in the following formats:

- DXF Files (11/12 [AC1009]) (*.dxf)
- Drawing Files (2013/LT2013) (*.dwg)
- Bentley Drawing Files (v8) (*.dgn)

The DXF format exports a single file with a collection of DXF lines based on intersections between the selected evaluation and the section planes.

The offset sections that make up an alignment serial section can also be exported as a section layout. See <u>Section Layouts</u> for more information.


Section Layouts

With the **Section Layout Editor**, you can create a section layout for an existing section and then export the section. You can customise the section layout by:

- Adding models, surfaces and lines the section has been evaluated against
- Adding boreholes and planned boreholes
- Changing the page size, orientation and margins
- Adding titles, a scale bar, legends, annotations and images, such as a standard form or logo

The appearance of all objects can be customised without changing how objects from the project tree are displayed in the scene.

Section layouts can be displayed in the scene by dragging a layout into the scene:



Some sections will be too large to display in the scene, which will be indicated in the section layout editor.

Displaying section layouts in the scene is useful when you are editing a section layout and wish to see the effect of changes. Detach the section layout tab from the main window and position it adjacent to the scene window. Periodically save your changes to the section layout to see the effects of those changes in the scene.

This topic describes how to work with section layouts. It is divided into:

- Setting Up the Section
- <u>Creating New Section Layouts</u>
- <u>Creating Master Section Layouts</u> (alignment serial sections only)
- <u>Copying Section Layouts</u>
- Working With the Section Layout Editor


- Changing Page Properties
- Changing the Basic Section Properties
- Organising Objects on the Section
- Setting Up the Legend
- Adding and Organising Annotations

Setting Up the Section

Once you have created a section but before you start creating the section layout, take the following steps.

1. Check the section's extents and orientation.

The initial dimensions of the section on the page are determined by the size of the section plane, and its orientation on the page is determined by the front (F) and back (B) faces of the section plane. Here, the front and back faces of the section have been swapped, which results in the section displayed on the page being flipped:



2. Check that the section has been evaluated against objects you wish to display on the page.

To do this, right-click on the section in the project tree and select **Evaluations** or **Evaluate Surface**.

3. Add planned boreholes to the project.

Planned boreholes can be displayed on the section, but these must be defined before you start the process of laying out the section.

Creating New Section Layouts

To create a new section layout, right-click on an existing section in the project tree and select **New Section Layout**. The **New Section Layout** window will appear, together with the **Section Layout Editor**:

Name: 4890322.5 North L	ayout 😰 New Section Layout 🛛 🗙 🔛	
ayout Tree Page Section Models Boreholes Surfaces Lines	Scale Scale 1: 12000) Eit to Page Project Linits: Metres Vertical Exaggeration: 1 Page Properties	4890322.5
 Legend Group Annotations Title Title Block 	Page size: A4	
No selection	Evaluations Selected Models: Selected Surfaces:	
	Select Models Select Surfaces	1165200 1164700
	Select Lines Extents O Section Extents O Evaluation Extents	

The settings in the **New Section Layout** window determine the basic section layout:

- The **Scale** settings determine the scale used to display the section on the page. If you want a specific page size, select **Fit to Page** to set a scale that best fits the page width. You will be able to change the page margins once you have closed the **New Section Layout** window.
- The **Page Properties** settings determine the page size and orientation. If you wish to use a specific **Scale**, select the **Orientation** required, then click **Fit to Section** to choose the best page size.
- For **Evaluations**, select from the models, surfaces and lines the section has been evaluated against. When you select an evaluation, it will be added to the preview.
- For Extents, choose whether to use the Section Extents or Evaluation Extents. If you wish to use the extents from a model evaluation, add only that model to the Models, Surfaces or Lines list, then select the Evaluation Extents option. Once you have closed this window, you will be able to add further models, surfaces and lines using the section layout editor.

As you change settings and add objects to the section, the preview in the **Section Layout Editor** window will be updated. All settings in the **New Section Layout** window can be changed once the layout has been created.

Click **OK** to close the **New Section Layout** window. You can then make further changes to the page layout in the **Section Layout Editor**. See Working With the Section Layout Editor.

Copying Section Layouts

If you have already created a section layout and wish to reuse it, you can copy it to other sections.

For alignment serial sections, creating a master section layout is an alternative to duplicating and managing multiple section layouts. See <u>Creating Master Section Layouts</u> for more information.

Copying a section layout copies the evaluations used in the original section layout, together with the page size and orientation and the position of the **Layout Tree** objects on the page. How models, surfaces and boreholes are copied depends on the section to which the layout is being copied:

- All models and surfaces that can be displayed on the section will be copied.
- The boreholes copied to the layout will depend on the type of section the layout is being copied from and whether or not a filter is set for the layout:
 - If no distance filter was set for the original layout, all boreholes selected for the original layout will be copied.
 - If a distance filter was applied to the original section, the filter will be applied and boreholes selected that are within that distance of the section to which the layout is being copied.
 - When the original layout is from an alignment serial section or a fence section, borehole evaluations will not be copied with the section layout.

To copy a layout, right-click on the layout you wish to copy and select **Copy Layout To**. In the window that appears, a summary of the information that will be copied is displayed so you can see what information will be copied to the selected sections. Move the sections you wish to copy the layout to into the **Selected Sections** list, then click **OK**. A copy of the layout will appear in the project tree under each section you selected. The layout copies are not linked to the original layout and so will not be updated when the original is updated.

Copying section layouts to multiple sections can result in numerous section layouts in a project, which can be difficult to work with. The recommended workflow for creating a section layout that you intend to make multiple copies of is to first get the layout right on one section before copying it to other sections.

Creating Master Section Layouts


For alignment serial sections, you can create a master section layout and apply this master layout to all the child sections of an alignment section. When the master layout is updated, changes will be reflected wherever it has been applied. To create the master section layout, right-click on the top-level section and select **New Master Section Layout**.

The master section layout editor works the same way as the standard layout editor. When you save the layout, it will be stored as part of the alignment section, separately from the child sections and evaluations. To copy the master layout to child sections, right-click on it and select **Copy Master Layout To**. The master layout will be applied to the selected child sections.

You can edit the child layouts that are linked to the master layout, but doing so will break the link to the master layout; the child layout will no longer be updated when changes to the master layout are made.


Working With the Section Layout Editor

In **Section Layout Editor**, the **Layout Tree** shows the different layers that can be added to the page. The different parts of the **Layout Tree** as they relate to the page preview are shown below:




When you select an object in the layout tree, it will be highlighted by a blue line on the page. In the example above, the **Section** object is selected.

Click on an object in the page preview to move or resize it. This will also select the object in the **Layout Tree** and you can see what properties can be changed. For example, in the preview, click on the **Title** to view its styling options:



Text displayed in the section layout is controlled by a style sheet that can be accessed whenever you are editing a text object. For example, clicking on **Edit Styles** for the **Title** opens the list of **Text Styles**

with the **Title** selected, but also allows you to change the appearance of styles used for other text objects visible in the preview:



Changing Page Properties

In the Layout Tree, click on Page to change the Page Size, Orientation and Margins:

Layout Tree			
📄 Page 🕯			
▼ 🚿 Section	n		
🕨 📄 Mo	dels		
🕨 🖿 Dril	Iholes 7		
🕨 📄 Sur	faces		
🕨 📄 Line	- /		
🕨 📰 Legend	d Group		
🛡 🚞 Annot			
🛕 Titl			
🔺 Titl			
*	le Ba		
Tex			
lm Im			
Page	10		
Page si <u>z</u> e:	A4	✓ <u>Fit to</u>	Section
Orient <u>a</u> tion:	Landscape		~
Dimensions:	297 , 210		
Margins			
1	Г <u>о</u> р: 10 🗘		
L <u>e</u> ft: 20	0	<u>R</u> ight	
Bott	om: 10 🗘		

If you wish to use a specific **Scale**, select the **Orientation** required, then click **Fit to Section** to choose the best page size.

Changing the Basic Section Properties

To change the section layout's basic properties, click on the **Section** object in the **Layout Tree**. In the **Section** tab, you can change the scale and units used in the layout and the amount of **Vertical Exaggeration**:

ayout Tre	e					
📄 Pag						
• 🧊 Sec	tion					
Anr	end Group notations		-111			
🖇 Sect	ion					
ection	Extents >	(- <u>A</u> xis	<u>Y</u> -Axis			
	<u>E</u> xtents	<- <u>A</u> xis	<u>Y</u> -Axis			
Section Scale Scale		<- <u>A</u> xis	<u>Y</u> -Axis	Ŷ	<u>F</u> it to I	Page
Scale Scale		<- <u>A</u> xis		0	Eit to I	Page

For the **Scale**, you can enter a specific value to use in displaying the section on the page, or, if you want a specific page size, select **Fit to Page** to set a scale that best fits the page width.


If you want to change the page size and the margins used, click on the **Page** object.

To change the size of the section contents (models, boreholes, surfaces and lines) on the page, click on the **Extents** tab:


Layout Tre	e			
📄 Pag	e			
► 🥵 Sect	tion			
🕨 🗄 Leg	end Grou	р		
🕨 🚞 Anr	notations			
			111	
🧊 Sect	ion			
Section	Extents	X- <u>A</u> xis	<u>Y</u> -Axis	
Extents				
• Se	ction Exte	ents		
⊖ <u>E</u> v	aluation l	Extents		
Section	Adjustm	ents		
Additi	onal <u>s</u> ky:	5	0	
Sh	iow e <u>n</u> d p	oint labe	els	
	<u>O</u> pt	ions		=

For Extents, choose whether to use the Section Extents or Evaluation Extents.


You may wish to add more space above the section, especially if you will be adding boreholes to the section and need extra space for the collar labels. To do this, change the **Additional sky** setting. These images show the effects of two different **Additional sky** settings:




Enable **Show end point labels** to display the section's end points as text:



Click **Options** to change how the end points are displayed relative to the section's axes. There are two options that control where the end points are displayed, **Points above** and **Points aligned inside**. The **Points above** setting determines whether the end points are displayed above or beneath the axes. Note here the difference between **Points above** being disabled and enabled:



The **Points aligned inside** setting determines whether the end points are displayed inside or outside the section's axes:




You can also change the spacing between the end point labels and the section axes.

Edit the text used to display the end points by enabling the **Edit** box and then changing the text. You can edit the style used for displaying the labels by clicking **Edit Styles** to change the style or by selecting a different style from the dropdown list.

	Lef	t Label	😢 End Point Optio	ns X
	I		✓ Points above	Points aligned inside
400 -	_		Vertical spacing: <u>H</u> orizontal spacing:	4 ····
		rolenic not	S Labels: ✓ <u>E</u> dit	
200 -	-	Ĭ		Left Label
	Gravel nestone	Gravel	<u>R</u> ight label:	Right Label
-0 –	orite sill o	Limestone Schist Quartz diorite sill	End Point Label	Celit Styles
	Schist	Schist		X Close
-200 -				

To change how the axes are displayed, click on the either the **X-Axis** tab or the **Y-Axis** tab. One of the options available for the axes is how much information is displayed for the **Real World Coordinates** on each axis:



You can also change how **Grid Lines** are displayed, including the **Line style**, **Line width**, **Pattern scale** and colour. A **Preview** is displayed and the grid lines are updated in the section preview.

🧊 Secti	on		
Section	<u>E</u> xtents	X- <u>A</u> xis	<u>Y</u> -Axis
	World Co		es
✓ <u>G</u> rid	Lines		
<u>L</u> ine st	yle:		
Line w	i <u>d</u> th: 0.	2 🗘	Pattern scale: 2.0
Preview	w: -		
Axis			
V Pri	mary	🗸 Lab	els 🗹 Ticks 🗹 Outside
Se	condary	🔽 Lab	els 🗹 Ticks 🗹 Outside

By default, the axes are displayed only on the left-hand side and along the bottom of the section. To display axes along the right-hand side and above the section, tick the **Secondary** option.

For the Ticks ,	Leapfrog	Works automatically	calculates an	Initial Value:
------------------------	----------	---------------------	---------------	----------------

xis		
Primary	🗸 Labels 🗸 Ticks	✓ Outside
Secondary	🗸 Labels 🗸 Ticks	✓ Outside
icks		
Tick Length:	3	\$
Ti <u>c</u> k Spacing:	1000	Aut <u>o</u>
Initial <u>V</u> alue:	1184000	Ĵ
Start <u>V</u> alue:	0	0
abels		
Offset: 3	🗘 Suffix:	
Decimal Places	: 0	0 🗸 Auto

If you wish to change this, disable Auto and enter the required value.

If you wish to set an X-axis **Start Value** other than 0, you must first disable the **Real World Coordinates** option:

3 Section
Section Extents X-Axis Y-Axis
Real World Coordinates
✓ Grid Lines
Line style:
Line width: 0.2 C Pattern scale 1.0 C
Preview:
Axis
🗸 Primary 🗸 Labels 🗸 Ticks 🗸 Outside
Secondary 🗹 Labels 📝 Ticks 🗹 Outside
Ticks
Ti <u>c</u> k Length: 3
Ti <u>c</u> k Spacing: 1000
Initial Value: 11000 🗘 🗸 Auto
Start Value: 1000
Labels
Offset: 3 🗘 Suffix:

Edit the style used for displaying the axis labels by clicking **Edit Styles** to change the style or by selecting a different style from the dropdown list.

Organising Objects on the Section

The folders below the **Section** object are used to add and organise models, boreholes, surfaces and lines and to customise how they are displayed:


La	yout Tree	
	📄 Page	
₹	Section	
	Models	
	Boreholes	
	Surfaces	
	Lines	
▶	E Legend Group	
▶	annotations	

If you selected models, surfaces and lines when you created the section, they will appear in one of these folders. You can add new objects by right-clicking on a folder and selecting an **Add** option:



- For the **Add Model**, **Add Surface** and **Add Line** options, you will be able to choose from the objects that have been evaluated on the section. See Evaluating on Sections for more information.
- For the **Boreholes** folder, there are two options, **Add Boreholes** and **Add Planned Boreholes**. For both options, you can choose from the boreholes and planned boreholes available in the project; it is not necessary to evaluate these onto the section before you can add them to the layout.

Models, boreholes, surfaces and lines occupy the same space on the section layout, and opacity settings and an object's position among the layers can be used changed to emphasise relevant information. To change the order of objects on the page, right-click on them and select an option:



Models will always be among the lower layers, with lines on top of all the other layers.

You can remove objects from the layout by right-clicking on them and selecting **Delete**.

To change the opacity of an object, click on it, then adjust the object's **Opacity** using the slider:

Layout Tree	
Page	
▼ 🗯 Section	
🛡 🛅 Models	
🕨 🊺 GM	
Combined Model	
🛅 Boreholes	
Surfaces	
Lines	
Legend Group	
Annotations	
M	
🧭 Combined Model	
✓ <u>V</u> isible Opacity:	0.50
	~~


Adding and Styling Models

The **Models** folder contains all models that have been added to the section layout. To add another model, first make sure it has been evaluated on the section, then right-click on the **Models** folder and select **Add Model**. Select from those available and click **OK**.

When you display multiple models on the section, you can end up with a large number of objects that obscure the information you want to emphasise. You can:

- Use the **Opacity** setting for each model to expose and emphasise information.
- Right-click on the models to move them up or down in the layer hierarchy.
- For geological models, numeric models and combined models, expand the model in the **Layout Tree** to change how each output volume is displayed. You can also hide some of the output volumes.
- For flow models, you can hide categories or filter the values used to display the model


If a geological model with an active fault system is added to the section layout, it will include a **Fault System** that contains all the active faults in the model. Click on the **Fault System** to control whether or not it is **Visible** and to set is **Opacity**:




Click on the individual faults to control how they are displayed:

Layout Tree	2
Page	
▼ 👹 Section	
▼ 🛅 Models	
🛡 🊺 GM	-
Surfaces	
🛡 🚔 Fault System	
Fault 2	
🗝 Fault 3	
- Fault 4	
- Fault 5	
Output Volumes	~
Fault 2	
☑ <u>V</u> isible	
Description: 🗌 Edit	
Fault 2	
Line style:	
Line wi <u>d</u> th: 0.5	1.0 🗘
Add <u>m</u> arker	
Preview:	


Edit the fault's **Description** by enabling the **Edit** box and then changing the text. You can also change how the fault is displayed, including the **Line style**, **Line width**, **Pattern scale** and colour. You can also define a marker to display along the line by enabling **Add marker** and then specifying a **Symbol** to use. A **Preview** is displayed and the fault will be updated in the section preview:




For the volumes in the **Output Volumes** folder, line, border and swatch properties by clicking on the volume in the **Layout Tree** and then changing their properties. Swatches for output volumes can be displayed using a hatched fill. To do this, click on the volume, enable the **Hatch** option and click on the sample to view the available patterns:




A single line style is used to display a model's output volumes. There is, however, a **Highlight** option that can be enabled to make a volume of interest stand out from the other volumes:




Another way to emphasise a particular volume is to use the surfaces in the model's **Surfaces** folder. This folder contains a single surface for every contact with the section, rather than a single surface for each contact surface in the model:



It can result in a large number of surfaces to work with, but does provide you more control over how these surfaces appear on the section layout. For example, here the outline of the GnD volume can be shown in different styles (as with the D2 contact) or not at all (as with the Dike contacts):



You can display a contact surface on a section layout as a surface evaluation, but you can have only one line style and you don't have control over what parts of the surface are displayed. For example, you cannot hide the surface where it is intersected by the dike:



Flow models appear in the **Models** folder as a single object. They can be displayed using a flat colour or any of the **Colouring** options available for the model:

Layout Tree	^				
Page					
▼ 🗯 Section	=				
▼ 🛅 Models					
▶ 🚺 GM					
Value					
Ontaminant					
III modflow					
Boreholes	~				
modflow					
✓ Visible Opacity:					
✓ Show edge lines					
Line style:					
Line wi <u>d</u> th: 0.2 C Pattern scale: 1.0 C					
✓ <u>F</u> ill					
Colouring: 🔒 Flat colour					
🔂 Flat colour					
🍫 SimpleGM_Initial Head					
🍫 SimpleGM_Kx					
🍫 SimpleGM_Ky					
🍫 SimpleGM_Kz					
🍫 SimpleGM_Ss					
🍫 SimpleGM_Sy					
🗲 SimpleGM					
🕒 Contaminant					
🕒 value					

Click **Options** to change the colours used to display the model:

- For category evaluations, you can change what categories are visible and the colours used to display them.
- For numeric evaluations, you can filter values and use a different colourmap.

For example, here, a MODFLOW model is displayed using the **Colouring** from an evaluated geological model:

Layout Tree	Â			
Page				
🖉 🥵 Section	=			
▼ 🛅 Models			w	
III modflow				
▼ 🚺 GM				×
Surfaces		BIOCK CO	louring Legend	
🕨 😂 Fault System		Colou	Name	
Output Volumes			Coal	
Sulfur structural trend			Conglomerate	
Combined Model	~		Fault Block 2 Unit 0	
modflow			Fault Block 2 Unit 1.5	
			Fault Block 2 Unit 2	
☑ <u>V</u> isible Opacity:			Fault Bock 2 Unit 1	
			Gravels	
✓ Show edge lines			Limestone	
Line style:			Mudstone	
			Unknown	118
Line width: 0.1 Determ scale: 1.0		┫ —		
Preview:				
			<u>S</u> <u>C</u> lo	se
Colouring: 🗲 GM 🛛 🗸 Option	ns			

The colours used to display categories cannot be changed in the **Block Colouring Legend** as they are the colours used by the evaluated model itself. You can, however, hide some categories so they are not displayed on the section layout.

Here, the MODFLOW model is displayed using the **Colouring** from an evaluated numeric model:

Layout Tree	
Page	
V 🗯 Section	
V 🛅 Models	W
III modflow	
🛡 🊺 GM	
Surfaces	400 -
🕨 😂 Fault System	
Output Volumes	😢 Block Colouring Legend 🛛 🗙
Sulfur structural trend	
Combined Model	Colourmap:
modflow	□ <u>V</u> alue filter: -2.9280312 ⁽) - 5.83758330 ⁽)
✓ Visible Opacity:0.70	Display style
	Solid Bar graph Line graph
✓ Show edge lines	
Line style:	X ⊆lose 1185000 1186000
Line width: 0.1 Dettern scale: 1.0 C	
Preview:	
I Eili	
Colouring: 🗟 Sulfur structural trend 🗸 Options	

You can change the **Colourmap** used to display the model on the section and you can filter the values displayed.

If a flow model is too big for the section layout, changing the section extents or the section layout extents will effectively "crop" the flow model and make it small enough to display on the section layout. There are two ways to do this:

• Change the section layout extents by clicking on **Section** in the **Layout Tree**, then clicking on the **Extents** tab. If **Extents** is set to **Evaluation Extents**, change it to **Section Extents**.

• Change the size of the section by double-clicking on it in the project tree and then editing its dimensions in the scene.

Adding Styling Boreholes and Planned Boreholes

The **Boreholes** folder contains all boreholes and planned boreholes that have been added to the section layout. Up to three columns of data can be displayed, and numeric data can be displayed as a graph.

To add boreholes to the section, right-click on the **Boreholes** object and select either **Add Boreholes** or **Add Planned Boreholes**.

For adding boreholes, you will be prompted to select the interval table to display.

For both boreholes and planned boreholes, you can filter the boreholes based on a minimum distance from the section plane:

		um distance to section plane 91.	
<u>v</u> c	lip geometry	to filter <u>d</u> istance Displayin	g 11 of 22 hole
	Hole ID	Distance from section	^ _
	LAFEAS003	1	
	LAFEAS008	14	
	LAFEAS007	22	
	LAFEAS009	27	
	LAFEAS001	36	
	hole007	38	
	LAFEAS006	42	
	hole005	54	
	hole008	57	-
	LAFEAS004		

This is the minimum distance to any point on each borehole trace.

If you tick the **Clip geometry to filter distance** option, only parts of the borehole within the **filter distance** will be included in the section layout. Select the required boreholes and click **OK**.

When boreholes and planned boreholes are added to a curved section, a projection is made based on the locations of neighbouring segments of the section, using the bisectors of the angles between each segment and its neighbour. These determine the projection point of origin for a given segment of the section. When boreholes are filtered by the distance to the section plane, the distance is measured at 90 degrees from the section. Some boreholes may report a distance that is greater than the specified minimum distance; if this is the case, it is because the evaluation distance is relative to the projection origin.

On the inside of a tight corner, a single borehole may be projected multiple times onto the section. If this is the case, the multiple instances of the borehole will appear in the boreholes list and you can turn individual instances off, if required.


When a fence section is updated, borehole evaluations are updated. If there are multiple instances of a borehole evaluation, how they appear on the section may change when the section is updated:

- If all instances of a borehole evaluation have been enabled, then all remain enabled when the section is updated.
- If all instances of a borehole evaluation have been disabled, then all will remain disabled when the section is updated.

• If only some instances of a borehole evaluation have been enabled, then all instances will be enabled when the section is updated.


When a section layout is copied to another section from a fence section, borehole evaluations will not be copied with the section layout.

You can have the following type of labels at different points along the borehole trace: top labels, intercept labels, bottom labels and depth markers. To hide or change the appearance of borehole labels, click on the borehole table, then on the **Points and labels** tab. Click **Options** to change how the labels are displayed. You can rotate labels and have a line connecting the label to the collar:




You can also click on the labels in the layout and move them. Note that the label lines will only appear once the borehole label has been moved away from the collar.

If you want to return all labels to their default positions, click **Reset Dragged Labels** in the **Points and Labels > Label Options** window.



How boreholes are displayed is controlled by the **Colourings** settings in the **Lines** tab:

Click the **Options** button to display data (category data) or filter values (numeric data) on the boreholes:




🔗 Edit Colouring: Left Display style Labels Colour Name 👁 📃 MX 💊 ۲ OX Ð M) <u>....</u> -☑ <u>H</u>atched ☑ <u>O</u>utlined Hatch colour: \$ Hatch scale: 15.00 Hatch Line width: 0.2 Div 4 **C**lose

Boreholes can be displayed using hatching patterns. In the **Display style** tab, tick the **Hatched** option, then select from the patterns available:

For columns of numeric data, you can display data as a bar graph or line graph. These options are available in the **Display style** tab. Here, data is displayed as a bar graph:

💈 Edit Colouring: Left	×	EM_71 ^{JM_084}
Display style Labels Colourmap: Fe_new ↓ Yalue filter: 0.00000		
Log <u>a</u> rithimic scale	ose	

Select a **Max length** that means that displayed data does not interfere with other boreholes or data displayed on the section layout. This is especially useful when two graphs are displayed:



If you only want to plot a limited range of data, tick the **Axis limit** box and set the required range.


Displaying data with the logarithmic scale enabled may enhance differences in the values, and negative values can be scaled.

The bar and line graph options are not available for the centre of the borehole, although the solid option can be used.

Adding and Styling Surfaces

The **Surfaces** folder contains all surfaces that have been added to the section layout. To add another surface, first make sure it has been evaluated on the section, then right-click on the **Surfaces** folder and select **Add Surface**. Select from those available and click **OK**.

Click on the surface in the **Layout Tree** to view styling options:



Edit the text used to display the surface by enabling the **Edit** box and then changing the text. You can change the **Line style**, **Line width**, **Pattern scale** and colour. You can also define a marker to display along the line by enabling **Add marker** and then specifying a **Symbol** to use. A **Preview** is displayed and the surface will be updated in the section preview.

You can see below how changes to the **Line style**, **Symbol** and **Occurrence** can be used to indicate different conditions:

Line style:			
Line wi <u>d</u> th: 0.2	<u>Pattern scale</u> :	1.4	\$
☑ Add <u>m</u> arker	Marker size:	3.0	\$
Symbol: ?	Occurrence:	2	\$
Preview:?	??	-?	- ?

- Line style: Long dash
- Symbol: ?
- Occurrence: 2

Line style:	~		
Line wi <u>d</u> th: 0.2	Pattern scale:	1.4	\$
✓ Add marker	Marker si <u>z</u> e:	3.0	\$
Symbol: ?	Occurrence:	3	\$
Preview: ?	?	?	

- Line style: Solid line
- Symbol: ?
- Occurrence: 3

Line style:	~		
Line wi <u>d</u> th: 0.2	<u>P</u> attern scale:	1.4	\$
Add <u>marker</u>	Marker size:	3.0	\$
Symbol: #	Occurrence:	5	\$
Preview: #····	###…	##	

- Line style: Dotted
- Symbol: #
- Occurrence: 5

Adding and Styling Lines


The **Lines** folder contains all lines that have been added to the section layout. To add another line, first make sure it has been evaluated on the section, then right-click on the **Lines** folder and select **Add Line**. Select from those available and click **OK**.

Click on the line in the **Layout Tree** to view styling options, including the size, shape and colour of the pierce point:

🕅 Tunnel - Alignment							
✓ Visible	✓ Visible Opacity: 1.00					1.00	
✓ <u>S</u> how	in leg	end					
Descriptio	n: 🗆	<u>E</u> dit					
Tunnel -	Align	ment					
<u>S</u> hape:				•	•		Ň
Size:	٠	0	\times	Ν	••	Х	- 20
			+	/	:	ф	
C <u>o</u> lour:	▼	∇	\Box	\mathbf{i}	\bigtriangledown	÷	
	▲	Δ	\Box	>	$\[\]$	\oplus	
	٠	\diamond	<	Λ	,	\boxtimes	
	C	٥	V	\prec		¢	
	•	D	Г	*	0	۰	
	I.	۵	${}$	8	T		
	-		Ζ	8	*		

Setting Up the Legend

The **Legend Group** and the individual legends underneath it control how the legend is displayed on the page.




Click on the Legend Group object to change the layout of the legend as a whole:

Layout Tree						
Page						
▼ 🚿 Section						
Models						
Boreholes						
Surfaces						
Lines						
E Legend Group						
Annotations						
Egend Group						
Sho <u>w</u> title Legend	/					
Group title style: beading V Edit Styles						
Legend title style: Sub Heading V Edit Styles						
Legend entry tyle: Body V Edit Styles						
Layout 🗡						
Colu <u>m</u> ns:	Horizontal		~			
Colour Swatch Size:	7) 7	\$			
Gra <u>d</u> ient Swatch Size:	60	\$ 5	\$			
Swatch <u>W</u> idth:	13	•				
Boundary box						
Line style:						
Line width: 0.2	eattern scale:	1.0				

Columns can be laid out vertically or horizontally, and you can also change the swatch size and gradient and add a **Boundary box**. For individual legends that have a large number of entries, you may need to

increase the number of rows. For example, for the combined model, the number of rows has been increased to accommodate the number of entries in the legend:



When you have multiple models, surfaces, lines and boreholes on the section layout, you can end up with a large number of entries in the **Legend Group**. How you hide a legend in the **Legend Group** depends on the type of object. Objects displayed on the section layout appear in the **Legend Group** as follows:

• Each model on the layout has an individual entry. Hide a model in the **Legend Group** by clicking on the model's entry and disabling the **Visible** option.

Layout Tree	^
📄 Page	
Section	=
🔻 🗐 Legend Group	
🧿 Sulfur structural trend legend 🔨	
🗭 Combined Model legend 🛛 🔪	
🖓 Lines	
∧ Geology_with_assays left legend	
∧ Geology_with_assays right legend	~
☐ <u>Visible</u> Title: ☑ Show ☐ <u>E</u> dit	
Sulfur structural trend	
Su <u>b</u> title Text:	
Rows: 5	2 Default

• Each geological model, numeric model and combined model has a **Surfaces** folder, which will have its own entry in the **Legend Group** when at least one surface in that folder has been set to **Show in legend**. The surfaces legend for a model itself can be hidden in the **Legend Group** by clicking on the entry and disabling the **Visible** option:

Layout Tree	Â	Layout Tree
Page		Page
▼ 🗯 Section	=	Section
🔻 🚞 Models		▼ 🗄 Legend Group
🔻 🧿 Sulfur structural trend		- Sulfur structural trend Surfaces legend
▼ m Surfaces		Sulfur structural trend legend
- 0.5		🗭 Combined Model legend
- 1.0		₹ _a Lines
- 2.0		∧ Geology_with_assays left legend
- 3.0		∧ Geology_with_assay_right legend
Output Volumes Official of the second of the sec		Sulfur structural trend Surfaces legend Visible Title: Show Edit Sulfur structural trend Surfaces Subtitle Text:
-		Rows: 4

• Each borehole column that appears on the section has an individual entry. Hide a column in the **Legend Group** by clicking on the column's entry and disabling the **Visible** option:

Layout Tree	
Page	
Section	
▼ 🗄 Legend Group	
 Sulfur structural trend Surfaces legend 	
Sulfur structural trend legend	
🧭 Combined Model legend	
🚬 Lines	
🔨 Geology_with_assays left legend	
🔨 Geology_with_assays right legend	~
✓ Geology_with_assays left legend ✓ Visible	
Title: ☑ Show □ Edit	
lithology	

- Planned boreholes that appear on the section do not appear in the **Legend Group**.
- Surfaces in the **Section > Surfaces** folder appear in the **Legend Group** as a single entry. Hide a surface in the **Legend Group** by clicking on the surface in the **Surfaces** folder and disabling the**Show in legend** option:


Layout Tree
Page
▼ 🏂 Section
Models
Boreholes
▼ 📄 Surfaces
🛆 Topography 🚤
Lines
▶ 🗐 Legend Group
Annotations
Topography
Visible Pracity:
✓ Show in legend
Description: 🗌 Edit
Topography
Line style:
Line width: 0.2 2 Pattern scale: 1.0
Add <u>m</u> arker
Preview:

• Lines in the Section > Lines folder appear in the Legend Group as a single entry. Hide a line in the Legend Group by clicking on the line in the Lines folder and disabling theShow in legend option:

Layout Tree	
Page	
▼ 🗯 Section	
Models	
Boreholes	
Surfaces	
▼ 🛅 Lines	
📉 GIS line (On Topography)	
▶ 🗉 Legend Group	
Annotations	
Silve (On Topography) Image: Show in Legend	1.00
Description: 🗹 <u>E</u> dit	
GIS Line	
Shape:	~
Si <u>z</u> e: 1.0	\$
C <u>o</u> lour:	


The order in which legends appear in the **Legend Group** is the order in which they appear in the **Layout Tree**. To change the order in which the legends appear, right-click on them and select a **Move** option.

The colours, line widths, fills and hatches displayed in the **Legend Group** are controlled by the objects themselves. For example, to change how a shell is displayed for the interpolant, click on the output volume, under the **Models** object:



Adding and Organising Annotations

Once you have laid out the main **Section** object and organised the **Legend Group**, you can add a number of different types of annotation to the layout, including a title, a title block, location information and a scale bar, text boxes and imported images.



Displaying a Title


The **Title** object formats the title displayed on the page. To move the title, click on it in the layout preview. The text used for the **Title** is the name for the section in the project tree, but this can be changed in the properties panel. Enable the **Edit** option, then edit the text in the box:

Layout Tree		
🗋 Page		
Section	n	
▶ 🗄 Legen	d Group	
🛡 🚞 Annot	ations	
🔺 Titl	le	
📃 🔺 🔺 Titl	e Block	
🥒 Sca		
Co Co		
Tex		
lma 📄	ages	
🛕 Title		
✓ Visible		
Text: Title		← Edit Styles
Borland Coa	al Deposit Section	
Boundar	y box	
Line style:	0.2 C Pattern se	cale: 1.0 ^
_		
Preview:		

You can display a line around the **Title** by enabling the **Boundary box** option. You can customise the **Line style**, **Line width**, **Pattern scale** and colour of the box. A **Preview** is displayed and the boundary is updated in the section preview.

Displaying a Title Block


When the **Title Block** is visible, a title block based on ISO 7200 is displayed on the layout:




To display the **Title Block** on the section, select it in the **Layout Tree**, then tick the **Visible** box. In this panel, you can also change the styles used to display the information in the block.

Displaying a Scale Bar and Location Information

There are a number of different styles available for the **Scale Bar**, and you can control its **Length**, **Partitions** and **Thickness**:



You can show the **Scale Bar** with or without labels, and labels can be shown all along the bar by disabling the **End Points Only** option:



The **Text** options determine whether or not the scale and vertical exaggeration are shown on the scale bar.

ayout Tree 1187000 1188000 1189000 Page Section

 Section

 Group

 Annotations A Title A Title Block Scale Bar 1.3 2.5 3.8 5 Location
 Text Boxes 🛅 Image Location Visible <u> Fitle</u> Location Location Heading ← Edit Styles W: 1183245, 4907382, 531 General Show Z coordinate E: 1189060, 4907382, 531 Decimal places: 0 Scale: 1:24.000 Body ✓ Edit Styles Vertical exaggeration: 1.5x Boundary box 400m 800m 1200m 1600m 2000m 0m


The **Location** object controls how location information is displayed:

You can include the Z coordinate, if required and change the number of decimal places used to display coordinates.

There is a **Boundary box** option for both the **Scale Bar** and the **Location**. You can customise the **Line style**, **Line width**, **Pattern scale** and colour of the box. A **Preview** is displayed and the boundary is updated in the section preview.

Text Boxes

With the **Text Boxes** object, you can add text boxes and arrows to highlight information and details on the section:



There is a **Show Outline** option for the text box, and corners can be square or rounded. You can customise the **Line style**, **Line width**, **Pattern scale** and colour of the outline. A **Preview** is displayed and the text box is updated in the section preview.


Arrows are connected to text boxes, and so initially only text boxes can be added. Right-click on a text box to add an arrow to it. When the **Automatic anchoring** option is enabled for an arrow, the arrow's anchor will move when its associated text box is moved:

Layout Tree	^
El Legend Group	
Annotations	
A Title	
A Title Block	
🥒 Scale Bar	=
🔍 Location	-
Text Boxes	
▼ Ӓ TextBox	
Arrow	
Images	~
Arrow	
✓ Visible	
Automatic anchoring	
Line style:	
Line width: 0.35	\$
Preview:	

If this option is disabled, the arrow will move when you move the text box, but you will have to place its anchor manually.

Images

If you wish to import an image such as a logo or map, right-click on the **Images** object and select **Add Image**. Navigate to the folder that contains the image file and select the file. Click **Open** to import the file, which will automatically be added to the section layout:




Move the image by clicking on it in the preview and dragging it. You can resize the image using the controls in the preview.


Rendered Images

Leapfrog Works can render high-quality images that you can save on your computer in a format that can be used in presentations and documents. To do this, click on the **Render Image** button in the toolbar (

or click on the **Leapfrog Works** menu and select **Render Image**. Leapfrog Works renders an image from the current scene window, then displays it in the **Render Image** window:



If you are displaying multiple views in the scene, you can select which ones you want to render from the **Render View** list:



Views that are open in tabs are also listed in the **Render View** list. However, the **All (Multi View)** option only renders the split of views displayed in the **Scene View** tab.


Use the zoom tools to view the rendered image. You can change the image settings by:

- Selecting a new image size. To constrain the image's proportions when changing size, tick the **Keep aspect** box.
- Changing supersampling options to smooth jagged edges. Select the required option from the list. The highest sampling option (**4x4**) will take longer to process than the lowest sampling option or turning supersampling off.
- Viewing the image with or without overlays. See <u>Overlay Settings</u> for more information about further customising the overlays displayed in the scene.

Click the **Render** button to update the image with the changed settings. Once you are satisfied with the rendered image, click **Save**. You will be prompted to enter a filename and location.

Background Rendering

You can keep the **Render Image** tab open while continuing to work in your project, which is useful for rendering a series of images. To work in this way, dock the **Render Image** tab adjacent to the scene window. When you have set up your scene, right-click on the **Render Image** tab and choose one of the options:



The **Render and Copy Image** option will render a new image from the scene and copy it to the clipboard.

The **Render and Save Image** option will render a new image and prompt you for a filename and location.

Saved Scenes

A saved scene is a way of storing the objects in the shape list and their settings. Saved scenes are stored in the **Saved Scenes and Movies** folder and can be dragged into the scene, restoring the list of objects and their settings. A saved scene is, in effect, a bookmark of a specific view of the project data. A saved scene does not maintain an independent copy of the data in the project, and so if the data changes, then the appearance of the scene will also change.

When a scene is saved, comments can be entered documenting what is in the scene. Saved scenes provide a stable point of reference in a project and can explain important features of the project, which is especially useful for explaining features of a model to others using the project or viewing scene files.

Saved scenes can also be:

- Exported to Leapfrog Viewer. You can export a single scene or a series of scenes.
- Used to create a movie. See the <u>Movies</u> topic for information on using a series of saved scenes to create and export a movie.

The rest of this topic describes:

- Saving Scenes
- Exporting Scenes
- Linking to Scene Files

Saving Scenes

To save the list of objects currently displayed in the **Scene View** tab, right-click on the **Saved Scenes and Movies** folder and select **Save Current Scene**. The **Save Scene** window will be displayed:

A Save Scene	×
Description	
Name: Scene 1	\sim
(?) <u>Cancel</u> QK	

Enter a name and description for the scene and click **OK**. The scene will be saved and added to the **Saved Scenes and Movies** folder.

When you save a scene, the properties settings in the shape list are saved for the objects displayed in the scene. For example, if a lithology table is displayed with the legend in the scene, the legend will be displayed when the scene is restored. However, saved scenes do not store copies of the objects in the project tree, and objects deleted from the project tree are no longer available in saved scenes.

To edit a scene, double-click on it. The **Edit Saved Scene** window will be displayed and you can update the information.

To display a scene, drag it into the **Scene View** tab.

Exporting Scenes

Once you have a series of saved scenes, you can use them to create a scene file that can be opened in Leapfrog Viewer.

To export a scene, right-click on the **Saved Scenes and Movies** folder and select **Export Scenes**. The **Export Scenes** window will be displayed. Move the scenes you wish to export to the **Selected scenes** list and reorder them, if required.

🐸 Export Scenes					×
Saved scenes:			Selected scenes:		
12 5. Contact surfaces sliced	-			1. Topography with lithology data	
C 6. Model with lithology sliced			(millionter e)	Lithology data imported, collars used to create the topography	
				2. Granite - Lower Basalt contacts	
			C. PARKET I	Contact surface created as part of stratigraphic sequence	
				3. Lower Basalt - Sandstone contacts	
			desides.	Contact surface created as part of stratigraphic sequence	
		>		4. All contact surfaces	\wedge
		<	Alektron (All contact surfaces created as part of stratigraphic sequence	\sim
1			Export hidden shapes		
<u> </u>			 Export shapes only Export all data that applications 	pears when I click	
0				<u>C</u> ancel <u>E</u> xpo	rt

You can also export an individual scene by right-clicking on the scene and selecting **Export**.

If you tick the **Export hidden shapes** box, objects in the shape list that are not visible in the scene window will be included in the exported scene.

You can also export the data associated with the objects in the scene window, if required. To do so, select the **Export all data that appears when I click** option. If viewing the data is not required, or if you wish to keep sensitive data secure, select the **Export shapes only** option.

When the **Export all data that appears when I click** option is selected, all data represented by shapes in the exported scene will be accessible when the scene is opened in Leapfrog Viewer.

When you have the scenes arranged, click **Export**. You will be prompted for a filename and location. Exported scenes cannot be reimported to the project.

Linking to Scene Files

Links to scene files can be included in HTML files using the following format:

link text


Linked scene files will be opened directly in Leapfrog Viewer only from browsers that support custom URI schemes.

Movies

Once you have a series of saved scenes (see <u>Saved Scenes</u>), you can use them to create a storyboard and export a movie.

To create a new movie, right-click on the **Saved Scenes and Movies** folder and select **New Movie**. A tab will open in which you can create a storyboard and edit how each scene and transition is displayed. You can detach the tab from the main window and create scenes in the main window while working on scenes in the movie tab. Click the **Refresh Scenes** button to refresh the scenes in the movie tab when you have made changes.

Select the saved scenes you wish to add to the movie by clicking on them in the list, then click the **Add To Storyboard** button (,). When subsequent scenes are added, transitions will be added to separate the scenes:



Change properties for the selected scene or transition, then click the play button (*) to preview the settings. To preview the whole movie, click the **Select All** button then click play.

You can make changes to the included scenes without having to close and reopen the movie window. Simply update the scenes, then, in the movie editor, click the **Refresh Scenes** button.

Enter a name and description for the movie and click the **Save** button (🖹). The movie will be saved in the **Saved Scenes and Movies** folder.

To export the movie, click the **Save and Export** button (**d**). The **Export Movie** window will appear:

🖉 Export Movie	×		
Movie			
Movie Size:	640 x 480 $$		
Frames Per Second:	25 ~		
Quality:	High \checkmark		
Total Duration:	30.0 seconds		
Export frame images			
Cancel	<u>ο</u> κ		

If you tick **Export frame images**, individual frames will be saved as images, together with the movie file. Click **Export**. You will be prompted to select a filename and location. Click **Save** to export the movie. Leapfrog Works will then save the movie in the specified location, which may take some time.

Contour Lines

You can create contour lines from surfaces in the project and export those contour lines to GIS packages.

Creating Contour Lines

To create contour lines from a surface, right-click on the **Cross Sections and Contours** folder and select **New Contour Lines From Surface**. In the **New Contours** window, select the surface to contour from the list. Adjust the **Contour Spacing**, if required.

If you want to offset the contours by a vector, enter a **Contour offset** value.

Click **OK** to generate the contours.

The new contours will appear in the project tree under the **Cross Sections and Contours** folder.

You can edit the contours by double-clicking on them.

Exporting GIS Contours

To export a contour lines object, right-click on the contour lines in the **Cross Sections and Contours** folder and select **Export**. Select whether or not to export the contours in 2.5D format, then click **Export**. You will be prompted for a filename and location.